INCH-POUND

MIL-R-55168B(CR)
26 July 1990
SUPERSEDING
MIL-R-55168A(EL)
19 August 1965

MILITARY SPECIFICATION

RETRANSMISSION CABLE KIT MK-456( )/GRC
(UNITS OF)

This specification is approved for use by the Communications-Electronics Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers one type of equipment designated as Retransmission Cable Kit, MK-456( )/GRC. It consist of the following units: (see 6.1).

a. Cable Assembly, Special Purpose, Electrical CX-4656()/GRC.

b. Bag, Cotton Duck CW-502( )/GRC.

1.2 Part or Identifying Number (PIN). A specification - based PIN to identify retransmission cable kits is included in 6.3.

2. APPLICABLE DOCUMENTS

2.1. Government documents.

2.1.1. Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations,additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Communications-Electronics Command, ATTN: AMSEL-ED-TO, Fort Monmouth, NJ 07703-5000, by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

ASMC N/A FSC 5995

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

QQ-S-571 - Solder, Tin Alloy, Lead-tin Alloy, and Lead Alloy

MILITARY

MIL-T-152 - Treatment, Moisture-and Fungus Resistant, of Electrical Equipment
MIL-V-173 - Varnish, Moisture-Fungus-Resistant, for the Treatment of Communications, Electronics, and Associated Electrical Equipment
MIL-C-3885 - Cable Assemblies and Cord Assemblies, Electrical (For Use in Electronic, Communication and Associated Electrical Equipment)
MIL-P-11268 - Parts, Materials and Processes Used in Electronic Equipment
MIL-M-13231 - Marking of Electronic Items
MIL-F-14072 - Finishes for Ground Signal Equipment
MIL-F-14256 - Flux, Soldering, Liquid
MIL-I-46058 - Insulating Compound Electrical (For coating Printed Circuit Assemblies)
MIL-P-55110 - Printed Circuit Boards

STANDARDS

FEDERAL

FED-STD-595 - Color

MILITARY

MIL-STD-252 - Wired Equipment, classification of Visual and Mechanical Defects
MIL-STD-810 - Environmental Test Methods

(Unless otherwise indicated, copies of the federal and military specifications, standards, and handbooks are available from: Standardizaiton Documents Order Desk, Bldg 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.

DRAWINGS

SC-DL-366983 - Cable Assembly, Special Purpose, Electrical CX-4656/GRC

SM-C-367004 - Cable Assembly, Special Purpose, Electrical CX-4656/GRC
SC-DL-367012 - Bag, Cotton Duck, CW-502 ( )/GRC

(Copies of specifications, standards, and other Government documents required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, (except for associated detail specifications, specification sheets, or MS standards) the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1. First article. When specified (see 6.2), the contractor shall furnish two (2) sample units for first article inspection (see 6.4), in accordance with 4.3.

3.2. Construction. Retransmission Cable Kit, MK-456( )/GRC shall be fabricated in accordance with the following drawings:

SC-DL-366983 - Cable Assembly, Special Purpose, Electrical CX-4656( )/GRC (See 3.10)
SC-DL-367012 - Bag, Cotton Duck CW-502( )/GRC

3.3. Parts, materials, and processes. In addition to the requirements of this specification, the requirements of MIL-P-11268 including the selection requirements therein shall apply (see 4.4).

3.3.1. Finish, Protective. The network box and decoupling choke box, part of Cable Assembly, Special Purpose, Electrical CX-4656 ( )/GRC, shall be given protective finish in accordance with MIL-F-14072. This includes finish of hardware and necessary touch-up after mounting. The final paint film on type 1 surfaces shall be a green color (olive drab), semigloss enamel matching color chip No. X-24087 in accordance with Federal Standard No. 595 (see 4.4).

3.3.2. Marking. Marking shall conform to MIL-M-13231 (see 4.4).

3.3.2.1. Visibility. Wherever practicable, parts shall be so mounted that their identification markings will be readily visible with minimum disassembly of the equipment.

3.3.2.2. Serial Numbers. Cable Assembly, Special Purpose, Electrical CX-4656( )/GRC shall have serial numbers.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:33Z
Check the source to verify that this is the current version before use.

3.3.3. Soldering. Solder shall conform to QQ-S-571. For soldering electrical connections, composition SN60, type AR or S, shall be used for general purposes; and composition SN62 or SN63, type AR or S, for special purposes. When type S solder is used for soldering electrical connections, the flux shall conform to MIL-F-14256.

3.3.4. Acid or acid salts. No acid or acid salts shall be used in preparation for or during soldering; however, exception is permitted for preliminary tinning of electrical connections and for tinning or soldering of mechanical joints not used to complete electrical circuits, but in no case shall acid or acid salts be used where they can come in contact with insulation material. Where acid or acid salts are used , as permitted above, they shall be completely neutralized and removed immediately after use.

3.3.5. Process. There shall be no sharp points or rough surfaces resulting from insufficient heating. The solder shall feather out to a thin edge, indicating proper flowing and wetting actions, and shall not be crystallized, overheated, or under heated. The minimum necessary amount of flux and solder shall be used for electrical connections. Any means employed to remove an unavoidable excess of flux shall not incur the risk of loose particles of flux, brush bristles, or other foreign material remaining in the equipment; flux being spread over a larger area; or damage to the equipment. Insulation material that has been subjected to heating during the soldering operation shall be undamaged and parts fastened thereto shall not have become loosened.

3.4. Interchangeability. Like units, assemblies, sub-assemblies, and replaceable parts shall be physically and functionally interchangeable, without modification of such items or of the equipment (See 4.11). Individual items shall not be handpicked, for fit or performance. Reliance shall not be placed on any unspecified dimension, rating or characteristic, etc.

3.5. Printed wiring boards. Materials and processes for printed wiring boards shall conform to MIL-P-55110 unless otherwise specified (see 4.4).

3.5.1. Conformal Coatings. Printed wiring assemblies shall be conformally coated with a Type ER Insulating Compound per MIL-I-46058. The coating shall be applied to both sides of the cleaned printed wiring assembly. These assemblies shall be cleaned of flux and other contaminants prior to coating. Cleaning compounds shall have no deleterious effects on any part of the printed wiring assembly and the thickness shall be 0.0035 inch $\pm$ 0.0025 inch. Electrical and mechanical mating surfaces such as connector contact points, test points, screw threads, etc., shall not be coated.

3.6. Service conditions. Cable Assembly, Special Purpose, Electrical CX-4656( )/GRC shall meet the service conditions as specified herein.

3.6.1. Operation. Continuous use for a period of 1 year, under the environmental conditions specified in 3.6.2 through 3.6.6, with no more than normal maintenance and replacement of parts. Where the contractor is required to make a selection of parts, materials, processes, construction methods, etc., he shall be guided by this requirement. Approval of the first article sample (see 3.1) shall be considered as compliance with this requirement.

3.6.2. Temperature (see 4.6.1).

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.

a. Operating: Ambient temperature in the range of +150° F to -40° F (The 150° F temperature includes effect of sun-load). Exposure at the high temperature extreme not to exceed 4 hours, and at the low temperature extreme not to exceed 72 hours, at any time.

b. Nonoperating: Exposure in the range of +160° F to -80° F; exposure at the high temperature extreme not to exceed 4 hours and at the low temperature extreme not to exceed 24 hours, at any one time.

3.6.3. Moisture resistance (See 4.6.3). During each 24 hours on test, up to 97 percent relative humidity for 20 hours; and exposure at 100 percent relative humidity, with condensation, for 4 hours over the period of years stated in 3.6.1 meeting the tests of 4.6.3 shall be considered as compliance with this requirement.

3.6.4. Immersion (See 4.6.2). Three feet of water for 2 hours.

3.6.5. Fungus. Equipment and assemblies shall show no evidence of viable fungus or corrosion when subjected to 28 days of fungus tests in accordance with 4.6.4. Corrosion is defined as any visible degradation that can be attributed to flaky, pitted, blistered or otherwise loosened finish of metal surface.

3.6.6. Salt Fog. The equipment and assemblies shall be exposed, in their operating configuration, to 48 hours of salt fog in accordance with 4.6.5 and shall show no evidence of corrosion as evidenced by any visible degradation that can be attributed to flaky, pitted, blistered or otherwise loosened finish of metal surface.

3.7. Cable Assembly, Special Purpose, Electrical CX-4656( )/GRC requirements.

3.7.1. Terminations with U-229/( )/U connector. The cables terminated with Connector, Plug U-229( )/U shall meet the applicable requirements for flexure, internal seal, and pull as specified in MIL-C-3885.

3.7.2. Twist, flexure and pull test for box-to-cable junctions. The cables terminated in the Network and Decoupling Choke boxes shall be subjected to the tests of 4.9. Following the test, the cable assembly shall meet the continuity tests of 4.8 as well as the immersion test of 4.6.2.

3.7.3. Circuit continuity. The cable assembly shall conform to the functional wiring diagram of SM-C-367004. Conformance with this requirement shall be verified by the continuity test of 4.8.

3.7.4 Dielectric (See 4.7). Cable Assembly CX-4656( )/GRC shall be capable of withstanding, without arcing or showing evidence of electrical leakage between parts, an alternating current potential of 500 volts applied between all mutually insulated current-carrying parts and shell, for a minimum period of one minute.

3.8. Bag, Cotton Duck CW-502( )/GRC (See 4.10). Construction of Bag, Cotton Duck CW-502( )/GRC shall be in accordance with SC-DL-367012 and the documents listed thereon. After subjection to tests determining compliance with requirements listed on the drawings, including "tests for shrinkage," it shall

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:33Z
Check the source to verify that this is the current version before use.

be of proper size to house the complete Cable Assembly, Special Purpose CX-4656( )/GRC.

3.9. Workmanship (see 4.12). Retransmission Cable Kit MK-456( )/GRC shall be manufactured and assembled in accordance with the equipment drawings and the applicable portions of the following paragraphs herein:

Paragraphs

3.3.3 Solder
3.3.4 Acid or Acid Salts
3.3.5 Process for soldering

3.10. Moisture and Fungus Proof (MFP) Treatment for Equipment and Assemblies. An MFP coating in accordance with MIL-V-173 shall be applied as specified in MIL-T-152 to equipments, assemblies and parts which have been cleaned prior to coating to remove such contaminants as lubricating oils, mold release agents, sand, corrosion products, solder flux, fingerprints and dust. It is required that printed circuit boards receive a conformal coating of Type ER Insulating Compound per MIL-I-46058 and do not receive the MFP coating at any time (see para 4.6).

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1. Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.2 Classification of inspection. Inspection shall be classified as follows:

a. First article inspection (does not include preparation for delivery). (See 4.3.)

b. Inspection covered by subsidiary documents. (See 4.4.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:33Z
Check the source to verify that this is the current version before use.

c. Quality conformance inspection of equipment before packaging (see 4.5).

4.3 First article inspection. This inspection shall consist of the inspection specified in the subsidiary documents covering the items listed in 4.4, and the inspection specified for Group A, Group B and Group C (see Tables I, II, and III respectively).

4.4. Inspection covered by subsidiary documents.

Item	Where Required
Finish	3.3.1
Marking	3.3.2
Printed wiring boards	3.5

4.5. Quality conformance inspection of equipment before packaging. The contractor shall perform the inspection specified in 4.4 and 4.5.1 through 4.5.3. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition the Government--at its discretion-- may perform all or any part of the specified inspection, to verify the contractor's compliance with specified requirements. (See 6.7) Test equipment for Government verification inspection shall be made available by the contractor.

4.5.1. Group A inspection. This inspection shall conform to table I and be performed in any order which is satisfactory to the Government.

TABLE I. Group A inspection.

Inspection	Requirement paragraph	Inspection paragraph
Visual and mechanical Network box Decoupling box Bag CW-502( )/GRC Overall Cable Assembly CX-4656( )/GRC	3.9	4.12
Continuity	3.7.3	4.8

4.5.2. Group B inspection. This inspection shall conform to table II. Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection.

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.

4.5.2.1. Order of inspection within group B. Group B inspection shall be performed in any order which is satisfactory to the Government.

TABLE II. Group B inspection.

Inspection	Requirement paragraph	Inspection paragraph
Dielectric	3.7.4	4.7
Interchangeability (Dimensions)	3.4	4.1

4.5.3. Group C inspection. This inspection shall be as listed in Table III, and shall normally be performed on sample units that have been subjected to and met group A and group B inspection. The inspection in subgroups I through III shall be performed in the order listed

4.5.3.1. Sampling for inspection of equipment. For Subgroup I inspection, two units shall be selected at random every month. Subgroup II inspection shall be two units from the first fifty production units and two units every three months thereafter. Subgroup III inspection shall be two units from the first fifty production units and two units from the first lot following the mid-point of production. Subgroup III tests shall be performed on a separate sample.

TABLE III. Group C inspection.

Inspection	Requirement paragraph	Inspection paragraph
Subgroup I		
Immersion	3.6.4	4.6.2
Test for shrinkage	3.8	4.10
Twist, flexure and pull at box-to-cable junctions*	3.7.2	4.9
Subgroup II		
Temperature	3.6.2	4.6.1
Moisture Resistance	3.6.3	4.6.3
Subgroup III		
Fungus	3.6.5	4.6.4
Salt Fog	3.6.6	4.6.5

*Units satisfactorily subjected to this test shall not be shipped as part of the production lot from which originally selected. However, the units may be re-submitted as normal production units of the next subsequent production lot provided new cabling is installed between the network box and the choke box as well as between both U-229( )/U connectors and the boxes.

4.5.3.2. Noncompliance. The contractor shall immediately report, in writing, each Group C failure occurrence, including details of the failure and characteristics affected. The contractor shall immediately conduct an

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.

investigation and document the details of the proposed corrective action on the process and materials, as applicable, and identify all units of product which were manufactured under the same conditions and which the government considers subject to the same failure. Reports shall be forwarded to the responsible technical activity designated in the contract, through the Quality Assurance Representative. After corrective action has been taken, additional sample units shall be subjected to Group C inspection (all inspections, or the inspections which the sample failed, at the option of the government) and Group A and B inspection may be reinstituted; however, final acceptance and shipment will be withheld until the Group C inspection results have shown that the corrective action was effective.

4.5.3.3 Disposition of Group C sample units. Unless otherwise specified, sample units which have been subjected to and passed Group C inspection may be delivered as part of the order, provided they have been refurbished to the satisfaction of the government.

4.6. Service conditions tests.

4.6.1. Temperature test. The equipment shall be subjected to the temperature cycle shown in MIL-STD-810. The continuity tests of 4.8 shall be performed at steps 1,3,8, and 10.

4.6.2. Immersion test. Cable Assembly, Special Purpose CX-4656 ( )/GRC shall be immersed to a minimum depth of 3 feet of fresh water for 2 hours. Immediately prior to immersion, the temperature of the equipment shall be 40° F, or more, above the temperature of the water. The tank in which the equipment is immersed shall be of sufficient capacity to maintain the water within ±2° F of its initial temperature, or the temperature of the water shall be maintained within those limits by other means. After completion of the 2-hour period of immersion, the equipment shall be removed from the water and wiped dry on exterior surfaces. When the equipment is opened, there shall be no evidence of leakage.

4.6.3. Moisture-resistance test. Cable Assembly, Special Purpose CX-4656( )/GRC shall be tested as follows:

a. Do not move equipment from the humidity chamber for measurements.

b. Complete measurements as rapidly as possible.

c. The seal on the network and decoupling choke boxes shall be broken during all five 48 hour cycles.

4.6.3.2. Test method.

a. Dry at 130° F ±5° F for 24 hours.

b. Condition at 77° F ±5° F and 40 to 50% relative humidity

c. Check Cable Assembly CX-4656( )/GRC for continuity and measure the insulation resistance of the cable assembly.

d. Subject the cable assembly to continuous cycling for five 48 hour cycles. Temperature, relative humidity, and period of time for each portion

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.

of the cycle shall conform to MIL-STD-810.

e. After cycling has been completed, condition the equipment for 24 hours at 77° F ±5° F and 40 to 60 percent relative humidity.

4.6.3.4. Performance after test. Cable Assembly CX-4656( )/GRC shall meet the continuity check of 4.8 and the insulation resistance shall be measured. Insulation resistance measurements shall not vary by more than 35 percent of the resistance measured under 4.6.3.2(c). In addition, there shall be no mechanical deterioration as evidenced by corrosion of metal parts.

4.6.4. Fungus. The equipment and assemblies shall be subjected to 28 days of the fungus test specified in Method 508 of MIL-STD-810. Covers shall be removed and interior parts and materials shall be sprayed with the spore suspension. The equipment shall be subjected to the test in this open condition.

4.6.5. Salt Fog. The equipment and assemblies shall be exposed in their operating configuration to salt fog, in accordance with Method 509 of MIL-STD-810, for 48 hours. Equipment shall not be required to be operated.

4.7. Dielectric test. Cable Assembly CX-4656( )/GRC shall be tested for conformance to 3.7.4. For this test the diodes shall be shorted out of the circuit and one terminal of the capacitors disconnected.

4.8. Continuity test (see 3.7.3). The assembled cable assembly shall be checked for electrical continuity of wiring and other connections by the following point-to-point continuity measurements.

4.8.1. Cable thru junction boxes (end to end).

Pin to Pin		Resistance (ohms)
A	A	0
B	B	2020 ± 102
C	C	Infinite
D	D	320 ± 10
E	E	INFINITE

The metal terminal boxes shall be connected to Pin A and shields of cable.

4.8.2. Receiver cable end of network box to network box headset receptacle.

Pin to Pin		Resistance (ohms)
A	A	0
B	B	2020 + 102
C	C	Infinite
D	D	320 + 10
E	E	Infinite

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.

4.8.3. Network box headset receptacle to choke box cable end.

Pin to Pin		Resistance (ohms)
A	A	0
B	B	2 + 1
C	C	2 + 1
D	D	2 + 1
E	E	Infinite

4.8.4. Diode continuity thru junction boxes (end to end with ohmmeter lead polarities as indicated below). Use the R x 1 scale on the ohmmeter (See Table IV).

TABLE IV. Ohmmeter lead polarities.

Network box Cable end	Choke box Cable end	
Pin and polarity	Pin and polarity	Resistance (ohms)
- E	+ C	less than 100
+ E	- C	Infinite
- C	+ E	Infinite
+ C	- E	less than 100

4.9. Twist, Flexure and Pull Test for Box to Cable Junctions. The network and decoupling choke box-to-cable junctions, after assembly of the cable, shall be subjected to a twist and flexure test with a minimum of 25 pounds pull being constantly applied to the cable jacket. The twist shall be applied by gripping cable 2 or 3 inches from the box-to-cable junctions and turning 360° in a clockwise direction and releasing. Repeat the twist 360° in the counterclockwise direction and release. Failure of cable to return to its original position after each release shall be cause for rejection of the sample. This torque and pull shall be applied and removed alternately in each direction from the normal for a total of 50 times (25 times in each direction). The flexure test shall be performed with the box held so that the concentric axis of the cable entry and exit junctions are horizontal and the cable is allowed to hang vertically. After the 25 pound pull has been applied to the vertically suspended cable jacket at a distance of 3 to 5 inches away from the box, the box shall be rotated about the horizontal cable axis for 100 rotations. Upon completion of the twist, flexure and pull tests on all four box-to-cable junctions, the cable shall be tested to determine compliance with 3.7.2.

4.10. Tests for Bag, Cotton Duck CW-502( )/GRC. Bag, Cotton Duck CW-502 ( )/GRC shall be inspected for conformance to 3.8.

4.11. Inspection for interchangeability. The dimensions listed below shall be gaged or measured to determine conformance to the physical interchangeability requirement of 3.4. When a listed dimension is not within specified or design limits, it shall be considered a major defect:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T22:33Z
Check the source to verify that this is the current version before use.

a. Cases: The maximum overall dimensions and location of mounting screw holes.

b. Covers: The maximum overall outside dimensions, length and width, and location of mounting screws.

c. External dimensions of insertable assemblies when such dimensions affect mating of parts.

4.12. Visual and mechanical inspection. The equipment shall be examined for the applicable defects listed in MIL-STD-252 and Table V. The bag shall be examined for workmanship, mechanical fit, application of specified treatment, and miscellaneous defects. Fastening devices shall be inspected for mechanical operation (see 3.9).

TABLE V. Classification of visual and mechanical defects for Bag CW-502( )/GRC.

Classification	Defect
Major	101 - End clip missing or loose 102 - Broken Stitches 103 - Strap missing or loose 104 - Fastening devices missing, inoperable, or incorrectly attached. 105 - Loose stitching 106 - Holes in material
Minor	201 - Color not as specified 202 - Marking not as specified 203 - Stains on material

4.13. Equipment verification review. The contractor shall perform an Equipment Verification Review (EVR), consisting of a complete technical audit of the equipment on order against the drawings cited for construction (para 3.2). The EVR shall consist of the following:

4.13.1. Drawings audit. An audit to establish that "as-built" equipment (unit, assembly, module, or part) is in accordance with the cited end product drawings.

4.13.2. Acceptance requirements audit. An audit to establish that "as-built" configuration of unit, assembly, module, or part meet the acceptance requirements (other than equipment specification performance) specified for each unit, assembly, module, or part. The audit shall record all acceptance test methods used together with resulting verification test data.

4.13.3. EVR Report. The contractor shall compile an EVR report(s) containing the following information:

a. Identification of unit, assembly, module, or part and details proving compliance with 4.13.1 and 4.13.2 above.

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.

b. Discrepancies noted.

c. Corrective action taken.

4.13.4. EVR Report availability. The contractor shall make available to the government copies of this EVR report(s) no later than 15 days prior to the submission of the first production unit or lot. The results of the EVR shall be subject to inspection by authorized government personnel at the time the first unit or production lot is offered for acceptance. Government inspection will be to the depth and extent necessary to demonstrate that the "as built" hardware is in accordance with the cited drawings. Copies of the EVR reports shall be made available to the government personnel during the inspection. The contractor shall provide the following:

a. Segregation of units, assemblies, modules, and parts to permit reviewing personnel access for detailed inspection.

b. As required, responsible personnel from each functional department available for discussions in their respective areas.

c. Adequate administrative support for the EVR.

5. PACKAGING

5.1 Packaging requirements. The packaging requirements for the desired level(s) of protection shall be as specified by the acquisition activity.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1. Intended use. Cable assembly, Special Purpose, Electrical CX-4656( )/GRC is used in connecting two Radio Sets AN/PRC-25( ) together or Radio Set AN/PRC-25( ) to Radio Set AN/VRC-12( ) or AN/PRC-77( ) for retransmission usage. Bag, Cotton Duck CW-502( )/GRC is used for stowage and carrying of the cable assembly.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification and any amendment thereto.

b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1).

c. Type required.

d. When first article is required (see 3.1), specify the following:

Makeup of pack(s).
Number of each kind of pack to be submitted.
Inspection to be performed thereon.

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.

e. Marking and shipping of samples.

f. Place of final inspection.

g. When rough handling and functional tests are required.

6.3. Part or Identifying Number (PIN). The PIN to be used for items acquired to this specificaiton is created as follows:

M	55168
Prefix to indicate military specification.	Specification number

6.4. First article. When first article inspection is required, the contracting officer should provide specific guidance to offerors whether the item(s) should be a first article sample, a first production item, or a standard production item from the contractor's current inventory and the number of items to be tested as specified in 4. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of first article test results and disposition of first articles. Invitations for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract.

6.5 Subject term (key word) listing.

Box Decoupling Choke
Box Network
Boards, Printed Wiring
Cable Special Purpose

6.6 Group C inspection. Approval to ship may be withheld, at the discretion of the Government, pending the decision from the contracting officer on the adequacy of corrective action (See 4.5.3.2).

6.7 Nomenclature. The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example: CW-502W/PR. The contractor should apply for nomenclature in accordance with the applicable clause of the contract (See 1.1).

6.8 Color of textiles. Standard samples of Olive Drab No. 7 may be obtained from the Sample Loan Unit, Military Clothing and Textile Supply Agency, Philadelphia, Pennsylvania. When requesting samples, indication should be given as to type of material concerned.

6.9 Verification inspection. Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.

will be limited in severity to the definitive quality assurance provisions established in this specification and the contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product.

6.10 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:
Army - CR

Preparing Activity:
Army - CR
(Project 5995-A132)

Review Activity:
DLA - GS

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-R-55168B(CR)	2. DOCUMENT DATE (YYMMDD) 90/07/26

3. DOCUMENT TITLE RETRANSMISSION CABLE KIT MK-456( )/GRC (UNITS OF)

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME U.S. ARMY CECOM	b. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON
c. ADDRESS (Include Zip Code) AMSEL-ED-TO FORT MONMOUTH, NJ 07703-5000	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340. AUTOVON 289-2340

DD Form 1426, OCT 89 *Previous editions are obsolete.* 198/290

Source: https://assist.dla.mil -- Downloaded: 202610-22T22:33Z
Check the source to verify that this is the current version before use.