# MILITARY SPECIFICATION

## CABINET, ELECTRICAL EQUIPMENT

This Specification has been approved by the
Naval Air Systems Command, Department of the Navy

## 1. SCOPE

1.1 Scope - The Electrical Equipment Cabinet covered by this specifi tion shall be for Intermediate Level use and shall be a standard cabinet for mounting and operation of the RF Noise Analyzer, Electronic Units.

1.2 Classification - The Electrical Equipment Cabinet (663R331G01) shall consist of the following items and shall hereinafter be referred to as t Cabinet.

| Item | Applicable Paragraph |
|---|---|
| Cabinet Frame | 3.4.1 |
| Cabinet Enclosure | 3.4.2 |
| Shock Mounts | 3.4.3 |
| Bottom Frame | 3.4.4 |
| Cable Harness | 3.4.5 |

1.3 Associated Equipment - The Cabinet shall operate with the followi equipment which shall not be supplied as part of the Cabinet:

(a) Electronic Units, RF Noise Analyzer, (TS-2573A/AWG-10) (hereinafter referred to as Electronic Units)

(b) Waveguide Run Kit (662R821G01)

(c) Cable Installation, RF Noise Analyzer (652R185G01)

## 2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the dat of invitation for bids form a part of this specification to the extent specified herein:



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

Military

| | |
|---|---|
| MIL-C-17 | Cables, Radio Frequency; Coaxial, Dual Coaxial, Twin Conductor, and Twin Lead |
| MIL-C-3767 | Connectors, Plug and Receptacle, Electrical, (Power, Bladed Type), General Specification for |
| MIL-T-5422 | Testing, Environmental, Aircraft Electronic Equipment |
| MIL-H-15362 | Harnesses; Test Bench, Avionic Equipment, General Specification for |
| MIL-W-16878 | Wire, Electrical, Insulated, High Temperature |
| MIL-M-17508 | Mounts; Resilient; Naval Engineering Experiment Station Types 6E2000, 6E900, 7E450, 6E150 and 6E100 |
| MIL-E-17555 | Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of |
| MIL-T-18303 | Test Procedures; Preproduction and Acceptance for Aircraft Electronic Equipment, Format for |
| MIL-N-18307 | Nomenclature and Nameplates for Aeronautical Electronic and Associated Equipment |
| MIL-T-21200 | Test Equipment for use with Electronic and Fire Control Systems, General Specification for |
| MIL-T-23336 | Technical Directives (Letter type): Preparation of |

STANDARDS

Military

| | |
|---|---|
| MIL-STD-189 | Racks, Electrical Equipment, 19-inch and Associated Panels |

DRAWINGS

Military

| | |
|---|---|
| MS3120 | Connectors, Receptacle, Electric, Crimp-Type |
| MS3126 | Connector, Plug, Electrical |



Source: https://assist.dla.mil -- Downloaded: 20261O-26T04:35Z
Check the source to verify that this is the current version before use.

Westinghouse Electric Corporation (97942)

| | |
|---|---|
| 411R684 | Key Drawing, Electronics Units, RF Noise Analyzer |
| 507R926 | Panel |
| 515R352 | Shock Mount Kit, Centerline Bench |
| 515R353 | Shock Mount Kit, Side Bench |
| 575R516 | Connector, Plug, Pigmy E Type |
| 577R569 | Connector, Electrical, Coaxial |
| 577R590 | Connector, Receptacle, Electrical |
| 577R831 | Connector, Receptacle, Polarized, Duplex |
| 579R284 | Thermistor, Mount |
| 579R339 | Mount, Resilient, Spool Type, Kit |
| 579R831 | Connector, Electrical, Coaxial Plug, Type BSM |
| 606R552 | Frame |
| 610R437 | Mixer-Preamplifier |
| 610R782 | Power Supply Drawer |
| 610R786 | Electronics Drawer |
| 610R787 | Meter Panel |
| 616R183 | Spectrum Analyzer |
| 616R184 | IF Unit |
| 616R185 | Converter |
| 616R233 | Enclosure Assembly |
| 652R185 | Cable Installation |
| 653R219 | RF Panel |
| 662R821 | Waveguide Run Kit |
| 663R331 | Rack Assembly, RF Noise Analyzer |

2.1.1 Availability of Documents - Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting office. See 6.4.

## 3. REQUIREMENTS

3.1 Parts and Materials - In the selection of parts and materials, fulfillment of major design objectives shall be the prime consideration. In so doing, the following shall govern:

(a) Parts and Materials as approved by MIL-T-21200 shall be given first consideration.

(b) Guidelines for the selection of nonstandard parts shall be in accordance with MIL-T-21200.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

(c) In the selection of parts, the above considerations shall apply if the assembly is to be built for detail part maintenance. In the event the entire assembly is built to be expended, the assembly shall be such that the unit as a whole will pass electrical and environmental tests.

3.1.1 Nonstandard Parts - Nonstandard parts and materials shall be as outlined in MIL-T-21200, Materials, Parts and Processess, except the mechanical parts shall be considered as nonstandard parts only when the material requirements of MIL-T-21200, as modified herein, are not met.

3.1.2 Noncorrosive Hardware - External Military Standard (MS) hardware which is used during servicing, accessing or installing test equipments shall be of a corrosive-resistant type and shall not be further finish-treated.

3.2 Design and Construction - The Cabinet shall conform with all applicable requirements of MIL-H-15362 for design, construction and workmanship, unless otherwise specified herein.

3.2.1 Total Weight - The total empty weight of the Cabinet, including all cabling, bottom shock mounts, and bottom frame shall not exceed 400 pounds. The gross weight with all Electronic Units installed shall not exceed 700 pounds.

3.2.2 Cables and Connectors - The Cabinet shall provide for the use of cables and connectors in accordance with MIL-H-15362.

3.2.3 Interchangeability - The Cabinet shall meet the interchangeability requirements as defined in MIL-T-21200.

3.2.4 Standard Conditions - The following conditions shall be used to establish normal performance characteristics under standard conditions and for making laboratory tests.

| | |
|---|---|
| Temperature | Room Ambient: 30° ±10° Centigrade (C)<br>86° ±18° Fahrenheit (F) |
| Altitude | Normal Ground |
| Vibration | None |
| Humidity | Room ambient up to 90% relative humidity |



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

3.2.5 Service Conditions - The Cabinet shall operate satisfactorily under any of the environmental service conditions or reasonable combination of these conditions as specified in MIL-H-15362.

3.2.6 Nomenclature and Namplates - Nomenclature assignment and nameplate approval for equipment identification shall be in accordance with MIL-N-18307.

3.3 Performance

3.3.1 General - Unless otherwise specified, values set forth to establish the requirements for satisfactory performance apply to performance under both standard and extreme service conditions. When reduced performance under the extreme conditions is acceptable, tolerances or values setting forth acceptable variations from the performance under the standard conditions will be specified.

3.3.2 Function - The Cabinet shall provide mounting and interconnection for the Electronic Units at the Intermediate Level of Maintenance. When connected to a 115 V, 60/400 cps, single phase, 632 VA capability, it shall permit operation of the Electronic Units for detailed maintenance of the AN/AWG-10 Missile Control System.

3.3.3 Form Factor - The Cabinet shall be a standard 19 inch cabinet per MIL-STD-189 with suitable means for deck mounting and vibration isolation. The maximum dimensions shall be 35 inches by 22 inches by 72 inches. The weight of the cabinet shall not exceed 400 pounds, including the interconnecting cables, bottom shock mounts, and bottom frame.

3.3.4 Acoustic Environment - The Cabinet shall provide protection for satisfactory operation of the contained Electronic Units in an acoustic noise environment of 90 decibels (dB) referenced to a 0.0002 microbar level.

3.4 Detail Requirements

3.4.1 Cabinet Frame

3.4.1.1 Function - The Cabinet Frame shall provide the means for mounting and housing the individual units of the RF Noise Analyzer, TS-2573A/AWG-10 and for supporting the Cable Harness (3.4.5). The bottom of the Frame shall provide for attachment of the bottom Shock Mounts (3.4.3).

3.4.1.2 Form Factor - The Cabinet Frame shall be a standard 19 inch frame per MIL-STD-189 and shall use slide rails to permit insertion and withdrawal of the Electronic Units. Dimensions shall not exceed 22 inches by 22 inches by 70 inches.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

3.4.1.3 Enclosure Assembly - An enclosure shall be provided to house and shield acoustically the RF Panel. The enclosure shall be a five-sided container and shall not exceed 18 inches by 15 inches by 16 inches. The front face shall be open to receive the RF Panel. Acoustic foam shall be used to cover the outside surfaces of the Enclosure Assembly and shall provide the acoustic shielding required by the RF Panel. Slide rails shall be mounted on the two inside side walls which shall permit insertion and withdrawal of the RF Panel.

3.4.1.4 Electrical Connections

3.4.1.4.1 Receptacle Strip - A Receptacle Strip shall provide ac power connection to the Converter and Analyzer Units of the Spectrum Analyzer and to the Power Meter of the Meter Panel. The Receptacle Strip shall provide two 577R831H02 duplex ac power receptacles conforming to MIL-C-3767 and shall be mounted on the right rear of the Cabinet Frame.

3.4.2 Cabinet Enclosure

3.4.2.1 Function - The Cabinet Enclosure shall consist of panels for two sides, the rear and the top of the Cabinet Frame (3.4.1) to provide physical protection to the Electronic Units.

3.4.2.2 Form Factor - The Enclosure shall be open to receive the Electronic Units. The top of the Enclosure shall include a 7.3 inch by 7.3 inch frame-mounted no. 8 mesh 0.028 diameter wire aluminum screen for ventilation and a MS3120E12-3P connector for primary power input. The Cabinet Enclosure overall dimensions, when mounted on the Cabinet Frame (3.4.1) shall not exceed 32 inches by 22 inches by 67 inches.

3.4.3 Shock Mounts

3.4.3.1 Function - Shock Mounts shall permit the Cabinet to meet the shock and vibration requirements of MIL-H-15362.

3.4.3.2 Form Factor - Six Shock Mounts shall conform to MIL-M-17508 and shall be type 579R339H01. Four Shock Mounts shall mount to the Bottom Frame (3.4.4) to provide vertical isolation. Two Shock Mounts shall mount in an assembly (Shock Mount Kit) to provide lateral isolation and stability. The assembly shall include mounting plates suitable for bolting the assembly to the right side or rear of the Cabinet and to the MCS Support Structure.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

3.4.4 Bottom Frame

3.4.4.1 Function - The Bottom Frame shall provide a means of fastening the bottom Shock Mounts (3.4.3) to the Cabinet Frame (3.4.1) and of fastening the Cabinet to adjacent bench structures. The Bottom Frame shall also serve as a support for shipping and transportation use.

3.4.4.2 Form Factor - The type 606R552G01 Bottom Frame dimensions shall not exceed 35 inches by 22 inches by 1-1/2 inches, excluding the brackets for fastening the Bottom Frame to adjacent bench structures.

3.4.5 Cable Harness

3.4.5.1 Function - The Cable Harness shall provide interconnection for the Electronic Units, when installed, and shall connect external prime power to these units.

3.4.5.2 Form Factor - The Cable Harness shall consist of trunk and branch cables containing interconnecting wiring and coaxial cabling. It shall terminate in connectors suitable for attachment to the Electronic Units.

3.4.5.3 Connections - Connections to the Electronic Units shall be provided as listed in table 1.

TABLE 1

| Connector | Receptacle | Function |
|---|---|---|
| 53A1P1 | 577R590H36 | Meter Panel Power and Signal Input |
| 53A1P2 | 577R569H01 | Meter Panel Deviation Signal Input |
| 53A1P4 | 577R569H01 | Meter Panel Deviation Output |
| 53A1P5 | 577R569H01 | Meter Panel 30 mc Calibration Output |
| 53A1P7 | 577R569H01 | Meter Panel Video Cal |
| 53A3P2 | 577R569H01 | SA Analyzer Unit Signal Input |
| 53A4P2 | 575R516H03 | SA Filter Unit Noise Voltage Output |
| 53A5P1 | 577R590H27 | Electronics Drawer Power Input |
| 53A5P2 | 579R831H01 | Electronics Drawer 30 mc Output |
| 53A5P3 | 579R831H01 | Electronics Drawer Phase Detector Current Measure |
| 53A5P4 | 579R831H01 | Electronics Drawer Deviation Signal Measure |



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

TABLE I (Continued)

| Connector | Receptacle | Function |
|---|---|---|
| 53A5P5 | 579R831H01 | Electronics Drawer 30 mc Input |
| 53A5P6 | 579R831H01 | Electronics Drawer AM Detector Current Measure |
| 53A5P7 | 579R831H01 | Electronics Drawer Signal Output |
| 53A5P8 | 579R830H01 | Electronics Drawer FM Signal Input |
| 53A5P9 | 579R830H01 | Electronics Drawer AM Signal Input |
| 53A5P10 | 579R831H01 | Electronics Drawer Frequency Discriminator Output |
| 53A5P11 | 579R831H01 | Electronics Drawer 30 cps Output |
| 53A5P12 | 577R590H41 | Electronics Drawer Signal/Control |
| 53A5P19 | 579R831H01 | Electronics Drawer Deviation Loop Input |
| 53A6P1 | 579R114H02 | RF Panel AM Preamplifier Output |
| 53A6P2 | 577R569H01 | RF Panel AM Detector Current Output |
| 53A6P5 | 577R569H01 | RF Panel 30 mc Input |
| 53A6P7 | 577R590H36 | RF Panel Signal Ground Input |
| 53A6P8 | 577R590H10 | RF Panel Control Signal Input |
| 53A6P9 | 577R569H01 | RF Panel Phase Detector Current Output |
| 53A6P10 | 579R114H02 | RF Panel FM Output |
| 53A6P11 | 577R569H01 | RF Panel 30 cps Input |
| 53A6P12 | 577R569H01 | RF Panel FM Preamp Video Cal Output |
| 53A7P1 | 577R590H45 | Power Supply (PS) Power and Signal Output |
| 53A7P3 | 577R569H01 | PS Deviation Input |
| 53A7P4 | 577R569H01 | PS Deviation Signal Output |
| 53A7P5 | 577R569H01 | PS Deviation Loop AFC Output |
| 53A11P1 | 577R831H02 | Meter Panel Power Meter Power Input |
| 53A11P2 | 577R831H02 | SA Analyzer Power Input |
| 53A11P3 | 577R831H02 | SA Converter Unit Power Input |



Source: https://assist.dla.mil -- Downloaded: 202610-26T04:35Z
Check the source to verify that this is the current version before use.

## 4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Classification of Tests - Items covered by this specification shall be subjected to the following tests to determine compliance with all applicable requirements:

(a) Preproduction Tests

(b) Production Sample Tests

(c) Acceptance Tests

4.2 Preproduction Tests - Preproduction tests shall be made on an equipment representative of the production equipments to be supplied under the contract. Preproduction tests shall consist of the following:

(a) Contractor Demonstration Tests

(b) Service Approval Tests

4.2.1 Contractor Demonstration Tests - Contractor demonstration tests shall be accomplished under the responsibility of the contractor and shall be conducted in accordance with the approved test procedure of (4.5). The Government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the service of a commercial testing laboratory satisfactory to the procuring activity.

4.2.2 Service Approval Tests - At the completion of the contractor's demonstration test and when requested by the procuring activity the equipment shall be delivered to the Government for additional testing. This additional testing may consist of duplicating tests previously conducted and such other tests as are deemed necessary to determine compliance with all applicable design and performance requirements.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

4.2.3 Scope of Tests - Preproduction tests shall include all tests necessary to determine that the equipment meets all the requirements of this specification and the contract. Preproduction tests shall include environmental testing in accordance with procedures of MIL-T-5422 with test limits modified to correspond with the limits specified herein.

4.2.4 Preproduction Approval - Approval of the preproduction models shall be by the Naval Air Systems Command upon satisfactory completion of all tests. All preproduction models, except those consumed in testing or those rendered irrepairable for their intended use, shall be returned to the Contractor for his use in the fabrication and testing of equipment to be submitted for acceptance. The preproduction models shall not be considered as equipments under this contract; however, such models may be reworked and submitted for acceptance as production equipments. Incorporation of design changes, in delivered production equipments, found to be necessary as a result of the preproduction test program, shall be the subject of separate and independent negotiations on an individual basis.

4.3 Acceptance Tests - The Contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the Government Inspector. Contractors not having testing facilities satisfactory to the procuring activity shall engage the service of a commercial testing laboratory acceptable to the procuring activity. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of acceptance of the finished products. Acceptance tests shall consist of the following:

(a) Individual Tests

(b) Sampling Tests

(c) Special Tests

4.3.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the invidual tests. These test shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability. As a minimum, each equipment accepted shall have passed the following tests;

(a) Examination of Product

(b) Operational Tests

(c) Reliability Test



Source: https://assist.dla.mil -- Downloaded: 202610-26T04:35Z
Check the source to verify that this is the currentversion before use.

4.3.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material, workmanship and interchangeability requirements have been met.

4.3.1.2 Operational Test - Each equipment shall be operate long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

4.3.1.3 Reliability Test - Each equipment shall be operated for a period of 6 hours without failure, under the conditions specified herein. Only those adjustments will be permitted which can be made by using such controls and adjustments as are accessible to the operator during the normal use of the equipment.

| | |
|---|---|
| Temperature | Room Ambient |
| Humidity | Room Ambient |
| Vibration (10 minutes) | Any selected frequency within the range of 20 to 30 cps (excluding resonant points) and a minimum double amplitude of 0.036 inch. |

The equipment shall be vibrated (without vibration isolators between the equipment and test fixtures) for a period of 10 minutes prior to the beginning of the 6-hour period of operation. Where feasible, the equipment shall be operated during this vibration period for the purpose of detecting flaws and imperfect workmanship. Operation within the specified limits of satisfactory performance is not necessarily required during the vibration period. The direction of vibration should be vertical to the normal mounting plane for 5 minutes and lateral to that plane for 5 minutes. Where it is not feasible to vibrate the equipment in 2 directions the vertical direction shall be used. During the 6-hour period of operation following the 10-minute vibration period, the equipment shall be cycled periodically through its phases of operation. Should a failure occur, it should be repaired and tests started over, except the 10-minute vibration period need not be repeated when it is certain the failure was not a result of the vibration. Should repetitive failures occur, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures. The 6-hour period specified above may be composed of two 3-hour periods to conform with standard working hours.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

4.3.2 Sampling Tests - Sampling tests shall be conducted on complete equipments which have successfully passed the individual tests. The following equipments shall be selected for Sampling tests:

| Quantity of Equipments Offered for Acceptance | Quantity to be Tested |
|---|---|
| First 10 | 1 |
| 11 to 100 | 2 additional |
| 101 to 200 | 1 additional |
| Over 200 | 1 for each additional 200 or fraction thereof |

4.3.2.1 Scope of Tests - As a minimum, each equipment selected for sampling tests shall be subjected to the following tests after successful completion of the tests of 4.3.1.

(a) Complete operational tests at ambient room conditions making all necessary measurements to assure that all applicable specification requirements have been met.

(b) Operational test at environmental conditions when the results from the preproduction test indicate that these environmental conditions cause degradation(s) which result in marginal or unsatisfactory performance.

4.3.3 Special Tests - Special tests shall be conducted on a quantity of equipments for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the sampling tests.

4.3.3.1 Special Test Schedule - Selection of equipments for special tests shall be made as follows:

(a) On an early production equipment.

(b) On an equipment midway of the production run.

(c) On an early equipment after an extensive engineering change.

(d) When failure reports or other information indicate additional equipment should be tested. (This will be determined by the procuring activity.)



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

Exceptions from the above may be necessary when the number of equipments procured under contract or other factors affecting performance may require a variation to assure satisfactory control. The maximum number of special tests shall be defined by the procuring agency at the time of request for bids.

4.3.3.2 Scope of Test - Special tests shall consist of such tests as are selected by the procuring activity. Test procedures previously approved for the preproduction and sampling tests shall be used where applicable. As a minimum, the following tests shall be made, except that for those equipments selected as a result of design changes and failure reports, only such tests required to check the characteristics in question need be conducted:

(a) Temperature - Altitude Tests

(b) Vibration Tests (90 minutes cycling in each of 3 planes)

(c) Humidity Tests

4.3.4 Equipment Failure - Should a failure occur during either the sampling or special tests, the following action shall be taken:

(a) Determine the cause of failure

(b) Determine if the failure is an isolated case or design defect.

(c) Where practical, include a test in the individual test to check all equipment for this requirement until assurance is obtained that the defect has been satisfactorily corrected.

4.4 Life Test - A 300-hour life test shall be conducted at the contractor's plant on an early equipment representative of current production. The life test shall be performed under the conditions specified in 4.4.1. The life tests sample shall be selected by the Government Inspector in accordance with the following: (Equipments which have successfully passed the sampling tests or special tests may be selected for life tests.)

| Quantity of Equipments Offered for Acceptance | Quantity to be Tested |
|---|---|
| First 25 | 1 |
| 26 - 200 | 1 additional |
| 201 - 500 | 1 additional |
| Over 500 | 1 for each additional 500 or fraction thereof. |



Source: https://assist.dla.mil -- Downloaded: 20261O-26T04:35Z
Check the source to verify that this is the current version before use.

4.4.1 Test Conditions - The life test shall be conducted under the following conditions:

| | |
|---|---|
| Temperature | Room Ambient |
| Altitude | Normal Ground |
| Humidity | Room Ambient |

4.4.2 Test Periods - The test may be run continuously or intermittently. Any period of operation shall be of sufficient duration to permit the equipment temperature to stabilize. Periodically, the equipment shall be turned on and off and put through its various phases of operation.

4.4.3 Performance Check - At approximately 8-hour intervals during the test, a limited performance check shall be made. The performance check proposed by the contractor shall be subject to approval by the procuring activity.

4.4.4 Reconditioning of Life Test Sample - An equipment which has been subject to the life test shall be reconditioned as follows:

(a) On completion of the life test, the equipment shall be reworked by the contractor by replacing all "wear" items. The "wear" items shall be determined by agreement between the contractor and the procuring activity.

(b) After reworking, the contractor shall resubmit the equipment for acceptance.

4.5 Test Procedure - Preproduction test, acceptance tests and life tests shall be performed in accordance with a test plan and procedures mutually agreeable to the procuring activity and the contractor. The test plan shall be prepared by the contractor. MIL-T-18303 shall be used as a guide for preparation of test procedures. When approved procedures are available from previous contracts, the procuring activity will furnish the procedures to be used for testing.

4.6 Presubmission Testing - No item, part or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply to the best of his knowledge and belief, with all applicable requirements.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

4.7 Rejection and Retest - Equipment which has been rejected may be reworked or have parts replaced to correct the defects and be resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejection and the action taken to correct the defects found in the original shall be furnished the Government Inspector. Units rejected after retest shall not be resubmitted without the specific approval of the procuring activity.

4.8 Equipment Changes - After approval of the preproduction model, no changes which might affect weight, installation interchangeability or interchangeability of maintenance parts of assemblies shall be incorporated in the equipment unless approved by the procuring activity. To obtain procuring activity approval, the Contractor shall submit an Engineering Change Proposal (ECP) giving the necessary information concerning the change. This shall apply for either a procuring activity recommended change or a contractor's proposed change. When required, the contractor shall also prepare a Material Change (MC) and a Material Bulletin (MB) to cover the approved change. Engineering Change Proposals, Material Changes and Material Bulletins shall be prepared in accordance with MIL-T-23336.

## 5. PREPARATION FOR DELIVERY

5.1 General - All major units and parts of equipment shall be preserved, packaged, packed and marked for the level of shipment specified in the contract or order in accordance with MIL-E-17555.

## 6. NOTES

6.1 Ordering Data - Purchasers should exercise any desired options offered herein and procurement documents should specify the following:

(a) Title, Number, and date of this specification.

(b) Selection of applicable levels of packaging and packing (see 5.1).

6.1.1 Electronic Units, RF Noise Analyzer, 411R684G01 - This term shall apply to the following combination of units:

(a) Electronics Drawer, 610R786G01

(b) Power Supply Drawer, 610R782G01

(c) Meter Panel, 610R787G01

(d) RF Panel, 653R219G01



Source: https://assist.dla.mil -- Downloaded: 20261O-26T04:35Z
Check the source to verify that this is the current version before use.

(e) Spectrum Analyzer, 616R183G01

(f) IF Unit, 616R184G01

(g) Converter, 616R185G01

(h) Panel, 507R926G01

(i) Thermistor Mount, 579R284H02

(j) Mixer-Preamplifier, 610R437G01

6.2 Precedence of Documents - When the requirements of the contract, this specification, or applicable subsidiary specifications are in conflict, the following precedence shall apply:

(a) Contract - The contract shall have precedence over any specifications.

(b) This Specification - This specification shall have precedence over all applicable subsidiary specifications. Any deviation from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

(c) Referenced Specifications - Any referenced specification shall have precedence over all applicable subsidiary specifications referenced specifications shall apply to the extent specified.

6.3 Notation of Revisions - A bar in the margin denotes a change made in that paragraph from the previous version of the document. This has been done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in those notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content as written irrespective of the marginal notations and relationship to the last previous issue.

6.4 Availability of Documents - When requesting specifications, standards, drawings, and publications refer to both title and number. Copies of this specification and applicable specifications required by contractors in connection with specific procurement functions may be obtained upon application to the Commanding Officer, Naval Supply Depot, Code 105, 5801 Tabor Avenue, Philadelphia, Pennsylvania 19120.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

TABLE OF CONTENTS


| | Page |
|---|---|
| 1. SCOPE | 1 |
| 1.1 Scope | 1 |
| 1.2 Classification | 1 |
| 1.3 Associated Equipment | 1 |
| 2. APPLICABLE DOCUMENTS | 1 |
| 2.1 General | 1 |
| 2.1.1 Availability of Documents | 3 |
| 3. REQUIREMENTS | 3 |
| 3.1 Parts and Materials | 3 |
| 3.1.1 Nonstandard Parts | 4 |
| 3.1.2 Noncorrosive Hardware | 4 |
| 3.2 Design and Construction | 4 |
| 3.2.1 Total Weight | 4 |
| 3.2.2 Cables and Connectors | 4 |
| 3.2.3 Interchangeability | 4 |
| 3.2.4 Standard Conditions | 4 |
| 3.2.5 Service Conditions | 5 |
| 3.2.6 Nomenclature and Nameplates | 5 |
| 3.3 Performance | 5 |
| 3.3.1 General | 5 |
| 3.3.2 Function | 5 |
| 3.3.3 Form Factor | 5 |
| 3.3.4 Acoustic Environment | 5 |
| 3.4 Detail Requirements | 5 |
| 3.4.1 Cabinet Frame | 5 |
| 3.4.1.1 Function | 5 |
| 3.4.1.2 Form Factor | 5 |
| 3.4.1.3 Enclosure Assembly | 6 |
| 3.4.1.4 Electrical Connections | 6 |
| 3.4.1.4.1 Receptacle Strip | 6 |
| 3.4.2 Cabinet Enclosure | 6 |
| 3.4.2.1 Function | 6 |
| 3.4.2.2 Form Factor | 6 |
| 3.4.3 Shock Mounts | 6 |
| 3.4.3.1 Function | 6 |




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

Page

3.4.3.2 Form Factor . . . . . 6
3.4.4 Bottom Frame . . . . . 7
3.4.4.1 Function . . . . . 7
3.4.4.2 Form Factor . . . . . 7
3.4.5 Cable Harness . . . . . 7
3.4.5.1 Function . . . . . 7
3.4.5.2 Form Factor . . . . . 7
3.4.5.3 Connections . . . . . 7
4. QUALITY ASSURANCE PROVISIONS . . . . . 9
4.1 Responsibility for Inspection . . . . . 9
4.1.1 Classification of Tests . . . . . 9
4.2 Preproduction Tests . . . . . 9
4.2.1 Contractor Demonstration Tests . . . . . 9
4.2.2 Service Approval Tests . . . . . 9
4.2.3 Scope of Tests . . . . . 10
4.2.4 Preproduction Approval . . . . . 10
4.3 Acceptance Tests . . . . . 10
4.3.1 Individual Tests . . . . . 10
4.3.1.1 Examination of Product . . . . . 11
4.3.1.2 Operational Test . . . . . 11
4.3.1.3 Reliability Test . . . . . 11
4.3.2 Sampling Tests . . . . . 12
4.3.2.1 Scope of Tests . . . . . 12
4.3.3 Special Tests . . . . . 12
4.3.3.1 Special Test Schedule . . . . . 12
4.3.3.2 Scope of Test . . . . . 13
4.3.4 Equipment Failure . . . . . 13
4.4 Life Test . . . . . 13
4.4.1 Test Conditions . . . . . 14
4.4.2 Test Periods . . . . . 14
4.4.3 Performance Check . . . . . 14
4.4.4 Reconditioning of Life Test Sample . . . . . 14
4.5 Test Procedure . . . . . 14
4.6 Presubmission Testing . . . . . 14
4.7 Rejection and Retest . . . . . 15
4.8 Equipment Changes . . . . . 15
5. PREPARATION FOR DELIVERY . . . . . 15
5.1 General . . . . . 15
6. NOTES . . . . . 15
6.1 Ordering Data . . . . . 15
6.1.1 Electronic Units, RF Noise Analyzer, 411R702 . . . . . 15



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

Page

6.2 Precedence of Documents . . . . . 16
6.3 Notation of Revisions . . . . . 16
6.4 Availability of Documents . . . . . 16



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.