MILITARY SPECIFICATION

Simulator, Radar Beacon SM-658/APM

This specification has been approved by the Naval Air Systems Command, Department of the Navy

1. SCOPE

1.1 Scope - The equipment covered by this specification shall be used for organizational level testing of the Radar Receiver R-1623/APN Automated Carrier Landing System (ACLS).

1.2 Classification - The equipment covered by this specification shall consist of the following items:

Type Designation	Applicable Paragraph
Simulator Assembly	3.5.1
Transit Case	3.5.2
Power Cable	3.5.3
Video Cable	3.5.3
Trigger Cable	3.5.3

1.3 Associated Equipment - This equipment shall operate with the following associated equipment.

AN/APM-230B Test Set, Radar Beacon

2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the date of invitation for bids form a part of this specification to the extent specified herein:

FSC-6625

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:38Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

Military

MIL-T-5422	Testing, Environmental, Aircraft Electronic Equipment
MIL-E-17555	Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of
MIL-T-18303	Test Procedures; Preproduction and Inspection, for Aircraft Electronic Equipment, Format for
MIL-N-18307	Nomenclature and Nameplates for Aeronautical Electronic and Associated Equipment
MIL-T-21200	Test Equipment for Use with Electronic and Fire Control Systems, General Specification for

STANDARDS

Military

MIL-STD-461	Electromagnetic Interference Characteristics, Requirements for Equipment
MIL-STD-462	Electromagnetic Interference Characteristics, Measurement of
MIL-STD-463	Definitions and Systems of Units, Electromagnetic Interference Technology.

Naval Air Systems Command

AR-5	Microelectronic Devices Used in Avionics Equipment, Procedures for Selection and Approval of	(3.3.2)

2.1.1 Availability of Documents -

(1) When requesting specifications, standards, drawings, and publications, refer to both title and number. Copies of this specification and applicable specifications required by contractors in connection with specific procurement functions may be obtained upon application to the Commanding Officer, Naval Supply Depot, Code 105, 5801 Tabor Avenue, Philadelphia, Pennsylvania, 19120.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:38Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Production - This specification makes provision for preproduction testing.

3.2 Parts and Materials - In the selection of parts and materials, fulfillment of major design objectives shall be the prime consideration. In so doing the following shall govern:

(1) Parts and materials requirements shall conform to Specification MIL-T-21200.

(2) Nonrepairable subassemblies, as outlined in Specification MIL-T-21200, shall be used when practicable. The general size of the subassembly and the amount of circuitry to be included therein shall be approved by the procuring activity. Nonrepairable subassemblies must be reliable. (See 6.3.1)

(3) When previously produced models of this equipment did not use nonrepairable subassemblies, the design shall not be changed to employ nonrepairable assemblies without the approval of the procuring activity.

3.2.1 Nonstandard Parts and Materials Approval - Approval for the use of nonstandard parts and materials other than microelectronic devices shall be obtained as outlined in Specification MIL-T-21200.

3.2.2 Microelectronic Items - When used, microelectronic items shall be in accordance with AR-5.

3.3 Design and Construction - The equipment shall conform with all the applicable requirements of Specification MIL-T-21200, for design, construction, and workmanship to the extent specified herein.

3.3.1 Total Weight - The total weight of the equipment shall be a minimum consistent with good design and shall not exceed the weight listed below.

Radar Beacon Simulator	- 6 pounds
Transit Case	- 9 pounds
Cables	- 2 pounds

3.3.2 Reliability -

3.3.2.1 Operational Stability - The equipment shall operate with satisfactory performance, continuously or intermittently, for a period of at least 200 hours without the necessity for

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:38Z
Check the source to verify that this is the current version before use.

readjustment of any controls which are inaccessible to the operator during normal use.

3.3.2.2 Operating Life - The equipment shall have a minimum total operating life of 5000 hours with reasonable servicing and replacement of parts. Parts requiring scheduled replacement due to wear during the life of the equipment, and the wearout life of such parts, shall be specified by the contractor.

3.3.3 Cables and Connectors - The equipment shall provide for the use of cables and connectors in accordance with Specification MIL-T-21200. Insofar as is practicable, all connectors on the front panel shall be mounted such that the connecting cables will not interfere with the operating controls. Permanently numbered wires may be used in lieu of color coding.

3.3.3.1 Cable Assemblies, Power Electrical - Applicable input power cable and connections are listed in 3.5.3.

3.3.4 Interchangeability - The equipment shall meet the interchangeability requirements as defined in Specification MIL-T-21200.

3.3.5 Interference Control - The generation of radio interference by the equipment and the vulnerability of the equipment to radio interference shall meet the requirements of MIL-STD-461.

3.3.6 Maintenance Provisions and Field Testing - Provisions for maintenance shall be as specified in MIL-T-21200.
Specific test points and test facilities shall be provided to the greatest extent practicable for ease of field testing and maintenance.

3.3.7 Nomenclature and Nameplates - Nomenclature assignment and nameplate approval for equipment identification shall be in accordance with Specification MIL-N-18307.

3.3.8 Standard Conditions - The following conditions shall be used to establish normal performance characteristics under standard conditions and for making laboratory bench tests.

Temperature	Room ambient ($30^{o} \pm 10^{o}C$)
Altitude	Normal ground
Vibration	None
Humidity	Room ambient
Input power voltage	28 $\pm$1 VDC

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:38Z
Check the source to verify that this is the currentversion before use.

3.3.9 Service Conditions - The equipment shall operate satisfactorily under any of the environmental service conditions or reasonable combination of these conditions as specified in MIL-T-21200 for class 2 equipment.

3.3.10 Warm-up Time - The time required for the equipment to warm-up prior to operation shall be kept to a minimum and shall not exceed 10 minutes under standard conditions and 20 minutes at extreme service conditions.

3.3.11 Primary Input Power Requirements - The equipment shall be capable of satisfactory operation when supplied input power having characteristics as defined in Specification MIL-T-21200. The power required shall be of the following type: 27 ± 2 Vdc.

3.4 Performance - The performance of the equipment shall be as set forth in paragraph 3.5. Unless otherwise specified, these requirements shall apply under both standard and extreme service conditions. When reduced performance requirements for service conditions are acceptable, such variations will be specified.

3.5 Detail Requirements - The equipment shall meet the following requirements.

3.5.1 Radar Beacon Simulator Assembly -

3.5.1.1 Function - The equipment covered by this specification shall be used in conjunction with the AN/APM-230B for flight line confidence tests on the airborne portion of the Automated Carrier Landing System (ACLS). It receives primary power, synchronizing triggers, and video representative of the beacon replies from the AN/APM-230B. K_a-band pulses generated by the equipment actuate the R-1623/APN receiver from the ACLS. Circuitry within the equipment processes the received video from the AN/APM-230B and checks any amplitude modulation on the pulse train for amplitude and phase.

3.5.1.2 Electrical Requirements -

3.5.1.2.1 DC Power - The input dc power current drain shall be no greater than 350 milliamps. Electrical overload protection is supplied by the associated equipment.

3.5.1.2.2 RF Power - The rf power output shall be -26 ± 5 dBm peak as measured from the Radar Beacon Simulator rf output coupled into the R-1623/APN receiver antenna, AS-2406/APR.

The antenna and simulator output must be coupled to each other as they would be during normal operation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:38Z
Check the source to verify that this is the current version before use.

3.5.1.2.3 Frequency - The rf frequency shall be 33.2 ±0.2 GHz.

3.5.1.2.4 Output Pulse - The rf output pulse width shall be 200 ±500 nanoseconds with a leading edge rise time of 50 nanoseconds maximum.

3.5.1.2.5 Trigger Input - The equipment shall respond to an input trigger as specified below.

Polarity	Positive
Amplitude	3.5 volts peak minimum
Rise Time	50 nanoseconds maximum
Pulse Width	0.2 to 0.5 microseconds
Pulse Rate Frequency	2.3 ±0.2 KHz

3.5.1.2.6 Over-Interrogation - The equipment shall provide protective circuitry to limit the maximum reply frequency to 15 KHz maximum.

3.5.1.2.7 AM Modulator - The equipment shall be capable of amplitude modulating the rf output with a square wave at 100 ±30 Hz with a modulation level of 1.5 to 5.5 dB (peak-to-valley).

3.5.1.2.8 Video Processor - Video circuitry shall be provided to process video signals received at J2. These video pulses shall cause the modulation test indicator to illuminate if they have the following characteristics:

Polarity	Positive
Amplitude	1 to 5 volts
Pulse Width	0.2 to 1.0 microsecond
PRF	Same as trigger (2300 pps nominal)
Delay From Trigger	1.5 microseconds nominal
Amplitude Modulation Level	2 to 6 dB peak-to-valley
Modulation Frequency	Same as rf output amplitude modulation

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:38Z
Check the source to verify that this is the current version before use.

Modulation Phase Angle relative to the modulation on the rf output	Within ±20 degrees

3.5.1.2.9 Delay - The delay from the leading edge of the input trigger pulse at J3 and the K_a-band rf output pulses shall not exceed 200 nanoseconds.

3.5.1.3 Form Factor - The outline dimensions of Radar Beacon Simulator SM-658/APM shall not exceed the following: 10.5 x 5.5 x 3 inches.

3.5.1.4 Weight - The weight of the simulator assembly shall not exceed 6 pounds.

3.5.1.5 Contents - The simulator assembly shall contain the following subassemblies:

3.5.1.5.1 Power Supply - The power supply shall provide voltages required by the internal circuitry.

3.5.1.5.2 Video Processor - The video processor shall provide circuitry for processing the received video pulses and for generating and processing the amplitude-modulating signals.

3.5.1.5.3 K_a-Band Waveguide Assembly - This assembly shall provide circuitry to generate K_a-band output pulses for every trigger input within the limits of 3.5.1.2.5, to set the K_a-band output power, and to provide a means for amplitude modulating the rf output.

3.5.1.5 Controls - The following controls shall be provided on the front panel.

(a) PWR — Applies dc power to the Radar Beacon Simulator. Two positions are required: ON, OFF.

(b) MOD — Applies 100 Hz, amplitude modulation to the K_a-band output and to the Mod test lamp circuits. The following two positions are required: ON, OFF.

3.5.1.6 Electrical Connections - Connections to external circuits shall be provided as follows:

Designation	Receptacle Type	Function
Not assigned	Couples to the AS-2406/APR	K_a-band output

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:38Z
Check the source to verify that this is the current version before use.

Designation	Receptacle Type	Function
J1 - PWR IN	MS3114E10-6P	DC power input
J2 - VIDEO	BNC-UG912B/U	Video input
J3 - TRIG	BNC-UG912B/U	Trigger input

3.5.1.7 Indicators - The following indicators shall be provided on the front panel.

(a) PWR ON — Green lamp lights when dc power is applied to the Radar Beacon Simulator and the power switch is on.

(b) MOD TEST — Green lamp lights to indicate that video having the proper characteristics has been received at J2.

3.5.2 Transit Case - A transit case shall be provided for the protection during storage of the Radar Beacon Simulator and cables. It shall conform to the requirements of MIL-T-21200.

3.5.2.1 Form Factor - The transit case dimensions shall not exceed the following: 9.5 x 10 x 14 inches.

3.5.3 Cable Assemblies - The following cables shall be provided.

3.5.3.1 Cable Designation and Length - Cable designation, length, and function shall be as shown below.

Designation	Nominal Length (inches)	Function
W1	180	Input power cable, input from AN/APM-230B
Not assigned	180	Video Cable. Detected video input from AN/APM-230B
Not assigned	180	Trigger Cable. Trigger pulse input from AN/APM-230B

3.5.3.2 Cable Connectors - Cables listed in 3.5.3.1 shall have the following connectors or equivalents:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:38Z
Check the source to verify that this is the current version before use.

Cable Designation	P1	P2
W1	MS3116F10-6S	MS3116F10-6P
Video	MS39012/16-0001	MS39012/16-0001
Trigger	MS39012/16-0001	MS39012/16-0001

3.6 Design Data - No data is required by this specification or by applicable documents unless specified in the contract or order.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the Specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Classification of Tests - Items covered by this subjected to the following tests to determine compliance with all applicable requirements:

(1) Preproduction Tests

(2) Acceptance Tests

4.2 Preproduction Tests - Preproduction tests shall be made on an equipment representative of the production equipments to be supplied under the contract. Preproduction tests shall be accomplished under the responsibility of the contractor and shall be conducted in accordance with the approved test procedure of 4.4. The government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the services of a commercial testing laboratory acceptable to the government.

4.2.1 Preproduction Test Data - The contractor shall submit all data collected in conducting these tests to the procuring agency for review and approval.

4.2.2 Scope of Tests - Preproduction tests shall include all tests deemed necessary by the procuring activity to determine

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:38Z
Check the source to verify that this is the current version before use.

that the equipment meets all the requirements of this specification and the contract. Preproduction test shall include environmental and interference tests in accordance with the requirements of MIL-T-5422, MIL-STD-461, and MIL-STD-462 to the limits specified in Specification MIL-T-21200.

4.2.3 Preproduction Approval - Approval of the preproduction sample shall be by the procuring activity upon satisfactory completion of all tests. No production equipments shall be delivered prior to the approval of the preproduction sample. Prefabrication of production equipment prior to the approval of the preproduction sample is at the contractor's own risk.

4.2.4 Production Equipments - Equipments supplied under the contract shall in all respects, including design, construction, workmanship, performance and quality, be equivalent to the approved preproduction sample. Each equipment shall be capable of successfully passing the same tests as imposed on the preproduction sample. Evidence of non-compliance with the above shall constitute cause for rejection. For equipment already accepted by the Government, it shall be the obligation of the contractor to make necessary corrections as approved by the procuring activity.

4.3 Acceptance Tests - The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the government inspector. Contractors not having testing facilities satisfactory to the procuring activity shall engage the service of a commercial testing laboratory acceptable to the procuring activity. The contractor shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the contractor or laboratory, as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following.

(1) Individual Tests

(2) Sampling Tests

(3) Special Tests.

4.3.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy, and reliability. As a minimum, each equipment accepted shall have passed the following tests:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:38Z
Check the source to verify that this is the current version before use.

(1) Examination of Product

(2) Operational Test

(3) Manufacturing Run-In Test.

4.3.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

4.3.1.2 Operational Test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

4.3.1.3 Manufacturing Run-In Test - Each equipment shall be operated under the conditions specified herein for a period of 6 hours without failure. A failure shall be defined as anything which causes malfunctioning of the equipment. Only those adjustments will be permitted which can be made by using such controls and adjustments that are accessible to the operator during the normal use of the equipment.

Temperature	Ambient room
Humidity	Ambient room
Vibration	Any selected frequency within the range of 20 to 30 cps (excluding resonant points) and a minimum amplitude of ±3 g.

The equipment shall be vibrated (without vibration isolators) for a period of 10 minutes prior to the beginning of the 6-hour period of operation. Where feasible, the equipment shall be operated during this vibration period for the purpose of detecting flaws and imperfect workmanship. Operation within the specified limits of satisfactory performance is not necessarily required during the vibration period. The direction of vibration should be vertical to the normal mounting plane for 5 minutes, and lateral to the plane for 5 minutes. Where it is not feasible to vibrate the equipment in two directions the vertical direction shall be used. During the 6-hour period of operation following the 10-minute vibration period, the equipment shall be mechanically cycled periodically through its various phases of operation. Should a failure occur, it should be repaired and the test started over, except that the 10-minute vibration period need not be repeated when it is certain the failure was not a result of the vibration. Should repetitive failures occur, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures. The 6-hour period specified above may be composed of two 3-hour periods to conform with standard working hours.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:38Z
Check the source to verify that this is the current version before use.

4.3.2 Sampling Tests - Equipment selected for sampling tests shall first have passed the individual tests. Equipments shall be selected for sampling tests by the government inspector in accordance with the following:

Quantity of Equipments Offered for Acceptance	Quantity to be Selected For Sampling Tests
First 10	0
Next 50	1
Next 75	1
Next 100	1
1 for each additional 200 or fraction thereof.	

4.3.2.1 Scope of Tests - As a minimum, each equipment selected for sampling tests shall be subjected to the following tests:

(1) Complete operational test at ambient room conditions, making all necessary measurements to assure that all applicable specification requirements have been met.

(2) Operational test at certain environmental conditions. The conditions may vary for each equipment tested and should be based on results of the preproduction, individual, and special tests.

(3) Manufacturing run-in test specified in paragraph 4.3.1.3 except that the test duration shall be 120 hours minimum with no restriction on the number of failures. However, each failure shall be analyzed as to cause and remedial action necessary to reduce the possibility of its recurrence in future equipment.

4.3.4 Special Tests - Special tests shall be conducted on a quantity of equipments for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the sampling tests.

4.3.4.1 Special Test Schedule - Selection of equipments for special tests shall be made as follows:

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:38Z
Check the source to verify that this is the current version before use.

(1) On an early equipment after a significant engineering or material change.

(2) Whenever failure reports or other information indicate additional tests are required. (This will be determined by the procuring activity.)

4.3.4.2 Scope of Tests - Special tests shall consist of such tests as approved by the procuring activity. Test procedures previously approved for the preproduction tests shall be used where applicable. When not applicable, the contractor shall prepare a test procedure and submit it to the procuring activity for approval prior to conducting the tests.

4.3.5 Equipment Failure - Should a failure occur during either the sampling or special tests, the following action shall be taken:

(1) Determine the cause of failure

(2) Determine if the failure is an isolated case or design defect.

(3) Submit to the procuring activity for approval, proposed corrective action intended to reduce the possibility of the same failure(s) occurring in future tests.

(4) Where practical, include a test in the individual test to check all equipment for this requirement until reasonable assurance is obtained that the defect has been satisfactorily corrected.

4.4 Test Procedures - The procedures used for conducting preproduction tests and acceptance tests shall be prepared by the contractor and submitted to the procuring activity for review and approval. The right is reserved by the procuring activity or the government inspector to modify the tests or require any additional tests deemed necessary to determine compliance with the requirements of this specification and the contract. Specification MIL-T-18202 shall be used as a guide for preparation of test procedures. When approved test procedures are available from previous contracts, such procedures will be provided and may be used when their use is approved by the procuring activity. However, the right is reserved by the procuring activity to require modification of such procedures, including additional tests, when deemed necessary.

4.5 Reconditioning of Tested Equipment - Equipment which has been subjected to sampling or special tests shall be

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:38Z
Check the source to verify that this is the current version before use.

reconditioned by the contractor by replacing all wear or damaged items. After reworking, the contractor shall resubmit the equipment for acceptance.

4.6 Presubmission Testing - No item, part, or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.7 Rejection and Retest - Equipment which has been rejected may be reworked, or have parts replaced to correct the defects, and resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejection and the action taken to correct the defects found in the original shall be furnished to the government inspector.

5. PREPARATION FOR DELIVERY

5.1 General - All major units and parts of the equipment shall be preserved, packaged, packed, and marked for the level of shipment specified in the contract or order in accordance with Specification MIL-E-17555.

6. NOTES

6.1 Intended Use - The equipment covered by this specification, in conjunction with the Radar Beacon Test Set AN/APM-230B, is intended for flight line confidence tests on the airborne portion of the Automated Carrier Landing System (ACLS). When held against Antenna AS-2406/APN of Radar Receiver R-1623/APN, and when triggered by the AN/APM-230B, the equipment shall generate an amplitude/modulated Ka-band signal that stimulates the receiver. The amplitude-modulated video, resulting from X-band radar beacon replies at the AN/APM-230B "video" output and coupled to the test equipment via a coaxial cable, will cause a go indication, if the corresponding amplitude modulation on this video has the proper characteristics.

6.2 Performance Characteristics - Nominal performance characteristics shall be determined at input voltage of 27 ±1.0 Vdc. Limiting performance characteristics shall be determined at the highest and lowest values of specified input voltages. These characteristics shall be used when testing the equipment for compliance with the minimum acceptable standard of performance.

6.3 Performance Objectives - Minimum size and weight, simplicity of operation, ease of maintenance, and an improvement in the performance and reliability of the specific functions beyond the requirements of the specification are objectives which shall be considered in the production of this equipment. Where it appears, a substantial reduction in size and weight or improvement in simplicity of design, performance, ease of maintenance or reliability will result from the use of materials, parts, and processes other than those specified in Specification MIL-T-21200, it is desired that their use be investigated. When investigation

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:38Z
Check the source to verify that this is the current version before use.

shows advantages can be realized, a request for approval shall be submitted to the procuring activity for consideration. Each request shall be accompanied by complete supporting information.

6.3.1 When nonrepairable subassemblies are used, a mean-time-between-failure of more than 5000 hours should be the goal.

6.4 Precedence of Documents - When the requirements of the contract, this specification, or applicable subsidiary specifications are in conflict, the following precedence shall apply:

(1) Contract - The contract shall have precedence over any specifictiion.

(2) This Specification - This specification shall have precedence over all applicable subsidiary specifications. Any deviation from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

(3) Referenced Specifications - Any referenced specifications shall have precedence over all applicable subsidiary specifications referenced therein. All referenced specifications shall apply to the extent specified.

6.5 The parentheses (*), when used in the type designation, will be deleted or replaced by either a number or letter furnished by the procuring activity upon application by the contractor for assignment of nomenclature in accordance with 3.3.7. The complete type number shall be used on nameplates, shipping records, and instruction books, as applicable.

6.6 Ordering Data - Purchasers should exercise any desired options offered herein, and procurement documents should apecify the following:

(1) Title, number, and date of this specification.

(2) Selection of applicable levels of packaging and packing (see 5.1).

(3) Data requirements (see 3.6).

6.7 Asterisk - In specification revisions and superseding amendments, an asterisk "*" preceding a paragraph number denotes paragraphs in which changes have been made from the previous issue. This has been done as a convenience only and the government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:38Z
Check the source to verify that this is the current version before use.

evaluate the requirements of this document based on the entire content as written, irrespective of the asterisk notations and relationship to the last previous issue.

6.8 Associated Equipment - The equipment shall operate with the following associated equipment: Test Set, Radar Beacon AN/APM-230B.

Project No. 6625-N585

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:38Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

MIL-S-81923(AS) SIMULATOR, RADAR BEACON SM-658/APM

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

S/N-0102-014-1801 C-25254

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:38Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY
Naval Air Systems Command
Washington, D.C. 20361

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

NAVAL AIR SYSTEMS COMMAND (AIR-52021)
DEPARTMENT OF THE NAVY
WASHINGTON, D.C. 20361

FOLD

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:38Z
Check the source to verify that this is the current version before use.