MIL-C-14906A (MU)
25 NOVEMBER 1970
SUPERSEDING
MIL-C-14906 (MU)
24 July 1968

MILITARY SPECIFICATION

CDU-4/B and CDU-14/B

LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the loading, assembling and packing for one type of canister designated as CDU-4/B and CDU-14/B.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-A-2550	-	Ammunition and Special Weapons, General Specification for
MIL-R-11470	-	Radiographic Inspection, Qualification Of Equipment, Operators and Procedures
MIL-I-45607	-	Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109	-	Quality Assurance Terms and Definitions
MIL-STD-1168	-	Lot Numbering of Ammunition
MIL-STD-1235	-	Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

MIL-STD-1167 - Ammunition Data Cards

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

F9228097 - CDU-4/B
F9234270 - CDU-14/B
F9227366 - Packing and Marking for Kit, Mine, Canister: CDU

PUBLICATIONS

ARMY

ET-9234270 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

2.2 Other publications.-The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall apply.

CODE OF FEDERAL REGULATIONS

49 CFR 71-78 - Interstate Commerce Commission Rules and Regulations for the Transporation of Explosives and Other Dangerous Articles

(The Interstate Commerce Commission Regulations are now a part of the Code of Federal Regulations (1949 Edition and revisions) available from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402. Orders for the above publications should cite "49 CFR 71-78 (latest revision)".)

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and specifications.

3.2 Parts.-The parts shall comply with all requirements specified on Drawing (dwg.) 9234270 or 9228097 as applicable,

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

all associated drawings, and with all requirements specified in applicable specifications.

3.3 Electrical continuity of liquid level sensor, prior to loading.-The liquid level sensor shall have electrical continuity of no more than .15 ohms resistance from pin E to pin H of the connector when the float is in its uppermost vertical position. The continuity and resistance (pin E to pin H) shall be continuous during the downward travel of the float for .062" minimum. After the float has dropped at least .062" from its uppermost position and before it reaches its bottom most position, the sensor shall show continuity of no more than .15 ohms resistance from pin E to pin D of the connector. The continuity and resistance (pin E to pin D) shall be continuous for the remaining float drop. As the float rises and before it reaches .062" from its uppermost position, the sensor shall again shown continuity of no more than .15 ohms resistance from pin E to pin H. The continuity and resistance (pin E to pin H) shall be continuous as the float rises to its uppermost position. At no time shall there be simultaneous continuity of both pin E to pin H and pin E to pin D. The resistance of each open circuit shall be tested and must be greater than 1 megohm.

3.4 Shunt verification of explosive opener fixed delay assembly (dwg. 9233359).-There shall be electrical continuity and no more than 0.3 ohms resistance measured at the termination of the detonator leads.

3.5 Electrical continuity, resistance and shorts of the cable assembly (dwg. 9223682) (Prior to Loading).-There shall be continuity and no more than 0.1 ohm resistance between each pair of wired contacts of the cable assembly. There shall also be a minimum of 10 megohms resistance between each wire and all other wires of the P1 connector.

3.6 Functioning of the electronic opener assembly (dwg. 9227463) (prior to loading)

3.6.1 Minimum time delay.-The opener shall show a time delay of 1.25 seconds $\pm$ 0.25 seconds before exhibiting an output pulse.

3.6.2 Maximum time delay.-The opener shall show a time delay of 24.00 seconds $\pm$ 2.40 seconds before exhibiting an output pulse.

3.6.3 Output.-The opener shall exhibit a minimum output of one (1) volt for one hundred (100) microseconds measured across a two (2) ohm + 0.20 ohm load.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

3.7 Continuity and resistance of the opener switch assembly (dwg. 9227439) prior to loading

3.7.1 With switches in normally closed (relaxed) position.- The opener switch assembly shall show evidence of continuity and no more than 10.0 ohms resistance between the B pin of the connector and the terminal closest to the chamfered edge of the plug (blue wires) and between pin D of the connector and the terminal farthest from the chamfered edge of the plug (yellow wires). There shall also be no more than 0.5 ohm resistance between pin C of the connector and the pin receptacle (black wires).

3.7.2 With switches actuated.-There shall be less than 600 K ohms between pin C of the connector and the terminal closest to the chamfered edge of the plug and less than 60 K ohms between pin C of the connector assembly and the terminal farthest from the chamfered edge of the plug. A maximum force of 1000 grams shall be applied to the switch plungers to cause them to actuate.

3.8 Continuity of the electrical circuits of the loaded canister assembly.-This test shall be performed after assembly and re-torquing of the retention rod nuts. There shall be continuity between the following points:

a. Pin 4 and Pin 5 of the P1 connector.
b. Pin 7 of the P1 connector and the electronic opener mounting plate.
c. There shall be less than 600 K ohms resistance between the opener mounting plate and the terminal closest to the chamfered edge of the opener switch assembly plug.
d. There shall be less than 60 K ohms resistance between the opener mounting plate and the terminal farthest from the chamfered edge of the opener switch assembly plug.

There shall be no continuity between the following points:

e. Pin 6 of the P1 connector and the terminal closest to the chamfered edge of the opener switch assembly plug.
f. Pin 8 of the P1 connector and the terminal farthest from the chamfered edge of the opener switch assembly plug.

For purposes of this requirement, no continuity shall mean a resistance greater than 10 megohms.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

3.9 Freon leakage.-The loaded and sealed canister shall exhibit no freon leakage in excess of 1.0×10^{-3} cc/sec.

3.10 X-ray of loaded canister assembly

3.10.1 Freon level.-The freon level in the loaed and sealed canister when in an upright position shall be as specified on dwg. 9234965 when measured from the top of the canister. The point on the top of the canister at which the freon level is to be measured from shall be a point 9" from the aft end of the canister.

3.10.2 Mines above spacer or in EOD area.-The loaded and sealed canister shall not show evidence of mines closer than 1.25 inches from the top of the canister at the end marked for EOD (aft), or mines positioned horizontally on top of either spacer.

3.11 Electrical continuity of loaded container.-The loaded container shall show evidence of electrical continuity when tested through the monitor and ready connector (P2 connector). and as specified in 4.4.9.

3.12 Proving ground.-The loaded canister assembly shall be subjected to the following proving ground tests (see 6.4).

3.12.1 Static functioning.-The loaded canister assembly when conditioned to 120°F shall not detonate, lose any freon or suffer any permanent damage. Upon completion of this test, the canister shall be statically functioned as specified in 4.4.10. The following information shall be recorded for each test (see 6.4):

a. Canister lot number
b. Type of malfunction
c. Number of mines detonating on impact
d. Number of mines damaged

3.12.2 Vibration.-The loaded and completely assembled canister when conditioned to 120°F. and vibrated as specified in 4.4.10 shall not detonate, lose any freon or suffer any permanent damage. Upon completion of this test, static functioning of the canister shall be conducted as specified in 4.4.10. The following information shall be recorded for each test. (See 6.4):

a. Canister lot number
b. Type of malfunction
c. Number of mines detonating on impact
d. Number of mines damaged.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

3.12.3 Flight test.-The loaded canister assembly when assembled to its proper dispenser and mounted to a suitable aircraft in flight shall release freely from the dispenser without damage to any of its components, after which the canister shall break open in the time frame specified by the design agency, spilling its contents. There shall be no damage to or detonation of the mines during the breaking of the canister or upon impact with the ground. The following information shall be recorded for each flight test. (See 6.4)

a. Canister lot number.
b. Type of malfunction.
c. Number of mines detonating on impact.
d. Aircraft speed and ejection altitude.

3.13 Workmanship.-All parts and assemblies shall be fabricated, loaded and assembled in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, grease, rust and other foreign matter. The cleaning method used shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agents. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

3.14 Submission of results of contractor-conducted examinations and tests.-The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract. (See 6.4)

3.15 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

3.16 Tension verification of strapping machine.-Dynamometer load shall be no less than 140 pounds, when tested as specified in 4.3.3.11. (Stall reading, prior to engaging weld lever, shall not exceed 250 pounds).

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Military Standard MIL-STD-109 in order to define terms used herein. The provisions of Military Specification MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified within this specification.
b. Number of units of product inspected.
c. Results obtained, by defect code, for all inspections performed.
d. Drawing, specification number and date, together with an identification and date of changes.
e. Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.
f. Number of items in the lot.
g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a sample of forty (40) loaded canister assemblies to a Government proving ground designated by the Contracting Officer for testing in accordance with the provisions of 4.2.2 (see 6.1). All parts and material shall be the same as will be used in production and shall be obtained from the same source of supply. Prior to submission, the sample shall be inspected by the contractor to the degree necessary to assure that it conforms to the requirements of the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

4.2.2 Inspections to be performed.-Assemblies will be subjected by the Government to the following tests:

4.2.2.1 Freon leakage.-The forty (40) loaded canisters shall be subjected to this test. The test shall be performed as specified in 4.4.6.

4.2.2.2 X-ray of loaded canister assembly.-The forty (40) loaded canisters shall be subjected to this test. The test shall be performed as specified in 4.4.7.

4.2.2.3 Proving ground tests.-After completion of tests specified in 4.2.2.1 and 4.2.2.2, the loaded canisters of the quantity indicated below shall be subjected to these tests. The tests shall be performed in accordance with the test paragraph specified below:

Test	Quantity	Test Procedure Para.
Static functioning	15	4.4.10
Vibration	15	4.4.10
Flight	10	4.4.10

4.2.3 Rejection.-If any assembly or component fails to comply with any of the applicable requirements, the first article quantity shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity or portion thereof. Until a first article quantity is accepted, the contractor is in no way authorized by the Government to resume regular production unless directed by the Contracting Officer.

4.3 Inspection Provisions

4.3.1 Lot formation.-The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, specification or revision thereof.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

Changes to either the process, specification or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of the lot. The lot shall comply with MIL-STD-105 and shall be numbered in accordance with MIL-STD-1168. Unless otherwise approved by the Contracting Officer, the inspection lot size of major assemblies or end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period, nor more than the largest quantity contractually scheduled for delivery during any month of the contract period. Inspection lots for components or sub-assemblies, other than the items of delivery, shall be homogeneous and of a size mutually convenient to both the contractor and the Government inspector. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each lot shall contain:

a. Mines of one lot interfix number from one manufacturer.
b. Canister (metal parts) of one lot interfix number from one manufacturer.
c. Explosive opener fixed delay assemblies of one lot interfix number from one manufacturer.
d. Electronic openers and switch assemblies of one lot interfix number from one manufacturer.
e. Liquid level sensors of one lot interfix number from one manufacturer.

4.3.2 Examination.-Sampling plans and procedures for the following classifications of defects shall be in accordance with Military Standard MIL-STD-105 (ABC-STD-105), except that inspection for Critical defects shall be 100 percent. Contractor's sampling plans, if used shall be approved by the Government and shall provide, as a minimum, the protection afforded the Government by the sampling plans in Military Standard MIL-STD-105 (ABC-STD-105). Continuous sampling plans in accordance with Military Standard MIL-STD-1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each Major defect and an AQL of 0.65 percent for each Minor defect except where 100 percent inspection is specified. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

4.3.2.1 CDU-4/B and CDU-14/B, during loading and prior to sealing (see dwg. 9234270)

Categories	Defects	Method of Inspection	Defect Code
Critical:			
1.	EOD tube assembly missing or improperly installed	Visual	01001
2.	Location of indicator eye hole	Gage	01008
Major:	100 Percent		
101.	Protective sleeve missing	Visual	01002
102.	Forward or rear internal spacer missing	Visual	01003
103.	Set screw (2) not below flush or missing	Visual	01010
Major:	AQL 0.65 Percent		
104.	Incorrect number of mines	Visual	01004
105.	Distance from tube assembly to bottom of canister	Gage	01005
106.	Loading procedure improperly performed	Visual	01006
107.	Protrusion of eye (max.)	Gage	01009
Minor:	AQL 0.65 Percent		
201.	Evidence of poor workmanship (see 3.13)	Visual	01007

4.3.2.2 CDU-4/B and CDU-14/B, after sealing and prior to final assembly (see dwg. 9234270)

Categories	Defects	Method of Inspection	Defect Code
Critical:			
1.	Incorrect torque of liquid level sensor	Test	02001
Major:	AQL 1.00 percent		
101.	Alignment of cap assembly	Visual	02002
102.	Depth of cap assembly	Gage	02003
103.	Parallelism of cap assembly	Gage	02004
104.	Excessive heat seal flashing	Visual	02006
105.	Incorrect torque on base plate mounting screws	Test	02007

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Defect Code
Minor:	AQL 0.65 Percent		
201.	Evidence of poor workmanship (see 3.13)	Visual	02005

4.3.2.3 CDU-4/B and CDU-14/B (see dwg. 9234270)

Categories	Defects	Method of Inspection	Defect Code
Critical:			
1.	Distance to EOD marking from top of canister, max.	Gage	03001
2.	Color of EDO marking (2 places)	Visual	03002
Major:	100 Percent		
101.	Lanyard damaged, broken or improperly assembled	Visual	03003
102.	Plastic connectors between the opener and switch assembly not mated (prior to attaching the lid assembly and after performing the test in 4.4.8)	Visual	03004
103.	Pin receptacle not securely fastened to opener mounting plate ground pin (prior to attaching lid assembly and after performing the test in 4.4.8)	Visual/Manual	03005
104.	Incorrect number of opener plate spacers (when applicable see dwg. 9234965)	Visual	03006
105.	Gap of opener mounting plate with support adapter	Gage	03007
106.	Gap of opener switch mounting plate with opener mounting plate	Gage	03008
107.	Improper routing of electrical special purpose cable assembly and electronic opener cable (see dwg. 9234270)	Visual	03009
108.	Staking of retention rods and stamped nuts missing or improper	Visual	03010
Major:	AQL 1.00 Percent		
109.	Incorrect torque of retention rod nuts	Test	03011

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

110.	Incorrect torque of electronic opener and opener switch assembly mounting screws	Test	03012
111.	Electronic opener cable and explosive opener cable improperly clamped	Visual	03013
112.	Position and seating of explosive opener assembly	Gage/Manual	03014
113.	Any component missing or damaged	Visual	03015
114.	Marking incorrect, misleading or unidentifiable	Visual	03016
115.	Feed-thru splice missing or loose	Visual/Manual	03017
116.	Cargo door assembled incorrectly (door plug not aligned with EOD tube)	Visual	03019
117.	Incorrect torque of lanyard retaining screw	Test	03020
118.	Improper positioning of straps and windshield pads	Visual/Manual	03021
119.	Incorrect alignment of cargo door, retention rods and retention ring relative to canister	Gage	03021
120.	Incorrect torque on cargo door screws	Test	03025
Major:	100 Percent		
121.	Explosive opener cable assembly pinched between base plate and opener plate or between opener plate and electronic opener	Visual/Manual	03023
122.	Loose, cut or exposed wire or lanyards (after switch assembly (before and after cover assembly))	Visual	03024
123.	Lead wires tied to lanyard post (just prior to assembly of opener cover)	Visual	03025
124.	Improper positioning of lead wires and ground wire of electronic opener (just prior to installation of lid assembly) (see drawing 9235824, Fig. 10)	Visual	03026
Minor:	AQL 0.65 Percent		
201.	Evidence of poor workmanship (see 3.13)	Visual	03018

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

4.3.2.4 Container for CDU, prior to assembling cover (see dwg. 9227366)

Categories	Defects	Method of Inspection	Defect Code
Critical:			
1.	Monitor cable connector(s) assembled to canisters in incorrect bays (see 4.4.9)	Visual	04001
2.	Canisters improperly placed in crate	Visual	04002
3.	EOD entry holes unclear	Visual	04003
4.	Any part of indicator eye not showing black (indicates low freon level)	Visual	04010
Major:	100 Percent		
101.	Ejector assembly package missing or improperly secured to platform	Visual	04004
102.	Pressure cartridge assembly package missing or improperly secured to platform	Visual	04005
103.	Indicator eye not visible through hole in kit	Visual	04009
Minor:	AQL 0.65 Percent		
201.	Assembled canisters placed in incorrect loading bay of container (see Table "A" of dwg. 9234270)	Visual	04006
202.	Proper position of special purpose electrical cable assembly (see sheet 2 of dwg. 9234270)	Visual	04007
203.	Evidence of poor workmanship (See 3.13)	Visual	04008

4.3.2.5 Container for CDU (See dwg. 9227366)

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 0.40 Percent		
101.	Incorrect torque of bolt(s)	Test	05001
102.	Marking incorrect, misleading, or unidentifiable	Visual	05002

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.00 Percent		
201.	Metallic seal(s) missing	Visual	05003
202.	Evidence of poor workmanship (see 3.13)	Visual	05004

4.3.3 Testing

4.3.3.1 Electrical continuity of liquid level sensor (see 3.3), Critical Defect, Defect Code 06001.-Each liquid level sensor shall be subjected to this test prior to loading. If any sensor fails to comply with the applicable requirement, it shall not be used in assembly of the canister. The test shall be performed as specified in 4.4.1.

4.3.3.2 Shunt verification of explosive opener fixed delay assembly, prior to loading (see 3.4), Critical Defect, Defect Code 07001.-This test shall be performed 100 percent. Any explosive opener fixed delay assembly which fails to comply with the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.2, using equipment in accordance with 4.3.4.

4.3.3.3 Functioning of electronic opener, prior to loading (see 3.6), Major Defect, Defect Code 08001.-This test shall be performed 100 percent. Any opener which fails to comply with the specified requirements shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.3, using equipment in accordance with 4.3.4.

4.3.3.4 Continuity and resistance of the opener switch assembly, prior to loading (see 3.7), Major Defect, Defect Code 08002.-A sample of 200 switches shall be selected from each lot and shall be tested as specified in 4.4.4, using equipment in accordance with 4.3.4. If any switch assembly fails to comply with the specified requirements, the lot shall be rejected. In the event of rejection, the lot shall be tested 100 percent for compliance with the specified requirements.

4.3.3.5 Electrical continuity, resistance and shorts of the cable assembly, prior to loading (see 3.5), Major Defect, Defect Code 09001.-This test shall be performed 100 percent. Any canister which fails to comply with the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.5, using equipment in accordance with 4.3.4.

4.3.3.6 Freon leakage test (see 3.9), Critical Defect, Defect Code 10001.-This test shall be performed 100 percent. Any

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

canister which fails to comply with the specified requirements shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.6, using equipment in accordance with 4.3.4.

4.3.3.7 X-ray of loaded canister assembly (see 3.10).-Each loaded canister shall be x-rayed as specified in 4.4.7, using equipment as specified in 4.3.4.

4.3.3.7.1 Freon level, Major Defect, Defect Code 10002.-Any loaded canister assembly which fails to comply with the requirements as specified in 3.10.1 shall be classed defective and removed from the lot.

4.3.3.7.2 Mines in or above internal spacer area, Critical Defect, Defect Code 10003.-Any loaded canister assembly which fails to comply with the requirements as specified in 3.10.2 shall be classed defective and removed from the lot.

4.3.3.8 Continuity of the electrical circuits of the loaded canister (see 3.8), Major Defect, Defect Code 11001.-This test shall be performed 100 percent after assembly and re-torquing of the retention rod nuts. Any canister which fails to comply with the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.8, using equipment in accordance with 4.3.4.

4.3.3.9 Electrical continuity of loaded container (see 3.11) Critical Defect, Defect Code 12001.-This test shall be performed 100 percent. Any loaded container which fails to comply with the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.9, using equipment in accordance with 4.3.4.

4.3.3.10 Proving ground tests.-The proving ground tests as called for below shall be for informational purposes only. In the event that a month's production contains canisters from more than one (1) lot, the samples selected shall be representative of each lot contained in that month's production.

4.3.3.10.1 Vibration.-A sample of four (4) loaded canisters shall be randomly selected from each month's production and shipped to a Government-owned proving ground as designated by the Contracting Officer. The test shall be conducted as specified in 4.4.11. Upon completion of this test, the static functioning test shall be conducted.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

4.3.3.10.2 Flight test.-A sample of ten (10) loaded canisters shall be randomly selected from each month's production and shipped to a Government owned proving ground as designated by the Contracting Officer. The sample selected shall make up a complete reload kit (see dwg. 9227366). The test shall be conducted as specified in 4.4.11.

4.3.3.11 Tension verification of strapping machine.-Three (3) strap samples shall be welded and tested as specified in accordance with 4.3.4 to qualify each strapping machine for use in each production shift. In addition, one (1) sample per 160 welds shall be tested as a control of each machine during production.

If any strap sample fails during the qualification of the machine, that strapping machine shall not be used in production.

If the test sample used for control of the machine fails, three (3) additional samples shall be tested and if any samples fails, the machine shall be removed from production.

All strapping machines removed from production because of some faulty operation may, after rework, be returned to production provided they pass the above qualification test.

4.3.3.12 Leakage test, Major Defect, Defect Code 10004.-This test shall be performed 100 percent. Any canister which fails to comply with the specified requirements shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.12, using equipment in accordance with 4.3.4.

4.3.4 Inspection equipment.-Equipment Tabulation (ET) number 9234270 and Equipment Lists (EL's) referenced thereon identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, contruction, survey, and whenever inspection equipment drawings are needed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

4.3.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.4. Test Methods and Procedures

4.4.1 Electrical continuity of liquid level sensor, prior to loading.-The liquid level sensor shall be tested using fixtures, instruments, and the method as shown on the equipment list and dwg. D9292901. This is a non-destructive test; sensors that meet the requirements of 3.3 may be returned to the lot.

4.4.2 Shunt verfication of explosive opener fixed delay assembly, prior to loading.-The equipment specified on the equipment list shall be assembled to the explosive opener lead assembly and the opener assembly checked for compliance with the requirement specified in 3.4. A maximum current of one (1) milliampere shall be applied to the explosive opener. This is a non-destructive test; parts so tested may be returned to the lot.

WARNING: This test shall be performed behind a suitable barricade.

4.4.3 Functioning of electronic opener, prior to loading.-The electronic opener shall be assembled to a fixture as shown on the equipment list and tested for compliance with 3.6. This is a non-destructive test; parts so tested may be returned to the lot.

4.4.4 Continuity and resistance of the opener switch assembly, prior to loading.-The opener switch assembly shall be assembled to a fixture as shown on the equipment list and tested for compliance with 3.7. This is a non-destructive test; parts so tested may be returned to the lot.

4.4.5 Electrical continuity, resistance and shorts of cable assembly, prior to loading.-The cable assembly shall be assembled to the equipment specified on the equipment list and checked for compliance with 3.5. This is a non-destructive test; parts so tested may be returned to the lot.

4.4.6 Freon leakage.-The loaded canister shall be placed into a fixture as specified on the equipment list and tested for freon leakage. This is a non-destructive test; canisters so tested may be returned to the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

4.4.7 Freon level of loaded canister.-The loaded canister shall be x-rayed in the vertical position one (1) hour minimum after sealing. There shall be no shaking of the canister or mixing of its contents for the one (1) hour period immediately prior to x-raying. The fixture, x-ray equipment, positioning of canister, positioning of x-ray equipment, exposure mode, etc., shall be as specified in the applicable equipment list. Any deviations from established procedure, as specified in the equipment list, shall be sent to Picatinny Arsenal, ATTN: SMUPA-ND8 (See 6.4). The developed films identified as to the canister lot and canister serial number shall be retained for a minimum period of one (1) year. Radiographic equipment, operators and procedures shall be qualified in accordance with MIL-R-11470. In addition, the sensitivity or radiographic density of the film used shall be at least 1.25 percent and the radiographic density of the film used shall be of a quality which will produce a definite internal structure as well as showing the level of freon. This is a non-destructive test; canisters so tested shall be returned to the lot, if acceptable.

4.4.8 Continuity of the electrical circuits of the loaded canister.-The equipment specified on the equipment list shall be assembled to the loaded canister and the canister checked for compliance with 3.8. This test shall be performed after assembly and re-torquing of the retention rod nuts.

4.4.9 Electrical continuity of the loaded container.-Prior to placing the cover on the container and connecting the monitor and test cable to the canisters, connect an XM67 Test Set (See dwg. 9211625) to the P2 receptacle mounted on the container. Insert the shorting plug specified on the equipment list into connector number 1 of the monitor and test cable. The monitor lite of the XM67 Test Set should light and the audible alarm should function. Remove the shorting plug and repeat the test until all ten (10) connectors have been checked. Remove the shorting plug (9227399) from the P1 receptacle mounted on the container and replace it with a ten-lite test set (see dwg. 9227398). Again insert the shorting plug mentioned above into connector number 1 of the monitor and test cable. Lite number 1 of the test set should light. Remove the shorting plug and immediately mate the connector to the canister in the corresponding numbered bay. Repeat the test until all ten (10) connectors have been checked. Each connector shall be immediately mated to the canister in the numbered bay corresponding to the lighted lite on the ten-lite test set prior to checking the next connector. After all ten (10) canisters have been mated to the monitor and test cable, remove the ten-lite test set and replace it with the shorting plug (9227399). Depress the ready button on the XM67 Test Set and

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

insure that the green ready lite lights. If the XM67 Test Set does not operate as stated above or if any lite on the ten-lite test set does not light when its corresponding numbered connector is shorted, the loaded container shall be rejected. This is a non-destructive test; containers so tested may be returned to the lot.

4.4.10 Proving ground test.-These tests shall be conducted as stated in the applicable test program request initiated by the design agency (see 6.4).

4.4.11 Strapping machine verification.-The test sample shall be assembled to a fixture as specified on the equipment list and tested for strap tension.

4.4.12 Leakage.-The canister with the indicator eye assembly and EOD tube assembly installed and prior to loading shall be placed in a fixture as specified on the equipment list and tested for leakage. This is a non-destructive test. Canisters so tested may be returned to the lot.

5. PREPARATION FOR DELIVERY

5.1 Packing.-The loaded canister shall be packed in accordance with dwg. 9227366.

5.2 Marking.-Marking shall be in accordance with dwg. 9227366 and Interstate Commerce Commission Regulations 49 CFR 71-78.

5.3 Shipping.-When shipments from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of First Article Samples.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the number of drawings for Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army designs, the contractor shall comply with and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor-prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.

necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes, and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedures provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category E, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit one copy of final designs as a rolled set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor designs.-All submitted designs shall contain a reference to the applicable five-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND8. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

6.4 Submission of test results.-Information as required in Section 3 and paragraph 4.4.7 of this specification shall be forwarded to:

Commanding Officer
Picatinny Arsenal
ATTN: SMUPA-ND8
Dover, New Jersey 07801

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1345-A-258

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:05Z
Check the source to verify that this is the current version before use.