MIL-S-62469(AT)
5 July 1983

MILITARY SPECIFICATION
SEMITRAILER, LOWBED, 15 TON, 4 WHEEL, PATRIOT, M974 SERIES

This specification is approved for use by US Army Tank-Automotive Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a four-wheel, low-bed semitrailer with a maximum payload capacity of 30,000 pounds (lbs) for use as equipment transporter in the Air Defense System, Guided Missile, PATRIOT.

1.2 Classification. Semitrailer shall be of the following models as specified (see 6.2).

TABLE I. Semitrailer models.

Model	Description
M974	Semitrailer, lowbed, PATRIOT
M976	Semitrailer, lowbed, guided missile transporter
M1033	Semitrailer, lowbed, large repair parts transporter

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Tank-Automotive Command, ATTN: DRSTA-GSS, Warren, MI 48090, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document, or by letter.

FSC 2330

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. Unless otherwise specified, the following specifications, standards, and handbooks, of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS
FEDERAL

TT-C-490	- Cleaning Method and Pretreatment of Ferrous Surfaces for Organic Coatings
TT-P-1757	- Primer Coating, Zinc Chromate, Low Moisture Sensitivity

MILITARY

MIL-P-514	- Plates, Identification, Instruction and Marking, Blank
MIL-T-12459	- Tire, Pneumatic, for Military Ground Vehicles
DOD-P-15328	- Primer (Wash), Pretreatment (Formula No. 117 for Metals) (Metric)
MIL-R-0046164	- Rustproofing for New and Fielded Military Vehicles
MIL-P-52192	- Primer Coating, Epoxy
MIL-E-52798	- Enamel, Alkyd, Camouflage
MIL-E-52835	- Enamel, Modified Alkyd, Camouflage, Lusterless
MIL-E-52929	- Enamel, Alkyd, Camouflage, Flash Dry

STANDARDS
MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-130	- Identification Marking of US Military Property
MIL-STD-209	- Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment
MIL-STD-454	- Standard General Requirements for Electronic Equipment
MIL-STD-642	- Identification Marking of Combat and Tactical Transport Vehicles
MIL-STD-1261	- Welding Procedures for Constructional Steels

2.1.2 Other Government documents, drawings, and publications. The following documents, drawings, and publications form a part of this specification to the extent specified herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

DRAWINGS
ARMY

8750023	- Semitrailer, lowbed, PATRIOT, M974
10252280	- Conversion kit, semitrailer, guided missile transporter, M976
11455333	- Conversion kit, semitrailer, large repair parts transporter, M1033

(Copies of specifications, standards, handbooks, drawings, and publications required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity, or as directed by the contracting officer.)

2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section 9, Welding and Brazing Qualifications.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017).

AMERICAN WELDING SOCIETY (AWS)

D1.1 - Structural Welding Code, Section 5, Qualification.

(Application for copies should be addressed to the American Welding Society, 2501 Northwest 7th Street, Miami, FL 33125).

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 First article preproduction inspection. When specified (see 6.2), a preproduction model of the complete semitrailer to be furnished under this specification shall be produced after award of contract and before beginning production. Samples shall be representative of units to be manufactured in quantity and should be constructed with tools and equipment normally used in

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

quantity production. Samples shall be inspected and pass the preproduction tests specified in 4.4. After preproduction approval is granted, any change in formula, material, or manufacturing procedure shall void approval. Product, with changes incorporated shall be examined and tested in accordance with, and shall pass preproduction inspection specified in 4.4.

3.1.1 Initial production inspection. Unless otherwise specified (see 6.2), an initial production semitrailer to be furnished under this specification shall be produced after award of contract. The initial production samples shall be selected by a Government representative from the first production units manufactured. The samples selected shall be inspected and pass the tests specified in 4.4.1.1. After initial production approval is granted, any change in formula, material, or manufacturing procedure shall void approval. Product, with changes incorporated shall be examined and tested in accordance with, and shall pass initial production tests specified in 4.4.l.l.

3.2 Reliability-maintainability.

3.2.1 Reliability. The trailer shall meet a reliability requirement of 6,000 Mean Miles Between Failure (MMBF) to be demonstrated when coupled with suitable towing vehicle in accordance with the operational profile (3.2.1.1) during test (see 4.4.2.3) (see 6.6 for definition and classification of a failure.).

3.2.1.1 Operational profile. An 8,000-mile operational profile test shall be apportioned as shown in table II.

TABLE II. Operational profile test.

COURSE	DISTANCE	PERCENTAGE
High-speed paved road	1,875 miles	23.4%
Improved gravel road	1,625 miles	20.3%
Level, substantial road bed, moderate cross-country	1,250 miles	15.6%
Hilly secondary road	2,500 miles	31.2%
Belgian block	750 miles	9.4%

3.2.2 Maintainability. Total maintenance, excluding driver and crew checks and services, shall not exceed 12 man-hours during the first 8,000 miles of specified operation. This equates to a maintenance ratio (MR) of 0.030 at 20 operational miles equivalent to one operational hour. The scheduled maintenance interval shall be 8 months or 8,000 miles, whichever comes first (see 4.4.2.3.1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

3.3 Materials. Materials shall be as specified herein and in referenced specifications and drawings. Material shall be free of all defects that might affect serviceability and functions of the finished product (see 4.1.2 and 6.7).

3.3.1 Qualified products. The contractor shall be responsible for using all assemblies and parts necessary in semitrailer construction that are listed as qualified products on the Qualified Products List (QPLs) and those approved for inclusion on the QPLs. Assemblies and parts determined as QPL items appear on the engineering parts list. The contractor manufacturing inspection records shall specifically list all QPL items by part or drawing number, name of supplier, and number and date of the QPL. When assemblies and parts are approved as qualified products but not yet listed on QPLs, the contractor shall list the products by number and date of the approval document with the name of supplier (see 4.1.2).

3.3.2 Fungus resistant product. Materials required to resist fungus shall meet the requirement of MIL-STD-454, Requirement 4 (see 4.1.2).

3.3.3 Flammable materials. Flammable materials shall not be used unless the materials are provided with suitable protection to prevent hazard (see 4.1.2).

3.3.4 Ozone resistance. When rubber components are required to be ozone resistant, the degree of resistance shall be as specified in applicable specifications or drawings (see 4.1.2).

3.4 Construction. Trailer components, subassemblies and assemblies shall be fabricated and assembled into a complete trailer in accordance with applicable drawings (see 2.1.2). Guided missile transporter M976 is manufactured from the M974 base trailer and from the conversion kit, Drawing 10252280. Large repair parts transporter M1033 is manufactured from the M974 base trailer and from the conversion kit, Drawing 11455333. All parts, assemblies, and subassemblies requiring identification shall be identified in accordance with MIL-STD-130. The fabrication and manufacture of equipment shall be executed in a manner commensurate with the intended use of the end item and accepted Government standards and specifications delineated herein.

3.4.1 Wheel bearing seals. When fording or operating in mud, sand, or snow, seals shall prevent entrance of foreign matter into bearings. Water contamination of wheel bearing lubricant after fording operations, shall be not more than 2 percent by volume. All bearing seals shall prevent leakage of lubricants from the bearings (see 4.8.2).

3.4.2 Electrical system. The trailer shall be equipped with a 24-volt electrical lighting and signaling system in accordance with applicable drawings and provide connection to a suitable towing vehicle 24 volt system (see 4.8.3).

3.4.2.1 Electrical circuits. Electrical circuits shall maintain continuity from end to end without evidence of internal or external shorts during all trailer operating conditions (see 4.8.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

3.4.2.2 Lights. Lights specified on applicable drawings shall be capable of operating throughout all trailer operating conditions (see 4.8.4).

3.4.3 Welding. Metal-arc welding of structural steels and the procedures required for documentation prior to production welding shall be in accordance with MIL-STD-1261. The contractor shall have an accepted welding procedure and accepted workmanship samples in accordance with MIL-STD-1261 for each type of weld before any production welding can be accomplished (see 4.8.5).

3.4.3.1 Welder and welding operator certification. Before assigning any welder to manual welding work, the contractor shall provide the contracting officer with certification that the welder has passed qualification codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

a. AWS D1.1, Structural Welding Code, Section 5, qualification.

b. ASME Boiler and Pressure Vessel Code, Section 9, Welding and Brazing Qualifications

If only flat or horizontal welds are required, the contractor need not, qualify welders for "all position welding". Subject to approval by the Government, the contractor standard welder qualification may be substituted in lieu of the above codes provided the contractor procedure is, as a minimum, equivalent to the above codes. The contractor shall be responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with the contractor or manufacturer welding procedures (see 4.8.5).

3.4.3.2 Welding repairs and burning operations. Welding repairs and burning operations of any type or class shall be made only when and to the extent specifically authorized by the acquisitioning activity (see 4.8.5 and 6.2).

3.4.4 Lifting attachments. Trailers shall be provided with lifting attachments in accordance with applicable drawings. The lifting attachments shall be structurally adequate to lift the trailer when loaded with maximum payload (see table III). Lifting slings, with spreader bar, shall conform to MIL-STD-209 (see 4.8.6).

3.4.5 Tires. In accordance with Drawing 8750023, tube type, 12 ply, 11.00 - 20 tires shall be furnished conforming to class CC, style a of MIL-T-12459. When mounted on the trailer, the tires shall be inflated to 75 psi (see 4.8.7).

3.4.6 Landing gear. Landing legs shall support the fully loaded trailer and withstand the strains imposed when coupling and uncoupling the trailer from the towing vehicle and raising and lowering the loaded trailer. The landing gear shall operate freely when trailer is loaded or unloaded and shall operate without physical interference (see 4.8.8).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

3.4.7 Tiedown devices. Trailers shall be provided with tiedown devices, in accordance with applicable drawings and of sufficient number and structural strength to be adequate for transport by rail, sea, and air (see 4.8.9).

3.4.8 Air brake system. Trailer braking system includes air actuated service brakes equipped with fail safe units to provide parking and emergency braking. The air brake system shall be capable of operation throughout all ranges of trailer operating conditions. The brake adjustment system shall function properly and maintain adjustment within required settings during all trailer operating conditions (see 4.8.10).

3.4.8.1 Air lines and fittings. Air lines and fittings shall be internally clean prior to and after making connections and shall be free from leaks. All lines and fittings shall be secured to prevent rubbing on adjacent lines or trailer appendages. Air system leakage shall not allow a pressure drop of more than 34 pound force per square inch (psi) in a 1-hour period, with 100 $\pm$ 10 psi (shop air) initially in air supply tanks, and ambient temperature of $70^0 \pm 10^0$F; or 6 psi drop at 120 $\pm$ 10 psi for 2 minutes at $70^0 \pm 10^0$F (see 4.8.10.1).

3.4.8.2 Brake actuator seals. The brake actuator shall be completely sealed to preclude leakage of lubricants and the entrance of water, sand, or other foreign matter into the actuator during normal operation and fording as specified in 3.5.8 (see 4.8.10.2).

3.5 Performance. The trailer shall meet performance requirements of this specification when equipped as specified herein, serviced as specified in applicable lubrication drawing, loaded with M976 or M1033 payload (see 3.5.2 and 3.5.3) and coupled to the towing vehicle (see 4.8.11 through 4.8.11.6).

3.5.1 Environmental conditions. The trailer, when properly serviced and coupled to a suitable towing vehicle, shall operate and transport equipment in ambient air temperatures from minus 50 degrees fahrenheit (^{0}F) to 120^{0}F. When in storage, the trailer shall withstand temperatures from minus 50 ^{0}F to 160 ^{0}F without deterioration that causes failure of any component (see 4.8.11.1).

3.5.2 Simulated M976 payload. Performance and functional characteristics specified herein, reliability, and maintainability requirements shall be met with a payload of four PATRIOT missile containers loaded to a gross weight of 3,740 lbs each, with a center of gravity as indicated by the containers and mounted with the M976 mounting devices (see 4.8.11).

3.5.3 Simulated M1033 payload. Performance and functional characteristics specified herein, reliability, and maintainability requirements shall be met with a payload of 30,000 lbs securely fastened to the trailer in the following position. The center of gravity of the simulated load shall be located centrally across the vehicle, 48 3/8 inches above the loading deck and 239 inches to the rear of the kingpin centerline (see 4.8.11).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

3.5.4 Payload and speeds.

3.5.4.1 Highway operation. The trailer shall provide satisfactory operation over smooth hard surfaced roads, when loaded with highway payload and towed at the speed specified in Table III. When towed at specified speed in a straight line, trailer shall track the towing vehicle without shifting or swerving more than 3 inches from side to side of the path of the towing vehicle (see 4.8.11.2.1).

3.5.4.2 Cross-country operation. The trailer shall provide satisfactory operation over unimproved roads, open, rolling, or hilly terrain when loaded with the maximum payload and towed at the speed specified in table III (see 4.8.11.2.2).

TABLE III. Semitrailer weights, loads and speeds.

Semitrailer weight	Maximum payload	Maximum gross weight	Speed
M976-13,500 lbs	14,960 lbs (cross country or highway)	30,000 lbs	20 mph cross country 50 mph highway
M1033-13,500 lbs	30,000 lbs (cross country or highway)	43,500 lbs	20 mph cross country 50 mph highway

3.5.5 Gradeability. When towed over a dry, hard surface free of loose material, the trailer shall exhibit the gradeability and stability specified herein.

3.5.5.1 Longitudinal inclines. The trailer shall follow the towing vehicle without weaving to an extent affecting control of the vehicle combination when ascending and descending longitudinal inclines with 20 percent grade (see 4.8.11.3.1).

3.5.5.2 Side slopes. The trailer shall follow the towing vehicle without slipping or upsetting when operating on left and right side slopes with 20 percent grade (see 4.8.11.3.2).

3.5.6 Braking.

3.5.6.1 Service brakes. The service brakes of the trailer and towing vehicle shall decelerate and stop the vehicle combination with maximum payload on dry, smooth, level, hard-surfaced roads free of loose materials. Stopping distance shall be not more than 50 feet at 20 miles per hour (mph) (see 4.8.11.4.1).

3.5.6.2 Automatic brake actuation. The trailer shall be equipped with an automatic actuating device to apply the trailer brakes upon breakaway from the towing vehicle. When loaded with the maximum payload, the breakaway device shall maintain application of the brakes and hold trailer stationary on 30 percent grade for not less than 15 minutes (see 4.8.11.4.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

3.5.7 Turning. The semitrailer-towing vehicle combination shall be capable of making complete turns to the right or left (with the trailer assuming a 90 degree angle) without cramping or damage to either the towing vehicle or trailer (see 4.8.11.5).

3.5.8 Fording. Trailer shall ford salt or fresh water to a depth of 30 inches for periods up to 15 minutes duration without damage to the trailer or its components, and without special preparation or servicing before and after fording operations. No evidence of water leakage or moisture penetration into the sealed wheeled bearings or brake actuators per 3.4.1 and 3.4.8.2 shall be permitted (see 4.8.11.6).

3.6 Painting, marking and identification plates.

3.6.1 Painting. Paints and paint colors shall be as directed on applicable drawings (see 4.8.12.1). For field painting application, all equipment exterior surfaces shall require alkyd enamel forest green paint per MIL-E-52929 Type II. For production painting, application of primer, MIL-P-52192 and finish only, apply to non-metallic surfaces. Application of all metallic exterior equipment surfaces shall require the following surface treatment, primer, and finish:

a. Treat per TT-C-490 Cleaning Method and Pretreatment of Ferrous Surfaces for Organic coatings Type III.
b. (DOD-P-15328 Primer (Wash) Pretreatment (Formula No. 117 for Metals) (Metrics)).
c. Prime per TT-P-1757 Primer Coating, Zinc Chromate, Low Moisture Sensitivity.
d. Composition L or MIL-P-52192 Primer Coating Epoxy, Composition L.
e. Finish per MIL-E-52929 Enamel, Alkyd, Camouflage, Flash Dry (Type II).

3.6.2 Marking. Identification marking shall be as specified in MIL-STD-642 (see 4.8.12.2). Exterior markings shall be black lusterless paint having infrared reflectance of MIL-E-52798 or MIL-E-52835 and shall be as follows:

a. National symbol (star). A 3-inch star shall be centered on the front and rear of the semitrailer.
b. Registration numbers. Registration numbers shall be placed on both sides in uniform Gothic characters. Characters shall optionally be 3 or 4 inches in height.
c. Safety and instructional markings. Markings such as tire pressure, tiedown, and center of gravity, shall be black, lusterless letters or numbers no larger than 1-inch in height.

3.6.3 Name, shipping and service data plates. The information to be included on data plates shall be in accordance with applicable drawings or as specified by the acquisitioning activity (see 6.2). The plates shall meet the requirements of MIL-P-514 (see 4.8.12.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

3.7 Rustproofing. Corrosion preventive compound shall be applied to the trailer in accordance with MIL-R-0046164 (see 4.8.13).

3.8 Safety. No condition shall exist which may create a safety hazard to operating or maintenance personnel (see 4.8.14).

3.9 Servicing. The trailer shall be adjusted for immediate operation and shall be serviced for the climatic conditions prevailing at the delivery point. Servicing shall be compatible with processing for shipment as specified by the acquisitioning activity (see 4.8.15 and 5.1).

3.10 Workmanship. Workmanship shall be of such quality as to assure that the trailer and its components are free of defects that compromise, limit, or reduce the capability of the trailer in the performance of its intended use (see 4.8.16).

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Inspection equipment. Unless otherwise specified in the contract, the supplier is responsible for the provision and maintenance of all inspection and test equipment necessary to assure that supplies and services conform to contract requirements. Commercial, modified commercial, or supplier designed inspection equipment or measuring set-ups must be capable of repetitive measurements to an accuracy of 10 percent of the component tolerance.

4.1.2 Materials and construction. To determine conformance to 3.3 through 3.4 inspection, test, and material certification records shall be maintained by the contractor. Records shall be subject to review by the Government. Records shall include date, part, or characteristic identification, inspection results, disposition of lot (accepted or rejected), and corrective action taken on noted defects.

4.1.3 Parts and components. Parts, components, and assemblies shall be inspected in accordance with the drawings subordinate to the appropriate semitrailer drawing (see 2.1.2). When applicable, inspection shall be in accordance with Supplementary Quality Assurance Provisions (SQAPs) or Quality Assurance Requirements (QARs).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspections. Classification of inspections shall be as follows:

a. First article inspection (see 4.4).
b. Quality conformance inspection (see 4.5).
c. Control tests (see 4.6).
d. Comparison tests (see 4.7).

4.3 Inspection conditions. Unless otherwise specified herein, all inspections shall be performed in accordance with ambient test conditions of 73 ± 18°F, 28.5 ± 2.5 inches of mercury, and relative humidity of 50 ± 30 percent.

4.4 First article inspection.

4.4.1 Preproduction inspection tests. When specified (see 3.1), a preproduction semitrailer shall be inspected and tested as specified in table IV. Testing shall be conducted by the Government at a Government proving ground.

4.4.1.1 Initial production inspection. Unless otherwise specified, to determine conformance to 3.1.1, after completion of the first production trailer inspection described herein, two additional trailers shall be selected by the Government from the first month's production (or from the first 10 trailers produced). The trailers shall be subjected to initial production inspection (IPI) specified in table IV. The trailers shall be tested with either an actual or simulated payload except the first and last 50 miles shall be without payload. IPI is to be performed by the Government. The contractor shall expeditiously furnish repair parts to adequately support the test. Trailer breakdown due to poor quality of workmanship or material, or failure of the contractor to comply with a specification or drawing requirement, shall not be the basis for adjustment of the contract delivery schedule or the contract price. When specified (see 6.2) the contractor shall recondition each test trailer to like-new condition (see 6.9) upon test completion.

4.4.1.1.1 Failure. Failure of any specimen to pass the specified tests shall be cause for the Government to withhold preproduction or initial production approval until action by the contractor to correct defects and prevent recurrence has been approved by the Government.

4.4.2 First production trailer inspection.

4.4.2.1 Joint inspection. When the first production trailer is completed, joint inspection will be conducted by contractor personnel and government representative(s) to evaluate conformance of materials and workmanship to requirements of specified documents. The trailer, suspension, and electrical components shall be available for inspection. These inspections shall be made at contractor or subcontractor facility prior to application of primer and paint. Processing and welding procedures, quality system, and inspection records shall be reviewed and evaluated during this inspection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

TABLE IV. Classification and location of inspections.

Title	Requirement	Preproduction initial prod inspection (GPG 1/)	First production vehicle inspection (contractor)	Control test (contractor)	Comparison inspection (GPG)
First article inspection	3.1/ 3.1.1	4.4			
Comparison tests					4.7
Reliability	3.2.1	4.4.3.1			
Maintainability	3.2.2	4.4.3.2			
Wheel bearing seals	3.4.1	4.8.2			4.8.2
Electrical system	3.4.2	4.8.3	4.8.3		4.8.3
Electrical circuits	3.4.2.1	4.8.3	4.8.3		4.8.3
Lights	3.4.2.2	4.8.4	4.8.4		
Welding & welding repairs	3.4.3		4.8.5		
	3.4.3.1		4.8.5		
	3.4.3.2		4.8.5		
Lifting attachments	3.4.4	4.8.6	4.8.6	4.8.6	4.8.6
Tires	3.4.5	4.8.7	4.8.7		4.8.7
Landing gear	3.4.6	4.8.8	4.8.8	4.8.8	4.8.8
Tiedown devices	3.4.7	4.8.9	4.8.9		4.8.9
Air brake system	3.4.8	4.8.10	4.8.10	4.8.10	4.8.10
Air lines & fittings	3.4.8.1	4.8.10.1	4.8.10.1	4.8.10.1	4.8.10.1
Brake actuator seals	3.4.8.2	4.8.10.2		4.8.10.2	4.8.10.2
Environmental conditions	3.5.1	4.8.11.1		4.8.11.1	4.8.11.1
Highway operations	3.5.4.1	4.8.11.2.1	4.8.11.2.1	4.8.11.2.1	4.8.11.2.1
Cross-country operations	3.5.4.2	4.8.11.2.2	4.8.11.2.2	4.8.11.2.2	4.8.11.2.2
Gradeability	3.5.5.1	4.8.11.3.1	4.8.11.3.1	4.8.11.3.1	4.8.11.3.1
	3.5.5.2	4.8.11.3.2	4.8.11.3.2	4.8.11.3.2	4.8.11.3.2

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

TABLE IV. Classification and location of inspections. - Continued.

Title	Requirement	Preproduction initial prod inspection (GPG 1/)	First production vehicle inspection (contractor)	Control test (contractor)	Comparison inspection (GPG)
Service brakes	3.5.6.1	4.8.11.4.1	4.8.11.4.1	4.8.11.4.1	4.8.11.4.1
Automatic brake actuation	3.5.6.2	4.8.11.4.2	4.8.11.4.2	4.8.11.4.2	4.8.11.4.2
Turning	3.5.7	4.8.11.5	4.8.11.5	4.8.11.5	4.8.11.5
Fording	3.5.8	4.8.11.6	4.8.11.6	4.8.11.6	4.8.11.6
Painting	3.6.1	4.8.12.1	4.8.12.1		4.8.12.1
Marking	3.6.2	4.8.12.2	4.8.12.2		4.8.12.2
Data plates	3.6.3	4.8.12.3	4.8.12.3		4.8.12.3
Rustproofing	3.7	4.8.13	4.8.13		4.8.13
Safety	3.8	4.8.14	4.8.14		4.8.14
Servicing	3.9	4.8.15	4.8.15		4.8.15
Workmanship	3.10	4.8.16	4.8.16		4.8.16
Packaging	5.1	4.8.17	4.8.17		

1/ Government proving ground.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

4.4.2.2 Completed trailer inspection. The production trailer shall be road tested 50 miles and inspected by the contractor for conformance to the requirements of contract and specifications. The applicable road test shall be in accordance with 4.6.3 but without payload. Upon completion, the contractor shall submit the trailer (and make available all inspection records and certifications) to the responsible government inspection element at contractor plant for inspection. Inspection and tests per table IV shall be conducted.

4.4.2.2.1 Repair of defects. Defects shall be corrected by the contractor at no cost to the Government. Failure of the contractor to promptly correct defects shall be cause for suspension of acceptance of production trailers until corrective action has been accomplished.

4.4.2.2.2 Semitrailer disposition. After completion of inspection, the first production trailer shall remain at the manufacturing facility, as a production sample, and shall be the last trailer shipped on the contract. The trailer may be released sooner at the discretion of the contracting officer. The contractor shall service and maintain the trailer during this period in accordance with applicable documents for care and preservation while in storage.

4.4.2.2.3 Final approval and acceptance. Final approval and acceptance by the Government of the first production trailer shall be withheld until the initial production inspection has been completed and a final determination has been made regarding conformity of the trailer to contractual requirements including, but not limited to workmanship and materials.

4.4.2.3 Reliability verification. To determine conformance to 3.2.1, a minimum acceptable value (MAV) of 8,000 miles shall be demonstrated during IPI specified in 4.4.1.1. A point estimate MAV will be computed using the cumulative test mileage of all trailers divided by the cumulative number of chargeable failures of all trailers.

4.4.2.3.1 Maintainability. To determine conformance to 3.2.2, the requirements shall be verified during IPI. The test trailer shall meet specified scheduled and unscheduled maintenance man-hours at required maintenance intervals.

4.4.2.3.2 Maintainability failures. Failure of the trailer to meet any of the maintainability requirements specified as a result of IPI shall be cause for rejection of the trailer. The Government shall refuse to continue acceptance of the production trailers until all maintainability requirements on trailers accepted prior to completion of IPI are accomplished at no cost to the Government.

4.4.2.3.3 Failure. Deficiencies of test trailers resulting from workmanship or materials found during (or caused by) the IPI, shall be cause for rejection of the trailers until evidence has been provided by the contractor that corrective action has been taken. Any deficiency found as a result of IPI, shall be evidence that all trailers accepted prior to completion of IPI are similarly deficient unless evidence satisfactory to the contracting officer is furnished by the contractor that they are not similarly deficient. Such deficiencies shall be corrected on all trailers by the contractor at no additional cost to the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

4.5 Quality conformance inspection.

4.5.1 Sampling.

4.5.1.1 Lot formation. An inspection lot shall consist of all semitrailers from one day production subjected at one time to acceptance inspection.

4.5.1.2 Sampling for examination. Samples for quality conformance examination shall be selected in accordance with MIL-STD-105.

4.5.1.3 Sampling for acceptance testing. Samples for acceptance testing shall be selected in accordance with level of MIL-STD-105.

4.5.1.4 Sampling failures. Rejected lots shall be processed in accordance with the acceptance and rejection criteria of MIL-STD-105.

4.5.2 Quality conformance examination.

4.5.2.1 Acceptable quality level. Each sample, selected in accordance with 4.5.1.2, shall be examined for conformance to the following acceptable quality levels (AQLs), on the basis of percent defective:

Classification	AQL
Major	25
Minor	150

4.5.5.2 Classification of defects. For examination purposes, defects shall be as specified in tables V and VI.

4.5.3 100% inspection. Each trailer, after final inspection, shall be operated for a distance of not less than 10 miles by the contractor. Trailers shall be completely assembled and serviced prior to road test. Performance of trailers shall be demonstrated without payload at place of manufacture on a smooth, level, hard-surfaced road. During road test trailers shall be observed for handling characteristics, tracking, braking, turning ability, and landing leg operation.

4.5.3.1 Failure. If any trailer fails to pass 100% inspection the Government shall withhold acceptance until evidence has been provided by the contractor that corrective action has been taken to correct trailer deficiencies.

4.5.4 Sampling. When authorized by the Government acquisitioning activity (see 6.3), the contractor may perform final inspection of trailers on a sampling basis rather than 100% inspection as stated in 4.5.3.

4.5.4.1 Lot formation. An inspection lot shall consist of all trailers from one day production submitted at one time for acceptance inspection.

4.5.4.2 Sampling for inspection. For the purpose of visual, dimensional, and primary functional inspection, a representative sample shall be selected from each inspection lot in accordance with inspection level II of MIL-STD-105. Before sampling may be accomplished by

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

TABLE V. Major defects AQL - 25 defects per 100 units.

Defect number	Characteristic	Major defect	Method of Inspection
101.	Frame and gooseneck	Structural and welding defects.	Visual
102.	Landing gear	Malfunction; extended, restricted, or stowed.	Functional
103.	Axle	Improper assembly or installation; welding defects.	Visual
104.	Service brakes	Malfunction; leaks; component damage; nonconformance to stopping distance (see 3.5.6.1.).	Visual and functional
105.	Fail safe brakes	Malfunction; nonconformance to holding ability (see 3.5.6.2).	Functional
106.	Fifth wheel plate and kingpin	Improper mounting and assembly; welding defects.	Visual
107.	Electrical system components	Malfunction; inoperative; damage.	Visual and functional
108.	Suspension system components	Damage; malfunction.	Visual and functional
109.	Wheels and tires	Tire damage; malfunction.	Visual and functional

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

TABLE VI. Minor defects AQL - 150 defects per 100 units.

Defect number	Characteristic	Minor defect	Method of Inspection
201.	Wheels and tires	Improper size, type, or mounting.	Visual
202.	Wiring, tubing and hose	Improperly coded; protected, assembled or installed.	Visual
203.	Brake system components	Improper assembly, installation or adjustment.	Visual and functional
204.	Electrical system components	Improper assembly or installation.	Visual
205.	Suspension system components	Improper assembly or installation.	Visual
206.	Landing gear	Improper assembly or installation.	Visual
207.	Tiedowns, lashing hooks and lifting devices	Missing; improperly located; welding defects.	Visual
208.	Platform, stake pockets, lifting eyes, lashing rings, stowage compartments, and tool boxes	Missing; defective wood parts; improper installation, fit or location; welding or rivet defects; sheet metal defects.	Visual
209.	Paint	Improper application or color.	Visual
210.	Accessories	Improper assembly, installation or fit; defective.	Visual
211.	Lubrication fittings	Defective; missing; improperly installed.	Visual
212.	Decals, data and instruction plates	Missing; incomplete data; improper.	Visual
213.	Lubrication	Improper application.	Visual
214.	Protective coatings	Improper application, materials or coverage.	Visual
215.	Records, forms and publications	Missing; improperly processed.	Visual
216.	Workmanship	Improper manufacture or assembly; defective material.	Visual and functional

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

the contractor, the contractor shall 100% inspect 20 consecutive trailers to establish a process average (see 6.4), to allow normal sampling in accordance with MIL-STD-105.

4.5.4.3 Quality conformance examination by sampling. Each trailer selected by sampling for final inspection shall be inspected by the contractor utilizing the final inspection record to verify conformance of produced trailers to the requirements of this specification and applicable drawings. Examinations shall be performed against the classification of defects and AQLs specified in tables V and VI.

4.5.4.4 Quality conformance testing by sampling. Each trailer selected by sampling for final inspection shall be operated for a distance of not less than 10 miles by the contractor. Trailers shall be completely assembled and serviced prior to road test. Performance of trailers shall be demonstrated without payload at the place of manufacture on a smooth hard-surfaced road.

4.5.5 Unclassified defects. All defects that have no effect on function, safety, interchangeability, or life, but that are considered departures from good workmanship, shall be noted in writing. Workmanship deficiencies falling within this category and recurring in five consecutive lots, or ten lots or more within a thirty-day period, will be added to the minor defects classification with no increase in AQLs.

4.5.6 Recurring deficiencies.

4.5.6.1 Recurring major deficiencies. A major deficiency (see 6.5) is recurring when the same defect occurs more than once in the same sample lot or when the defect occurs in two successive sample lots. A major defect may be considered recurring when inspection records reflect such a condition. Recurring major deficiencies shall be cause for the entire lot or lots to be inspected for the recurring deficiencies. The deficiencies shall be corrected by the contractor when found.

4.5.6.2 Recurring minor deficiencies. A minor deficiency (see 6.5) is recurring if it occurs more than twice in the same sample lot or when the defect occurs in four successive samples or lots. Recurring minor deficiencies shall be cause for the entire lot or lots to be inspected for the recurring deficiencies and correction shall be accomplished prior to acceptance.

4.5.7 Failure of sampled inspection vehicles. If any trailer fails to pass examination or test (4.5.4.3 and 4.5.4.4), the Government shall withhold acceptance of all trailers till evidence has been provided by the contractor that corrective action has been taken to correct deficiencies. Contractor shall revert to 100% inspection as defined in 4.5.3, until satisfactory evidence of correction has been provided by the contractor to the Government.

4.6 Control tests. Control tests for maintaining control of manufacturing operations shall be conducted by the contractor as specified herein (see table IV).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

4.6.1 Frequency. The government shall select at random one out of each 50 trailers submitted, or one a month, (but not more than two trailers or less than one trailer in any given 30 day period), for examination, test, and 50 mile road test by the contractor. Semitrailer(s) selected shall have passed the quality conformance examination in 4.5 through 4.5.3.

4.6.2 Failure. If a trailer fails to pass any control test specified herein, the Government inspector shall withhold acceptance of subsequent trailers until evidence has been provided by the contractor that corrective action has been taken.

4.6.3 Fifty mile test. The test trailers shall be equipped with all stowage and on vehicle equipment, loaded with maximum payload; and operated for a distance of 50 miles. This test shall be performed at the place of manufacture by the contractor and be witnessed by Government representatives. The test course shall be a relatively smooth hard surfaced road.

4.7 Comparison tests. The Government may select a trailer at any time during the contract production period and subject this trailer to all applicable tests specified in table IV and a 3,000 mile test using the percentage of mileage specified in table II. Tests shall be conducted by the Government at a site selected or approved by the Government. Trailer, selected for comparison test shall not include any trailer previously tested for conformance to 4.6 by the contractor. Unless otherwise specified by the Government (see 6.2), the contractor shall recondition the test trailer to like-new condition after test completion (see 6.9).

4.7.1 Failure. Deficiencies of comparison test trailers found resulting from workmanship or materials shall be cause for rejection of such test trailers until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiency. Any deficiency found during, or as a result of the comparison test, shall be evidence that all trailers currently produced are similarly deficient unless evidence satisfactory to the contracting officer is furnished by the contractor that they are not similarly deficient. Deficiencies on all trailers shall be corrected by the contractor at no additional cost to the Government.

4.8 Methods of inspection.

4.8.1 Frame examination. To determine conformance to 3.4, each semitrailer frame shall be examined for proper assembly. Prior to the welding of the top and bottom cover plates, the trailer frame welds shall be visually examined. All frame examinations shall be accomplished prior to application of primer and paint,

4.8.2 Seal leakage examination. To determine conformance to 3.4.1, after fording operation (see 4.6.11.6), all wheel bearings, as applicable, shall be checked for lubricant leakage. Water contamination shall not be more than 2 percent by volume.

4.8.3 Electrical circuit examination. To determine conformance to 3.4.2 and 3.4.2.1, current and voltage levels and continuity of the electrical system shall be tested.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

4.8.4 Lighting system examination. To determine conformance to 3.4.2.2, the lights, wires/cables, and sockets shall be checked for conformance to the applicable drawing and tested for operation.

4.8.5 Welding and burning examination. To determine compliance with 3.4.3, 3.4.3.1, and 3.4.3.2 all welding, welding repairs, and burning operations shall be visually examined for removal of slag and to determine if approved procedures have been followed.

4.8.6 Lifting attachments test. To determine conformance to 3.4.4, the fully loaded trailer (see table III) shall be lifted a minimum of 12 inches and held for 15 minutes; then examined for damage to the trailer and lifting devices.

4.8.7 Tire examination. To determine conformance to 3.4.5, tires shall be examined. Tires must be 12 ply, 11.00-20, tube type, inflated to 75 psi.

4.8.8 Landing gear test. To determine conformance to 3.4.6, the trailer shall be loaded with the maximum payload (see table III) to assure that the landing gear can support the intended load. The landing gear shall then be tested (exercised) for meeting functional requirements and ease of operation.

4.8.9 Tiedown device examination. To determine conformance to 3.4.7, all trailer tiedown devices shall be examined for drawing and specification requirements.

4.8.10 Air brake system test. To determine conformance to 3.4.8, the brake system shall be actuated to assure function of the parking, emergency and brake adjustment systems.

4.8.10.1 Air line and fitting examination. To determine conformance to 3.4.8.1, the air lines, fittings, and air system shall be inspected for cleanliness and leakage as specified. Air pressure of 100 $\pm$ 10 psi (shop air) shall be applied to the brake system. All brake line tubing and joints shall be covered with a soap water solution to find leaks in the tubing or joints. When fittings and tubing have been secured from leakage, a pressure gage shall be applied to the system after it has been pressurized to 100 $\pm$ 10 psi. A pressure drop of more than 34 psi in one hour shall be considered a deficiency. The installation shall be checked to insure that fittings are properly assembled and that air lines are not chafing each other or adjacent parts of the trailer. As an alternative, truck air pressure of 120 $\pm$ 10 psi may be used with no drop in pressure beyond 6 psi in 2-minutes. Air loss through porous fitting on the emergency valve is allowed but not in excess of test requirements.

4.8.10.2 Brake actuator seals examination. To determine conformance to 3.4.9.2 during normal operations and after fording, the seals shall be checked for leakage and water contamination.

4.8.11 Performance.

4.8.11.1 Environmental operation test. To determine conformance to 3.5.1, trailer shall be capable of withstanding the temperature extremes specified.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

4.8.11.2 Payload and speeds.

4.8.11.2.1 Highway operation test. To determine conformance to 3.5.4.1, the trailer shall be operated as specified on paved and gravel roads and observed for towing and performance requirements.

4.8.11.2.2 Cross-country operation test. To determine conformance to 3.5.4.2, the trailer shall be operated over cross-country terrain as specified without damage to the trailer or the towing vehicle.

4.8.11.3 Gradeability.

4.8.11.3.1 Longitudinal inclines test. The trailer connected to the prime mover shall longitudinally ascend and descend a 20 percent grade without weaving to an extent affecting the controllability of the vehicle combination as specified in 3.5.5.1.

4.8.11.3.2 Side slope test. To determine conformance to 3.5.5.2, the tractor-trailer combination shall be operated on a right and left side 20 percent grade slope without slipping or upsetting.

4.8.11.4 Braking.

4.8.11.4.1 Service brakes test. To determine conformance to 3.5.6.1, the tractor trailer combination with maximum payload shall be accelerated up to 20 mph on a dry, smooth, level, hard-surfaced road free from loose materials and the brakes applied. The tractor-trailer combination must stop in not more than 50 feet from point of application of the brake pedal.

4.8.11.4.2 Automatic brake actuation test. To determine conformance to 3.5.6.2, the semitrailer with maximum payload shall be towed to a 30 percent grade and the intervehicular air lines shall be disconnected for 15 minutes while the front of the trailer is pointed upgrade, and 15 minutes while the front of the trailer is pointed downgrade. The automatically actuated brakes shall hold the trailer for the period of time indicated without slippage or movement of the trailer.

4.8.11.5 Turning ability test. To determine conformance to 3.5.7, the tractor-trailer combination on a flat level surface shall assume a 90 degree angle both to the right and left without cramping or damage to either.

4.8.11.6 Fording ability test. To determine conformance to 3.5.8, the trailer shall be placed in or towed into water with a depth of 30 inches for 15 minutes without special preparation. All sealed items and bearings shall be examined for water impingement beyond the 2 percent allowed for wheal bearings and none allowed for brake actuator seals. Disassembly to the extent necessary for inspection shall be conducted.

4.8.12 Painting, marking, and identification plates.

4.8.12.1 Painting. To determine conformance to 3.6.1, preparation and painting shall be examined during and after application.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

4.8.12.2 Marking. To determine conformance to 3.6.2, trailer markings shall be examined.

4.8.12.3 Identification plates. To determine conformance to 3.6.3, all identification plates shall be examined.

4.8.13 Rustproofing. To determine conformance to 3.7, the trailer shall be inspected for proper application of rustproofing compound, as specified in the part drawing and applicable specifications.

4.8.14 Safety. To determine conformance to 3.8, all electrically energized exposed parts shall be located, insulated, and fully enclosed or guarded to prevent hazards to operating personnel or equipment malfunction. All moving parts which are a hazard to operating personnel, shall be enclosed or guarded. Protective devices shall not impair operating functions.

4.8.15 Servicing and adjustment. To determine conformance to 3.9, servicing and adjustment of specified systems shall be examined.

4.8.16 Workmanship. To determine conformance to 3.10, trailers shall be examined during manufacture.

4.8.17 Packaging. To determine conformance to section 5, trailer processing and marking shall be inspected prior to shipment.

5. PACKAGING

5.1 Processing and marking. Processing and marking shall be in accordance with Equipment Preservation Data Sheet for the level of protection specified in 6.2.

6. NOTES

6.1 Intended use. The PATRIOT semitrailer towed by a suitable towing vehicle with crane is intended for use in the PATRIOT Air Defense System as the Guided Missile Transporter (M976) or as the Large Repair Parts Transporter (M1033).

6.1.1 Semitrailer preparation. The trailer manufactured in accordance with this specification is prepared from a base trailer M974. A conversion kit then is installed for M976 and M1033 models. The M976 and M1033 are missile system support equipment trailers which provide respectively (1) a capability to deliver and load resupplied missile rounds and (2) a means to transport and store large, heavy repair parts. The M976 has a capacity of four missile rounds, and the integral crane on the towing vehicle has the capability of transferring missile rounds from trailer to missile launcher. Stowage space is also provided on the M1033 for items of handling equipment needed to move heavy repair parts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

6.2 Order data. Acquisitioning documents should specify the following:

a. Title, number, and date of this specification.
b. Model(s) to be acquired (see 1.2).
c. Preproduction model(s) if required (see 3.1).
d. Initial production sample(s) if not required (see 3.1.1).
e. Whether welding repair is authorized and extent allowed (see 3.4.3.2).
f. Need for reconditioning test vehicles (see 4.4.1.1 and 4.7).
g. Information to be shown on data plates (see 3.6.3).
h. Selection of applicable levels of protection (see 5.1).

6.3 Sampling of trailers. Sampling inspection of trailers may be initiated by the production contractor only upon receipt of written authorization from the Government acquisitioning activity. In the event the Government authorizes sample inspection of the end item, the production contractor must then meet the sampling criteria specified in 4.5.4. Sample inspection of components or materials however, is at the discretion of the contractor. Such sampling must be in accordance with sampling plans of applicable military standards and must be part of the contractor Quality Assurance System approved by the Government.

6.4 Process average. Sampling may be initiated when authorized by the Government acquisitioning activity (see 6.3) and when the process average value for 20 consecutive trailers inspected is less than the AQL specified in the classification of defects for major and minor defects.

Process average shall be computed as follows:

$$\text{Process average} = \frac{\text{Number of defects}}{\text{Number of trailers inspected}} \text{X100}$$

If the computed process average exceeds the specified AQL, 100 percent inspection shall be performed and continued until such time that the process average for 20 consecutive trailers is less than the specified AQL.

6.5 Definitions of recurring major and minor defects. The Government Inspector will verify that a thorough inspection of each trailer is performed by the contractor not only for the listed characteristics (see tables IV, V and VI), but also for any other departures from good workmanship. The Government Inspector will assure that all deficiencies encountered during the inspection are enumerated on the deficiency sheet for the semitrailer. The defects noted on the deficiency sheet shall contain sufficient description to enable the Government inspector and the contractor representative to classify the deficiency in accordance with the classification of defects of the semitrailer specification and definitions contained in MIL-STD-105. Corrective action shall be taken for recurring deficiencies.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

6.6 Failure definition. Failure of the trailer is defined as inability to perform its specified operational functions during emplacement or mobile events. Accordingly, semitrailer failure is a function of the PATRIOT Air Defense System Guided Missile Transporter and Large Repair Parts Transporter mission events; that is, air defense mission, march order, road march and emplacement.

6.6.1 Failure classifications. Failure incidents shall be classified for reliability assessment purposes as:

a. Chargeable failures (relevant).

(1) Mission essential.

(2) Non-mission essential.

6.6.2 Scoring criteria.

a. Chargeable failures (relevant).

(1) Failures from workmanship deficiencies.

(2) Failures during maintenance action not induced by maintenance action.

(3) Failures which require component replacement or adjustment at other than prescribed intervals.

(4) Failures caused by human factors design.

(5) All independent chargeable simultaneous failures.

(6) All trailer incidents which would result in the inability to complete air defense mission events, even though there is no evidence of hardware failure, shall be scored.

(7) Trailer failures which are functionally redundant or do not singularly prohibit completion of air defense mission events, that is, relevant (non-mission essential), shall be scored in determining the MTBF of the trailer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.

b. Non-chargeable failures (non-relevant).

(1) Secondary failures induced by chargeable primary failures.

(2) Failures which occur as a result of incorrect test-peculiar maintenance activities.

(3) Failures which occur as a result of misuse or abuse.

(4) Failures resulting from failure to perform prescribed preventive maintenance.

(5) Failures resulting from system operation outside established requirements.

6.7 Recycled materials. The use of recycled materials which meet the requirements of the applicable material specifications without jeopardizing the intended use of the item shall be encouraged (see 3.3).

6.8 First article. First article samples shall be tested and approved under the appropriate provisions of 7-104.55 of the Defense Acquisition Regulation. The contracting officer should include specific instructions in all instruments regarding arrangements for examination, tests and approval of the first article (see 3.1).

6.9 Like-new condition. Like-new condition is a vehicle condition that conforms to requirements of the final inspection record and does not exceed component wear tolerances.

Custodian:
Army - AT

Preparing activity:
Army - AT

Project No. 2330-A799

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:41Z
Check the source to verify that this is the current version before use.