MIL-S-17041G
29 April 1985
SUPERSEDING
MIL-S-17041F
22 April 1980

MILITARY SPECIFICATION

SNOW REMOVAL UNITS, SELF PROPELLED, DIESEL ENGINE DRIVEN, 40 TONS PER MINUTE CAPACITY

This specification is approved for use by all Departments and Agencies of the Department of Defense.

* 1. SCOPE

1.1 Scope. This specification covers snow removal units consisting of an independently diesel engine driven rotary blower plowhead mounted on the front of a four-wheel drive, diesel-engine-driven carrier.

1.2 Capability. Snow removal units shall be capable of removing 40 tons of snow per minute at speeds up to 20 miles per hour (mph).

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. Unless otherwise specified (see 6.2), the following specifications, standards, and handbooks of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATION

MILITARY

MIL-B-121 - Barrier Material, Greaseproofed, Waterproofed, Flexible.
MIL-T-704 - Treatment and Painting of Material.

STANDARDS

FEDERAL

FED-STD-297 - Rustproofing of Commercial (Nontactical) Vehicles.
FED-STD-595 - Colors.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, Port Hueneme, CA 93043, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 3825

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-STD-129 - Marking for Shipment and Storage.
MIL-STD-209 - Sling Eyes and Attachments for Lifting and Tying Down Military Equipment.
MIL-STD-281 - Automobiles, Trucks, Truck Tractors, Trailers and Trailer Dollies; Preservation and Packaging of.
MIL-STD-1223 - Administrative Wheeled Vehicles Treatment, Painting, Undercoating, Identification Marking, Data Plates and Warranty Notice Standards.
MS51317 - Light, Warning, Vehicular, Rotating, DC.

(Copies of specifications, standards, handbooks, drawings, and publications required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.

(Copies of military specifications and standards required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other Government documents, drawings, and publications. The following other Government documents form a part of this specification to the extent specified herein.

DEPARTMENT OF TRANSPORTATION (DoT)

Federal Motor Carrier Safety Regulations.

(Application for copies should be addressed to the Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402.)

CODE OF FEDERAL REGULATIONS (CFR)

Title 45, Environmental Protection Agency (EPA)

Part 1201 - Motor Vehicle Air Pollution Standards.

(Application for copies should be addressed to the Public Affairs Office, Environmental Protection Agency, Rockville, MD 20852.)

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, Inc., 400 Commonwealth Drive, Warrendale, PA 15096.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

TIRE AND RIM ASSOCIATION, INC. (TRA)

TRA Yearbook.

(Application for copies should be addressed to the Tire and Rim Association, Inc., 3200 West Market Street, Akron, OH 44313.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

* 3.1 Description. The snow removal unit shall be the commercial product of the manufacturer's latest design and shall meet the requirements specified herein. The rotary plowhead shall be hydraulically controlled and driven by a diesel engine mounted on the carrier chassis. The plowhead shall be equipped with truck loading and spot casting discharge chute(s), blowers or rotaries and ground support shoes. The rotary plowhead shall be mounted on the front of a four wheel, four-wheel drive, diesel-engine-driven, engine forward, cab over engine chassis or rear engine type. Rear wheels shall interchange with the front wheels and have the same tracking width as the front wheels without the use of spacers. The snow removal unit shall have the minimum capability of removing 40 tons of 20-30 pounds per cubic foot (lbs/cu ft) snow per minute. The snow removal unit shall have all accessories, parts, and components to make a complete and serviceable unit.

3.2 First article. When specified (see 6.2), the contractor shall furnish one complete snow removal unit for first article inspection and approval (see 4.2.1 and 6.4).

* 3.3 Standard commercial product. The equipment shall, as a minimum, be in accordance with the requirements of this specification and shall be the manufacturer's standard commercial product. Additional or better features which are not specifically prohibited by this specification but which are a part of the manufacturer's standard commercial product, shall be included in the unit being furnished. A standard commercial product is a product which has been sold or is being currently offered for sale on the commercial market through advertisements or manufacturer's catalogs, or brochures, and represents the latest production model.

* 3.3.1 Cleaning, treatment and painting. Surfaces shall be cleaned, treated and painted, in accordance with MIL-T-704, Type A. The surfaces to be painted shall be primed with Zinc Phosphate Primer Paint applied to a dry film thickness of 1.5. The primer used shall be compatible with the final paint system. The finished paint shall be Polyurethane Enamel applied to a dry film thickness of 1.8 - 2.5 mils. The finish color shall be Yellow gloss No. 13538 of FED-STD-595, and shall be applied to all surfaces normally

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

painted in good commercial practice. Radiator grille, headlight rings and other exterior trim shall match the exterior color specified except that chromium plated, cadmium plated, stainless steel or anodized surface need not be painted.

3.3.1.1 Identification marking. Identification marking and registration numbers for the snow removal unit shall comply with MIL-STD-1223.

3.3.2 Instruction plates. The snow removal unit shall be equipped with instruction plates suitably located, describing any special or important procedures to be followed in operating and servicing the equipment including schematic of piping, valves and controls. Plates shall be of a material which will last and remain legible for the life of the equipment, and shall be securely affixed to the snow removal unit with non-ferrous screws, bolts or rivets of not less than 1/8-diameter. Unless protected against electrolytic corrosion, dissimilar metals shall not be used in contact with each other.

* 3.3.3 Rustproofing. The vehicle shall be rustproofed in accordance with FED-STD-297 (see 6.2).

3.3.4 Drain plugs. All drain plugs installed for the purpose of draining lubricants and hydraulic fluids shall be of the permanent magnet type.

3.3.5 Radio interference characteristics. When specified (see 6.2), the snow removal unit shall conform to the radio interferance characteristics requirements and test limits of SAE J551.

3.3.6 Towing devices. Not less than two hooks, loops or pins for towing the snow removal unit shall be provided on the rear of the carrier and shall be attached to the frame members.

3.3.7 Rear wheel splash and stone throw protection. Manufacturer's standard splash guards shall be provided in the back of the rear tires. Splash and stone throw protection shall conform with SAE J682.

3.3.8 Tying down attachments. When specified (see 6.2), the carrier shall be provided with tying down attachments conforming to MIL-STD-209.

3.4 Safety. All rotating or reciprocating parts and all parts subject to high operational temperatures that are of such a nature, or are so located, as to be or become a hazard to operating or attending personnel, shall be substantially guarded or insulated to the extent necessary to eliminate the hazard, except the blower impellers and/or cutters. A back up alarm or warning horn, complying with SAE J994, shall be provided. Blower impellers and/or cutters shall have an operator controllable quick shutdown.

3.5 Materials. Materials used shall be free from defects which would adversely affect the performance or maintainability of individual components or of the overall assembly. Materials not specified herein shall be of the

Source: https://assist.dla.mil -- Downloaded: 202610-18T09:42Z
Check the source to verify that this is the current version before use.

same quality used for the intended purpose in commercial practice. Unless otherwise specified herein, all equipment, material, and articles incorporated in the work covered by this specification are to be new and fabricated using materials produced from recovered materials to the maximum extent possible without jeopardizing the intended use. The term "recovered materials" means materials which have been collected or recovered from solid waste and reprocessed to become a source of raw materials, as opposed to virgin raw materials. None of the above shall be interpreted to mean that the use of used or rebuilt products are allowed under this specification unless otherwise specified.

* 3.6 Interchangeability. All units of the same classification furnished with similar options under a specific contract shall be identical to the extent necessary to insure interchangeability of component parts, assemblies, accessories, and spare parts.

3.7 Fenders, walking surfaces, and handholds. Fenders shall be provided over front and rear wheels. All exterior platforms, steps and other walking surfaces and standing surfaces shall be of open metal grating with nonskid surface. Ladders, steps, and handholds shall be furnished on the sides of the cab and superstructure as required for unhampered and non-hazardous access. Step surfaces and walkways shall be nonskid type.

3.8 Performance.

3.8.1 Speed and gradeability. The fully equipped snow removal unit, loaded to rated gross vehicle weight (gvw) and with rotary plowhead in transport position, shall be capable of maintaining a continuous forward speed of not less than 35 mph on dry level pavement and negotiating a 4 percent dry, smooth paved grade at 25 mph.

3.8.2 Brake performance. With the plowhead in the transportable position the service brakes shall comply with the performance requirements specified in DoT Motor Carrier Safety Regulations, section 393.52. The parking brake shall be adequate to hold the fully equipped snow removal unit on a 30 percent grade, on a surface free from snow, ice, or loose material. In any event, the parking brake shall be capable of locking the braked wheels to the limit of traction.

* 3.8.3 Snow removal operation. Snow removal performance requirements shall conform to the following:

a. General. The snow removal unit shall clear a swath at least 8 feet wide in one pass leaving snow not more than 1/2 inch deep, while operating in a depth from 1-1/2 inches to 4 feet at a rate of 2400 tons per hour at speeds up to 15 mph.
b. Plowing. When operating in snow having one of the density ranges shown in Table I, the snow removal unit shall cast snow at the required tonnage rate and distance shown in Table I. Casting

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

distance shall be measured from the longitudinal centerline of the snow removal unit to the center of the mass within the perimeter of the cast pattern. Casting performance shall be obtained under no wind conditions.

c. Speed. When clearing an 8 foot wide swath in snow having one of the density ranges and speed shown in Table I and depth of at least 3 inches, the snow removal unit shall operated effectively without spillage, leaving snow no more than 1/2 inch deep.

d. Spot casting. The snow removal unit shall be capable of casting snow, having any of the densities shown in Table I, through truck loading and spot casting chute(s). The truck loading chute(s) shall be capable of directing the snow being cast throughout a horizontal arc of at least 90 degrees (°) to the right and 90° to the left of the centerline of the snow removal unit. Additionally, the chute(s) shall be capable of directing the snow being cast to any point on the ground from 14 feet to 50 feet from the center of the rotary plowhead, throughout the horizontal casting range.

e.

TABLE I

SNOW DENSITY LBS/CU FT	SPEED MPH	CASTING DISTANCE FEET	TONS PER HOUR
Under 10	20	100	2200
20 - 30	15	95	2400
30 - 40	10	90	2600

3.9 Environmental conditions.

3.9.1 Temperature conditions. Snow removal unit shall start and operate in any ambient temperature as low as -25° Fahrenheit (F), and shall not be damaged by being stored in any ambient temperatures from +160°F to -65°F.

* 3.9.2 Winterization. When specified (see 6.2), the complete snow removal unit shall be winterized and shall be able to start and operate in an ambient temperature as low as -40°F.

* 3.10 Engine(s). The carrier engine and the plowhead engine shall be diesel powered and use the same type fuel. Each engine shall have horsepower (hp), torque and speed characteristics to satisfactorily meet all its performance requirements as specified herein. If a single engine driven carrier and plowhead is provided, the snow removal unit must meet or exceed all of the performance requirements specified herein. The engine manufacturer shall furnish written approval of each engine application.

3.10.1 Oil filter. A full flow type oil filter shall be furnished for each engine.

3.10.2 Fuel system. The fuel systems shall conform to DoT Motor Carrier Safety Regulations, section 393.65.

Source: https://assist.dla.mil -- Downloaded: 202610-18T09:42Z
Check the source to verify that this is the current version before use.

* 3.10.2.1 Air cleaner. An engine air cleaner shall be furnished for each engine. The cleaners shall be located and protected to meet the respective engine manufacturers recommendations for this type of equipment. Air cleaners shall be dry type, with condition indicator.

3.10.2.2 Fuel tank(s) and fuel lines. Fuel tank(s), having a total capacity sufficient to supply fuel to both the carrier engine and the plowhead engine when both engines are operating at rated intermittent hp at governed speed for not less than 8 hours, shall be provided. When more than one tank is furnished, means shall be provided to assure equalized fuel level in both tanks. Fuel lines shall be interconnected so that either or both engines are supplied with fuel. Fuel lines shall be securely fastened in place, installed to prevent chafing or strain and protected by grommets where lines project through metal apertures.

* 3.10.3 Heavy-duty cooling sytems. A heavy-duty cooling system shall be provided. The cooling system shall be of the pressurized type of sufficient capacity to maintain a cooling liquid temperature of not less than 140°F, and to provide proper cooling without overheating or loss of coolant when operating in an ambient temperature range of -25°F to +125°F during operating conditions of either stationary or mobile performance as specified.

* 3.10.3.1 Coolant recovery system and indicators. The coolant recovery system shall include a de-aeration system, and, if required, a surge tank, or a coolant recovery reservoir of not less than 2 quarts capacity. In addition, a low coolant level or high coolant temperature alarm buzzer and red warning light shall be provided on the cab instrument panel.

3.10.4 Exhaust system. The exhaust system shall conform to DoT Motor Carrier Safety Regulations, section 393.83, and include muffler, if necessary, and exhaust piping. Horizontal portions of the exhaust systems shall be provided with a cover plate that will shed fluids, where spilled fuel may come in contact with the system. Exhaust piping, when located at the rear of the carrier cab, shall be furnished with a heat shield. Vertical exhaust piping shall be equipped with a rain shield.

* 3.10.5 Starting system. The carrier engine shall be furnished with an electric starting system. The plowhead engine shall be furnished with an electric or air starting system, as specified (see 6.2). Each system shall be complete, including all necessary components and controls. The system shall have the capacity to start the carrier engine and plowhead engine at -25°F ambient temperature (-40°F if winterization is specified in 6.2). The starting aid system shall be of the heat sensing type which avoids use with a hot engine.

3.10.5.1 Electric start. The starting system shall be of 24 volt (V) or 12V negative ground type. The starting motor shall be of heavy-duty type.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

3.10.5.2 Pneumatic starting. The pneumatic starting system shall utilize the brake system air compressor as a source of compressed air. The system shall include a cranking motor, separate air reservoir of not less than 11 cu ft volume, filter, and all necessary piping and valves, including a one way check valve installed ahead of the starting air reservoir.

* 3.10.6 Governors. The carrier and plowhead engines shall each be equipped with a governor, set to limit the engine speed to the maximum engine operating speed. The plowhead engine shall provide a no load and a full load maximum speed governor.

3.10.7 Engine hour meters. One engine hour meter for each engine shall be furnished, having a totalizing mechanism of not less than 9,999 hours, to register accurately the number of hours of engine operating time. Meters shall be of strong rugged construction to insure continuous trouble-free performance under the extreme equipment operating conditions indicated herein and shall be mounted on the snow removal unit so that they can be conveniently and easily read by personnel servicing the snow removal unit.

3.10.8 Safety devices. The plowhead engine shall be provided with visual and audible systems to indicate shut off of the engine under conditions of low lubricating oil pressure and high engine temperature.

3.10.9 Air pollution control. All vehicles shall comply with the EPA regulations governing control of air pollution for New Motor Vehicles and Engines applicable on the date of manufacture to non-military, non-export motor vehicle products.

3.11 Housings. The carrier and plowhead engines shall be provided with housings to properly protect the engines under extreme weather conditions. All joints and overlaps shall be weather tight. Doors and hinged covers, reinforced as required for rigidity, shall be provided to afford convenient access to engine and controls and shall be furnished with positive fastening devices. All latches and handles shall be designed for operation by personnel wearing arctic mittens. Intake for combustion air shall be so located as to minimize the entry of blowing snow and shall not be subject to contamination by exhaust gases. Provisions shall be made for draining the cooling system, oil pan and fuel system. Housings on engine(s), which are located to the rear of the carrier cab, shall be an integral assembly provided with lift attachments for removal by a hoist.

3.12 Carrier.

* 3.12.1 Chassis. The carrier chassis shall be constructed to perform under all operating conditions indicated herein without permanent deformation and with a minimum of maintenance. The chassis shall be provided with four single wheels, arranged for four-wheel drive. Four wheel steering may be used to meet the turning circle. Frame shall be of pressed or structural steel channel, reinforced as required to prevent distortion under maximum loads.

Source: https://assist.dla.mil -- Downloaded: 202610-18T09:42Z
Check the source to verify that this is the current version before use.

3.12.2 Dimensions. Limiting snow removal unit dimensions shall be as follows:

a. Overall height excluding rotary plowhead, lights and exhaust stack, no more than 132 inches.
b. Overall width without rotary plowhead, not more than 108 inches.
c. Wheelbase, not more than 162 inches.
* d. Wall-to-wall turning circle with rotary plowhead, maximum 75 feet.
* e. Ground clearance without rotary plowhead, at least 11 inches.

3.12.3 Electrical system. The electrical system shall be 12/24V negative ground system. All components required to provide a complete and functional system shall be furnished. Wiring shall, when possible, be grounded together and protected by a nonmetallic covering capable of withstanding severe abrasion, or be enclosed in a metallic sheath or tube. Wiring shall be properly supported and located so as to not be overheated or immeshed in moving parts. All electrical wiring shall conform to SAE J556.

* 3.12.3.1 Battery charging system. An alternator and regulator shall be furnished with sufficient capacity to maintain the carrier's battery(s) in a fully charged state while the units electrical system is operating at a maximum capacity, regardless of engine revolutions per minute.

* 3.12.3.2 Batteries. Not less than two 12V negative ground batteries, of the maintenance free type, shall be provided. The batteries shall be rated for at least the engine manufacturer's recommended cold cranking ampere for engine starting at -25°F (-40°F if winterized) and for the necessary reserve capacity for the electrical load. Batteries shall be contained in a metal box or frame with an acid resistant interior coating and/or pan, in a protected, easily accessible location. Batteries shall not be mounted on the top of the chassis front fenders.

3.12.3.3 Lighting system. Lighting system shall conform to DoT Motor Carrier Safety Regulations, sections 393.12, 393.19 through 393.31 and 393.33. The electrical circuits shall be protected by circuit breakers and shall be controlled by heavy-duty service switches. Circuits shall be color coded or numbered. Wiring identification shall be consistent throughout the snow removal unit. Headlights and turn signals shall be mounted so that the rotary plowhead will not interfere with illumination of road or visibility of the signals. The following additional lights shall be furnished:

a. Two spotlights, one on each side of the forward part of the carrier and controllable by the driver when seated in his operating position.
b. One amber warning light, conforming to MS51317, part number MS51317-3 or MS51317-4, or equal as applicable. The warning light shall be so installed on the top of the cab as not to be obstructed by exhaust pipes or other components for more than 15° continous horizontal angle by each obstruction.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

c. Two 4 inch back up lights shall be provided on the rear of the carrier aimed to provide maximum illumination for backing. Lights shall be automatically operated in the act of shifting into reverse gear.
d. Instrument and dash panel, with dimming rheostat, and cab interior lights.

3.12.4 Transmission. A torque convertor and manually controlled power-shift, automatic or hydrostatic type transmission matched to the operating characteristics of the carrier engine shall be provided. Design of transmission and location of controls shall provide for the maximum practicable ease of gear selection. The transmission shall have not less than four forward and one reverse speed gear ratios. The shifting of gears in forward speed, either up or down through all gear ratios, shall be possible without interrupting the output of power from the engine through the drive train of the carrier. Torque capacity of the components shall be adequate to transmit the maximum gross torque of the engine through all gear reductions or torque multiplications, or not less than the torque required for wheel slip on a surface having a static coefficient of 0.80 whichever is less. Gears shall be heat treated and properly finished to ensure quiet operating. The torque converter shall operate at no less than 70 percent efficiency to meet the performance requirements specified herein.

* 3.12.5 Transfer asssembly. The transfer assembly shall provide a drive to the front and rear axles. When a cam or gear type differential is used, a manual or automatic locking means shall be provided that will maximize the transmission of torque to all wheels, regardless of traction conditions.

3.12.6 Axles. Front and rear axles shall be the manufacturer's standard full floating type, designed for single tire mounting. The front and rear tread widths shall not vary more than 3-1/2-inches. Wheel spacers shall not be used to obtain correct tread widths. The axles shall be equipped with manual or automatic locking type differentials. The torque capacity of each axle and differential shall be at least 10 percent in excess of the maximum torque to which the axle could be subjected, under any operating condition, with the carrier fully loaded. Axle ratings shall be at least equal to the load imposed on each axle, measured at the ground, at rated gvw. The power transmitting shaft, on the steering axle, shall incorporate steeing joints of the type that produce no objectionable steering characteristics throughout their range of angular travel with the steering joints enclosed in protective housings.

3.12.7 Suspension. The suspension system of the carrier shall be equipped with components having a rated capacity of at least equal to the load imposed on each member, measured at the ground, with carrier loaded to rated gvw, and with rotary plowhead in the transportable position. Auxiliary springs may be provided on front and rear axles. When suspension capacity is rated at the spring pads, unsprung weight shall be deducted.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

3.12.8 Wheels, rims, and tires. Carrier shall be equipped with single front and single rear disc type wheels. Rims and tire ratings shall conform to TRA recommendations for the same type and size tires furnished. Tire and rim sizes shall be the same for all wheels on each snow removal unit and must be interchangeable between front and rear.

3.12.8.1 Tires. Tires shall be tubeless type with traction type tread. Tires shall be of rated capacity at least equal to the load imposed on each tire, measured at each wheel at the ground, when the snow removal unit is loaded to its gvw and the rotary plowhead is in transport position. Tires shall be not less than 100 level quality.

3.12.8.2 Spare wheel. When specified (see 6.2), one spare wheel shall be furnished.

3.12.8.3 Tire chains. When specified (see 6.2), four anti-skid tire chain assemblies, consisting of two side chains with cross chains and suitable end fasteners, shall be provided. Tire chain assemblies shall be designed for use with the tires and wheels furnished with the snow removal unit.

3.12.8.4 Tire clearance. Clearance shall be provided for installation and use of tire chains on all wheels, in accordance with SAE J683.

3.12.9 Brakes. Brakes shall conform to the DoT Motor Carrier Safety Regulations, sections 393.40, 393.42, 393.45 through 393.51, and as specified herein.

3.12.9.1 Service brakes. Snow removal unit shall be equipped with manufacturer's standard full-air type or air over hydraulic four wheel service brakes. Braking system shall be complete with all necessary components including the following:

a. Air compressor, engine driven and engine oil lubricated, air or water cooled, with rated capacity recommended by carrier manufacturer for this type of vehicle.
b. Air storage reservoirs with total capacity, as recommended by the carrier manufacturer, each tank equipped with a drain and with safety and check valves between compressor and last reservoir tank.
c. Foot control, suspended or treadle type.
d. Limiting valve for front brakes, combined with quick-release valve (for full air brakes).
e. Quick-release valve, for rear brakes (for full air brakes).
f. Air-dryer with heated moisture ejector.

* 3.12.9.3 Emergency brake system. The emergency/parking brake system shall be capable of being manually applied by the operator seated in the driver's seat. The emergency system shall conform to DoT Motor Carrier Safety Regulations, section 393.41. Spring applied type emergency brakes shall be of the type that is an integral part of, or mounted on the brake chamber.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

* 3.12.10 Steering. The front axle shall be equipped with hydraulic assisted mechanical steering of the front wheels. Steering components shall be installed in such a manner to protect them from damage.

3.12.10.1 Emergency steering. With power assist disabled, vehicle shall meet or exceed performance tests in SAE J53 to the second finish line, when tested as a wheel tractor.

* 3.12.11 Cab. The cab shall be of steel or aluminum construction, fully enclosed, insulated and shall be provided with cushioned seats for two men. The seat for the driver shall be adjustable for height and fore-aft positions. The cab shall have an overall width when measured at the rear of the doors at the seat level, of not less than 65 inches. The cab glazing and window construction shall conform to DoT Motor Carrier Safety Regulations, sections 393.60(a) and 393.61(a). Windshield shall be tinted for glare protection in accordance with manufacturer's standard for tinted, heat absorbing glass. Tinting of lamination is not acceptable. The windshield shall be heated with electrical heating elements incorporated into the windshield construction, and controlled with a dash switch. Cab shall be provided with dual sun visors of the type that will afford the driver and the plow operator sun protection. Cab ventilators, if used, shall be screened and shall be so located to minimize entry of snow. The cab shall have a hinged door on each side providing easy access. Running boards, cab steps, assist handles and bars shall be of ample size and design to insure safety and easy entrance and exit of both sides of the cab for personnel wearing bulky arctic overshoes, mittens and outer garments. All step surfaces on the exterior of the cab shall be of the nonskid open grate type. Cab shall have two heated west coast type outside rearview mirrors, one mounted on each side of the cab, each with at least 85 square inches of reflective area, and each with at least three supporting arms. Manufacturer's standard fastenings and two pairs of seat belts shall be installed.

3.12.11.1 Cab insulation and heating. Cab insulation and cab heater shall be capable of providing and maintaining a minimum inside temperature of 55°F at an ambient temperature of -25°F with 10-15 mph wind. Heater shall be the manufacturer's standard liquid coolant operated type meeting the requirements of DoT Motor Carrier Safety Regulations, section 393.77, as applicable. Defroster shall meet the requirements of DoT Motor Carrier Safety Regulations, section 393.79, shall keep not less than 75 percent of the windshield area clear at an ambient temperature of -25°F, and shall be provided with an air regulation control. Heater and defroster controls shall be mounted on the instrument panel within normal reach of the driver.

3.12.11.2 Windshield wipers and washers. Cab shall be equipped with dual, air or electric operated, multi-speed type windshield wipers. Dual windshield washers shall be furnished, with a minimum of a one gallon supply container.

3.12.11.3 Two-way radio equipment. When specified (see 6.2), installation space shall be provided in the cab for two-way radio equipment. Dimensions of the required space shall be specified (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

3.12.11.4 Instrument panel. The cab shall be provided with an instrument panel equipped with instruments and controls located in full view of the operator. Control levers and switches shall be designed to be operated by an operator in winter gloves and gear. All instruments and controls shall be labeled, in English, in a manner legible for the life of the carrier, to indicate function and be illuminated by rheostat controlled lighting for night operation. All instruments and controls necessary for proper operation of the snow removal unit and the plowhead engine shall be provided and shall, as a minimum, include the following:

a. Ammeter or voltmeter.
b. Fuel level gauge(s).
c. Lubricating oil pressure gauges for carrier and plowhead engines.
d. Engine coolant temperature guages for carrier and plowhead engines.
e. Speedometer with odometer.
f. Tachometers for carrier and plowhead engines.
g. Brake-air reservoir pressure gauge.
h. Low air pressure warning, visual and audible type.
i. Engine hour meters for carrier and plowhead engines.
j. Light switches and head light beam indicator.
k. Starting controls for carrier and plowhead engines.
l. Torque converter oil temperture and pressure gauge, if required, (when equipped with converter).
m. Cranking system air reservoir pressure gauge (when equipped with air start system).
n. Hydrostatic pressure gauge(s) (when equipped with hydrostatic system).
o. Hydrostatic temperature gauge(s) (when equipped with hydrostatic system).

3.12.11.5 Horn. The carrier shall be equipped with an air horn of sufficient volume to be heard above the sound level of both of the engines when operating at full power.

3.13 Rotary plowhead assembly. The rotary plowhead assembly shall consist of the engine, power train, rotary plowhead with hitch, and hydraulic system.

3.13.1 Engine mounting. The plowhead engine shall be mounted to the carrier chassis.

* 3.13.2 Power train components. The power train shall consist of a clutch, converter, or hydrostatic unit, shafts, universal joints, reduction gears and chains as applicable. Clutch shall be rated for transmitting maximum gross torque of the engine as developed through the intervening gear reduction. Clutch housing, converter or hydrostatic unit, shall be rigidly mounted on the engine block to prevent misalinement. Clutch, converter or hydrostatic control and engine speed control shall be located in the carrier cab convenient to the driver.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

* 3.13.3 Rotary plowhead. The cutting head of the rotary plowhead assembly shall have a minimum cutting width of 8 feet and a minimum cutting height of 4 feet. The rotary plowhead shall be equipped with one or two truck loading and spot casting discharge chute(s), blowers or rotaries, and shall be capable of complying with the requirements specified herein. Chute(s) shall be hydraulically operated from controls located in the carrier cab. The fans, cutters, rakers, feeders, augers, or helical cutter blades, blowers or rotaries, as may be incorporated in the manufacturer's design, shall be provided with individual shearpins or bolts or with hydrostatic pressure override and relief valves that will protect the operating machinery from damage or excessive stress due to contact with solid foreign objects. Shearpins or bolts shall be replaceable by personnel wearing arctic clothing and using common tools, without the removal of components. The moldboard, when in transport position, shall have a ground clearance of not less than 9 inches, and be held in the transport position mechanically so as to completely relieve the hydraulic system. The rotary plowhead shall be designed to enable the snow removal unit to negotiate uneven surfaces and obstacles in forward and reverse without damage. The ground support shoes shall be bolt-on adjustable skate, roller or saucer shape rotating type. Shoes shall be of sufficient strength to support the weight of the rotary plowhead, and be replaceable by operating personnel in the field. The rotary plowhead shall be attached to the carrier by means that will transmit the rotary plowhead thrust directly to the carrier without damage to, or misalinement of, any member.

3.13.4 Cutter bars. When specified (see 6.2), cutter bars shall be furnished in accordance with the manufacturer's design. When fitted with cutter bars, the snow removal unit shall be capable of removing snow up to 8 feet in depth.

3.13.5 Hydraulic system. The hydraulic system shall consist of cylinders, pump, piping, fittings, valves, controls, fluid reservoir, fluid filter and all other parts essential to efficient operation. The system shall be capable of positioning the hydraulic actuated equipment on any chosen position within the design limits of travel, and shall be of such capacity that all controls can be operated simultaneously without notable reduction in response. All hydraulic controls for operating the rotary plowhead shall be located in the carrier cab within easy reach of the operator. Hydraulic system shall be constructed to withstand all loads imposed in the snow removing operations without the use of mechanical locks. No high pressure hydraulic valves or hoses shall be located inside the cab. Filtration of the hydraulic system shall conform to SAE J931.

3.13.5.1 Hydraulic pump and power takeoff. Pump shall be heavy-duty type, driven by the carrier drive engine and shall have sufficient capacity to operate all hydraulic equipment specified herein under all operating conditions and speeds.

* 3.13.5.2 Hydraulic lines and fittings. Hydraulic tubes, hoses, and fittings conforming to SAE J514, J516, J517, and J524 shall be used. A minimum number of fittings, joints, and connections shall be used to prevent excessive back pressure and leakage. Hydraulic lines shall be of sufficient size to permit free flow of hydraulic fluid at temperatures down to -40°F.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

3.13.5.3 Hydraulic fluid tank. The hydraulic fluid tank shall be equipped with a filler neck, strainer, drain plug, and shutoff valve. An air vent shall be incorporated in the filler cap. Baffles, as required, shall be provided. The tank capacity shall be adequate to hold not less than 120 percent of the volume of oil required for operation of any combination of attachments.

3.13.5.4 Hydrostatic system. When hydrostatics are used, the system shall consist of a variable-displacement pump, fixed or variable-displacement motor, high-pressure hoses and/or piping, fittings, valves, controls, fluid reservoir, return line filter of not less than 10 micron element, and all other components essential to efficient operation.

3.13.5.5 Hydrostatic fluid tank. The hydrostatic fluid tank shall be equipped with a filter neck with strainer, drain plug, and shutoff valve. Baffles as required shall be provided. The tank capacity shall hold not less than 120 percent of the volume of oil required for operation.

* 3.14 Lubrication. Lubrication means shall be provided for all parts of the equipment normally requiring lubrication. Where the use of high lubrication pressure will damage grease seals or other parts, fittings with pressure release shall be used. Unless otherwise specified in section 5, the snow removal unit shall be lubricated prior to delivery with lubricants designated for use in the ambient air temperature at the delivery point. The snow removal unit shall be conspicuously tagged to identify the lubricants and their temperature range. All bearings (except sealed-for-life type), mating gears and sliding parts shall be provided with means for lubrication. The reservoirs of splash-type systems shall be fitted with an acceptable method or checking the oil level. All oil holes, grease fittings and filler caps shall be easily accessible. All drain plugs installed for the purpose of draining lubricants and hydraulic fluids shall be of the permanent magnet type.

3.15 Fire extinguisher. When specified (see 6.2), fire extinguisher(s) shall be provided. Such extinguisher(s) shall be mounted so as to be readily accessible to the operator. Type size and quantity shall be specified in 6.2.

3.16 Tools. When specified (see 6.2), the snow removal unit shall be furnished with tools required for exchanging mounted tire assembly with the spare assembly and shall include at least a jack, jack handle, and wheel nut wrench. The jack shall be of such closed height as to permit its location under either axle, or other satisfactory lift point, at any wheel with a flat tire. The jack, without blocking, shall be capable of raising any wheel of the loaded snow removal unit to a height adequate to permit removal and replacement of wheel and tire assembly. Stowage space of sufficient size to accommodate the jack, handtools, warning flares, reflectors and tire chains shall be provided. If storage space for these tools is located outside of the cab, it shall be in a readily accessible location, weather proof and shall provide for locking with a padlock.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

* 3.17 Lifting attachments and quick disconnects.

a. Lifting attachments shall be installed on the snow blower or cutter head, located for quick and easy attachment for its removal.
b. Quick disconnects shall be mounted in the front of the carrier unit. The disconnects shall be compatible with the snow blower and snow cutter. The quick disconnects shall enable the driver, without assistance, to mount or remove the blower or cutter head attachment.

3.18 Workmanship. Workmanship of the snow removal unit, allied equipment and accessories shall be of the quality prevailing among manufacturer's normally produced equipment of the type specified herein. Defective components, parts or assemblies which have been repaired to overcome deficiencies shall not be furnished.

3.18.1 Steel fabrication. The steel used in fabrication shall be free from kinks, sharp bends, and other conditions which would be deleterious to the finished product. Manufacturing processes shall not reduce the strength of the steel to a value less than intended by the design. Manufacturing processes shall be done neatly and accurately. All bends shall be made by controlled means to insure uniformity of size and shape.

3.18.2 Fastening devices. All screws, pins, bolts, and similar parts shall be installed with means for preventing loss of tightness. All such parts when subjected to removal or adjustment shall not be swaged, peened, staked or otherwise deformed. Boltholes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in accordance with good commerical practice, and all bolts, nuts, screws shall be tight. Truck frame, if bolted, shall use SAE grade 8 bolts.

3.18.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of approved shape and of uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member.

3.18.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Welds shall be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the weld are subjected to proof and service loadings.

3.18.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping, or any other defect which reduces the castings ability to perform its intended function.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

3.19 Servicing and adjusting. Unless military preservation is required in section 5, prior to acceptance of the snow removal unit by the Government inspector, the contractor shall service and adjust each snow removal unit for operational use incuding at least the following: Focusing of lights, adjustment of engine, electrical, air brake sytems, and lubrication of the snow removal unit and equipment.

3.20 Identification plate. The contracting officer will furnish to the Government inspector the required identification plates. The contractor will be required to stamp the necessary data in the blank spaces thereon and securely affix said plates in a conspicuous place on each unit, assembly or subassembly, and parts as directed by the Government inspector. Nonferrous screws, rivets, or bolts of not less than 1/8-inch in diameter shall be used to affix the plates. The applicable nomenclature contained in the contract item description shall be placed in the top blank.

* 3.21 Noise level. The noise level for the cab interior shall be no greater than 85 decibal (db(A)) steady state and 140 db peak impulse when measured at the operators shoulder and 6 inches from either ear while the blower is operating at maximum capacity, with vehicle windows and vents closed and accessories in the off position. Exterior noise shall be less than 88 db(A) when measured in accordance with SAE J88.

* 4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Material inspection. The contractor is responsible for insuring that supplies and materials are inspected for compliance with all the requirements specified herein and in applicable referenced documents.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

4.2.1 First article inspection. The first article inspection shall be performed on one snow removal unit when a first article is required (see 3.2 and 6.2). This inspection shall include the examination of 4.3 and the tests of 4.4. The first article may be either a first production item or a standard production item from the supplier's current inventory provided the item meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining items to be furnished under the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

4.2.2 Quality conformance inspection. The quality conformance inspection shall include the examination of 4.3, the tests of 4.5, and the packaging inspection of 4.7.

4.3 Examination. Each snow removal unit shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any necessary redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

4.4 First article tests. The first article shall be subjected to the tests specified in 4.4.1 through 4.4.7 and if applicable, to the tests specified in 4.4.8 and 4.4.9. Failure to pass any phase of the required tests shall be cause for the Government to refuse acceptance fo all snow removal units under contract until corrective action has been taken.

4.4.1 Road tests. The fully equipped snow removal unit shall be driven not less than 50 miles. During this test the speed capabilities, gradeability and steering performance shall be tested to verify conformance to 3.8.1 and 3.12.10 respectively.

4.4.2 Turning test. Not less than five full 360° turns in both directions shall be made and the wall-to-wall circle diameter measured to verify conformance to 3.12.2(d).

4.4.2.1 Emergency steering test. Power assist shall be disabled and performance tests of SAE J53 shall be run to determine conformance to 3.12.10.1.

4.4.3 Service brake test. Not less than 25 sudden and successive stops shall be made from a speed of 20 mph on a dry, smooth, level, hard surface road to determine conformance to 3.8.2.

* 4.4.4 Parking brake test. Parking brake test shall be conducted on a 30 percent grade. Parking brake shall hold the snow plow loaded to its gross vehicle weight rating with no slippage in forward and reverse direction.

* 4.4.5 Low temperature test. The snow plow unit shall be subjected to an ambient temperature of -25°F for 24 hours. At the end of this period, at least three engine starts shall be accomplished with each engine to determine conformance to 3.9.1, allowing a minimum interval of two hours between starts. While at an ambient temperature of -25°F, it shall be demonstrated that the cab heater complies with 3.12.11.1. After the last start, the engines shall be allowed to warm to normal operating temperature and all other operable components of the test items shall be operated in a normal manner and examined for possible defects. Written certification may be provided by the manufacturer that the above tests have been conducted on an identical model and test records available.

Source: https://assist.dla.mil -- Downloaded: 202610-18T09:42Z
Check the source to verify that this is the currentversion before use.

4.4.6 Rotary plowhead performance. The snow removal tests specified in 4.4.6.1 and 4.4.6.2 shall be conducted on a snow covered paved airport runway or an adequate size paved airport taxiway. The snow removal test specified in 4.4.6.4 may be conducted on a snow covered, reasonably smooth and level paved roadway, parking area, or runway.

* 4.4.6.1 Snow removal. The snow removal unit shall make at least two snow removal passes in snow not less than 28 inches in depth. At each pass, the snow removal unit shall clear a path at least 1500 feet long by 8 feet wide. Snow depth and density shall be determined in at least five intermediate locations and the average calculated. Density shall be determined from a vertical section of the snow depth. The time of each pass shall be measured by a stopwatch and the length and width of each pass measured. The snow removal rate shall be calculated and the cast distance measured to determine conformance to 3.8.3(b) and Table I.

4.4.6.2 High speed snow removal. The snow removal unit shall make at least two snow removal passes, each at least 1500 feet long, in snow approximately 3 inches in depth, at a continuous forward speed of at least equal to the speed shown for the measured density to determine conformance to the requirements of 3.8.3(c) and 3.8.3(e).

4.4.6.3 Spotting chute test. Spot casting ability shall be tested by casting snow through the complete horizontal arc range at the minimum casting distance to determine conformance to 3.8.3(d).

4.4.6.4 Equipment shakedown and fuel capacity test. The snow removal unit shall be operated over snow covered, paved ground for a period of 8 hours in snow ranging in depth from 3 inches to 4 feet. During this time, the performance of the snow removal unit shall be observed to determine that the various components are of adequate strength, function properly and meet all the requirements of this specification. Snow removal unit shall not be refueled during this time period per paragraph 3.10.2.2.

4.4.7 Lifting attachments and quick disocnnects test. The rotary plowhead shall be tested for conformance to paragraph 3.17.

4.4.8 Test for radio interference characteristics. When radio interference is required, the snow removal unit shall be tested to determine conformance to 3.3.5. In lieu of tests to determine conformance to SAE J551, the manufacturer may furnish a certification that the snow removal unit meets the requirements, together with a list of the suppression devices installed. The list shall be sufficiently detailed to allow visual determination that the devices are installed.

4.4.9 Winterization. When winterization is required, the snow removal unit shall be exposed to an ambient temperature as specified by the procuring activity for a period of 36 hours or until temperature stabilization is reached. Winterized equipment shall then be started and operated to determine conformance to 3.9.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

4.4.10 Noise level testing. Operator noise level testing shall be done during testing in paragraphs 4.4.6, 4.4.7, and 4.4.8. The maximum peak sound level, minimum interval of peaks above 85 db, steady state base level, and the maximum steady state sound level A weighted (slow response) shall be measured. Peaks longer than 500 milliseconds or closer than one half second shall be considered steady state. Instrument calibration and instrument operator certificates shall be verified. Exterior noise shall be measured in accordance with SAE J88 to determine conformance to 3.21.

4.5 Production unit tests. Each snow removal unit shall be adjusted and serviced for operation. Both engines shall be started and then all controls shall be operated at least ten times to determine that the various components function properly. The unit shall be subjected to the road test specified in 4.4.1, except that the driving distance shall be at least ten miles. Service brakes shall be tested with at least five stops as specified in 4.4.3. Parking brakes shall be tested for conformance to the holding requirement specified in 3.8.2.

4.6 Production sample. Upon acceptance of the first production vehicle, it shall remain at the manufacturing facility as a production sample, and be the last vehicle shipped on the contract. The contractor shall maintain the vehicle in a serviceable condition for the duration of the contract.

4.7 Packaging inspection. The preservation, packing, and marking of the item shall be inspected to verify conformance to the requirements of section 5.

* 5. PACKAGING

5.1 Preservation. Preservation shall be level A or C as specified (see 6.2).

5.1.1 Level A. Each snow removal unit shall be preserved and packaged in accordance with mobile requirements of MIL-STD-281 and the following:

5.1.1.1 Hydraulic systems. The hydraulic fluid supply tanks shall be filled to the operating level with hydraulic fluid required for operation. The pistons shall be retracted as far as practicable into the cylinders and secured. When the pistons cannot be fully retracted, the exposed portions of the piston rods (ramshafts) shall be coated with type P-6 or P-11 preservative and the coated surfaces wrapped or covered with barrier material conforming to MIL-B-121, type I, grade A, class 2, extending the wraps approximately 2 inches onto the ram cylinders. The wraps shall be secured in place with waterproof tape. When the pistons can be fully retracted, any remaining uncoated surfaces of the piston rods shall be coated with type P-1 preservative, with no wrapping required. The hydraulic control valves shall be secured in the neutral position and preserved as specified herein for piston rods. Hoses shall not be disconnected. A weatherproof tag shall be attached to the control lever indicating: "The hydraulic supply tank is filled to the operating level with fluid required for operation. Do not drain." Markings shall be applied to the tag with a waterproof material.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

5.1.2 Level C. The equipment shall be preserved in accordance with the contractor's standard practice in a manner to prevent corrosion, deterioration, and damage. The equipment shall be lubricated and serviced for operation as specified in section 3.

5.2 Packing. Packing shall be level A, or C as specified (see 6.2).

5.2.1 Level A. Each snow removal unit shall be prepared for mobile shipment in accordance with applicable carrier rules and regulations. Consolidation containers shall be secured in the cab or on the unit in a manner not to increase cubage or interfere with towing or lifting the snow removal unit with slings.

5.2.3 Level C. The equipment shall be prepared for shipment in a manner which will insure arrival at destination in a satisfactory condition. Preparation for delivery shall comply with applicable carrier rules and regulations.

5.3 Marking. Marking shall be in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use. The snow removal unit covered by this specification is intended for use in removing and dispersing snow from airport runways, taxiways, parking areas, roads, and streets.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Specifications and standards (see 2.1.1).
c. When a first article is required for inspection and approval (see 3.2, 4.2.1 and 6.4).
d. When rustproofing is required (see 3.3.3).
e. When conformance to radio interferance characteristic requirements and test limits are required (see 3.3.5).
f. When carrier shall be provided with tying down attachments (see 3.3.8).
g. When winterization is required (see 3.9.2).
h. Type of starting system required for rotary plowhead (see 3.10.5).
i. When spare wheel is reqired (see 3.12.8.2).
j. When tire chains are required (see 3.12.8.3).
k. When space for two-way radio is required and dimensions of the space required (see 3.12.11.3).
l. When cutter bars are required (see 3.13.4).
m. When fire extinguisher(s) is required and type, size, and quantity required (see 3.15).
n. When tools are required (see 3.16).
o. Level of preservation and level of packing required (see 5.1 and 5.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T09:42Z
Check the source to verify that this is the current version before use.

* 6.3 Data requirements. When this specification is used in an acquisition which incorporates a DD Form 1423, Contract Data Requirements List (CDRL) and invokes the provisions of paragraph 52.227-7031 of the Federal Acquisition Regulations (FAR), the data requirements will be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the approved CDRL (DD Form 1423) incorporated into the contract. When the provisions of FAR 52.227-7031 are not invoked, the data shall be delivered in accordance with the contract requirements.

* 6.4 First article. When a first article inspection is required (see 6.2), the item will be tested and should be a first article sample or it may be a standard production item from the contractor's current inventory as specified in 4.2.1. The first article should consist of one unit. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, test, and approval of the first article.

6.5 Changes from previous issue. The margins of this specification are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

* 6.6 Title change. The title of this specification was changed from "Snow Removal Units, Self-Propelled, Diesel-Engine-Driven, 4 X 4, 36,000 GVW" to "Snow Removal Units, Self-Propelled, Diesel Engine Driven, 40 Tons Per Minute Capacity".

Custodians:

Army - ME
Navy - YD
Air Force - 99

Preparing Activity:

Navy - YD

(Project 3825-0166)

Review Activities:

Army - AT
Air Force - 84

User Activity:

Army - CE

Source: https://assist.dla.mil -- Downloaded: 202610-18T09:42Z
Check the source to verify that this is the current version before use.