MIL-F-48844 (PA)
9 June 1975
SUPERSEDING
See Section 6

MILITARY SPECIFICATION

FUSES, NORMAL, AND TIME-LAG BLOWING

1. SCOPE

1.1 This specification covers requirements, quality assurance provisions, and the preparation for delivery criteria for five types of fuses used to provide electrical and electronic circuit protection which are used in the Nike Hercules warhead section.

1.2 Classification. This specification covers fuses of the following types:

Type I	- Fuse, Normal Blowing, 2 Amperes.
Type II	- Fuse, Time-lag Blowing, 5 Amperes.
Type III	- Fuse, Time-lag Blowing, 10 Amperes.
Type IV	- Fuse, Time-lag Blowing, 1 Ampere.
Type V	- Fuse, Cartridge, 5 Amperes, Normal Instantaneous.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-E-5272	- Environmental Testing, Aeronautical and Associated Equipment, General Specification For.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-202	- Test Methods for Electronic and Electrical Components Parts.
MIL-STD-810	- Environmental Test Methods.
MIL-STD-1168	- Lot Numbering of Ammunition.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

MIL-STD-1169 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components.
MIL-STD-1460 - Soldering of Electrical Connections and Printed Wiring Assemblies, Procedure For.

DRAWINGS

ORDNANCE CORPS

8801516 - Fuse, Time-lag Blowing, 5 Amperes.
8801518 - Fuse, Normal Blowing, 2 Amperes.
8801581 - Fuse, Time-lag Blowing, 10 Amperes.
8822574 - Fuse, Time-lag Blowing, 5 Amperes.
8824868 - Fuse, Time-lag Blowing, 10 Amperes.
8824869 - Fuse, Normal Blowing, 2 Amperes.
9207939 - Fuse, Cartridge: Normal Instantaneous, 5 Amperes.
EL-8801516 - Equipment List.
EL-8801518 - Equipment List.
EL-8801581 - Equipment List.
EL-8822574 - Equipment List.
EL-8824868 - Equipment List.
EL-8824869 - Equipment List.
EL-9207939 - Equipment List.

PUBLICATIONS

UNDERWRITERS LABORATORIES, INC.

- Standard for Fuses.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials. The contractor shall furnish objective evidence (see 6.2) that the material complies with the specifications listed on the applicable drawing.

3.2 Assembly. The fuses shall comply with all requirements specified on the drawing (dwg) 8801516, 8801518, 8801581, 8822574, 8824868, 8824869, and 9207939, with all requirements specified herein, and with the requirements of all applicable specifications to the extent specified on the drawing and herein.

3.3 First article testing. Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

3.4 Voltage ratings.

3.4.1 Continuity. The fuse shall exhibit continuity when tested as specified in 4.4.1.

3.4.2 Current carrying capacity. The fuse shall function satisfactorily when tested as specified in 4.4.2.

3.4.3 Voltage rating. The fuse shall be capable of interrupting alternating or direct current short circuit currents of up to 10,000 amperes minimum at the maximum circuit voltage specified in the detail drawing without glass breakage or external flashover when tested as specified in 4.4.3.

3.4.4 Overload blow time at 135 percent of rated current (applicable to types II, III and IV only). The blow time shall be between 5 seconds minimum and 2 hours maximum when tested as specified in 4.4.4.

3.4.4.1 Overload blow time at 135 percent of rated current (Type V only). The blow time shall not exceed 1 hour when tested as specified in 4.4.4 and shall blow within the blow area as referenced on dwg 9207939.

3.4.5 Overload blow time at 200 percent of rated current.

3.4.5.1 Type I. The blow time shall be 1 minute maximum, when tested as specified in 4.4.5.

3.4.5.2 Types II, III, and IV only. The blow time shall be between 5 seconds minimum and 2 minutes maximum, when tested as specified in 4.4.5.

3.4.5.3 Type V only. The blow time shall not exceed 10 seconds when tested as specified in 4.4.5 and shall blow within the blow area as specified on dwg 9207939.

3.5 Ferrule torque. The ferrules shall be detached from the case and shall comply with the requirements of 3.4.1 and 3.4.2 after test specified in 4.4.6.

3.6 Environmental testing. The fuses shall comply with MIL-STD-810, visual inspection and failure criteria, section 3. The fuses shall also comply with 4.4.1 and 4.4.2 before and after each environmental test. Testing shall be as specified in 4.4.7. Tests shall be conducted in the order specified.

3.6.1 Shock. The fuse shall show no evidence of loosened ferrules or element and shall comply with the requirements of 3.4.1 and 3.4.2 after the test specified in 4.4.7.1.

3.6.2 Linear acceleration. The fuse shall comply with the requirements of 3.4.1 and 3.4.2 after the test specified in 4.4.7.2.

3.6.3. Vibration. The fuse shall show no evidence of loosened ferrules or element and shall comply with the requirements of 3.4.1 and 3.4.2 after the test specified in 4.4.7.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

3.6.4 High temperature. The fuse shall comply with the requirements of 3.4.1 and 3.4.2 at the high temperature specified in 4.4.7.4 and also after return to ambient temperature.

3.6.5 Low temperature. The fuse shall comply with the requirements of 3.4.1 and 3.4.2 during and after the test specified in 4.4.7.5.

3.6.6 Temperature shock. The fuse shall comply with the requirements of 3.4.1 and 3.4.2 after the test specified in 4.4.7.6.

3.6.7 Corrosion resistance. The fuse shall comply with the requirements of 3.4.1 and 3.4.2 after the test specified in 4.4.7.7.

3.7 Soldering. All soldering shall comply with the requirements specified in MIL-STD-1460.

3.8 Workmanship.

3.8.1 Plastic and metal characteristics. All components shall be free from cracks, splits, cold flow, shrinkage, cold shuts, inclusions, porosity, or any similar characteristic.

3.8.2 Threads. Threads shall be full and undamaged for the entire minimum length or depth as required on the applicable drawing.

3.8.3 Burrs. Parts shall be free from burrs.

3.8.4 Foreign matter. Parts shall be free from chips, dirt, grease, rust, corrosion, or any embedded foreign material.

3.8.5 Cleaning. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agent.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First article inspection.

4.2.1 Quantity to be submitted. When the contract requires first article inspection, the contractor shall submit 9 complete assemblies (see dwgs listed below) for first article testing to the testing facility designated in the invitation for bids or request for proposal.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

8801516	8824868
8801518	8824869
8801581	9207939
8822574	

4.2.2 Inspection and testing to be performed. The first article inspection sample shall be subjected to the inspections and tests specified in Table I. Tests shall be conducted in order specified in Table I.

Table I

First article inspection and tests

Inspection or Test	Dest	Non-Dest	No. Samples Tested
1. Classification of characteristics (see 4.3.2.1)		X	All 9
2. Continuity (see 3.4.1)		X	"
3. Ferrule torque (see 3.5)		X	"
4. Shock (see 3.6.1)		X	"
5. Linear acceleration (see 3.6.2)		X	"
6. Vibration (see 3.6.3)		X	"
7. High temperature (see 3.6.4)		X	"
8. Low temperature (see 3.6.5)		X	"
9. Temperature shock (see 3.6.6)		X	"
10. Corrosion resistance (see 3.6.7)		X	"
11. Voltage rating (see 3.4.3)		X	1 thru 3
12. Overload blow time at 135 percent of rated current (see 3.4.4)	X		4 thru 6
13. Overload blow time at 200 percent of rated current (see 3.4.5)	X		7 thru 9

4.2.3 Inspection equipment. The inspection and testing specified in 4.2.2 shall be accomplished by using the gages and test equipment specified in 4.3.4.1.

4.2.4 Rejection. If any item fails to comply with any of the applicable requirements, the first article sample shall be rejected.

4.3 Quality conformance inspection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

4.3.1 Lot formation.

4.3.1.1 Production lot. A lot shall consist of parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance, storage, or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The criteria and procedures for the assignment of lot numbers shall be in accordance with MIL-STD-1168.

4.3.1.2 Inspection lot. A lot or batch and its formation, size, and presentation is described in MIL-STD-105, Section 5. Accordingly, a lot shall mean an inspection lot and a batch shall mean an inspection batch for the purpose of this specification. The manner in which each inspection lot or batch is to be presented and identified by the contractor, shall be designated or approved by the Government representative.

4.3.2 Product inspection examination. A sample shall be selected at random from each inspection lot in accordance with the applicable major or minor characteristic table (see Table II and Table III), and inspected for all characteristics in the applicable classification. Any characteristics in the sample found to be defective shall reject the inspection lot. Sequence for the inspection of characteristics in each classification need not be followed as long as all characteristic inspections are performed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

Table II
Major Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-72	all	140-141	124	256-259	177	541-549	230
73	72	142	125	260-262	178	550-559	231
74	73	143-144	126	263-265	179	560-569	232
75	74	145	127	266-268	180	570-579	233
76	75	146-147	128	269-271	181	580-590	234
77	76	148-149	129	272-275	182	591-601	235
78	77	150	130	276-278	183	602-613	236
79	78	151-152	131	279-282	184	614-625	237
80	79	153-154	132	283-285	185	626-637	238
81-82	80	155-156	133	286-289	186	638-649	239
83	81	157	134	290-293	187	650-662	240
84	82	158-159	135	294-296	188	663-676	241
85	83	160-161	136	297-300	189	677-690	242
86	84	162-163	137	301-304	190	691-704	243
87	85	164-165	138	305-308	191	705-719	244
88-89	86	166-167	139	309-312	192	720-735	245
90	87	168	140	313-316	193	736-751	246
91	88	169-170	141	317-320	194	752-768	247
92	89	171-172	142	321-324	195	769-785	248
93	90	173-174	143	325-329	196	786-804	249
94-95	91	175-176	144	330-333	197	805-823	250
96	92	177-178	145	334-338	198	824-842	251
97	93	179-180	146	339-342	199	843-863	252
98	94	181-182	147	343-347	200	864-884	253
99-100	95	183-184	148	348-352	201	885-907	254
101	96	185-187	149	353-356	202	908-930	255
102	97	188-189	150	357-361	203	931-955	256
103	98	190-191	151	362-366	204	956-981	257
104-105	99	192-193	152	367-372	205	982-1008	258
106	100	194-195	153	373-377	206	1009-1036	259
107	101	196-197	154	378-382	207	1037-1066	260
108-109	102	198-200	155	383-388	208	1067-1098	261
110	103	201-202	156	389-393	209	1099-1131	262
111	104	203-204	157	394-399	210	1132-1166	263
112-113	105	205-207	158	400-405	211	1167-1204	264
114	106	208-209	159	406-411	212	1205-1243	265
115	107	210-212	160	412-417	213	1244-1285	266
116-117	108	213-214	161	418-424	214	1286-1330	267
118	109	215-217	162	425-430	215	1331-1378	268
119	110	218-219	163	431-437	216	1379-1429	269
120-121	111	220-222	164	438-443	217	1430-1483	270
122	112	223-224	165	444-450	218	1484-1542	271
123-124	113	225-227	166	451-457	219	1543-1605	272
125	114	228-230	167	458-465	220	1606-1673	273
126-127	115	231-232	168	466-472	221	1674-1747	274
128	116	233-235	169	473-480	222	1748-1827	275
129-130	117	236-238	170	481-488	223	1828-1914	276
131	118	239-241	171	489-496	224	1915-2010	277
132-133	119	242-243	172	497-504	225	2011-2115	278
134	120	244-246	173	505-513	226	2116-2232	279
135-136	121	247-249	174	514-521	227	2233-2361	280
137	122	250-252	175	522-530	228	over 2361	298
138-139	123	253-255	176	531-540	229		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

Table III
Minor Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-16	all	28-29	23	52-56	31	132-156	39
17	16	30-31	24	57-62	32	157-191	40
18	17	32-34	25	63-69	33	192-244	41
19-20	18	35-36	26	70-76	34	245-334	42
21	19	37-40	27	77-86	35	335-519	43
22-23	20	41-43	28	87-97	36	520-1120	44
24-25	21	44-47	29	98-112	37	over 1120	45
26-27	22	48-51	30	113-131	38		

4.3.2.1 Classification of characteristics (see 3.2). Critical, major and minor characteristics are defined in MIL-STD-105. Inspection shall be conducted as follows:

4.3.2.1.1 Fuze, time-lag and normal blowing (see dwgs 8801516, 8801518, 8801581, 8822574, 8824868, 8824869, and 9207939).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Total length	Gage
102.	Diameter of ferrule	Gage
103.	Crack in case	Visual
104.	Current and voltage rating marking missing from ferrules	Visual
105.	Protective plating on ferrule inadequate	Visual
106.	Looseness of element	Visual/Manual
107.	Objective evidence relative to material missing or improper (see 3.1)	Visual
Minor:		
201.	Any areas of ferrule not free from solder and flux other than that to which the fuse element is attached	Visual
202.	Case not sufficiently clear to permit element to be seen	Visual
203.	Evidence of poor workmanship (see 3.8)	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

4.3.2.1.2 Preparation for delivery.

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Preservation and packaging not in accordance with MIL-STD-1169 (see 5.1)	Visual
102.	Packing not in accordance with MIL-STD-1169 (see 5.2)	Visual
103.	Marking not in accordance with MIL-STD-1169 (see 5.3)	Visual
Minor:		
201.	Evidence of poor workmanship (see 3.8)	Visual

4.3.3 Testing. All tests shall be performed. Tests shall be performed in the order specified below:

	Test	Test Classification
a.	Continuity	Major
b.	Current carrying capacity	Major
c.	Overload blow time at 135 percent of rated current	Major
d.	Overload blow time at 200 percent of rated current	Major

Of these tests, c and d are considered destructive and samples so tested shall not be returned to the lot. Destructive samples are over and above the deliverable quantity of items required by the contract.

4.3.3.1 Continuity. Each fuse shall be tested in accordance with 4.4.1. If any item fails to comply with 3.4.1, the item shall be rejected and removed from the lot.

4.3.3.2. Current carrying capacity, overload blow time at 135 percent of rated current, and overload blow time at 200 percent of rated current. For each test, a sample group of relays shall be selected at random in accordance with Table IV. The sample group shall be tested in accordance with the applicable test method paragraph 4.4.2, 4.4.4, or 4.4.5, respectively. If any relay fails to comply with the respective requirement paragraph 3.4.2, 3.4.4, or 3.4.5, the lot shall be rejected.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

Table IV

Lot Size	Sample Size
2-8	1
9-15	2
16-25	3
26-40	5
41-65	8
66-110	13
111-180	22
181-300	26
301-and over	MIL-STD-105 (AQL 0.25 percent)

4.3.4 Acceptance inspection equipment.

4.3.4.1 Major characteristics and tests. Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions specified on the Equipment Lists (EL) (see EL-8801516, EL-8801518, EL-8801581, EL-8822574, EL-8824868, EL-824869 and EL-9207939).
When either of the conditions listed below exist, the contractor shall design required equipment or specify suitable commercial equipment and obtain approval prior to use on the contract.

a. Any deviation from equipment or procedures specified on the EL is desired (see 6.3).
b. The code "CD" is listed in the "Part or Identifying Number" column on the EL (see 6.1.2).

4.3.4.2 Minor characteristics and tests. Acceptance inspection equipment for minor characteristics is not specified on ELs. The acceptance inspection equipment, operating instructions and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

4.4 Test methods. The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used. Unless otherwise specified, tests required herein shall be made under combinations of conditions within the following ranges:

Temperature.....68° to 95°F
Relative humidity.....30 to 95 percent
Barometeric pressure.....28 to 31 inches

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

4.4.1 Continuity. Continuity of fuse shall be determined with a zero calibrated ohmmeter or other suitable means.

4.4.2 Current carrying capacity. The fuse shall be subjected to an ac or dc test current equal to 110 percent of its rating for 2 hours minimum. The test fuse shall be mounted horizontally in a standard single pole fuseholder having silver-plated beryllium copper clips rated for 30 amperes at 250 volts. Contact resistance between the ferrules and clips shall be held to a minimum. For this characteristic the fuses may be tested in series, in which case the fuse holders shall be spaced at least 6 inches apart and shall be electrically connected by approximately 2 foot lengths of No. 8 AWG insulated copper wire. Connections to the test current source shall be accomplished with the same wire in lengths of 4 feet minimum. When a test fails, it shall be removed from the circuit and the test resumed as quickly as possible. For the type I fuse, use test panel dwg 8853882, and operating instruction 8853883. For type II and type V use test panel dwg 8853912 and operating instructions 8853913. For the type IV fuse use test panel dwg 8853882 and operating instructions 8853883.

4.4.3 Voltage rating. The fuse shall be mounted in a fuse holder as specified in 4.4.2 and connected to an alternating or direct current of 10,000 amperes minimum at the maximum rated voltage of the fuse as determined by an oscillograph. Open circuit voltage shall be within 5 percent of voltage rating of fuse. Certification by the contractor that he has complied with the 10,000 amperes test as specifed in the Underwriter's Laboratories Standard for Fuses will be acceptable in lieu of actual testing. The certification shall be signed by a responsible agent of the certifying organization. Only the first certification shall be substantiated by evidence of the agent's authority to bind his principal, unless during the course of the contract, such authorization is vested in another agent of the certifying organization.

4.4.4 Overload blow time at 135 percent of rated current. The fuse shall be mounted in a fuseholder as specified in 4.4.2 and connected to the test current source by No. 8 AWG insulated copper wire leads that are 4 feet in length minimum. The fuse shall be subjected to 135 plus or minus (±) 2 percent of rated current, ac or dc and the time between application of current and blowing of the fuses shall be measured.

4.4.5 Overload blow time at 200 percent of rated current. The fuse shall be mounted in a fuseholder as specified in 4.4.2 and connected to the test current source by No. 8 AWG insulated copper wire leads 4 feet in length minimum. The fuse shall be subjected to 200 ± 2 percent of rated current, ac or dc, and the time between current application and fuse blowing shall be measured.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

4.4.6 Ferrule torque. The fuse shall be clamped securely by one ferrule and a 10 inch-ounce minimum torque shall be gradually applied to the other in the clockwise and counterclockwise directions successively. Alternately, the fuse case may be clamped and each ferrule tested individually. Following this test, the fuse shall be tested as specified in 4.4.1 and 4.4.2.

4.4.7 Environmental testing (see 3.6).

4.4.7.1 Shock. The fuse shall be mounted in a standard fuseholder and subjected to three shocks minimum in each direction along each of its three principal axes. Each shock shall be 15 g minimum for 11 ± 1 milliseconds. Following this test, the fuse shall be tested as specified in 4.4.1 and 4.4.2.

4.4.7.2 Linear acceleration. The fuse shall be placed in a centrifuge and subjected to a linear acceleration of 11 g minimum in each direction along each of the principal axes for a minimum of 1 minute. Following this test, the fuse shall be tested as specified in 4.4.1 and 4.4.2.

4.4.7.3 Vibration.

4.4.7.3.1 Vibration (types I, II, III and IV only). The fuse shall be mounted to a vibration table and vibrated 15 minutes along each of its three principal axes. The vibration frequency shall be varied from 10 to 55 Hertz (Hz) at a double amplitude of 0.064 inch. The frequency shall be carried uniformly from 10 to 55 Hz making approximately one cycle per minute. Following this test, the fuse shall be tested as specified in 4.4.1 and 4.4.2.

4.4.7.3.2 Vibration (type V only). The fuse shall be mounted to a vibration table and vibrated in accordance to Table V after which the fuse shall be tested as specified in 4.4.1 and 4.4.2.

Table V

Frequency (Hz)	Time (min)	Peak G's	Double Amplitude (inches)	No. of cycles in each axis
5-60	2.5		0.06 ± 0.006	1
61-300	5.0	10 ± 0.2		1
300-61	5.0	10 ± 0.2		1
60-5	2.5		0.06 ± 0.006	1

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

4.4.7.4 High temperature. The fuse shall be tested as specified in MIL-E-5272, procedure I with the exception that the high temperature stabilization (see 6.4) shall be +165 + 5 degrees fahrenheit (°F.), a relative humidity of 15 percent and a time duration of 50 hours shall be used. While at the high temperature, the fuse shall be tested as specified in 4.4.1 and 4.4.2 except that current carrying capacity of 80 percent shall be utilized in lieu of 110 percent for types II and III only. Upon return to ambient temperature and without any forced cooling, the fuse shall be tested in accordance with 4.4.1 and 4.4.2.

4.4.7.5 Low temperature. The fuse shall be tested as specified in 4.4.7.4 except that the temperature shall be reduced and stabilized at -65° + 5°F. and no forced warming shall be used to return the fuse to ambient temperature.

4.4.7.6 Temperature shock. The fuse shall first be placed within a test chamber wherein a temperature of +165° + 5°F. is maintained at this temperature for a period of 4 hours. Within 5 minutes after the conclusion of this portion of the cycle, the fuse shall be transferred to a chamber having an internal temperature -65° + 5°F. The fuse shall be subjected to this temperature for a period of 4 hours. The number of complete cycles shall be three. At the conclusion of the third cycle the fuse shall be removed from the test chamber and within a period of 1 hour, tested as specified in 4.4.1 and 4.4.2.

4.4.7.7 Corrosion resistance. The fuse shall be tested as specified in MIL-STD-202, Method No. 101A test condition A. Following this test, the fuse shall be tested as specified in 4.4.1 and 4.4.2.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.1).

5.1.1 Level A. The fuses shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169.

5.1.2 Level C. The fuses shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169.

5.2 Packing.

5.2.1 Levels A and C. The fuses shall be packed in accordance with the applicable instructions contained in MIL-STD-1169.

5.3 Marking. Marking shall be in accordance with MIL-STD-1169.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification.
b. Type required (see 1.2).
c. Selection of applicable level of packaging and packing required (see 5.1 and 5.2).

6.1.2 Contract data requirements (see 4.3.4.1). Data specified in 4.3.4.1 will be delivered as identified on a numbered DD Form 1664 when required on a DD Form 1423 incorporated in the contract.

6.2 Objective evidence. Records of contractor quality control and inspections which can be verified.

6.3 Acceptance inspection equipment (see 4.3.4.1). The contractor shall obtain approval from the Commander, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SARPA-QA-T.

6.4 Temperature stabilization. The temperature is considered stabilized when the greatest peaks (both highest and lowest) continually observed over 5 minutes min. do not exceed the nominal temperature plus tolerance specified.

6.5 Supersession data. This specification supersedes the requirements of Purchase Description PA-PD-1003 (Rev. 4) 31 July 1964.

Custodian:
Army - PA

Preparing activity:
Army - PA

Project No. NUOR-A038

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/ vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426

REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314



OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:41Z
Check the source to verify that this is the current version before use.