MILITARY SPECIFICATION

FUZE, POINT DETONATING, M527B1 LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the loading, assembling and packing for one type of fuze designated as Fuze, Point Detonating, M527B1.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL–A–2550 — Ammunition and Special Weapons, General Specification for.

MIL–I–45607 — Inspection and Special Weapons, General Specification for.

STANDARDS

MILITARY

MIL–STD–105 — Sampling Procedures and Tables for Inspection by Attributes (ABC–STD–105).

MIL–STD–109 — Quality Assurance Terms and Definitions.

MIL–STD–350 — Jolt Test for Use in Production of Fuzes.

MIL–STD–351 — Jumble Test for Use in Production of Fuzes.

MIL–STD–1235 — Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

ORDNANCE CORPS

8800461 — Fuze, P.D., M527B1, Assembly.

9206236 — Box, Packing, Ammunition, For Fuze, PD, M527, M527A1 and M527B1 in Fiber Container, M—.

9206235 — Container, Ammunition, Fiber, M— For Fuze PD, M527, M527A1 and M527B1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:28Z
Check the source to verify that this is the current version before use.

PUBLICATIONS

ORDNANCE CORPS

IEL–8800461 — Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material. Materials shall be in accordance with applicable drawings and specifications.

3.2 Fuzes. The fuzes shall comply with all requirements specified on drawing (dwg.) 8800461 and with all requirements specified in applicable specifications.

3.3 Jolt and jumble. The loaded fuze assemblies shall have no explosive elements explode, shall have its slider assembly remain in the unarmed position (firing pin point seated in the slider relief hole), shall not cause the head assembly to arm, shall not come apart, and shall have no parts broken, deformed or displaced in such a manner as to render the fuze unsafe to handle or dangerous to fire when subjected to the jolt test specified in Standard MIL–STD–350 and a jumble test of 3600 revolutions specified in MIL–STD–351. These tests shall be performed as specified in 4.3.2.

3.4 Proving ground. The fuzes shall comply with the following requirements when tested as specified in 4.3.3.

3.4.1 *Premature burst.* No fuze shall show evidence of premature burst (see 6.4).

3.4.2 *Functioning.* No fuze shall fail to cause the projectile to function upon impact.

3.4.3 *Arming safety.* The fuze shall not function on impact against a plywood screen when tested as specified in 4.3.3.2.

3.5 Specific gravity of booster lead cup assembly and booster cup assembly. The booster lead cup assembly and booster cup assembly shall meet a specific gravity requirement of 1.45 to 1.55.

3.6 Workmanship. All parts and assemblies shall be fabricated and loaded in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, rust and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

4. QUALITY ASSSURANCE PROVISIONS

4.1 General quality assurance provisions. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL–STD–109 in order to define terms used herein. The provisions of Specification MIL–A–2550 shall apply.

4.1.1 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:28Z
Check the source to verify that this is the current version before use.

(a) A statement that the lot complies with all of the quality assurance provisions specified within this specification.

(b) Number of units of product inspected.

(c) Results obtained, by defect code, for all inspections performed.

(d) Drawing, specification number and date, together with an identification and date of changes.

(e) Certificates of compliance on all material purchased by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

(f) Number of items in the lot.

(g) Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seroiusness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Inspection provisions.

4.2.1 *Lot formation.* A lot shall consist of fuzes loaded and assembled by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. Lots shall be submitted for inspection in accordance with Standard MIL–STD–105 (or Standard MIL–STD–1235, when applicable). Each lot shall contain:

(a) Parts and assemblies of one lot interfix number from one manufacturer.

(b) Detonator assemblies of one lot interfix number from one manufacturer.

(c) Booster cup assemblies of one lot interfix number from one manufacturer.

(d) Booster lead cup assemblies of one lot interfix number from one manufacturer.

(e) Tetryl of one lot interfix number from one manufacturer.

4.2.2 *Examination.* Inspection for Critical defects shall be 100 percent. Sampling plans and procedures for Major and Minor defects shall be in accordance with MIL–STD–105 except that continuous sampling plans in accordance with Standard MIL–STD–1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to individual characteristics

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:28Z
Check the source to verify that this is the current version before use.

listed using an AQL of 0.65 percent for each Minor defect and an AQL of 0.40 percent for each Major defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.2.4.

4.2.2.1 Assembly, prior to cementing of slider plug or booster cup assembly, or staking of head assembly, or depressing firing pin (see dwg. 8800461).

Categories	*Defects*	*Method of inspection*	*Code No. (see 6.2)*
Critical:	None defined.		
Major:	AQL 1.00 percent		
101.	Detonator loose	Test	01001
102.	Slider not free	Manual	01002
103.	Detonator inverted	Visual	01003
104.	Guide pin broken	Visual	01004
105.	Firing pin damaged	Visual	01005
106.	Any component missing	Visual	01006
Minor:	AQL 1.50 percent		
201.	Guide pin bent	Visual	01007
202.	Booster charge cracked, broken or above flush	Visual	01008
203.	Booster lead cup charge cracked, broken or above flush	Visual	01009
204.	Evidence of poor workmanship (see 3.6)	Visual	01010

4.2.2.2 Assembly, after positioning firing pin in slider but prior to cementing slider plug (see dwg. 8800461).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:			
1.	Firing pin not positioned in slider relief hole (see 4.3.1)	Test	02001
Major:	AQL 0.40 percent		
101.	Slider spring missing	Visual	02002
Minor:	AQL 0.65 percent		
201.	Pettman cement missing from threads	Visual	02003

4.2.2.3 *Assembly* (see dwg. 8800461).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:			
1.	Safety wire missing or loose	Visual-Manual	03001
2.	Safety pin missing	Visual	03002

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:28Z
Check the source to verify that this is the current version before use.

Categories	*Defects*	*Method of inspection*	*Code No.*
Major:	AQL 0.40 percent		
101.	Total length, max.	Gage	03003
102.	Length from rearward face to shoulder, max.	Gage	03004
Minor:	AQL 2.50 percent		
201.	Any component loose	Manual	03005
202.	Cord missing or insecure	Visual-Manual	03006
203.	Threads damaged	Visual	03007
204.	Marking misleading or unidentifiable	Visual	03008
205.	Evidence of poor workmanship (see 3.6)	Visual	03009

4.2.2.4 *Sealed fiber container* (see dwg. 9206235).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Sealing strip incomplete or badly wrinkled	Visual	04001
102.	Container cut or damaged through all impregnated layers	Visual	04002
103.	Metal end loose or distorted	Visual-Manual	04003
Minor:	AQL 2.50 percent		
201.	Sealing strip tab length, min.	Gage	04004
202.	Gap between cover and body of container greater than 1/8 inch	Visual	04005
203.	Cuts, scuffs or gouges in outer layer	Visual	04006
204.	Marking misleading or unidentifiable	Visual	04007
205.	Content loose	Manual	04008

4.2.2.5 *Sealed wood packing box* (see dwg. 9206236).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined.		
Major:	AQL 1.00 percent		
101.	Box damaged exposing contents	Visual	05001
102.	DOD symbol missing or incorrect	Visual	05002
103.	Strapping missing, broken or loose	Visual-Manual	05003

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:28Z
Check the source to verify that this is the current version before use.

Categories	*Defects*	*Method of inspection*	*Code No.*
104.	Hardware missing, broken or loose	Visual-Manual	05004
105.	Board loose, broken or nail protruding	Visual-Manual	05005
Minor:	AQL 2.50 percent		
201.	Car seal missing, unsealed or improperly positioned	Visual	05006
202.	Marking misleading or unidentifiable	Visual	05007
203.	Hardware improperly engaged	Visual-Manual	05008
204.	Strapping improperly assembled	Visual-Manual	05009
205.	Contents loose	Manual	05010

4.2.3 *Testing.*

4.2.3.1 Jolt and jumble (se 3.3)—Critical defect—Code No. 03010.—The test shall be performed as specified in 4.3.2 using equipment in accordance with 4.2.4.

4.2.3.1.1 Beginning with the first lot produced and continuing until three consecutive lots have complied with the acceptance criteria specified herein, 36 fuze assemblies shall be selected from each lot for these tests. If one or more fuze assemblies fail to comply with the requirement specified, the lot shall be rejected.

4.2.3.1.2 After three consecutive lots have complied with the criteria of 4..2.3.1.1, twelve fuze assemblies shall be selected for these tests. If any fuze assembly fails to comply with the requirements specified, the lot shall be rejected.

4.2.3.2 *Proving ground* (see 3.4).

4.2.3.2.1 Premature burst—Critical defect —Code No. 03011.—Failure to function—Major defect—Code No. 03012.

4.2.3.2.1.1 Beginning with the first lot produced and continuing until three consecutive lots have complied with the applicable requirement specified, 100 samples shall be selected for this test. If a premature burst occurs or if four or more assemblies fail to comply with the applicable functioning requirements, the lot shall be rejected. The test shall be performed as specified in 4.3.3.

4.2.3.2.1.2 After three consecutive lots have complied with the criteria of 4.2.3.2.1.1, a sample of 40 fuzes shall be selected from each lot for this test. If 4 or more fuzes fail to comply with the applicable requirement, the lot shall be rejected. If 2 or 3 fuzes fail, a second sample of 80 fuzes shall be tested. If the combined number of failures in both the first and second samples is 4 or more, the lot shall be rejected. This test shall be performed as specified in 4.3.3.

4.2.3.2.2 Arming safety—Critical defect—Code No. 03013.

4.2.3.2.2.1 Beginning with the first lot produced and continuing until three consecutive lots have complied with the acceptance criteria specified herein, 80 sample fuze assemblies shall be selected from each lot for this test. If one or more assemblies fail to comply with the requirement specified the lot shall be rejected. The test shall be performed as specified in 4.3.3.

4.2.3.2.2.2 After three consecutive lots have complied with the criteria specified in 4.2.3.2.2.1 the sampling plan for this shall be in accordance with Standard MIL–STD–105 Code letter G utilizing an AQL of 0.40 percent. The test shall be performed as specified in 4.3.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:28Z
Check the source to verify that this is the current version before use.

4.2.3.4 Check test for deterioration of detonators—Major defect—Code No. 06001.—If the total time between original acceptance of any detonator lot and the assembly of that lot into fuzes exceeds two years, or if the detonators have been subjected to adverse conditions, however brief, at any time since previous tests, the detonator lot shall be subjected to and must satisfactorily pass, the check test for deterioration specified in the applicable specification immediately before the detonator lot is assembled into the fuzes. This test shall be performed by the contractor on detonators selected by the Government inspector at the facility assembling the detonators into the fuzes (see 6.5).

4.2.3.4 Graphite content of tetryl (see dwgs. 8798674 and 8800466)—Major defect—Code No. 07001. The graphite content of the tetryl shall be determined for each lot as the time of loading. A sample of 15 grams shall be selected and tested as specified in 4.3.4. If the graphite content is in excess of the percentage specified, and if the loading has not begun, the lot of tetryl shall be rejected until proper corrective action has been accomplished as verified by repeating the graphite content test specified in 4.3.4. If loading has begun, action on the unloaded tetryl shall be as specified above and all components loaded with the questionable tetryl shall be rejected.

4.2.3.5 Specific gravity of booster lead cup assembly—Major defect—Code No. 08001 and booster cup assembly—Major defect—Code No. 08002. A sample of 13 booster lead cup assemblies and 13 booster cup assemblies shall be selected from each lot for this test. If any assembly fails to meet the requirement specified the lot shall be rejected. The test shall be performed as specified in 4.3.5 using test equipment specified in 4.2.4.

4.2.4. *Inspection Equipment.* Index of Inspection Equipment Number IEL–8800461 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.2.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.2.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL–I–45607.

4.2.4.3 *Government use of contractor's inspection and test equipment.* The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

4.3 Test methods and procedures

4.3.1 *Positioning of firing pin.* The assembly, prior to assembling the slider plug, shall be mounted in a fixture with the slider plug hole on top and the fuze axis in a horizontal plane. A manual or power operated ram shall exert the specified pressure against the striker assembly to seat the firing pin against the slider in the required position.

4.3.2 *Jolt and jumble.* The loaded fuze assemblies shall be subjected to the jolt test in accordance with MIL–STD–350. After completion of the jolt test, the fuzes subjected to the jolt test shall not be disassem-

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:28Z
Check the source to verify that this is the current version before use.

bled but shall be subjected to 3600 complete revolutions in a specified jumble machine at a speed of 30 plus or minus 2 revolutions per minute. Disassembly and examination of the fuzes shall be accomplished after both jolt and jumble tests have been completed. Examinations shall be made to determine compliance with 3.3.

4.3.3 *Proving ground.*

4.3.3.1 *Premature burst-functioning.* The test shall be performed at a Government proving ground. The fuze assembly shall be assembled to a 60MM Cartridge, Smoke, WP, M302, or Cartridge H.E., M49A2, and fired from a 60MM Mortar for which the round is standard. The mortar tube shall be elevated 45 degrees (°) or greater, for impact on firm ground. One half of the sample fuzes shall be assembled to cartridges assembled with an ignition cartridge (charge zone zero) and one half of the sample fuzes shall be assembled to cartridges assembled with an ignition cartridge and four propellant increments (charge zone four).

4.3.3.2 *Arming safety.* The fuze assembly shall be assembled as specified in 4.3.3.1 (charge zone zero) and fired against a ¼-inch plywood screen set at a distance of not less than 200 feet from the muzzle of the mortar.

4.3.4 *Determination of graphite content of tetryl.* A sample of approximately 5 grams of the tetryl shall be transferred to a 250 ml. beaker. Add 100 ml. of acetone and heat to dissolve the tetryl. Filter the solution through a weighed, tarred, filtering crucible and wash the residue in the crucible with two 25 ml. portions of acetone. Dry the crucible at 100°C for 1 hour, cool in a desiccator and weigh. Calculate the increase in weight of the crucible as percentage of graphite.

4.3.5 *Specific gravity of booster lead cup assembly and booster cup assembly.* The assembly shall be weighed on a balance and the weight recorded as dry weight. The assembly shall then be weighed while completely submerged in water. The temperature of the water shall be 68 degrees Fahrenheit (F) plus or minus 2 degrees F. This weight shall be recorded as weight under water. (When submerged, the position of the assembly shall be such that no air is entrapped.) Specific gravity shall be calculated as follows:

$$\text{Specific gravity} = \frac{A - B}{C}$$

where:

A = dry weight
B = weight under water

5. PREPARATION FOR DELIVERY

5.1 Preservation and Packaging.

5.1.1 *Level C.* The fuzes shall be preserved and packaged in accordance with drawing 9206235.

5.2 Packing.

5.2.1 *Level C.* The fuzes in fiber containers shall be packed in accordance with drawing 9206236.

5.3 Marking. Marking of the wood box shall be as specified on drawing 8796522. The fiber container shall be marked in accordance with drawing 8796521.

5.4 Data cards. Data cards shall be prepared for each lot in accordance with the information specified in MIL–A–2550.

6. NOTES

6.1 Ordering data. Procurement documents shall specify title number and date of this specification.

6.2 Inspection code numbers. The five digit code numbers assigned to the inspec

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:28Z
Check the source to verify that this is the current version before use.

tions herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (DD Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3. 6.3.4, 6.3.5 and 6.3.6 will be designated in the IEL by the following codes:

CDAF — Contractor's design responsibility on Army format in accordance with MIL–D–45608.

CDCF — Contractor's design responsibility on contractor format.

AD — Army design.

ADMU — Army design, mandatory for use.

CE — Commercial equipment.

SCD — Specification control drawing.

6.3.3 *Army designs.* Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawing.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved as described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:28Z
Check the source to verify that this is the current version before use.

universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL–D–45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electrostatic prints of top quality full size with black line on white background and shall provide a legible print produced via the 35MM microfilm process. Contractor shall submit one copy of the final design as a rolled set or flat set.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Premature bursts. Premature burst is defined as the functioning of the fuze in the weapon bore or in flight before impact.

6.5 Check test. The contracting officer will arrange for the contractor to be reimbursed for the expense incurred in the performance of the detonator assembly check test. The test shall be conducted at Government expense without cost to the contractor who loaded the detonators or the contractor assembling the detonators into the fuzes, and shall not constitute a basis for rejection against either contractor except where deterioration has occurred as a direct result of carelessness in handling, storage, etc. permitted while the detonator lot was under their jurisdiction.

Custodian:

Army—MU

Preparing activity:

Army—MU

Project No. 1390–A463

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:28Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1 OCT 64 1426

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:28Z
Check the source to verify that this is the current version before use.