MILITARY SPECIFICATION

PLANT, AGGREGATE, SECONDARY, WITH CONE CRUSHER, MOBILE, 75 TON PER HOUR CAPACITY

This specification is approved for use by the Naval Facilities Engineering Command, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

1.1 Scope. This specification covers a complete mobile, electric powered, crushing and screening plant capable of producing not less than 75 tons of aggregate per hour suitable for use in cement or asphaltic concrete.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. Unless otherwise specified (see 6.2), the following specifications, standards, and handbooks of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DODISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

L-P-378	- Plastic Sheet and Strip, Thin Gauge, Polyolefin.
QQ-S-781	- Strapping, Steel, and Seals.
SS-A-281	- Aggregate; (for) Portland-Cement-Concrete.
SS-S-445	- Slag, Stone and Gravel, Crushed (for Bituminous Paving Mixtures).
TT-P-664	- Primer Coating, Synthetic, Rust-Inhibiting, Lacquer-Resisting.
TT-V-119	- Varnish, Spar, Phenolic-Resin.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, Port Hueneme, CA 93043, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 3820

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:37Z
Check the source to verify that this is the current version before use.

MMM-A-260 - Adhesive, Water-Resistant, (for Sealing Waterproofed Paper).
PPP-B-601 - Boxes, Wood, Cleated-Plywood.
PPP-B-621 - Boxes, Wood, Nailed and Lock-Corner.
PPP-B-1055 - Barrier Material, Waterproofed, Flexible.
PPP-P-40 - Packaging and Packing of Hand Tools.

MILITARY

MIL-C-104 - Crates, Wood, Lumber and Plywood Sheathed, Nailed and Bolted.
MIL-P-116 - Preservation, Methods of.
MIL-B-121 - Barrier Material, Greaseproofed, Waterproofed, Flexible.
MIL-V-173 - Varnish, Moisture and Fungus Resistant (for Treatment of Communications, Electronic, and Associated Equipment).
MIL-C-3774 - Crates, Wood; Open, 12,000 and 16,000 Pound Capacity.
MIL-V-13811 - Varnish, Waterproofing, Electrical, Ignition.
MIL-E-16298 - Electric Machines Having Rotating Parts and Associated Repair Parts, Packaging of.
MIL-T-22085 - Tape, Adhesive, Preservation and Sealing.
MIL-B-22191 - Barrier Material, Transparent, Flexible, Heat Sealable.
MIL-P-46093 - Primer Coating, Synthetic (for Brake Drums).
MIL-C-52950 - Crate, Wood, Open and Covered.

STANDARDS

FEDERAL

Fed. Std. No. 595 - Colors.

MILITARY

MIL-STD-129 - Marking for Shipment and Storage.
MIL-STD-209 - Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.
MS51336 - Lunette and Coupler, Drawbar, Ring.

(Copies of specifications, standards, handbooks, drawings, and publications required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Other Government documents, drawings, and publications. The following other Government documents form a part of this specification to the extent specified herein.

DEPARTMENT OF LABOR (DoL)
OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA)

Occupational Safety and Health Standards.

(Application for copies of DoL should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:37Z
Check the source to verify that this is the currentversion before use.

2.3 Other publications. The following document(s) form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DODISS and the supplement thereto, if applicable.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

C131 - Test for Resistance to Abrasion of Small Size Coarse Aggregate by Use of the Los Angeles Abrasion Machine.
C170 - Test for Compressive Strength of Natural Building Stone.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

AB1 - Molded Case Circuit Breakers.
ICS - Industrial Controls and Systems.
MG1 - Motor and Generators.
PB2 - Dead-Front Distribution Switchboards.

(Application for copies should be addressed to the National Electrical Manufacturers Association, 2101 L Street, N.W., Washington, DC 20037.)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

No. 70 - National Electrical Code.

(Application for copies should be addressed to the National Fire Protection Association, Batterymarch Park, Quincy, MA 02269.)

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, Inc., 400 Commonwealth Drive, Warrendale, PA 15096.)

TIRE AND RIM ASSOCIATION, INC.

T&RA Yearbook.

(Application for copies should be addressed to the Tire and Rim Association, Inc., 3200 West Market Street, Akron, OH 44313.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.4 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

Source: https://assist.dla.mil -- Downloaded: 202640-23T06:37Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Description. The unit shall consist essentially of a cone crusher, vibrating screens, loading hopper, all electric power system, operating platform, semitrailer mounted, and all accessories for a complete portable unit.

3.2 First article. When specified (see 6.2), the contractor shall furnish one complete plant for first article inspection and approval (see 4.2.1 and 6.4).

3.3 Standard commercial product. The plant shall, as a minimum, be in accordance with the requirements of this specification and shall be the manufacturer's standard commercial product. Additional or better features which are not specifically prohibited by this specification but which are a part of the manufacturer's standard commercial product, shall be included in the plant being furnished. A standard commercial product is a product which has been sold or is being currently offered for sale on the commercial market through advertisements or manufacturer's catalogs, or brochures, and represents the latest production model.

3.4 Identical items. All components of the same classification furnished under any specific contract shall be physically and mechanically identical. This requirement includes parts, assemblies, components, and accessories. No deviation will be acceptable without prior written approval of the contracting officer.

3.5 Ease of maintenance. The unit shall be so designed and constructed that normal adjustments, repair, and overhaul can be readily accomplished by means of general purpose tools with a minimum removal or disturbance of other elements of the unit. Ease of maintenance provisions shall insure operating clearances for facilitating maintenance and servicing. Where possible, intricate locking devices, controls, and threaded fastenings, that can be easily over-torqued by operators lacking feel throught thick gloves or numbness, shall be avoided. Covers or plates that must be removed for component adjustment or for parts removal shall be equipped with substantial fastenings.

3.6 Safety. All rotating or reciprocating parts, and all parts subject to high operational temperature, that are of such nature or are so located as to be or become a hazard to operating or attending personnel, shall be adequately guarded or insulated to the extent necessary to eliminate the hazard. All platforms, steps, and handholds shall be provided for easy access to the operator's position and other work areas. The unit shall comply with OSHA regulations in effect at time of manufacture.

3.7 Materials. Materials used shall be free from defects which would adversely affect the performance or maintainability of individual components or of the overall assembly. Materials not specified herein shall be of the same quality used for the intended purpose in commercial practice. Unless otherwise specified herein, all equipment, material, and articles incorporated

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:37Z
Check the source to verify that this is the current version before use.

in the work covered by this specification are to be new and fabricated using materials produced from recovered materials to the maximum extent possible without jeopardizing the intended use. The term "recovered materials" means materials which have been collected or recovered from solid waste and reprocessed to become a source of raw materials, as opposed to virgin raw materials. None of the above shall be interpreted to mean that the use of used or rebuilt products are allowed under this specification unless otherwise specified.

3.8 Performance. The unit shall be capable of crushing any variety of rock having an average compressive strength of not less than 32,000 pounds per square inch when tested in accordance with ASTM C170; shall have a percentage of wear not exceeding 20 when tested in accordance with ASTM C131, and a free moisture content of not more than 6-1/2 percent. The unit shall be capable of crushing rock ranging in size from 6 inches to 3 inches cross section. The unit shall be capable of producing not less than 200 tons per hour (tph) in three sizes from 2-1/2 inches to 1/2 inch, which are suitable for use in cement concrete, and not less than 75 tph in three sizes ranging from 3/4 inch to No. 4 size, which are suitable for use in asphaltic concrete. The sizes and percentages of the crushed aggregates produced shall conform to the general requirements of SS-A-281 for cement concrete, or SS-S-445 for asphaltic concrete.

3.9 Cone crusher. The cone crusher shall be of the vertical type with a mantel sized large enough to produce material requirements as stated in 3.7. The cone crusher shall be protected from damage due to overload, tramp iron, and other noncrushable material. The unit shall have a mechanical overload release and reset with no readjustment being required. The crushing members shall have replaceable wearing surfaces of alloy steel with a minimum of 11 percent manganese content. A hydraulic means shall be provided to aid the adjustment for raising and lowering settings varying the crusher discharge opening. One extra set of crushing members, with resin and calking compounds, etc., if required, shall be furnished for the cone crusher. All moving parts of the cone crusher shall be lubricated by a force-feed system equipped with a pump, safety devices, oil temperature warning lights or alarm, oil low level and pressure warning devices, instruments, flexible hoses, piping valves, and all necessary components for efficient operation of the cone crusher.

3.10 Vibrating screens. Vibrating screens shall be either the horizontal or inclined type, with at least three decks designed to produce three products in addition to the oversize material which is routed to the cone crusher. Screen cloth shall be double crimp, standard or flattop oil-tempered steel with square openings, and adequate support shall be furnished to prevent sagging. All screens shall be readily replaceable. Screens shall be secured by an adjustable tensioning system. The vibrating mechanism shall be V-belt, electric-motor-driven, and shall consist of eccentric or unbalanced type drives for the horizontal type screen and one eccentric drive for the inclined type screen. A screen feed box or chute shall be provided to distribute the material on the screen. Master power panel for controlling the vibrating screens shall be operable from operator's platform. Two sets of screen cloths shall be furnished for the unit. Each set of screen cloths shall include the following sizes:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:37Z
Check the source to verify that this is the current version before use.

Minimum clear opening (inches)	Wire diameter (inches)
2-1/2	1/2
2	7/16
1-1/2	3/8
1	5/16
3/4	1/4
1/2	0.192
3/8	0.162
1/4	0.135

The vibrating screen vibrations shall not be transmitted to the main structure. The receiving end of the vibrating screen shall not exceed 9 feet in height. The receiving hopper shall be fabricated from rigidly reinforced steel plate and shall break down into removable sections to reduce cube during transport.

3.11 Loading hopper. A loading hopper may be provided to control and direct flow of material from the vibrating screen to the cone crusher feed opening. The loading hopper shall be fabricated from reinforced steel plate. The loading hopper shall break down into sections to reduce the cube during transport.

3.12 Conveyors. Conveyors shall be used to transport stone and gravel within the unit. Conveyors shall be of the belted type in accordance with the manufacturer's standard practice to provide for smooth and efficient flow of material.

3.12.1 Belt-type conveyors. Belt-type conveyors shall be equipped as follows: Troughing type idlers or rollers shall be provided with spacing of not more than 4 feet between centers. Troughing idlers shall be designed to insure true running and self-centering of the conveyor belts. Special rolls designed to absorb shock shall be installed under the conveyor belt, below receiving area. Return idlers shall be provided with a maximum spacing of 10 feet between centers. The width and running speed of all conveyor belts shall be such as to assure efficient movement of material, with a minimum of spillage and pileup at receiving points, when the unit is operating at full capacity. An accessible adjustment for maintaining proper belt tension shall be provided. Cleaning devices, capable of removing foreign material adhering to the pulley side of the belt, shall be provided. Conveyors which extend outside the basic dimensional limits of the unit shall be of the folding, retractable, or readily demountable type. Rubber coating on the carrying side of the belt shall be not less than 3/16-inch thick and rubber coating on the bottom side shall be not less than 1/16-inch thick. Each belt-type conveyor shall be driven from a separate electric or hydraulic motor. The capacity of the motors shall be sufficient to handle the loads encountered when the plant is operating at maximum capacity. Motors shall be positioned to transmit power directly or by V-belt to the head pulley. Inclined conveyors shall be designed to prevent rollback of the belt, in the event of power failure, if electric motors are used.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:37Z
Check the source to verify that this is the current version before use.

3.13 Operator's platform. The operator's platform shall be centrally located to enable the operator to observe the units conveyor and crusher operation. Controls for plant operation shall be mounted on the platform for safe convenient operation of the unit by one operator. Access ladders, handrails, and guardrails shall be provided. Antiskid surfaces shall be provided for the deck, catwalks, and ladders. Platforms and catwalks shall be furnished to provide access to points requiring routine maintenance and adjustment. All guardrails around platform shall be demountable to reduce cube during transport.

3.14 Bearings. All antifriction or bronze bearings used on the unit, exposed to the elements, shall be provided with a dust-sealed device to prevent against the entry of abrasive materials.

3.15 Electrical equipment. All electric motors shall conform to NEMA MG1 polyphase induction, totally enclosed, fan-cooled type. The rated horsepower (hp) for each motor shall be equal to or greater than the hp requirements of the equipment driven under all operating conditions. The hp of the motors shall be such as to allow progressive starting of all electrically operated components. The electric motors shall be suitable for operation on 230/460 volt (V), 60 Hertz (Hz), 3 phase, alternating current from an outside source and shall be connected for 460 V operation. A main distribution panel conforming to NEMA PB2 shall provide circuit breakers for each electrical circuit, and a master circuit breaker that will disconnect the entire unit from the electric power supply. Circuit breakers shall conform to NEMA AB1. A motor controller operated by momentary contact start and maintained contact stop pushbuttons shall be provided for control of each electric motor. Motor controllers shall conform to NEMA ICS. Motor control pushbuttons and an emergency panic pushbutton, which controls tripping of the master circuit breaker, shall be installed in an easily accessible location at the operator's platform and each control station for each electric motor used on the unit. Panic pushbutton enclosure shall be red. All enclosures for motors, motor controllers, distribution panel, pushbuttons, and other similar electrical apparatus shall be weatherproof and dustproof. All wiring of the plant shall be furnished, including interconnections between individual components and between components and the distribution panel, to provide an operable unit when connected to 60 Hz, 3 phase power source. A permanently legible wiring diagram shall be installed on or near the main distribution panel. The function of all circuit breakers and controls shall be permanently marked on their respective panels or enclosures. Conductors shall be color coded or suitably identified. All wiring shall be adequately protected from physical damage. The electrical system and components shall meet the applicable requirements of NFPA No. 70, including grounding requirements.

3.16 Semitrailer. The maximum stress imposed on any structural component of the semitrailer shall not exceed 60 percent of the yield point. The semitrailer for the crushing unit shall be equipped with a dolly and shall be capable of being safely towed over the road at speeds of at least 15 miles per hour (mph). The dolly drawbar shall be equipped with a lunette ring in accordance with MS51336. The angle of departure shall be at least 25° and projections below the main frame members shall be held to a minimum. The gross weight on any one axle, with the unit prepared for travel, shall be held

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:37Z
Check the source to verify that this is the current version before use.

to a minimum. The gross weight on any one axle shall be not in excess of 20,000 pounds (lb): For tandem axle assembly, not exceeding 40,000 lb; for triple axle assembly, not exceeding 60,000 lb. The semitrailer shall be equipped with straight air service brakes controllable from the towing vehicle cab. All necessary air hose and standard air couplings for connecting to the brake system of a towing vehicle shall be provided. The service brake installation shall include a breakaway system capable of automatically applying the brakes in case the semitrailer is accidentally separated from the towing vehicle and shall be capable of maintaining the application for at least 15 minutes. Parking brakes, or chock blocks securely chained to the vehicle frame, shall be provided for each wheel. Chock block chains shall be of sufficient length to permit placing the blocks either ahead or behind the wheels. The blocks shall be equipped with snaphooks for storage. At least six screw-jacks shall be provided on each unit The jacks shall be capable of supporting each unit when operating fully equipped and fully loaded. Supports near the feed end of the plant and near the cone crusher shall be provided for blocking the plant during operation. The jacks shall retract sufficiently to preclude interference with the units normal travel capacities.

3.17 Tires and rims. The tire and rim ratings shall conform to T&RA recommendations for the type and size of tires furnished. Tire and rim sizes shall be the same for all wheels. Tires shall be tube or tubeless type with highway tread. Tires shall be of rated capacity at least equal to the load imposed on each tire, measured at each wheel at the ground. Tires shall be not less than 100 level quality and shall be of domestic make. When tube type tires are furnished, inner tubes shall be heavy-duty type, and shall be of proper size for the tires furnished.

3.18 Identification plate. The contracting officer shall furnish the Government inspector the required identification plates. The contractor shall stamp the necessary data, as directed by the Government inspector in the blank spaces thereon, and securely affix said plates in a conspicuous place on each unit, as directed by the Government inspector, with nonferrous screws, bolts, or rivets of not less than 1/8 inch in diameter. The aplicable nomenclature contained in the contract item description shall be placed in the top blank.

3.19 Cleaning, treatment, and painting. Surfaces normally painted in good commercial practice shall be cleaned, treated, and painted as specified herein. Surfaces to be painted shall be cleaned and dried to insure that they are free from contaminants such as oil, grease, welding slag and spatter, loose mill scale, water, dirt, corrosion product, or any other contaminating substances. As soon as practicable after cleaning, and before any corrosion product or other contamination can result, the surfaces shall be prepared or treated to insure the adhesion of the coating system. The painting shall consist of at least one coat of primer and one finish coat. The primer shall be applied to a clean, dry surface as soon as practicable after cleaning and treating. Painting shall be with manufacturer's current materials according to manufacturer's current processes and the total dry film thickness shall be not less than 2.5 mils over the entire surface. The paint shall be free from runs, sags, orange peel, or other defects. Finish colors shall be No. 14065 green, conforming to Fed. Std. No. 595.

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:37Z
Check the source to verify that this is the current version before use.

3.20 Instruction plates. The unit shall be equipped with instruction plates suitably located, describing any special or important procedures to be followed in operating and servicing the equipment. Plates shall be of a material which will last and remain legible for the life of the equipment, and shall be securely affixed thereto with nonferrous screws or bolts of not less than 1/8-inch diameter.

3.21 Toolbox(s). One or more toolbox(s) shall be provided. The toolbox(s) shall be large enough to store all tools required for field service or maintenance. The toolbox(s) shall be steel with a hinged lid and a fastener to keep the lid secure when vibrated. The toolbox(s) shall be mounted in a protected accessible location.

3.22 Stenciling. The gross weight of each demountable component of the unit shall be stenciled on each side of the component in such a manner as to be readily discernible to personnel handling the equipment. The total gross weight of the unit shall be stamped on the identification plate by the contractor.

3.23 Prime equipment accessories. Prime equipment shall be shipped with all required accessories and tools unless written deviation is received from the contracting officer.

3.24 Lifting and tying down attachments. When specified (see 6.2), the unit shall be equipped with lifting and tying down attachments. Lifting and tying down attachments shall conform to MIL-STD-209, type III. Attachments shall be indicated by a transportation plate except tying down attachments may be identified by stenciling or other suitable marking on the unit. Tying down markings shall clearly indicate that the attachments are intended for tying down of the unit on the carrier when shipped. A diagram showing the lifting attachments and lifting slings shall be inscribed on the transport and plates with the lifting capacity of each attachment and the required length and size of each sling cable marked thereon. A silhouette of the plants showing center of gravity shall be required.

3.25 Lubrication. Lubrication shall be in accordance with the manufacturer's standard practice. The lubricating points shall be easily visible and accessible. All parts requiring lubrication shall be lubricated as specified in section 5. Hydraulic lubrication fittings shall be in accordance with SAE J534. Where use of high pressure lubricating equipment, 1,000 psi or higher, will damage grease seals or other parts, a suitable warning shall be affixed to the equipment in a conspicuous location.

3.26 Fungus resistance. Electrical components and circuit elements, including terminal and circuit connections, shall be coated with varnish conforming to MIL-V-173, except that:

a. Components and elements inherently inert to fungi or in hermetically sealed enclosures need not be coated.
b. Current-carrying contact surfaces, such as relay contact points, shall not be coated.

Source: https://assist.dla.mil -- Downloaded: 202640-23T06:37Z
Check the source to verify that this is the current version before use.

3.27 Workmanship.

3.27.1 Steel fabrication. Steel used in the fabrication of equipment shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the metal. Shearing and chipping shall be done neatly and accurately. All bends of a major character shall be made with controlled means in order to insure uniformity of size and shape.

3.27.2 Bolted connections. Bolt holes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in accordance with good commercial practice, and all bolts, nuts, and screws shall be tight.

3.27.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of approved shape and of uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member.

3.27.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Welds shall be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the weld are subjected to proof and service loadings.

3.27.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping, or any other defect which reduces the castings ability to perform its intended function.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Component and material inspection. Components and materials shall be inspected in accordance with all the requirements specified herein and in applicable referenced documents.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:37Z
Check the source to verify that this is the current version before use.

4.2.1 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

4.2.2 Quality conformance inspection. The quality conformance inspection shall include the examination of 4.3, the tests of 4.4, and the packaging inspection of 4.5.

4.3 Examination. Each plant shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any necessary redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

4.3.1 First article inspection. The first article inspection shall be performed on one plant when a first article is required (see 3.2 and 6.4). This inspection shall include the examination of 4.3 and the tests of 4.4. The first article may be either a first production item or a standard production item from the supplier's current inventory provided the item meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining items to be furnished under the contract.

4.4 Tests. The component units shall be arranged in the order as shown in the approved arrangements plan of the plant and the piping and accessories shall be connected to the component units for compatibility and subjected to test in accordance with 4.4.1 through 4.4.3. Nonconformance to the requirements as specified in section 3 shall constitute failure and cause for rejection.

4.4.1 Test conditions. Prior to being tested, the plant shall be lubricated. Oils shall be those designated for use in the ambient temperature at which the tests are being performed. During all plant tests, the motors shall be run at normal operating speeds. Where individual components are tested with the use of power sources other than the plant power supply, the component will be operated at the normal plant operating speeds. As services and adjustments are performed, the plant shall be checked for ease of maintenance.

4.4.2 Operational test. The plant produced in fulfillment of a Government contract or order shall be completely assembled, adjusted, lubricated, or otherwise serviced for operation. The motors shall be started and subjected to a warmup period as recommended by the manufacturer. The plant shall be given a run-in test and all controls operated a sufficient number of times to ascertain that the components and mechanisms actuated by the controls operate promptly, fully, and without restriction of malfunction. Each wheeled unit shall be towed a distance of not less than 10 miles at an average speed of not less than 15 mph over unpaved road. Failure to pass any phase of this test shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:37Z
Check the source to verify that this is the current version before use.

4.4.3 Lifting and tying down attachment tests. When lifting and tying down attachments are required, they shall be tested to conform to 3.24.

4.5 Packaging inspection. The preservation, packing, and marking of the plant shall be inspected to verify conformance to the requirements of section 5.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or commercial as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Methods of preservation. Cleaning processes, drying procedures, preservatives, and methods of preservation are listed in MIL-P-116 and shall conform to the requirements of MIL-P-116 and any applicable specifications.

5.1.1.2 Disassembly. Disassembly shall be the minimum necessary to protect parts subject to damage or loss, and to accomplish reduction in cube. Removed bolts, nuts, pins, screws and washers shall be reinstalled in mating parts and secured to prevent their loss.

5.1.1.3 Matchmarking. Parts removed and mating parts on the equipment and attachments shall be matchmarked to facilitate reassembly. Parts and accessories removed, and mating parts on the equipment, shall be identified with weatherproof tags attached to mating parts and locations. Markings shall be applied to the tags with a waterproof material.

5.1.1.4 Cleaning and drying. Prior to the application of preservative compounds or paint, surfaces shall be cleaned by process C-1 and dried by any applicable procedure of MIL-P-116.

5.1.1.5 Unprotected surfaces. Unprotected exterior metal surfaces requiring the application of a contact preservative in accordance with MIL-P-116 and not specifically provided for herein shall be preserved as follows:

5.1.1.6 Unfinished (not machined) surfaces. Unfinished exterior metal surfaces shall be coated with type P-1 preservative.

5.1.1.7 Machined surfaces. Exposed machined surfaces shall be coated with type P-6 or P-11 preservative and wrapped or covered, as applicable, with barrier material conforming to MIL-B-121, type I, grade A, class 2 or MIL-B-22191, type II. The material shall be secured in place with waterproof tape.

5.1.1.8 Drive belts and pulleys. Drive belts shall be removed or released from tension. Removed belts shall be preserved method IC-1 or IC-3. Unpainted surfaces shall be coated with primer conforming to TT-P-664 or MIL-P-46093. A weatherproof tag shall be attached in a conspicuous location indicating: "Belts have been (removed or released from tension.) (Install or tension) prior to operation." Markings shall be applied to the tags with a waterproof material.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:37Z
Check the source to verify that this is the current version before use.

5.1.1.9 Hydraulic systems. The hydraulic fluid supply tanks shall be filled to the operating level with hydraulic fluid required for operation. The pistons shall be retracted as far as practicable into the cylinders and secured. When the pistons cannot be fully retracted, the exposed portions of the piston rods (ramshafts) shall be coated with type P-6 or P-11 preservative and the coated surfaces wrapped or covered with barrier material conforming to MIL-B-121, type I, grade A, class 2, extending the wraps approximately 2 inches onto the ram cylinders. The wraps shall be secured in place with waterproof tape. When the pistons can be fully retracted, any remaining uncoated surfaces of the piston rods shall be coated with type P-1 preservative, with no wrapping required. The hydraulic control valves shall be secured in the neutral position and preserved as specified herein for piston rods. Hoses shall not be disconnected. A weatherproof tag shall be attached to the control lever indicating: "The hydraulic supply tank is filled to the operating level with fluid required for operation. Do not drain." Markings shall be applied to the tag with a waterproof material.

5.1.1.10 Electrical motors. Preserve level A by the alternate method of MIL-E-16298.

5.1.1.11 Electrical modules. Circuitry modules, printed circuit boards, and panel boards that are not hermetically sealed should be removed, if possible, and packaged method II. If the complexity of the circuitry will not allow removal, seal area with a waterproof barrier conforming to L-P-378 or MIL-B-22191, type III, or tape conforming to MIL-T-22085.

5.1.1.12 Conveyor belts. Metal facings shall be coated with varnish conforming to TT-V-119 or MIL-V-13811. Each belt shall be completely rolled with a tube or piece of round wood placed in each end fold of the belt to prevent sharp bends. Prior to rolling, belt surfaces shall be dusted with powdered talc to prevent surfaces from adhering together. When required, to hold belt in compact roll, strapping conforming to QQ-S-781, class 1, type I, finish B, shall be placed around the roll. Suitable protective cushioning shall be placed under the strapping, and the strapping not tensioned so tight as to damage the belting. Each rolled belt shall be wrapped with waterproofed barrier material conforming to PPP-B-1055, class E-1 or E-2, with all laps, seams, and folds sealed with adhesive conforming to MMM-A-260.

5.1.1.13 Lubrication. Lubricate all grease fittings with type P-11 preservative. Wheel bearings should be lubricated with a compound specified by the manufacturer. Lubricate control mechanisms, linkage, hinges, fasteners, and all pivot points with P-9.

5.1.1.14 Brakes. Clean all surfaces as required to remove contaminants. Coat unpainted exterior surfaces of rods, levers, cables, clevises, linkage, and associated parts with type P-1 preservative. Remove brake drum covers and spray enclosed metallic components with primer TT-P-664 or MIL-P-46093. Spray coat brake drum friction surfaces with a very thin coat (0.5-0.75 mil thick) of primer. Coat friction surfaces of cams, adjusting screws, and anchor pins with type P-6 or P-7 preservative. Backoff all brake shoe adjusters for maximum clearance between brake drum and brake shoes. Do not apply coating of any type to contact surfaces of electric brakes. Adjust brake shoes to

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:37Z
Check the source to verify that this is the current version before use.

provide maximum clearance to drum surfaces and lined surfaces. In a conspicuous location in the operator's compartment, attach a weatherproof warning tag marked, "Brakes preserved. Do not apply brakes when vehicle is being moved. Use tow bar or similar arrangement for moving vehicle. Adjust brakes before placing equipment into operation." Markings shall be applied with waterproof material.

5.1.1.15 Rubber tires. Tires mounted on the wheels (road tires) of the vehicle shall be inflated to 10 lb above pressure value recommended for maximum load.

5.1.1.16 Maintenance tools. Maintenance tools shall be preserved in accordance with level A preservation and packaging requirements of PPP-P-40.

5.1.1.17 Technical publications. Technical publications for each piece of equipment shall be preserved method IC-1 or IC-3.

5.1.1.18 Consolidation. Only components of one plant shall be consolidated together. Tool boxes shall be utilized for the consolidation of loose components, tools, and publications. The remainder of the components that will not fit in the tool boxes shall be consolidated, along with disassembled components, in boxes conforming to PPP-B-601, overseas type or PPP-B-621, class 2. Contents shall be cushioned, blocked, and braced to prevent movement within the containers. Containers shall be secured to the equipment with appropriate strapping. Arrangement and location on the equipment shall be such so as not to increase cubage or interfere with lifting or mobility of the equipment.

5.1.2 Commercial. The equipment shall be preserved in accordance with the contractor's standard practice in a manner to prevent deterioration and damage.

5.2 Packing. Packing shall be level A or commercial as specified (see 6.2).

5.2.1 Level A.

5.2.1.1 Basic plant (except conveyors). The basic plant shall be prepared for mobile shipment; openings shall be sealed to prevent the entry of free falling water. Large disassembled components that cannot be consolidated, packaged, or secured to the basic plant shall be packed in crates conforming to MIL-C-52950 or MIL-C-3774. The contents shall be anchored, blocked, and braced in accordance with the appendix to the crate specification.

5.2.1.2 Portable conveyors. Portable conveyors shall be shipped knocked down to the most practicable extent. The structural components shall be nested, arranged, and secured with bolts or steel strapping, in combination with suitable wood blocking or battens, as required to form nonshifting bundles. The strapping shall be 0.035 by 1-1/4 inch strapping conforming to QQ-S-781, class 1, type I, finish B. The strapping shall be stapled to any wood blocking or battens provided. Where it is not practicable to disassemble the equipment to the extent required for suitable bundling, the sections shall be secured to skid bases conforming to the skid type base of MIL-C-104, style A crates, and shipped as individual assemblies. The electric motors, conveyor

Source: https://assist.dla.mil -- Downloaded: 202640-23T06:37Z
Check the source to verify that this is the current version before use.

belts, bolts, nuts, washers, and any other small components requiring the protection of a container for safe convenient handling shall be packed in containers as specified for disassembled components. Where skid bases are used, consideration shall be given to consolidating and securing any bundled or boxed components on the skid bases.

5.2.2 Commercial. The equipment shall be prepared for shipment in a manner which will insure arrival at destination in a satisfactory condition. Preparation for delivery shall comply with applicable carrier rules and regulations.

5.3 Marking. Marking shall be in accordance with MIL-STD-129.

6. NOTES

6.1 Ordering data. Acquisition documents should specify the following:

a. Title, number and date of this specification.
b. When specification and standards shall be other than as specified (see 2.1.1).
c. When first article is required for inspection and approval (see 3.2, 4.2.1, and 6.4).
d. When lifting and tying down attachments are required (see 3.24).
e. Level of preservation and level of packing required (see 5.1 and 5.2).

6.2 Data requirements. When this specification is used in an acquisition which incorporates a DD Form 1423 and invokes the provisions of paragraph 7-104.9(n) of the Defense Acquisition Regulations (DAR), the data requirements will be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the Contract Data Requirements List (DD Form 1423) incorporated into the contract. When the provisions of DAR 7-104.9(n) are not invoked, the data shall be delivered in accordance with the contract requirements.

6.3 Electrical power requirements. The electrical power requirements of the plant is compatible with the electrical power available from tactical utility generator sets in the DoD Mobile Electrical Power Engine Generator Set Family. After power requirements of the plant has been determined, the model(s) of generator set(s) required may be selected from MIL-STD-633, and obtained in accordance with applicable departmental policy.

6.4 First article. When a first article is required, it shall be tested and approved under the appropriate provisions of paragraph 7-104.55 of the DAR. The first article should be a first production item consisting of one complete plant unit or it may be a standard production item from the contractor's current inventory as specified in 4.2.1. The contracting officer should include specific instructions in all acquisition instruments regarding arrangement for examinations, tests, and approval of the first article.

6.5 Title change. The title of this specification was changed to "PLANT, AGGREGATE, SECONDARY, WITH CONE CRUSHER, MOBILE, 75 TON PER HOUR CAPACITY".

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:37Z
Check the source to verify that this is the current version before use.

6.6 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue, due to the extensiveness of the changes.

Custodian:

Navy - YD

Preparing activity:

Navy - YD

Project No. 3820-N009

☆ U.S. GOVERNMENT PRINTING OFFICE: 1982—505-022/3710

Source: https://assist.dla.mil -- Downloaded: 202610-23T06:37Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 12503 WASHINGTON D. C.

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE NAVY

Commanding Officer (156)
Naval Construction Battalion Center
Port Hueneme, CA 93043

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:37Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.

NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. 3820-N009

DOCUMENT IDENTIFIER *(Number)* AND TITLE

MIL-C-82015B(YD) - PLANT, AGGREGATE, SECONDARY, WITH CONE CRUSHER MOBILE, 75 TON PER HOUR CAPACITY

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1 OCT 76 1426 Replaces edition of 1 Jan 72 which may be used. S/N 0102-LF-001-4260

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:37Z
Check the source to verify that this is the current version before use.