MIL-T-62223B(AT)
14 March 1985
SUPERSEDING
MIL-T-62223A(AT)
31 October 1980

MILITARY SPECIFICATION

TRUCK, MOBILE BLOOD DONOR AND COMPONENT LABORATORY, TILT CAB: DIESEL OR GASOLINE ENGINE DRIVEN, 24,000 POUNDS GVW, 4x2, COMMERCIAL

This specification is approved for use by US Army Tank-Automotive Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a completely self-contained, mobile, self-propelled unit, designed to serve as a combination mobile blood component processing laboratory and three-bed donor facility. The vehicle shall be diesel or gasoline engine driven, four-wheel, two rear wheel drive, having minimum gross vehicle weight (GVW) of 24,000 pounds and shall be equipped with a tilt cab, a 30 kilowatt (kW) auxiliary generator and a 4 kW auxiliary generator. The body shall be fully air conditioned and heated. Vehicles procured under this specification are commercial items which shall be warranted by the manufacturer as specified in procurement documents.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. Unless otherwise specified, the following specifications, standards, and handbooks of the issues listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation form a part of this specification to the extent specified herein.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Tank-Automotive Command, ATTN: AMSTA-GBS.1, Warren, MI 48397-5000, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC-2320

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS
FEDERAL

O-E-915	- Extinguisher, Fire, Dry-Chemical (Portable).
W-B-131	- Battery, Storage; Vehicular, Ignition, Lighting and Starting.
ZZ-T-381	- Tires, Pneumatic, Vehicular (Highway).

STANDARDS
FEDERAL

FED-STD-297	- Rustproofing of Commercial (Nontactical) Vehicles.

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-1223	- Nontactical Wheeled Vehicles Treatment, Painting, Identification Marking and Data Plate Standards.

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein.

DEPARTMENT OF TRANSPORTATION (DoT)
Federal Motor Carrier Safety Regulations.
Federal Motor Vehicle Safety Standards.

(Application for copies should be addressed to the Department of Transportation, Federal Transportation, Federal Highway Administration, Washington D.C. 20591.)

ENVIRONMENTAL PROTECTION AGENCY (EPA)
Control of Air Pollution from New Motor Vehicles and New Motor Vehicle Engines.
Noise Emission Stand Medium and Heavy Transportation Equipment - Medium and Heavy Trucks.

(Application for copies should reference the Code of Federal Regulations, 40 CFR, and the Federal Register and should be addressed to the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402.)

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)
NFPA No. 70 - National Electrical Code.

(Application for copies should be addressed to the National Fire Protection Association, Batterymarch Park, Quincy, MA 02269.)

SAE, INC.
SAE Standards and Recommended Practices

J245	- Engine Rating Code - Spark Ignition.
J537	- Storage Batteries (DoD adopted).
J551	- Performance Levels and Methods of Measurement of Electromagnetic Radiation From Vehicles and Devices (20-1000 MHz).
J588	- Turn Signal Lamps.
J589	- Turn Signal Switch.
J682	- Rear Wheel Splash and Stone Throw Protection (DoD adopted).
J688	- Truck Ability Prediction Procedure (DoD adopted).
J816	- Engine Test Code - Spark Ignition and Diesel.
J1349	- Engine Power Test Code - Spark Ignition and Diesel.

(SAE standards and recommended practices are available from SAE Inc., 400 Commonwealth Drive, Warrendale, PA 15096.)

THE TIRE AND RIM ASSOCIATION, INC.
Yearbook.

(Applications for copies should be addressed to the Tire and Rim Association, Inc., 3200 W. Market Street, Akron, OH 44313.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Standard vehicle and accessories. Except as specified in 3.1.1 through 3.1.1.9, the vehicle, components, assemblies, and accessories to be delivered under the contract shall be standard or optional items, which meet or exceed the requirements of this specification. All chassis items shall be as represented in the chassis manufacturer's technical data, and special bodies or mounted equipment shall be as represented in the body and equipment manufacturer's technical data and layout drawings. Technical data shall be limited to specifications and technical material, identical to that furnished to the authorized company representatives for selection of vehicle models and components, and shall be on file in the engineering offices of the procuring activity prior to delivery of the items. The chassis model furnished shall be not older than the chassis manufacturer's model on the date of invitation for bids.

3.1.1 Special requirements. In addition to the standard vehicle and components specified in 3.1, the vehicle shall be furnished with special equipment as specified herein.

3.1.1.1 Painting and marking. Treatment, painting, marking and data plates shall be in accordance with MIL-STD-1223. The exterior color shall be the manufacturer's standard gloss white. Identification markings shall be in accordance with the requirements of MIL-STD-1223 for the military service identified by the procuring activity (see 6.2).

3.1.1.2 Special markings. When specified by the procuring activity (see 6.2), special markings shall be applied to the vehicle exterior.

3.1.1.3 Rustproofing. When specified (see 6.2), the vehicle shall be rustproofed in accordance with FED-STD-297. When specified (see 6.2), tropical rusting in accordance with FED-STD-297 shall be furnished.

3.1.1.4 Heavy duty cooling system. A heavy duty cooling system shall be furnished that will maintain coolant at a temperature below the boiling point, with vehicle loaded to rated GVW and operated at 10,000 feet above sea level or in an ambient air temperature of not less than 125 degrees Fahrenheit (°F).

3.1.1.5 Coolant system and indicators. The coolant system shall include a de-aeration system, a surge tank, or a coolant recovery reservoir of not less than 2 quart capacity. A low coolant level or high coolant temperature alarm buzzer and red indicator warning light shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

provided on the dash instrument panel. A radiator servicing access door shall be provided to allow verification of coolant level.

3.1.1.6 Wood treatment. As specified herein (see 3.5.5), wood surfaces shall be treated in accordance with MIL-STD-1223.

3.1.1.7 Towing devices. Not less than two hooks, loops, or pins for towing the vehicle shall be furnished on the front of the vehicle.

3.1.1.8 Wheel splash and stone throw protection. The vehicle shall have rigid splash shields ahead of the rear wheels and rubber mud flaps to the rear of the rear wheels. The cab shall have rubber mud flaps to the rear of the front wheels. All splash shield and mud flap installation, front and rear, shall conform to the rear wheel splash and stone throw protection provisions of SAE J682.

3.1.1.9 General layout drawings. Two general layout drawings with dimensions, shall be furnished to the engineering office of the procuring activity, US Army Tank-Automotive Command, ATTN: AMSTA-GBS.1, Warren, MI 48397-5000 for customer approval, prior to production. Drawings shall include interior color scheme(s) for customer approval.

3.2 General design.

3.2.1 Federal Motor Vehicle Safety Standards. The vehicle and furnished accessories shall comply with all Federal Motor Vehicle Safety Standards in effect on date of manufacture.

3.2.2 Air pollution control. The vehicle shall comply with the Environmental Protection Agency Regulations governing Control of the Air Pollution from New Motor Vehicles and New Motor Vehicle Engines in effect on the date of manufacture. In addition, vehicles destined for California shall comply with State of California regulations governing air pollution control in effect on the date of manufacture.

3.2.3 Sound level. The interior sound level shall conform to Federal Motor Carrier Safety Regulation 393.94. The vehicle exterior sound level shall conform the Environmental Protection Agency Noise Emission Standard for Transportation Equipment, Medium and Heavy Trucks.

3.2.4 Curb weight. The curb weight shall include the weight of the chassis, cab and body, with all attachments, accessories, and equipment; and full complement of fuel, lubricants, and coolant.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.2.5 Gross vehicle weight. Gross vehicle weight (GVW) shall consist of curb weight, operator and an assistant (weight computed at 175 pounds each), plus a nominal payload of 500 pounds, evenly distributed in the van body load area. Additionally, the chassis manufacturer's gross vehicle weight rating shall be not less than 24,000 pounds, and this rating shall be increased if required to provide the payload allowance specific.

3.2.6 Ratings. Vehicle ratings shall be the manufacturer's published rating. Component and vehicle ratings shall not be raised to meet the requirements of this specification. When published ratings are not available, verification of ratings must be submitted to the engineering office of the procuring activity. The ratings shall be established by the manufacturer of the equipment being verified. Ratings shall be submitted with the questionnaire (Commercial Vehicle Engineering Data).

3.2.7 Overall width. The overall width of the vehicle, exclusive of mirrors, lights, reflectors and tires, shall be not more than 96 inches. The width over the tires shall be not more than 100 inches.

3.3 Performance.

3.3.1 Speeds and gradeability. High and low speed requirements shall be met with the truck loaded to required GVW.

3.3.1.1 High speed gradeability. The vehicle shall ascend continuous grades of not less than 1.0 percent at 50 miles per hour (mph). Gradeability requirements shall be met with the main transmission in direct drive. Gradeability shall be verified with calculations in accordance with SAE J688 (see 6.3).

3.3.1.2 Low speed. Low speed shall be calculated with engine operating at not less than 35 percent of recommended governed speed, and shall provide a vehicle speed of not more than 5 mph.

3.3.1.3 Maximum gear speed. Maximum gear speed governed speed shall be not less than 58 mph. Conformance to geared speed specified shall be determined by calculating in accordance with the following formula:

$$\text{Maximum geared speed (mph)} = \frac{\text{Governed speed (rpm)}}{\text{Total gear reduction X tire factor (see 6.3)}}$$

3.3.2 Service brakes. The service brakes shall control and hold the vehicle, when loaded to its required gross vehicle weight, on a 30 percent grade. The service brakes shall stop the

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

vehicle, loaded to required GVW, within the stopping distance requirements of Federal Motor Carrier Safety regulation 393.52.

3.4 Chassis components.

3.4.1 Engine. The engine furnished shall be the chassis manufacturer's standard or optional engine for the commercial model truck, which meet or exceed the requirements of this specification.

3.4.1.1 Diesel engine. Unless otherwise specified (see 3.4.1.2), the engine shall be a liquid cooled, compression ignition, two-stroke or four-stroke cycle diesel type, with not less than four cylinders. Engine net horsepower used in performance prediction calculations shall be determined in accordance with SAE J816 or SAE J1349. A fan clutch shall be provided. The fan clutch shall reduce the fan speed automatically when the fan is not required for cooling.

3.4.1.2 Gasoline engine. When specified (see 6.2), the engine shall be a liquid cooled, internal combustion, four-stroke cycle, gasoline type, with not less than six cylinders. The engine shall produce the required vehicle performance when operated on unleaded fuel with a research octane rating of 91, at engine speed not more than the manufacturer's recommended operating speed. The engine shall be capable of warranted operation on unleaded fuel, when used in accordance with the operator's manual. Engine net horsepower figures used in performance prediction calculations shall be determined in accordance with SAE J245 or SAE J1349. A fan clutch shall be provided. The fan clutch shall reduce the fan speed automatically when the fan is not required for cooling.

3.4.1.3 Oil filter. A full flow type oil filter shall be furnished.

3.4.1.4 Governor. An engine governor shall be furnished and set and sealed to limit the engine to engine manufacturer's maximum recommended operating speed.

3.4.1.5 Coolant temperature control. Thermostatic control of engine coolant temperature shall be provided. For diesel engine driven vehicles, control shall be provided. For diesel engine driven vehicles, control shall include partial thermostatic control of coolant flow through the radiator shutters, or complete thermostatic control of all coolant flow through the radiator.

3.4.2 Electrical systems. The electrical system shall be in accordance with Federal Motor Carrier Safety Regulations 393.27 through 393.31 and 393.33.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.4.2.1 Starting system. For diesel engine driven vehicles, a 12 or 24-volt starting system, with 12-volt direct current (dc) lighting system, and not less than a 60-ampere alternator, shall be furnished. Engine starting equipment shall include an ether starting system or glow plug. If an ether system is furnished in lieu of a glow plug, it shall be of the measured shot type. Measured shot type ether systems shall be key operated or manually operated from the driver's compartment, shall have a reservoir of not less than 12 fluid ounces and shall be inoperative with the engine warm.

3.4.2.2 Ignition system. For gasoline engine driven vehicles, a 12-volt dc ignition system shall be furnished. An alternator of not less than 40 amperes rated capacity, and which provides not less than 16 amperes dc output at normal engine idle speed, shall be furnished.

3.4.2.3 Lighting. All vehicle lights, reflectors, and wiring shall conform to Federal Motor Carrier Safety Regulations 393.12, 393.19, 393.20, and 393.22 through 393.26(d). Lights and reflectors shall not be mounted on vertical surface of rub rails (unless recessed and fully protected) or mounted on vehicle bumpers.

3.4.2.3.1 Turn signals. Turn signal lamps shall conform to SAE J588. Operating units shall conform to SAE J589, class A, and shall be mounted on the steering column. The vehicle shall be provided with doubled-faced front signal units and with single-faced rear signal units installed in accordance with SAE J588 Except that turn signals shall not be mounted on engine compartment hood. Turn signal operating units shall have visible and audible type flash indicator.

3.4.2.4 Batteries. Each battery shall be of 12-volt potential. The total reserve capacity ratings and the total cold cranking ampere rating at 0°F, both measured in accordance with SAE J537, shall be not less than specified in table I. The batteries shall be of the maintenance free type having the maintenance free characteristics listed in W-B-131.

TABLE I. Batteries.

Engine type	Reserve capacity (minutes)	Cold cranking (amperes)
Diesel	320	1200
Gasoline	100	450

3.4.2.5 Radio interference suppression. The vehicle shall be suppressed to limit electromagnetic radiation in accordance with SAE J551. Any body equipment emitting radiation shall be suppressed to the same level as the vehicle chassis.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.4.3 Fuel system. The fuel system shall conform to Federal Motor Carrier Safety Regulations 393.65 and 393.67.

3.4.3.1 Air cleaner. An air cleaner shall be furnished. When equipped with an oil-bath type air cleaner, oil capacity shall be not less than 1 quart.

3.4.3.2 Fuel tanks. Fuel tank(s) of not less than 100 gallons total capacity shall be provided. When more than one tank is furnished on diesel engine driven vehicles, means shall be provided to assure equalized fuel level in both tanks. When more than one tank is furnished on gasoline engine driven vehicles, a selector valve connecting either tank to the engine or auxiliary engine fuel intake shall be provided and means shall be provided to monitor the fuel level of either tank from a single fuel gage. A photoetched corrosion resistant plate, marked to denote the type of fuel used, shall be located in a conspicuous place near each fuel tank filler opening.

3.4.4 Exhaust system. The exhaust system shall conform to Federal Motor Carrier Safety Regulation 393.83. Vertical exhaust mufflers capable of being reached easily by personnel entering or leaving either side of the cab shall be provided with a heat shield. Vertical exhaust system shall be provided with a hinged rain cap.

3.4.5 Automatic or semiautomatic transmission. The vehicle shall be provided with automatic or semiautomatic transmission. The transmission shall provide continuous drive, a hydraulic torque converter and not less than four forward gear ratios. Normal driving range selector position shall provide not less than four forward gear ratios without movement of the selector. A drive gear for the power takeoff shall be provided. Input torque capacity of the transmission shall be not less than the maximum torque delivered by the engine.

3.4.6 Drive line components. Drive line components shall be adequate to transmit the maximum delivered torque of the engine, as developed through the maximum gear train reduction.

3.4.7 Frame. The chassis frame shall be the manufacturer's standard for the type and size vehicle furnished, and shall be adequate for mounting the body and equipment specified herein. The frame shall be lengthened or shortened to the required body length to provide support for all body crossmembers. Frame modifications shall be as recommended by the chassis manufacturer for the body builder's layout.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.4.8 Suspension. The vehicle shall be equipped with a suspension system, with components having a rated capacity at least equal to the load imposed on each member, measured at the ground, with the vehicle loaded to required GVW. When suspension is rated at the spring pads, unsprung weight shall be deducted. The vehicle shall be equipped with hydraulic, double-acting shock absorbers at the front wheels.

3.4.8.1 Full air rear air suspension. Rear axle equipped with full air suspension shall have four air springs of adequate diameter. The suspension design shall be such that the natural frequency of vertical vibration about any transverse axis shall not exceed 1.5 hertz at rated capacity for specific GVW. Full air system shall have none of the sprung weight carried on anything other than air springs. No other spring medium such as leaf, coil, or rubber springs may be used in conjunction with the air springs. Full air system shall incorporate four radius rods to control lateral and longitudinal movement. Radius rods shall transmit driving and braking forces to chassis and body. Each end of the radius rods shall be equipped with rubber bushings that do not require periodic lubrication. Suspension system shall include locking devices to lock up the suspension to preclude damage when lifting and towing the truck from the rear.

3.4.9 Axles. Axle ratings shall be at least equal to the load imposed on each axle, measured at the vehicle loaded to the required GVW. The gear ratio shall provide performance specified in 3.3.1. A single reduction rear axle shall be furnished.

3.4.10 Wheels, rims, tires, and tubes. The vehicle shall be equipped with single front and dual rear wheels. Rims and tire ratings shall conform to Tire and Rim Association recommendations, for the type and size of tires furnished. Rim and disc wheel sizes shall be the same for all wheels on each vehicle. Tire size and load range (ply rating) shall be the same for all tires on each vehicle. When specified (see 6.2), disc type wheels shall be furnished.

3.4.10.1 Tires. Steel belted radial or, when specified (see 6.2), bias ply tires shall be furnished. Tires shall be tube or tubeless type with highway tread. The tires shall be of a rated capacity at least equal to the load imposed on each tire, measured at each wheel, at the ground, with the vehicle loaded to required GVW. Tires shall conform to Tire and Rim Association recommendations or to ZZ-T-381 with a size designation system the same as the Tire and Rim Association.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.4.10.2 Inner tubes. When tube type tires are furnished, inner tubes shall be of the heavy duty type, and shall be of the proper size for the tires furnished. Tire flaps shall be furnished for tube type tires in accordance with Tire and Rim Association recommendations

3.4.10.3 Carrier for spare tire assembly. Unless otherwise specified (see 6.2), a carrier for a spare wheel or rim and tire assembly shall be installed in a readily accessible location on the vehicle. Threaded fasteners, when used to secure the spare tire in the carrier, shall be constructed of or plated with corrosion resistant material. The carrier design shall enable removal or mounting of the spare wheel assembly using only the tools specified in 3.4.16.1.

3.4.10.4 Spare wheel or rim. When specified (see 6.2), a spare wheel or rim shall be furnished. When a spare tire assembly is specified (see 3.4.10.5), a spare wheel or rim shall be furnished.

3.4.10.5 Spare tire assembly. When specified (see 6.2), a spare tire assembly shall be furnished. The spare tire assembly shall include an inflated spare tire mounted on the spare wheel or rim. The spare tire shall be of the same size, tread design and ply rating as the tires furnished on the vehicles.

3.4.11 Brakes. Brakes shall conform to Federal Motor Carrier Safety Regulations 393.40 through 393.43 and 393.45 through 393.52.

3.4.11.1 Service brakes. The vehicle shall be equipped with full-air brakes on all wheels. The braking system, complete with all necessary components, shall include:

(a) Air compressor, unloader-head type, engine driven and engine lubricated, air or water cooled, and having a capacity of not less than 7-1/4 cubic feet per minute (cfm).
(b) Air storage reservoir(s) with not less than 2,000 cubic inches total capacity, each tank equipped with drain, and with safety and check valves between compressor and last reservoir tank.
(c) Foot control, suspended or treadle type.
(d) Air control valves.
(e) Air pressure gage, visible to the driver.
(f) Low air-pressure warning, visible and audible.
(g) Service brake stop lamp switch.
(h) Alcohol aspirator with unbreakable transparent container.
(i) Automatic moisture ejector.
(j) Automatic slack adjusters.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

(k) When specified (see 6.2), in lieu of subparagraph (h), an air dryer shall be furnished. The air dryer shall be of the desiccant type.

3.4.12 Cab. A tilt type cab, with tilting and locking mechanism, shall be furnished. Cab doors shall be equipped with locks, operable from inside the cab through mechanical linkage, and with at least the curbside door equipped with external, key-operated lock. Drip rails shall be provided above the cab doors. Unless otherwise specified, the cab shall have upholstered, full width, adjustable seat and back or individual, adjustable driver's seat and individual passenger seat. When specified (see 6.2), an individual, adjustable driver's seat and individual passenger seat shall be provided. The color of the upholstery and the interior finish shall be compatible with the exterior color (3.1.1.1). White upholstery shall not be furnished. Interior lighting shall be provided. Manufacturer's standard fastenings and two pairs of seat belts shall be installed. Safety grips shall be provided on each side of the cab to assist personnel in entering and leaving the cab. Provisions to facilitate cleaning the windshield shall be provided by means of a bumper step, or bumper step cutouts, and a grab handle located under the windshield. When step height exceeds 24 inches, a secondary step shall be provided.

3.4.13 Steering. Power steering shall be furnished.

3.4.14 Windshield wipers and washers. The vehicle shall be equipped with dual windshield wipers and windshield washers. Windshield wipers shall be multispeed type and operated by either air or electric motor(s).

3.4.15 Bumpers. Unless the bumper is an integral part of the vehicle cab, a channel type front bumper shall be provided on the vehicle.

3.4.15.1 Rear end protection. The rear end of the vehicle shall be protected in accordance with Federal Motor Carrier Safety Regulation 393.86. A full width, channel type rear bumper shall be provided.

3.4.16 Tool stowage. Stowage space of sufficient size to accommodate vehicle jack, hand tools, antiskid chains, electrical lead-in cable, and emergency reflective triangles shall be furnished for retaining equipment during vehicle operation. Stowage space for these tools may be furnished inside the cab. When stowage space for these tools is located outside of cab, it shall be weatherproof and shall provide for locking with a padlock or shall be provided with a flushmounted, chrome, keyed lock.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.4.16.1 Tools. When specified (see 6.2), each vehicle shall be furnished with tools required for exchanging a mounted tire assembly with the spare assembly, and shall include at least a hydraulic jack, jack handle and wheelnut wrench. The jack shall be of such closed height as to permit its location under axle, or other satisfactory lift point at any wheel with the tire flat. The jack, without blocking, shall be capable of raising any wheel of loaded vehicle to a height adequate to permit removal and replacement of wheel and tire assembly.

3.4.17 Heater and defroster. The vehicle shall be provided with a hot water heater with fresh air intakes and discharge outlets to floor and to windshield defroster louvers. The heater shall be complete with blower and mounted controls convenient to the driver.

3.4.18 Controls and operating mechanisms. All controls and operating mechanisms shall be located for left-hand drive. Controls shall be complete and conveniently operable by the driver. Lever controls shall be designed and located to permit easy entrance and exit of the operator to and from the driver's compartment. Instruments and controls shall be identified as to their function and installed in a manner to facilitate removal and servicing. All instruments shall be panel mounted and visible to the driver when seated in driving position.

3.4.19 Accessories and equipment. Chassis equipment shall be complete with all accessories furnished as standard equipment by the manufacturer. The following minimum equipment shall be furnished:

(a) Key-operated ignition switch.
(b) Ammeter, charging indicator or voltmeter.
(c) Fuel gage.
(d) Oil pressure gage or indicator.
(e) Engine temperature gage or indicator.
(f) Speedometer with recording odometer.
(g) Ash receptacle.
(h) Dual sunvisors.
(i) Front door mounted armrest on driver's side.
(j) Driver's compartment ventilator other than window.
(k) Tachometer, for diesel engine driven vehicles only.

3.4.20 Rearview mirrors. Outside rearview mirrors shall be mounted on each side of the cab. The mirrors shall be of the combination type having flat and convex areas inclosed in a common housing. The flat portion shall have not less than 50 square inches of reflective area. The convex portion shall have not less than 20 square inches of reflective area. The mirrors shall have not less than two supports.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.4.21 Horn. The manufacturer's standard electric horn shall be furnished.

3.5 Body. The body material, construction, equipment and furnishing shall be as specified herein. The body shall be custom manufactured as specified, to provide a self-contained combination mobile blood component processing laboratory and a three-bed donor facility. The body shall be manufactured in accordance with the highest standards of the industry. All equipment and furnishings shall be secured to withstand mobile vehicle operations. Body nominal interior dimensions shall be 26-1/2 feet long by 7-1/2feet wide by 7 feet high. The body shall provide a comfortable environment for donors and working personnel for extended periods when the vehicle is parked.

3.5.1 Body mounting. Kiln-dried hardwood or dense southern yellow pine bed pieces shall be fitted to the top surface of the chassis frame and counter-bored as required to accommodate any chassis frame rivets and to give uniform load distribution over the vehicle frame. The hardwood bed pieces shall be capped with high-tensile steel 4-inch channel along the full length of the longitudinal chassis frame members. Evenly spaced, threaded "U" bolts, with tie bars and captive nuts, shall secure the body, steel channel and bed pieces to the chassis frame.

3.5.2 Framing and exterior. The body and roof framing shall be constructed of aluminum extrusions of nominal 0.125 inch thickness or not less than 1-3/4 inch square tubular high-tensile steel. Body framing shall be braced at all points of stress. The exterior sides, ends and roof shall be covered with aluminum alloy. Where steel framing is used, side posts may be of 1-1/2 inch square tubular high-tensile steel. Body and floor frame members shall be installed on nominal 16-inch centers. Door and window frames shall be reinforced and gusseted to prevent torsional twisting. Supports and reinforcements shall be provided for the installation of cabinets, lights and equipment. Metal tapping plates shall be installed between members to secure wall mounted equipment. Three-quarter inch thick plywood tapping plates shall be installed in the ceiling to positively secure fluorescent light fixtures. The body structure shall be capable of resisting all generally and locally applied loads resulting from normal intended usage without excessive deflection, cracking, permanent deformation, loosening of joints, or premature fatigue failure. Where aluminum and steel surfaces come into contact, effective means shall be provided to preclude electolytic action.

3.5.2.1 Exterior panels. The exterior side, end and roof panels shall be constructed of aluminum sheets of an alloy and thickness adequate to provide the required strength. The side and end panels shall be not less than 0.050 inch thick. The exterior body panels shall be all

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

smooth finish or the bottom half of the panels may be beaded. Sheets shall be overlapped and double-sealed with Alumelastic sealing compound, and shall be securely riveted to the body frame members. The roof shall be a one-piece panel of not less than 0.040 inch thick aluminum or not less than 20 gage (0.0359 inch) hot rolled steel with a rise at the center for efficient drainage. A drip molding shall be provided around the entire perimeter of the body. The body, roof and panel joints shall be watertight. The body exterior panels shall be leakproof. All adjoining surfaces shall prevent entry of water or moisture when exposed to a water spray test (see 4.3).

3.5.2.2 Wind deflector fairing. A wind deflector fairing shall be attached to the upper front face of the body, shall be functionally and dimensionally compatible with the air conditioning unit used, and shall enclose the air conditioning unit. Access panels for use in operating and maintaining the air conditioning unit shall be provided. The deflector shall have an aerodynamic fairing shape to direct airflow around the sides and over the top of the body. The deflector shall have a convex profile in both side and top views, forming a smooth compound curved surface blending into the rectangular body cross section. The lower edge of the fairing shall be located as required to minimize drag due to turbulent airflow from the cab. The fairing construction material shall be molded fiberglass. The structural design of the fairing and its attachment system shall withstand, without excessive deflection, cracking or failure in the fairing or body structure, all applied loads, vibrations, and environmental conditions normally associated with a five-year commercial service life. Design operational limits shall include forward vehicle speeds of 60 mph during wind gusts of 60 mph from any direction. The wind deflector shall not interfere with tilting the cab.

3.5.2.3 Doors. Entrance and emergency doors shall be aluminum faced plywood core, one piece molded fiberglass plastic laminate construction, or pan-type, constructed of 0.125 inch aluminum, with aluminum tube reinforcement. Doors shall be insulated and shall close on dust-sealing neoprene extrusions. Doors shall include safety glass window with removable curtains, and a double-acting door latch with keyed locks. Chromed grab handles shall be provided at door entrances. The entrance door shall be provided with a securing device to hold it in open position. The entrance door shall have an inset stepwell with a hinged aluminum cover equipped with non-skid safety tread, with pull-out steps under the stepwell. A foldout step shall be provided at the emergency door. All steps shall be capable of withstanding repeated loads up to 250 pounds. The emergency door shall be provided at the curbside within the Laboratory Area and the entrance door shall be on the curbside near the front.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.5.2.4 Windows. Not less than five tinted, sliding, heat absorbing, safety glass windows shall be provided. The windows shall be provided with fingertip control permitting easy opening and adjustment to various desired positions. The windows shall be rattleproof and, when closed, shall be rainproof, waterproof and windproof. Insect screens shall be provided for all windows. All windows shall be furnished with curtain rods and curtains of appropriate color to complement the interior decor. Curtain rods shall be removable. Windows shall be located as follows: one on the streetside in the interview-reception area: one on the streetside in the recovery area: and one above each of the three donor beds (two on the curbside and one on the streetside).

3.5.3 Insulation. The body shall be insulated on the sides, front, rear, on the entrance and emergency doors, under the floor, and in the ceiling. The insulation shall be either foamed-in-place flexible batt type, fibrous or cellular material. If foamed-in-place urethane insulation is installed, it shall be of a non-formaldehyde based compound. The material shall be fire retardant, odorless, shall not breed or promote growth of fungus, corrode metals, or settle. The insulation shall be installed between the space of the interior and exterior panels. A vapor barrier shall be installed between the interior panels and the insulation. A vapor barrier is not required with foamed-in-place insulation. The insulation shall be installed in a manner that prevents future sags or settling due to vibration. The insulation shall remain in a fixed position during vehicle operation on highways and gravel roads. The insulation shall be of sufficient density to enable the air conditioner and heaters to meet the requirements of 3.5.7 and 3.5.8.

3.5.4 Interior walls and ceiling. The interior of the body sides, front, rear and ceiling shall be insulated (see 3.5.3) and paneled. Foam tape (or equivalent) shall be installed on frame members, prior to installation of the interior paneling, to act as a thermal barrier. The interior walls shall be lined full width, height and length with vinyl coated plywood paneling. Pressed wood shall not be furnished. Panels shall be installed and secure with joiners, edgings and moldings. The ceiling shall be Armstong Reflex V, or equal, hardboard panels.

3.5.5 Floor. Floor crossmembers shall be of adequate size to support body and payload without fracture of failure under all combinations of expected loading. Above cross sills, galvanized sheet shall be installed to fully enclose the floor area. Insulating hardboard shall be secured above the galvanized sheets. Waterproof plywood, 1-1/2 inches nominal thickness, shall installed above the insulating hardboard. Unless otherwise specified (see 6.2), the floor shall

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

be surfaced with Armstrong, or equal, heavy duty, cushioned vinyl linoleum. The unit shall be constructed without wheelhousings to provide a straight-through floor. Wood parts, including plywood, shall be treated as specified in 3.1.1.6. Additional crossmembers shall be provided, if required, to support floor loads in critical stress areas.

3.5.6 Electrical system. The electrical system shall be in accordance with the National Electric Code (NEC), NFPA No. 70. The vehicle shall be equipped with a 30-kilowatt (kW), 120/240-volt, single phase, 60-hertz (Hz), 4-wire main generator and a 4 kW, 120/240-volt, single phase, 60-Hz, 4-wire auxiliary generator wired through appropriate circuit breaker(s) to the vehicle electrical system and to an external electrical receptacle to receive local power via lead-in cable. Wiring shall be provided for all 120/240-volt equipment. Circuit breaker box(es) of adequate capacity shall be installed at appropriate location(s) within the vehicle. An additional 120-volt power inlet shall be provided and wired as specified herein.

3.5.6.1 Wiring. All wiring shall be NEC standard plastic-jacketed, nonmetallic sheathed cable with ground. Wiring shall be concealed yet easily accessible for repairs. Wiring and related devices shall be installed in a workmanlike manner, mechanically and electrically secure. Devices, lamps and other equipment requiring periodic service shall be readily accessible and serviceable. Wiring shall be protected by grommets when passing through structural members. Wiring shall include the following:

(a) Individual 120-volt circuits provided for utility equipment lights, receptacles.
(b) 240-volt circuits for air conditioning, blood centrifuge units and electrical heating units.
(c) Duplex 120-volt receptacles shall be provided in convenient locations within the body interior.

3.5.6.2 Lighting. Fluorescent lights in standard 1, 2 or 4-tube fixtures shall be surface-mounted on the interior body ceiling within plastic diffuser panels or beneath cabinets above work counters to give a minimum light density of 75 foot candles at working distances in all parts of the room. Light fixtures shall be installed so that working personnel will not cast a shadow on their work. Diffusers shall be equipped with devices to prevent falling in transit. In order to limit light density, each bank of ceiling lights shall be wired in series so that 50 percent of the ceiling lights can be controlled by each of two wall switches. Twelve-volt dome lights shall be provided at each entrance/exit door and within each exterior body compartment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.5.6.3 Main generator. A 30-kW, 120/240-volt, 60-Hz ac, 4-wire, single phase main generator shall be provided. The generator shall be shock mounted on vibration isolators and shall be installed for easy servicing.

3.5.6.3.1 Generator compartment. The generator shall be driven by a liquid cooled engine. The generator shall operate on the same type of fuel as the vehicle's main engine. The generator engine shall output power to drive the main generator to meet the requirements specified in 3.5.6.3. The engine shall be equipped with starting battery, fuel pump, air cleaner, and critical area silencer. The generator engine shall be installed for proper heat and exhaust dissipation. The engine mounting shall minimize transfer of vibration. A seamless stainless steel exhaust section shall connect the generator engine manifold with the intake of the critical area silencer. A flexible, stainless steel exhaust section, not less than five feet in length, shall be provided. Exhaust section shall be equipped with a quick disconnect connector to add to underbody exhaust line for additional fume dissipation.

3.5.6.3.2 Generator compartment. A generator compartment shall be located at the rear of the vehicle. The ceiling and the back wall of the compartment shall be surfaced with fireproof panel sheets secured to 0.090 inch thick aluminum panels or 12 gage (.1046 inch) steel panels below the floor line and 24 gage (.0239 inch) steel panels above the floor line. Hinged vent panels shall be provided at each side for proper ventilation. The compartment shall be enclosed with not less than 1/2-inch thick Homesote, or equal, panels on the body interior and surface with Formica, or equal, countertopping and paneling on the interior wall (see 3.5.10.4(e)). The area between the generator and the body interior walls shall be insulated. The compartment shall be accessible from the rear of the vehicle via hinged, louvered doors equipped with flushmounted locks and holders for securing doors in open position.

3.5.6.3.3 Generator accessories. Generator accessories shall include:

(a) A pigtail cable section with not less than a 240-volt, 150 ampere waterproof receptacle for plugging into power inlet receptacle installed within the generator compartment.
(b) A remove start/stop button, hour meter, and battery condition indicator installed within the body interior.
(c) An ac instrument package.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.5.6.4 Auxiliary generator. There shall be installed in an insulated, fireproof compartment within the body skirt at streetside an auxiliary, 120/240-volt generator of not less than 4-kW capacity. The generator engine shall be supplied from the vehicle fuel tanks (see 3.4.3.2). Louvered access doors shall be provided. The generator shall provide electrical power to operate installed refrigerators, lights and at least one auxiliary electric heater while in transit. Auxiliary generator will relieve the cost of operation and maintenance of the 30-kW power plant when interior air conditioning and centrifuges are not being used. The auxiliary engine generator set installation, engine equipment and accessories, generator compartment, and generator accessories shall be furnished in accordance with the same requirements specified for the main engine generator in 3.5.6.3 through 3.5.6.3.3. Exhaust from the engine generator shall be directed towards the rear rather than the front for dissipation of exhaust gases during in-transit travel.

3.5.6.5 Power inlet, 120/240-volt. A weatherproof power inlet receptacle shall be provided near the rear of the vehicle to accept 150 ampere, 120/240-volt, 4-wire, single phase, 60-Hz local power. The receptacle shall be wired into the vehicle electrical system through appropriate circuit breakers/disconnects.

3.5.6.5.1 Lead-in cable. A 50-foot, neoprene-jacketed, 4-wire, lead-in cable equipped with a plug and weatherproof receptacle on one end and alligator clips on the other end shall be provided to permit 120/240-volt local power to be fed directly into the vehicle if so desired. The cable shall be sized to unit total capacity.

3.5.6.6 Power inlet, 120-volt. One 120-volt, 30-ampere, 3-wire, grounded, weatherproof inlet receptacle shall be provided on the vehicle exterior feeding a plugmold receptacle within the body interior. Separate line shall permit the use of plug-in 120-volt equipment plus a portable nighttime heater within the body interior through use of local power sources via the lead-in cable. A 50-foot lead-in cable, with standard plugs, shall be provided.

3.5.6.7 Exterior portable floodlights. Waterproof 120-volt receptacles shall be installed on the body exterior adjacent to the entrance door. Two brackets shall be mounted for holding floodlights for night illumination. Two 150-watt portable floodlights shall be provided. The floodlights shall be removable for storage during transit. The floodlight installation shall be protected by ground fault interrupters.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.5.7 Air conditioning. The vehicle shall be equipped with an air conditioning unit that is functionally compatible with the wind deflector fairing as specified in 3.5.2.2. The unit shall be a 28,000 Btu per hour cooing/177,065 Btu per hour electric resistance heating unit rated for 208/230 volts, 60 Hz. The unit shall be shockmounted, properly framed and supported, and connected with ceiling mounted ducts with adjustable air diffusers throughout the body interior. The unit shall be thermostatically controlled. The unit shall be of sufficient capacity to maintain an evenly circulated cooling temperature of 72°F maximum in 95°F ambient air temperature. A flexible tube shall be installed at the front bulkhead to carry condensate run-off directly to the ground. A rustproof metal dust shield shall be installed in front of the air conditioner intake.

3.5.8 Heating. A total of two electric fan blower heaters, 3,4000 Btu minimum, 240-volt, 60-Hz ac, shall be installed in the ceiling above the curbside doors. A thermostatically controlled, electric heater with blower, rated at 6,800 Btu per hour minimum shall be provided at each of two selected interior locations. The electric fan blower heater shall be capable of maintaining the inside vehicle body temperature at a minimum of plus 70°F midway between floor and ceiling in an outside ambient temperature of 0°F with no occupants.

3.5.9 Plumbing. A plumbing system shall be installed and shall include a 20-gallon fresh water tank, a 20-gallon waste water tank with hose connection (see 3.5.10.4(c)), an electric hot water heater installed at the sink, and a 12 volt, heavy duty water pump. The plumbing system shall be designed to receive water directly from local sources or from the installed water tank. Plumbing fixtures, devices and appurtenances shall be supplied with water in sufficient volume and at pressures adequate to enable them to function satisfactorily and without undue noise, leakage or loss of pressure. The plumbing drain system shall be installed to prevent any leakage (see 4.4.5.5 and 4.4.5.6). The fresh water tank shall be installed under the counter or within a heated skirt compartment for protection against freezing. An exterior water fill shall be provided for the fresh water tank. The plumbing system shall be equipped with check valves in accordance with approved commercial practice. One 50-foot fresh water hose and one 50-foot waste water hose shall be provided and shall be of different sizes to prevent intermix. One 5-gallon G.I. water can shall be provided for emergency use.

3.5.10 Interior furnishings. The interior furnishings shall include but not limited to the following features.

3.5.10.1 Interview and reception area. The interview and reception area shall have:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

(a) An L-section desk/counter surfaced with Formica or equal, with a center drawer. A 2-drawer file cabinet with lock and storage cabinets under desk. Storage cabinets above desk on streetside.
(b) A floor-to-ceiling staff closet equipped with access door and keyed lock, located at the end of the counter on the curb side.
(c) Castered upholstered chair for the interviewer and upholstered pedestal stool with backrest for the donor. Straps or holding devices shall be furnished to secure the chair and the stool when in transit.

3.5.10.2 Donor area. The donor area shall have:

(a) A floor-to-ceiling partition with safety handrail installed adjoining the stepwell.
(b) Three counters surfaced with Formica or equal, with removable, fitted pads secured with Velcro holding devices, of adequate size for use as donor beds. Counter height shall be 29 inches plus a 4-inch pad.
(c) Storage cabinets and drawers built under each donor bed. Latches shall be provided to insure positive closing for security in transit.

3.5.10.3 Recovery area. The recovery area shall have:

(a) Built-in upholstered lounge seat with backrest, with storage compartment under lift-up seat.
(b) A work counter, surfaced with Formica or equal, with stainless steel sink inset in counter. Storage cabinet above counter at ceiling. Coffee urn mounted on counter top adjacent to sink.

3.5.10.4 Laboratory area. Unless otherwise specified (see 6.2), laboratory area shall have:

(a) Folding doors installed at both streetside and curbside of body, with center latching device, to separate laboratory area from recovery area.
(b) Two DuPont Sorvall Model RC-3B, with rotor, of latest available model or equal, automatic refrigerated centrifuges installed, wired and secured. Centrifuge units shall include elevated control panel with combined master switch and circuit breaker, speed selector permitting automatic acceleration to all speeds from 150 rpm to 6,000 rpm, gyro-action self-centering direct drive, heavy duty refrigeration system with temperature control range from plus 32°F (0°Celsius (°C)) to plus 86°F (30°C);

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

temperature readout from minus 5°F (-20°C) to plus 104°F (40°C) at full speed, adjustable dynamic braking, electric tachometer, pilot lights, temperature control and indicator. Units to operate from 230 volts ac, 60 Hz, single phase, 25-ampere vehicle supply. Units shall be equipped with 0 to 30 minute timers.

(c) Sink and permanently mounted recreational vehicle style toilet, installed on streetside. The sink and toilet shall include a 14-gallon capacity polyethylene holding tank for out-of-sight, below-floor installation with either bottom or end drain and shall include fittings and connectors with disposal hose section (see 3.5.9).

(d) Opaque curtain to enclose sink and toilet with track at ceiling.

(e) A lab counter surfaced with Formica or equal, installed across rear bulkhead above generator compartment. With storage cabinets between top of counter and top of insulated recessed generator compartment if space permits.

(f) Storage cabinets with sliding doors and positive latches installed at ceiling above counter.

(g) A hinged Formica or equal, surfaced folding counter mounted on inside of emergency door.

(h) A Jewett Model CT-1 or equal, blood bank refrigerator shall be installed on the counter across the rear bulkhead. The refrigerator shall be equipped with temperature monitor and automatic controls factory set to produce and maintain a temperature of 2°C to 4°C. The refrigerator shall include a 7-day chart recorder. Insulation shall be installed, if required, to prevent excessive heat transfer from the engine generator set to the blood bank refrigerator.

(i) An access door for centrifuge service and removal shall be provided within the streetside wall. The access door opening shall be of adequate size to permit easy entrance and exit for servicing and removal of the centrifuge.

(j) Two 120-volt exhaust fans shall be installed within the wall or door for heat dissipation. One fan shall be located behind each refrigerated centrifuge.

3.5.11 Sound system. A sound system, including a solid state amplifier, an AM/FM radio/cassette tape recorder unit, and three ceiling-mounted speakers, shall be provided. The amplifier shall include a microphone and cords, and connectors to connect additional sound equipment. Speakers shall be provided with individual volume controls located to permit easy access by the operator. The sound system shall perform satisfactorily with all equipment in operation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.5.12 Fire extinguisher. A 5-pound chemical type fire extinguisher conforming to Federal Motor Carrier Safety Regulation 393.95(a) shall be mounted in a convenient location in the vehicle body. The fire extinguisher shall have an Underwriters' Laboratory rating of 10B:C or more, shall include a metal safety pin and wire and shall conform to type I or type II, class 2, size 5 of O-E-915. The fire extinguisher shall permit visual determination of condition of charge.

3.5.13 Emergency reflective triangles. Three emergency reflective triangles conforming to Federal Motor Carrier Safety Regulation 393.95(f)(2)(i) shall be furnished and properly stowed.

3.5.14 Stabilizing jacks. Two removable stabilizing jacks shall be mounted under the front bumper. Two adjustable, heavy duty, geared, 30 inch total travel jacks with eight turns to the inch travel shall be mounted behind the rear wheels. Each jack shall be rated at 12,000 pounds load capacity and shall be equipped with removable, adjustable height, 8-inch square sand plate foot section so that cranking can be limited to 2 to 3 inches. The jacks shall be capable of leveling the vehicle and shall provide adequate stability with relation to the ground while the vehicle is under normal stationary service.

3.5.14.1 Sight levels. Sight levels shall be provided at the body rear and at the curbside to aid in leveling the unit.

3.5.15 Awnings. When specified (see 6.2), two spring-loaded, roll-up awnings with support rods shall be provided and installed on the curbside of the vehicle. Brackets shall be installed on the body side to hold awning support rods when the awnings are in extended position. Awnings shall extend not less than 8 feet outward. Each awning shall be not less than 12 feet wide. Awnings shall be located to cover the front door, the rear door, and the area between the two doors.

3.6 Servicing and adjusting. Prior to acceptance of the vehicle by the Government, the contractor shall service and adjust the vehicle for operational use including at least the following: alinement of lights; adjustment of chassis engine, heating and air conditioning systems, and brake system; filling and charging of all batteries; alinement of front wheels; inflation of all tires; complete lubrication of chassis, engines and running gear with grades of lubricants recommended for the ambient air temperature at the delivery point; servicing of engine cooling systems with ethylene glycol type antifreeze and water in equal parts by volume; and servicing of windshield washer reservoir with water and appropriate additives.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.7 Workmanship. Defective components or parts and assemblies which have been repaired or modified to overcome deficiencies shall not be furnished. All parts shall exhibit no evidence of damage, mutilation, or poor workmanship. Damaged components or parts that have been subjected to rebuild or repair shall not be used as replacement arts or components. All mounting devices such as bolts, nuts, and rivets shall be complete and secure in accordance with the highest standards of the industry.

3.7.1 Metal fabrication. Metal used in the fabrication of equipment shall be free from kinks and sharp bends. The straightening of material shall be gone by methods that will not degrade the design strength of the metal. Shearing and shipping shall be done neatly and accurately. All bends of a major character shall be made with controlled means in order to insure uniformity of size and shape.

3.7.2 Bolted connections. Bolted holes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in accordance with good commercial practice, and all bolts, nuts and screws shall be tight.

3.7.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of an approved shape and of uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes, and shall be in full contact with the surface of the member.

3.7.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease or other foreign matter. Welds shall be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the welds are subjected to proof and service loadings.

3.7.5 Paneling installation. All interior and exterior paneling shall be installed uniformly, free of misalinement, open seams, gaps and uneven surfaces. Exterior paneling shall be securely riveted to the body frame and free of damaged or missing rivets. Sealing compound shall be applied uniformly. Interior paneling shall be secured and free of missalined joiners, edgings, and moldings. All paneling shall be free of buckling, waviness, dents, nicks, scratches, sharp edges, burrs, other forms of deformation, and surface defects.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

3.7.6 Door and window installation. All exterior doors and windows shall be properly located, fitted and sealed to prevent entrance of air, dust and water. All doors and windows and associated hardware shall operate without binding. Window curtains shall be the appropriate color, durable material, free of uneven stitching, crooked seams, runs, tears or color fade and shall be installed in an orderly fashion.

3.7.7 Installation of insulation. The insulation shall be installed in a manner that will exclude excessive voids, open spaces, rips, tears and other types of damage or defects. Wherever practical, the insulation shall be installed prior to the closing of spaces in the body interior. The insulation shall be installed and secured in a manner to retain the material in a permanent position under all operating conditions.

3.7.8 Floor installation and floor covering. Galvanized sheet metal used to enclose the floor area shall be securely installed and free of gaps, open seams, cuts or open holes. All wood parts shall be free of cracks or splinters and thoroughly treated to provide full and uniform coverage (see 3.5.4). The material shall be applied uniformly, free of thin or bare areas. The carpeting shall be installed on the floor surface and fitted without gaps, visible seams, bulges, frayed edges or color fade.

3.7.9 Electrical system installation. The electrical system installation shall provide proper routing of electrical wiring with clearances between wiring and applicable parts. All wiring shall be mechanically and electrically secured, fastened or clipped at points of bending and protected against chafing and damage. Wiring shall be concealed and easily accessible for repairs. All circuits shall be properly grounded. Electrical wire covering (insulation) shall be free of cracks, cuts, kinks, frays or similar defects. All wiring and outlets shall be securely installed to preclude loose or faulty connections. Wall outlets and electrical fixtures shall be installed uniformly. All electrical appliances shall be securely mounted and properly positioned to prevent damage.

3.7.10 Air conditioning and heating system installation. The ceiling mounted ducts shall be straight and smooth on the inside with joints neatly finished. Ducts shall be anchored securely and shall be free of vibration and undue noise. Joints and outlet connections shall be substantially airtight. Laps shall be made in the direction of the airflow. All edges and slips shall be smooth. Ducts shall be free of dents, nicks, buckling, open seams and deformation. The adjustable diffusers shall be securely mounted and fitted in a neat straight position. The diffusers

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

shall be capable of adjustment without binding or interference. The fan blower heaters shall be securely mounted, shall be free of gaps, exposed electrical wiring, and exposed insulation. The fan blower shall be capable of operating without malfunction, vibration or undue noise.

3.7.11 Plumbing installation. The installed plumbing system (appliances, fixtures, devices and associated equipment) shall be capable of functioning satisfactorily without water leaks, excessive vibration or undue noise. All plumbing equipment shall be securely mounted and shall show no evidence of damage (scratches, dents, chipping). All drainage plumbing shall be installed in a manner to prevent leakage caused by improperly assembled components.

3.7.12 Laminated surface of counters and desks. The counter and desk laminated surfaces (Formica) shall be securely installed, properly fitted, alined and level with the floor surface. Laminated surfaces shall be free of delamination, scratches, mars, uneven surfaces, rough edges, chipping and color fade. Counters, cabinets and desks shall be of rugged construction, properly alined and installed without any evidence of damage or deformation. Desk and cabinet drawers shall be fitted to provide ease of operation without binding, interference or excessive side movement during opening and closing.

3.7.13 Lounge seat and chairs. The built-in lounge seat with backrest and storage compartment under the lift-up seat shall be of sturdy construction and securely installed. The lounge seat and storage compartment surfaces shall be fitted and alined to provide blended surfaces and ease of operation of the lift-up seat. The catered chair and pedestal stool (with backrest) shall be of sturdy construction providing even contract with the floor.

3.7.14 Upholstery and padding. Removable fitted pads covering donor beds and all upholstery shall be of durable material and securely installed. Upholstery shall meet the flammability requirements of FMVSS 302. The material shall be free of rips, tears, splits, color fade or stains and installed with a uniform fit. The upholstery and cover color shall be coordinated with the applicable area. Padding shall be of force distribution, breathable material and shall provide a comfortable, safe condition free of bumps, bulges or uneven surfaces.

3.7.15 Handrail installation. The safety handrail shall be securely mounted and shall be of rigid construction. The handrail surface shall be smooth, free of burrs, snags, scratches or rough areas.

3.7.16 Sound system installation. The sound system's three ceiling mounted speakers shall be securely mounted and fitted, free of gaps, openings, exposed wiring or exposed

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

insulation. Speaker volume controls shall be securely mounted and conveniently located for the operator.

3.7.17 Exhaust fan installation. Exhaust fans shall be securely mounted in proper locations. The exhaust fans shall be installed and fitted free of gaps, openings, exposed electrical wiring or exposed insulation. The exhaust discharge mounting in the vehicle exterior panels shall be fitted and sealed to be rainproof and waterproof. The exterior sealing shall be neat in appearance and free of sloppy application. The exhaust fans shall operate free of vibrations, rattles and undue noises.

3.7.18 Awning installation. When applicable (see 3.5.15), the awning assemblies shall be securely installed. The installation shall provide sufficient support to the awnings when extended. The awning assemblies shall be installed in a uniform and level position. The support rods shall be free of dents, kinks and other types of damage or deformation. The awning material shall be of durable material, free of rips, tears, frayed edges, stains and color fade. The awning assemblies shall be capable of operation without binding, hang-ups or interference through the entire range of the extended position and the roll-up position.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Government verification. Quality assurance operations performed by the contractor will be subject to Government verification at unscheduled intervals. Verification will consist of observation of the operations to determine that practices, methods and procedures of the contractor's inspection are being properly applied. Failure of the contractor to promptly correct product deficiencies discovered shall be cause for suspension of acceptance until correction has been made or until conformance of product to specification criteria has been demonstrated.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

4.3 In-process water spray test. To determine conformance to 3.5.2.1, 3.5.2.3 and 3.5.2.4, each vehicle produced under the contract shall be subjected to a water spray test. The water spray test shall be performed prior to installation of the interior paneling and insulation. The vehicle shall be exposed to a 100 percent water spray test for not less than 15 minutes. The spray shall be delivered by nozzles operating at not less than 25 pounds per square inch (psi) water pressure. Nozzles shall be sufficient in number and so placed (approximately 4 feet from body) to afford full coverage of sides, roof, front, rear and undercarriage of the vehicle body. The spray shall be applied simultaneously or section by section. All door and windows shall be closed as normal travel position. During the water spray test, all doors, windows and paneling shall be examined and observed for leakage into the interior of the vehicle body. Any evidence of leakage (water or moisture) shall be cause for rejection.

4.4 First production vehicle inspection. To determine conformance to all the requirements of the contract, the first production vehicle produced under the contract shall be subjected to a water spray test, functional test, inspections contained in table II, and a road test. The inspections and road test shall be conducted by the contractor, at or near his plant, under the direction and in the presence of Government representatives. Acceptance of the first production vehicle shall not constitute a waiver by the Government of its rights under the contract.

4.4.1 Vehicle weight. To determine conformance to 3.2.4 and 3.2.5, the first production vehicle shall be weighed to determine the curb weight and the distribution of the curb weight on the front and rear axles. The imposed loading on front and rear axles will be computed using the curb weight, the operator weight at 175 pounds, and the payload (see 3.2.5) to provide the specified GVW. Calculated imposed loads on front and rear axles will be utilized to ascertain that the suspension, axles and tires furnished are adequate capacity to meet contractual requirements.

4.4.2 Road test. To determine conformance to 3.3 through 3.3.2 and 3.5.6.4, the first production vehicle, with rated payload, shall be road tested prior to the water spray test (see 4.3.1) and again after the final assembly. The vehicle shall be road tested for a distance of not less than 50 miles both times. The vehicle shall attain speeds up to at least 50 mph. At least 20 percent of the road test distance shall be over dry, unimproved or gravel roads at speeds up to 20 mph. The vehicle shall be subjected to not less than three sudden stops from speeds of not less than 20 mph on a substantially level, dry, smooth surface free of loose material. The vehicle shall be observed for the specified stopping distance. During the road test, the installed

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

refrigerators, lights and at least one auxiliary electric heater shall be operated. The lights and electrical equipment shall be observed to verify that the auxiliary generator provides sufficient electrical power for satisfactory operation during transit (see 3.5.6.4). Upon completion of the road test, the vehicle, components and accessories shall be examined for damage and leakage (lubricant or air). All equipment permanently installed or secured for transit shall be examined for damage.

4.4.3 Radio frequency suppression verification. The vehicle manufacturer shall indicate on the military questionnaire (commercial vehicle engineering data), if the vehicle will be suppressed to limit electromagnetic radiation in accordance with SAE J551.

4.4.4 Functional tests. After completion of the final road test the following functional tests shall be performed.

4.4.4.1 Electrical system test. To determine conformance to 3.5.6 through 3.5.6.2, the electrical system shall be subjected to a functional test. The satisfactory performance of the electrical system shall be verified, with the air conditioner operating, and then all lighting shall be turned on. The lighting shall be observed during the phase-in operation of the air conditioning compressor, to verify that the lighting does not fade. The air conditioning unit shall be observed for satisfactory operation. The power and electric circuits shall be verified to assure that the power load is in accordance with the specified requirements and actual loads imposed.

4.4.4.2 Air conditioning test. To determine conformance to 3.5.7, the air conditioning system shall be subjected to a functional test. The air conditioning vehicle body combination shall be tested under actual or simulated conditions at least as stringent as the specified requirements. Simulated conditions acceptable to the Government may be used. Performance of the air conditioning system shall be verified to determine that the system is capable of maintaining the inside of the vehicle body at an evenly circulated cooling temperature of 72°F (22°C) maximum in a 95°F (35°C) outside ambient. Inside temperature may be calculated either with the number of occupants required or through the use of a simulated heat load for sensible cooling.

4.4.4.3 Heating test. To determine conformance to 3.5.8, the vehicle body heating system shall be subjected to a functional test. The electric fan blower heaters and vehicle body shall be tested under actual or simulated conditions at least as stringent as the specified requirements. Simulated conditions must be acceptable to the, Government. Performance of the heating system

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

shall be verified to determine that the heating system is capable of maintaining the inside body temperature at a minimum of 70°F (21°C) midway between the floor and ceiling in 0°F (-18°C) outside ambient with no occupants.

4.4.4.4 Air conditioning and heating test data. Results of the air conditioning and heating tests performed in accordance with 4.4.5.2 and 4.4.5.3 shall be recorded. Test data, including a description of all applicable pertinent test conditions, shall be recorded and furnished to the Government representative. If the vehicle manufacturer has previously tested an identical model vehicle with the same components within a 12-month period, a certification and the specified test data verifying conformance to this specification may be provided in lieu of the first production vehicle air conditioning or heating test. Certification and previous test results, if furnished, shall be forward to the engineering office of the procuring activity with the commercial vehicle engineering data (questionnaire).

4.4.4.5 Water system test. To determine conformance to 3.5.9 and 3.7.11 the water system shall be subjected to a hydrostatic test. The in-place water supply system and water heater with connections shall withstand a pump pressure of 40 to 50 psi for a period of not less than 30 minutes with no evidence of leaking and no additional air or water being required to maintain the pressure. During the test period, the water system and water heater and connections shall be observed for leakage, undue noise and damage as a result of the test.

4.4.4.6 Water drain system test. To determine conformance to 3.5.9 and 3.7.11 the water drainage system shall be tested for leakage. With the main drain outlet capped, the sink shall be filled with water. After a period of not less than 30 minutes, the drain system shall be examined for leaks. Evidence of any leakage during the test shall be cause for rejection.

4.4.4.7 Laboratory equipment test. To determine conformance to 3.5.10.4, subparagraphs (b) and (h), the two automatic refrigerated centrifuges and the blood bank refrigerator shall be subjected to a functional test. Both centrifuge units with elevated control panel shall be operated to verify that the speed selector permits automatic acceleration to all speeds from 150 rpm to 6,000 rpm. The refrigeration system shall be observed to verify that the entire temperature control range of 32°F (0°C) to plus 86°F (30°C) at full speed and temperature readout from -5°F (-20°C) to plus 104°F (40°C). Both timers shall be observed for satisfactory performance for a period of 30 minutes. The blood bank refrigerator shall be operated and observed for satisfactory performance with the temperature monitor, the factory set automatic

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

controls and the chart recorder. The refrigerator shall be operated to the extent necessary to verify that it does produce and maintain a temperature of 35.6°F (2°C) to 39.2°F (4°C). Upon completion of the tests, all equipment, components and accessories shall be examined for damage or defects caused by the test.

4.4.4.8 Test of stabilizing Jacks. To determine conformance to 3.5.14, the stabilizing jacks shall be tested. With the jacks in place, the adjustable jacks shall be operated to level and stabilize the vehicle. The jacks shall be observed for proper operation without binding or malfunction. The vehicle shall be observed to verify the jacks will provide adequate leveling and stability in relation to the ground, under normal stationary service.

4.4.5 Production sample. Upon acceptance of the, first production vehicle, it shall remain at the manufacturing facility as a production sample and shall be the last vehicle shipped on the contract. The contractor shall maintain the vehicle in a serviceable condition for the duration of the contract.

4.4.6 Failure. Failure of the first production vehicle to meet any of the requirements of the contract shall be cause for rejection of the vehicle. Further, the Government shall continue to refuse acceptance of all vehicles under the contract, until the contractor has taken corrective action to eliminate the cause(s) of the failure.

4.5 Production vehicle inspection. Each completed production vehicle shall be subjected to dimensional inspection and operational tests as specified in section 3. The vehicle, associated controls and equipment shall be operated to the extent necessary to verify conformance to contractual requirements. The contractor's inspection system, as a minimum, shall assure that the vehicle and attached equipment conforms to the dimensional and operational requirements and the vehicle is capable of meeting the requirements herein. For each vehicle under contract, the contractor shall make available to the Government, at the point of final acceptance, records acceptable to the Government. The records shall indicate that servicing and adjusting required by 3.6 have been accomplished.

4.5.1 Vehicle body inspection. Vehicle bodies installed on the chassis shall be inspected for the characteristics and defects contained in table II. Sampling for inspection shall be in accordance with MIL-STD-105. Acceptance and rejection shall be in accordance with acceptance and rejection criteria of MIL-STD-105. Vehicle bodies shall be inspected for conformance to Acceptable Quality Level (AQL) on the basis of percent defective as specified in table II.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

TABLE II. Major defects AQL - 25 defects per 100 units.

Defect number	Characteristic	Major defects	Method of inspection
101	Exterior paneling	Unevenness, buckling, warping, missing or damaged rivets, overlapped panel surfaces not sealed, excessive or sloppy application of sealing material, surface defects (see 3.5.2.1 and 3.7.5)	Visual
102	Wind deflector fairing	Curved surface not blended smooth into body cross section, excessive deflection or cracking, interference with tilting cab, surface defects (see 3.5.2.2)	Visual
103	Doors and door hardware	Improper fit, not alined, warpage, sloppy application of door seals, improper material, inoperative door hardware, surface defects (see 3.5.2.3 and 3.7.6)	Visual and operational
104	Pull-out and fold-out steps	Damaged, defective, improper fit, binding or interference, inoperative (see 3.5.2.3)	Visual and functional
105	Sliding windows	Sloppy installation of weatherproof seals, windows not easily opened or adjusted to various openings, defective glass (cracks, scratches, nicks) (see 3.5.2.4 and 3.7.6)	Visual and operational
106	Internal panels	Unevenness, buckling, gaps, open seams, improper fit of joiners, edgings, moldings and surface defects (see 3.5.4 and 3.7.5)	Visual
107	Floor surfacing	Gaps, waviness, cracks, bulges, open seams, not secured, improper application of sound deadening material, thin or bare areas (see 3.5.5 and 3.7.8)	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

TABLE II. Major defects AQL - 25 defects per 100 units. - Continued

Defect number	Characteristic	Major defects	Method of inspection
108	Electrical system	Code violations, e.g. sloppy or loose connections, improper wiring clearances, color code errors, incorrect capacity of circuit breaker box(es), wiring not fastened or clipped, incorrect wire size, faulty materials, faulty solder joints, sloppy installation, inoperative electrical controls, noisy (see 3.5.6 and 3.7.9)	Visual and functional
109	Floodlights, installation	Not weatherproof, improper grounding, sloppy installation, brackets not secure, brackets not located as specified, inoperative (see 3.5.6.7)	Visual and operational
110	Air conditioner, heater and controls	Not shockmounted, not mounted securely, improper wiring and grounding, air duct diffusers not operative, noise, vibration, heater and air conditioner controls not operative (see 3.5.7, 3.5.8 and 3.7.10)	Visual and operational
111	Plumbing system, components and fixtures	Water leaks, undue noise, fixtures and components not mounted securely. Improper assembly or installation, defective material, malfunction, or inoperative (see 3.5.9 and 3.7.11)	Visual and functional
112	Desks, cabinets and counters, laminated surfaces	Delamination, scratches, mars. color fade, unevenness, bulging, rough edges, not level with floor, not alined or fitted, loose mounting, poor construction, improper counter height, interference of desks and cabinet drawers, inoperative key locking (see 3.5.10 through 3.5.10.4 and 3.7.12)	Visual and functional

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

TABLE II. Major defects AQL - 25 defects per 100 units. – Continued

Defect number	Characteristic	Major defects	Method of inspection
113	Lounge seat and chairs	Not rigid or sturdy construction, chair legs uneven and unstable, lounge seat not secure, improper alinement and fit, interference with lift-up seat (see 3.5.10.1, 3.5.10.2 and 3.7.13)	Visual and operational
114	Upholstery and padding	Sloppy installation, not durable material, uncomfortable, not uniform fit, rips, splits, color fade, stains, color not coordinated with applicable area (see 3.5.10.1 through 3.5.10.3 and 3.7.14)	Visual and tactile
115	Safety handrail	Improperly mounted, not secured, improper material, handrail surface not smooth, burrs, snags, scratches, rough areas (see 3.5.10.2 and 3.7.15)	Visual and functional
116	Sound system	Sloppy installation, loose connections, improper speaker installation, exposed wiring or insulation, improper location of volume controls, defective material, malfunction of controls (see 3.5.11 and 3.7.16)	Visual and functional
117	Exhaust fans	Not mounted securely, improper locations, improper fit to interior surface, exposed wiring, loose connections, improper fit to exterior panels, not weatherproof, sloppy caulking, inoperative, vibration, rattles, undue noise (see 3.5.10.4(j) and 3.7.17)	Visual and functional

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

TABLE II. Major defects AQL - 25 defects per 100 units. – Continued

Defect number	Characteristic	Major defects	Method of inspection
118	Awnings (when specified)	Not mounted securely, improper locations, unevenness, not level, improper dimensions, inferior material, rips, tears, frayed, stains, color fade, inoperative, binding, interference, hang-ups in extended and roll-up positions	Visual and functional
119	Curtains	Sloppy installation, not secure, inferior material, color not appropriate, uneven stitching, tears, frayed, color fade, stains (see 3.5.2.4 and 3.7.6)	Visual
120	Sealers and caulking	Sloppy application, incorrect amounts, improper material	Visual
121	Sheet metal duct work	Sloppy installation, not smooth on inside, joints not neatly finished, joints not air tight, laps not in direction of airflow, edges not smooth (see 3.5.7 and 3.7.10)	Visual
122	Fire extinguisher	Location not convenient, mounting not secure	Visual

5. PACKAGING

5.1 Vehicle processing. The vehicle shall be processed for shipment, from manufacturer's plant to initial receiving activity, in accordance with manufacturer's standard commercial practice.

6. NOTES

6.1 Intended use. The vehicle covered by this specification is intended for use at various installations in the United States; for trips over streets, highways and gravel roads; and for use as a self-contained mobile blood donor facility and blood component processing laboratory.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Identification of appropriate service for painting and marking (see 3.1.1.1).
(c) Special exterior markings, if required (see 3.1.1.2).
(d) Rustproofing, if required (see 3.1.1.3).
(e) Tropical rustproofing, if required (see 3.1.1.3).
(f) A gasoline engine, if required (3.4.1.2).
(g) Disc type wheels, if required (see 3.4.10).
(h) Bias ply tires, if required (see 3.4.10.1).
(i) If a spare tire carrier is not required (see 3.4.10.3).
(j) A spare wheel, if required (see 3.4.10.4).
(k) A spare tire assembly, if required (see 3.4.10.5).
(l) A desiccant type air dryer, if required (see 3.4.11.1(k)).
(m) Individual driver and passenger seats, if required (see 3.4.12).
(n) Tool, if required (see 3.4.16.1).
(o) Type of floor covering, if different (see 3.5.5).
(p) Laboratory equipment and furnishings, if different (see 3.5.10.4).
(q) Awnings, if required (see 3.5.15).

6.3 Performance prediction. Completed copies of SAE Truck Ability Prediction procedure form, and computation for maximum geared speed and low speed requirements for vehicle furnished under contract, should be submitted as specified in the contract. Unless other conditions are cited in the contract, computations should be made for normal atmospheric pressure, normal ambient air temperature, and in still, dry air. The factors to be used in predicting vehicle ability (see 3.3) are established as follows for the corresponding SAE J688 Truck Ability Prediction Procedure Tables:

Table 1	- Tire factor. This factor must relate to the size of tires furnished by the contractor in accordance with this specification.
Table 2	- Altitude factor. 1.00
Table 3	- Rolling factor. 1.613
Table 4	- Area factor. 0.173
Table 5	- Velocity factor. 250.0
Table 6	- Altitude factor. 1.00
Table 7	- Chassis friction horsepower. Use applicable power unit GVW (to nearest, higher 1,000 pounds) and the engine rpm (to nearest

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.

100 revolutions) which is required for 50 mph geared speed. For GVW and engine speed beyond the range of this table, factors shall be extrapolated.

Table 8 - Grade factor. 0.75
Table 8A - Correction factor. Not required.
Table 9 - Road factor. 0.0.

6.4 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue, due to the extensiveness of the changes.

Custodian:
Army - AT

Preparing activity:
Army - AT

Review activity:
U.S. Army Health Services Command,
Walter Reed Medical Center
Tripler Army Medical Center

Project No. 2320-AC41

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:26Z
Check the source to verify that this is the current version before use.