MILITARY SPECIFICATION

TRAINING AID; UNIVERSAL DISPLAY PANEL

This specification has been approved by the Naval Training Equipment Center. Department of the Navy

1. SCOPE

1.1 This specification covers the requirements for the design and construction of a backlighted Universal Display Panel.

1.1.1. The display panel has been designated as Device 3C127A by the Naval Training Equipment Center for Navy procurement (see 6.2).

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on the date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

Federal

W-C-596	Connector Plug; Electrical, Connector Receptacle; Electrical
PPP-B-601	Boxes, Wood Cleated-Plywood
PPP-B-621	Boxes, Wood, Nailed and Lock-Corner
PPP-B-636	Box, Fiberboard

Military

MIL-P-116	Preservation; Methods of
MIL-C-5756	Cable and Wire, Power, Electric, Portable

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

MIL-L-10547	Liners, Case and Sheet, Overwrap, Water-Vaporproof or Waterproof, Flexible
MIL-C-23422	Chromium Plating Electro-Deposited
MIL-T-23991	Training Devices, Military; General Specification for

STANDARDS

Federal

FED-STD-595	Colors

Military

MIL-STD-129	Marking for Shipment and Storage
MIL-STD-454	Standard General Requirements for Electronic Equipment

DRAWINGS

Naval Training Equipment Center (NAVTRAEQUIPCEN)

Drawing DL 327671E60001	Training Aid, Universal Display Panel, Device 3C127A

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

2.2 Other publications.- The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

AMERICAN NATIONAL STANDARD (ANS) INSTITUTE, INCORPORATED

Y32.2	Graphic Symbols for Electrical and Electronics Diagrams
Y32.16	Electrical and Electronics Reference Designations for Parts and Equipment.

(Application for copies should be addressed to the American National Standards Institute, Inc., 1430 Broadway, New York, New York, N.Y. 10018).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Materials.- Except as specified in 3.1.1, materials shall be as specified in MIL-T-23991 and 3.1.2 through 3.1.4.

3.1.1 Written approval of the Contracting Officer shall be required for the selection of materials from Standards and Specifications of MIL-STD-143, Groups II, III and IV in accordance with nonstandard materials and parts requirements of MIL-T-23991.

3.1.2 Wood.- Wood used shall be of select grades of hardwood lumber, having good appearance and finishing qualities, suitable for either clear or opaque finishes. Wood shall be properly seasoned, free from checks, splits, and crossgrain or seasoning defects causing warping.

3.1.2.1 Plywood.- Plywood shall have a minimum of five plies, or solid core hardwood, both surfaces to be of hardwood, all plies to be free of spaces or checks and joined by waterproof glue.

3.1.3 Glue.- Only a glue not adversely affected by lacquer or by the environmental conditions specified in 3.3.1 shall be used.

3.1.3.1 General cementing.- Glue shall permanently adhere to, penetrate, or weld the materials being joined. The glue and method of joining shall be tested to determine compliance with this specification. In addition to glueing, joints shall be mechanically reinforced wherever possible.

3.1.4 Hardboard.- Hardboard, where used, shall be tempered smooth on both sides, moisture resistant, and shall be suitable for painting.

3.2 Design.- The design of the training aid shall be in accordance with the NAVTRAEQUIPCEN Drawing DL 3276716E60001.

3.2.1 The training aid shall be a portable display panel used to backlight various illustrated overlays. The panel shall contain a backlighted display area, control panel, changeable programming system and a remote control unit. The panel shall be designed for use with the NAVTRAEQUIPCEN Device 3C128 Overlay System.

3.2.2 Safety.- Safety for personnel and equipment shall be in accordance with Requirement 1 of MIL-STD-454.

3.3 Reliability of operation.- Reliability of operation shall be considered of prime importance in the design and manufacture of the training aid. The contractor shall employ all methods possible in the process of manufacture to assure quality and maximum reliability. In the functional application of parts to equipment circuits, adequate factors of safety shall be provided by suitable deratings from the part specification values in order to insure high equipment reliability under all service conditions.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

3.3.1 The training aid shall be capable of withstanding continuous classroom use and shall not be adversely affected in any manner during storage (two years) and transportation when under ambient conditions of temperature ranging from -13 to +125° Fahrenheit, with relative humidity ranging up to 95 percent. The device shall be so designed and constructed that no fixed part or assembly or control shall become undesirably free or sluggish in operation, and no degradation shall be caused in the performance stipulated for the device, during 24 months of classroom operation at a rate of 80 hours use per month.

3.4 Construction.- Construction shall be in accordance with the processes requirements of MIL-T-23991.

3.4.1 Moving parts.- All movable or operable elements of the device shall be constructed so as to reduce friction and pressure to a minimum, and shall enable easy manual movement of all parts.

3.5 Dimensions and tolerances.-

3.5.1 Dimensions.- Dimensions shall be in accordance with the drawings of 3.2.

3.5.2 Tolerances.- All tolerances not specified shall be consistent with functional design, inherent qualities of the material being used, and shall afford freedom from binding in mechanical fit.

3.6 Details of display panel.- Each panel shall consist of the following major components, the design of which shall be as shown on the drawing of 3.2.

(a) Panel frame assembly (3.6.1)

(b) Backlighting assembly (3.6.2)

(c) Control panel (3.6.3)

(d) Program system (3.6.4)

(e) Remote control unit (3.6.5)

(f) Lamp power supply (3.6.6)

(g) Stepping switch power supply (3.6.7)

(h) Dust cover (3.6.9)

(i) Power cable (3.6.10).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

3.6.1 Panel frame assembly.-

3.6.1.1 The supporting stand for the panel shall be an integral part of the device. The stand shall have adjustable heights for varying the overall height of the panel from a minimum of 6 feet 2 inches to a maximum of 8 feet 6 inches.

3.6.1.1.1 The height adjustment shall be accomplished by means of a motor driven lifting mechanism. This motorized height adjustment shall be controllable from the front control panel.

3.6.1.2 The panel shall be supported by four rubber tired swivel casters with locking wheels. The diameter of the casters shall be 4 inches.

3.6.1.3 All internal wiring shall be coded in accordance with the wire and cable identification and marking requirements of MIL-T-23991. All wires to backlighted area lamps shall be marked with lamp position number. Cable ties shall not exceed three inch separations.

3.6.1.4 Size of wires and all wire connections requiring soldering shall be in accordance with MIL-T-23991.

3.6.1.5 Means shall be provided to support and hold the overlay *securely in place on the front of the backlighting assembly.*

3.6.1.6 The panel shall have alinement pins for alining overlays into correct position on the front of the backlighted area. The alinement system shall be for both an approximate 4 foot high by 7 foot wide overlay, and two each 4 foot high by 3 1/2 foot wide overlays.

3.6.1.7 Under the backlighting assembly, on the front of the panel, shall be two compartments with hinged doors. The left compartment shall contain the program plugboard receiver and two drum programming switches. The right compartment shall be arranged to house five spare program plugboards and ten spare programming drums. Each hinged door shall have two non-locking elbow type hinges to support the door in an open position.

3.6.1.7.1 *The right compartment shall have means for placing the* program drums into storage and removing drums from storage without causing displacement of drum actuators.

3.6.1.8 Removable doors shall be provided behind the backlighting assembly to provide protection for and maintenance of the electrical and mechanical equipment.

3.6.1.9 Under the backlighting assembly, on the rear of the panel, shall be two compartments with hinged doors. One of the compartments shall be used for the lamp power supply, the other shall be used for spare parts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

3.6.1.10 An electrical schematic of the display panel, laminated in plastic, shall be provided and fastened to the inside surface of the rear right compartment door. Electrical symbols shall conform to ANS Y32.2 and electronic reference designations shall conform to ANS Y32.16.

3.6.1.11 At the rear of the panel shall be means for holding three overlays for stowage. The overlays shall be easily removable without the use of tools.

3.6.1.12 Each end of the panel shall have a handle for use in moving the panel.

3.6.1.13 Provisions for stowage of the remote control unit and cable shall be provided on the left end of the display panel.

3.6.2 Backlighting assembly.-

3.6.2.1 The backlighting assembly shall contain a grid of vertical and horizontal metal strips, spaced at 2 inch intervals so as to provide 2 inch by 2 inch display windows throughout the backlighting assembly.

3.6.2.2 The windows in the backlighting assembly shall be placed 42 horizontally by 23 vertically for a total of 966 windows.

3.6.2.3 Width of the metal strips, the lamp sockets and the lamps selected for each window, shall be selected to provide even light distribution without hot spots or light flare onto other areas not lighted.

3.6.2.4 The lamp selected for each backlighting window shall have the necessary candle power rating to provide a minimum brightness of 24 foot lamberts on the front of each backlighting window. The lamp base shall be either bayonet or slide base. The manufacturer's rated life for the selected lamp shall be a minimum of 5000 hours at 24VDC. The lamps shall not be operated in an ambient temperature greater than that rated for the lamp.

3.6.2.5 The face of the backlighting assembly shall be of translucent plastic. This translucent panel shall be attached to the grid to prevent leakage of light into adjacent windows and to prevent warping under ambient heat from the backlighted area. The face of the backlighted area shall be flat within plus or minus .05 inches of a plane.

3.6.2.6 The upper left corner of each window shall contain a miniature two-pole, open circuit jack. The jack shall be rated to switch the power to the lights in the backlighting assembly. The jack opening shall extend through the translucent panel by not more than .04 inches.

3.6.3 Control panel.-

3.6.3.1 The control panel shall be placed to the left of the backlighting assembly on the front surface of the panel.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

3.6.3.2 Sixty switches, referred to as sequence select switches, all interlocking, shall be on the control panel. The switch arrangement shall be 5 switches horizontally and 12 switches vertically. The maximum switch operating pressure shall be 1 1/2 pounds.

3.6.3.2.1 The switches shall have square illuminated pushbuttons. All pushbuttons shall be white, engraved with numbers and filled black. The pushbuttons shall be numbered consecutively left to right, and top to bottom.

3.6.3.3 An advance step control, push-to-operate, momentary type switch shall be provided on the control panel.

3.6.3.4 The operation of the sequence select switches and the advance step control switch shall be automatically interchangeable without a mode select switch.

3.6.3.5 A power-on switch shall be provided on the control panel. An indicating lamp shall indicate when power is on.

3.6.3.6 The control panel shall have an engraved faceplate of lamicoid or equal, and shall have a satin surface. Lettering and marking on the faceplate shall be engraved and be in high contrast with the background.

3.6.3.7 The control panel shall have a lamp dimmer control for controlling the lamp voltage power supply from 70 percent to 100 percent of the lamp's maximum operating voltage.

3.6.4 Program system.- The program system shall provide flexibility in changing the program for each overlay placed in front of the backlighted area. This system shall consist of a removable plugboard system and a removable drum programming switch system.

3.6.4.1 A removable plugboard programming system shall be used to select the desired lamps in the backlighting assembly, for control by the program drum switches.

3.6.4.1.1 The plugboard shall have its positions marked on both front and back surfaces in the pattern as shown in the drawing of 3.2.

3.6.4.1.2 The plugboard shall be provided with a protective cover, as supplied by the manufacturer of the plugboard.

3.6.4.2 Two removable drum programming switches shall be used to activate the selected lamps for any desired training sequence.

3.6.4.2.1 Each removable drum programming switch shall have 60 steps in each 360° rotation, a minimum of 60 SPDT (single-pole double-throw) switches, and a motor or stepping solenoid which shall provide a transfer time for a 60 position step of less than 12 seconds.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

3.6.4.2.2 There shall be a minimum of 500 actuators supplied with each programming drum switch.

3.6.4.2.3 The drum programming switch shall have the capability of being operated one step at a time from the advance step switch on the control panel and the remote control. The drum will sequence only one step per operation for each operation of the advance step switch. When the drum programming switch has stopped stepping, the appropriate sequence select switch shall indicate the corresponding drum step position.

3.6.4.2.4 The programming drum shall have alinement marks to aline actuators to the drum switch location.

3.6.4.2.5 When any numerical sequence select switch (on the control panel) is operated, the drum programming switch shall automatically step to that corresponding step position. At that time, the operated sequence select switch shall illuminate and the corresponding programmed backlighted area lamp shall light.

3.6.4.2.6 The switch contacts on the drum programming switch shall be rated for not less than 2 amperes 24 VDC non-inductive load. The switch contacts shall conform with the reliability requirements of 3.3.

3.6.4.3 One programming plugboard and two programming drums will be programmed and provided with each display panel to be used for maintenance test. The program will provide illumination of all backlighted lamps, and lighted switches, during a 60 drum position sequencing test.

3.6.4.4 A blinking light control system shall be provided with a minimum of 9 independent switches. Each switch shall provide means for operating a minimum of 20 lamps on and off at a 0.5 second on and 1.5 second off rate.

3.6.4.4.1 These blinking control switches shall be grouped into 3 groups. The timing of each group shall be separated by a 1/3 cycle rate from the other groups.

3.6.4.4.2 The program plugboard shall contain the input and output line from each of the blinking control switches. The plugboard shall be marked reflecting the location of each control switch input and output lines.

3.6.5 Remote control unit.- A remote control of the sequence step function shall be provided. Each drum programming switch shall move one step for each time the remote control switch is operated.

3.6.5.1 A small light pendant, momentary action switch shall provide remote control switching.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

3.6.5.2 The body of the pendant switch shall protect switching control from dirt and dust.

3.6.5.3 A 25 foot cable shall be provided between the remote control unit and the display panel. The cable plug on the cable shall mate with a receptacle on the left side of the display panel.

3.6.6. Lamp power supply.- A power supply shall be provided to supply power for a minimum of 500 lamps simultaneously at 24 VDC, in the backlighting assembly, in addition to the lamps on the control panel.

3.6.6.1 The lamp power supply shall be remote programmed from a minimum of 70 percent to 100 percent of the maximum voltage operating of the selected lamps. The power supply shall have a voltage regulation of 2 percent or better from no load to full load and with a 5 percent change in input line voltage of 115V 60 Hz.

3.6.6.2 The lamp power supply system shall be designed to eliminate the effect of lamp inrush current on the power supply and training device switch contacts. Each time the drum program switches are stepped the lamp power supply system output voltage shall change to zero volts. When the drum programming stepping switches have stopped, the voltage to the desired lamps shall change to the dimmer control selected operating voltage.

3.6.6.3 The lamp voltage power supply shall be programmed from the control panel dimmer control for 70 percent to 100 percent of the lamp rated voltage.

3.6.6.4 The lamp power supply shall be short circuit protected and over voltage protected. Means shall be provided to prevent the power supply from providing greater than 30 volts to the backlighted area lamps.

3.6.7 Stepping switch power supply.- The drum programming stepping switch shall have a separate power source, and shall not use the lamp power supply.

3.6.7.1 The power supply system shall be short circuit protected.

3.6.8 The noise level from the power supply cooling systems, shall not exceed 40 dB at a distance of 6 feet in front of the device.

3.6.9 Dust cover.- A dust cover of medium grey, 16-ounce vinyl-coated nylon, Armor-Tite or equal in flexibility and durability, shall be provided to cover the display panel front.

3.6.9.1 The dust cover shall be attached along the top edge of the demonstrator panel, and shall completely cover the front. The cover shall have means for fastening the cover to the lower edge of the panel. The cover shall be capable of being stored over the top edge and behind the panel. The cover shall be removable without the use of special tools.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

3.6.10 Power cable.- Each display panel shall be equipped with a 25-foot, 3-wire (1 of which is a grounding wire) rubber-covered extension cable conforming to MIL-C-5756. Connectors shall be 3-wire grounding type conforming to W-C-596. A male connector shall be provided on the line end and a locking-type female connector on the display panel end. A matching male receptacle shall be provided on the display panel.

3.7 Spare parts kit.- The spare parts kit shall contain a minimum of 10 percent spare parts for each type of lamp, switch, relay, lamp socket, 900 drum activators, drum follow arm spring (913-0400-02-0-000), lug terminal, fuses and 10 program patch cords. The spare parts kit shall be made secure inside the spare parts compartment. Where ten percent spare parts for each type is less than one, a single item shall be supplied. A typed list of spares shall be placed with spare parts kit.

3.8 Finish.- Finish shall be in accordance with MIL-T-23991 and as specified in 3.8.1 through 3.8.5 of this specification.

3.8.1 All surfaces shall be free from marks, burrs, sharp edges, or blemishes of any kind.

3.8.2 Cushioning materials used shall be compatible with all finishes, so that migrating solvents in cements, cushioning or components will not adversely affect any part.

3.8.3 All non-metallic surfaces to be finished shall be properly sealed, primed, and finished with satin-surface lacquer. Application of finishes shall be accomplished in such a manner as not to impair performance of the equipment.

3.8.4 Except in applications where physical, electrical or electro-mechanical properties of the panel would be impaired, all exposed noncorrosion resistant steel components shall be chromium plated in accordance with MIL-C-23422.

3.8.5 Paint finish on metals shall be semigloss baked-on-enamels or semigloss exterior lacquer.

3.9 Color.- Shades of color shall be limited to the semigloss series of FED-STD-595. All wood surfaces shall be finished in dark gray FED-STD-595 color number 26152.

3.10 Nameplate.- A nameplate, furnished by the procuring activity, shall be affixed to the upper left front surface of the control panel.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

3.11 Workmanship.- Workmanship shall be in accordance with MIL-T-23991 and 3.11.1 of the specification.

3.11.1 All components when assembled shall be accurately alined and inherently strong as a unit. Particular attention shall be given to neatness and thoroughness in the coloring of the device and finishing.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspection.- Inspections to be performed are classified as follows:

(a) In-process inspection

(b) Quality conformance inspection.

4.3 In-process inspection.- In-process inspection shall include such visual, electrical, and mechanical examination, and testing of materials, subassemblies, parts and accessories (including purchased standard items) during the manufacturing process as may be necessary to assure conformance to all the requirements of this specification.

4.4 Quality conformance inspection.- Quality conformance inspection shall be as specified in 4.4.1 through 4.6.

4.4.1 Preproduction inspection.- When required by contract schedule, the preproduction inspection shall be conducted on the preproduction unit and shall consist of all the examinations and tests of 4.5 and 4.6.

4.4.2 Production inspection.- Production inspection shall be performed on production units to the extent necessary to maintain quality control following acceptance of the preproduction unit. The approved preproduction unit shall be used as a representative sample in the fabrication and testing of the production units to be submitted for acceptance.

4.5 Examinations.- Examinations shall be performed to verify conformance to the following requirements:

(a) Materials

(b) Design

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

(c) Safety

(d) Construction

(e) Dimensions and tolerances

(f) Details of components

(g) Finish

(h) Color

(i) Nameplates

(j) Workmanship

(k) Preparation for delivery.

4.6 Tests.- Functional tests shall be conducted to determine whether the display panel conforms to the requirements of 3.3, except for the temperature and humidity requirements.

4.6.1 Electrical operating tests.- In addition to any tests necessary to demonstrate proper functioning, as required by 4.6, all electrical circuits, equipment, and components shall be tested to ensure satisfactory operation under load and conformance to the safety requirements of this specification. Systems shall be fully energized and operated continuously or intermittently in accordance with the normal operating procedure, for a period of two hours, without failure or malfunction of any part of the circuit or of any component.

4.6.2 Motorized height adjustment.- Run height adjustment through full range of travel. Range shall cover range 6 feet 2 inches to 8 feet 6 inches. Limit switches shall stop length of travel.

4.6.3 Power supply.- Verify full range of power supply voltage. Maximum dimmer control is 24 volts, minimum dimmer control is 16.8 volts.

4.6.4 Window brightness.- Check backlighted window brightness for all lamps. Measure 24 foot lamberts minimum at maximum brightness setting.

4.6.5 Sequence select switch- Operate all sixty sequence select switches for proper operation and repeatability.

4.6.6 Lamp control.- Measure voltage at program drum switches to verify that voltage at drum switches is zero when program drum steps. Verify program control timer is set at minimum drum switching delay and still accomplish zero voltage at drum switch when drum steps.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

4.6.7 Interchangeable control.- Operate sequence select switches, manual control switch and remote control switch, and verify proper operation.

4.6.8 Maintenance program test.- With maintenance program plugboard and drums in place verify the correct operation of all lamps of the backlighted area, blinking circuits, and sequence select switches.

4.6.9 Pin jack switch.- Verify proper operation of each pin jack switch. Verify that pin jacks locations are correctly located from alignment pins. Verify pin jacks are in the upper left of each eggcrate as required by device drawing. Verify pin switches are on a true square grid and properly separated.

4.6.10 Lamp power supply.- Activate 500 lamps in the backlighted area, by the use of the program pin switches, and note that the lamp brightness does not decrease. Verify power supply regulation requirements of 3.6.6.

4.6.11 Interlock.- Verify all interlocks work properly (remove lamp voltage when interlock is opened).

4.6.12 Markings.- Verify that all lamps are marked with lamp position number. Verify plugboard is marked with lamp and drum switch location, per device drawing. Verify all electrical components are labeled.

4.6.13 Safety.- Verify all 110V AC connections are covered and marked for safety.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.- Preservation and packaging shall be Leval A or C as specified in the contract schedule.

5.1.1 Level A.- For Level A, each device shall be preserved and packaged for mechanical and physical protection in accordance with MIL-P-116, Method III.

5.1.1.1 Unit packaging.- Each display panel shall be packaged one unit to a container conforming to PPP-B-636, Class 2.

5.1.2 Level C.- For Level C, preservation and packing shall conform to manufacturer's commercial practice.

5.2 Packing.- Packing shall be Level A or C as specified in contract schedule.

5.2.1 Level A.- Units packaged in accordance with 5.1.1 shall be packed in exterior containers conforming to PPP-B-601, styles A or B with steel banding, or PPP-B-621, Class 2. Unless otherwise specified by the procuring activity, the gross weight shall not exceed the weight limitations of the

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

shipping container. Each exterior shipping container shall be lined with a waterproof barrier sealed with adhesive or tape to effect water resistance in accordance with MIL-L-10547. A case liner shall not be required where the package(s) and package dunnage have been treated to resist water. Unit fiber boxes, conforming to PPP-B-636, Class 2, exterior shipping containers, closed, reinforced and waterproofed in accordance with the appendix thereto, and used as shipping containers, shall not be overpacked.

5.2.2 Level C.- Units packaged as specified in 5.1.2 shall be packed in containers which will ensure acceptance by common carrier and safe delivery at destination. Shipping containers shall conform to common carrier rules or other regulations as applicable to the mode of transportation when such meets the requirements of this level. The base of the shipping container shall contain skids.

5.2.3 Physical protection.- All material shall be packaged and packed in containers constructed to provide a compact and nonshifting load. Adequate cushioning, blocking and bracing shall be provided within shipping containers in a manner designed to prevent damage due to shock, vibration or impact during shipment, handling and storage.

5.3 Marking.- Interior packages and exterior shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use.- The display panel will be used to demonstrate the operational sequence of logic blocks, schematic circuits and illustrated equipment when used with an overlay system.

6.2 Ordering data.- Procurement documents shall specify the following:

(a) Title, number and date of this specification

(b) Procuring activity designation (Device number or other, see 1.1.1)

(c) Nameplate information

(d) Selection of applicable levels of preservation, packaging, or packing (see 5.1).

PREPARING ACTIVITY:
Navy-TD

Navy-TD
Project No. 6910-N-329

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY

POSTAGE AND FEES PAID
DEPARTMENT OF THE NAVY

DoD 316

U.S. MAIL

PENALTY FOR PRIVATE USE $300

COMMANDING OFFICER
NAVAL TRAINING EQUIPMENT CENTER
ATTN: CODE N-2212, BLDG. 2065
ORLANDO, FL. 32813

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. *DoD contractors, government activities, or manufacturers/ vendors* who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 68 WHICH MAY BE USED S/N 0102-014-1802

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T21:23Z
Check the source to verify that this is the current version before use.