MILITARY SPECIFICATION

# VACUUM-AIR-NITROGEN DISTRIBUTION SYSTEM

This specification has been approved by the Naval Ordnance Systems Command, Department of the Navy

## 1. SCOPE

1.1 Scope. This specification states the requirements for the procurement of a Vacuum-Air-Nitrogen Distribution System, Naval Ordnance Systems Command Drawing 1874091 (LD 620161), also referred to herein as the "VAND System" or "system". The VAND System provides pneumatic testing facilities for advance underseas weapons. It is also capable of controlling the nitrogen supply for those weapons which are to be filled with an inert gas. The VAND System is of one type and one class. (See 6.1.2.)

## 2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on the date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

| | |
|---|---|
| PPP-B-601 | Boxes, Wood, Cleated, Plywood |
| PPP-B-621 | Boxes, Wood, Nailed and Lock-Corner |

MILITARY

| | |
|---|---|
| MIL-P-116 | Preservation, Methods of |
| MIL-A-907 | Antiseize Compound, High Temperature |
| MIL-A-8625 | Anodic Coatings for Aluminum and Aluminum Alloys |
| MIL-H-8795 | Hose; Aircraft, Hydraulic, Pneumatic Fuel and Oil Resistant |

FSC 1355

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

| | |
|---|---|
| MIL-E-17555 | Electronics and Electrical Equipment and Associated Spare Parts; Preparation for Delivery of |
| MIL-T-18404 | Torpedoes, Environmental Requirements; General Specification for |

STANDARDS

MILITARY

| | |
|---|---|
| MIL-STD-105 | Sampling Procedures and Tables for Inspection by Attributes |
| MIL-STD-129 | Marking for Shipment and Storage |

DRAWINGS

NAVAL ORDNANCE SYSTEMS COMMAND

| | |
|---|---|
| LD 620161 | Vacuum-Air-Nitrogen Distribution System |
| Dwg 1874091 | Vacuum-Air-Nitrogen Distribution System |

NAVAL SHIPS SYSTEMS COMMAND

| | |
|---|---|
| Dwg 10-T-2145 | Light Weight Shock Testing Machine |

PUBLICATIONS

NAVAL ORDNANCE SYSTEMS COMMAND

| | |
|---|---|
| WR-11 | Design and Test of Packaging, Packing, Shipping and Handling Equipment for Weapon System Components |
| OS 6341 | Miscellaneous General Ordnance Design Requirements |

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated the issue in effect on date of invitation for bids or request for proposal shall apply.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

NATIONAL BUREAU OF STANDARDS PUBLICATION

| | |
|---|---|
| Handbook H28 | Screw-Thread Standards for Federal Services |

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20360.)

## 3. REQUIREMENTS

3.1 Preproduction samples. Unless otherwise specified in the contract or order, preproduction samples of the VAND System shall be manufactured using the methods and procedures proposed for production. The sample will be tested as specified in Section 4 and is for the purpose of determining, prior to production, that the contractor's production methods are capable of yielding items that comply with the technical requirements of the contract.

3.2 General requirements

3.2.1 Materials. Unless otherwise specified in the contract, requisition, or order, all materials and purchased parts entering into the final assembly of the VAND System shall conform strictly to the detailed requirements indicated on the drawings and specifications listed in LD 620161.

3.2.2 Finishes, coatings, construction, and dimensions. Finishes, coatings, construction, and dimensions for the VAND System shall be strictly in accordance with the applicable drawings, specifications, and publications listed in LD 620161.

3.2.3 Moisture, fungus , and corrosion. The VAND System shall be rendered moisture, fungus, and corrosion resistant in accordance with the requirements of OS 6341.

3.2.4 Marking. Marking of assemblies, subassemblies, and parts shall be in accordance with the applicable drawings listed in LD 620161.

3.2.5 Interchangeability. Component parts of assembled units (unless otherwise specified on applicable drawings) fabricated in strict agreement with their applicable drawings shall be interchangeable and shall assemble with mating components of the unit without selection of fitting. If, during assembly of the fabricated parts of a unit, selection or fitting is required and changes in dimensions are necessary, no changes in the parts as delineated on applicable drawings will be made without prior revisions and correction of the applicable drawings.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

3.2.6 Gages. The contractor shall provide himself with whatever gages are necessary and adequate to ensure that the material to which this specification applies will meet the dimensional requirements shown on the applicable drawings. If so stipulated in the contract, order, or requisition, the Government will furnish drawings of pertinent Navy Final Inspection Gages for guidance in the design of the contractor's inspection gages. However, such procedure shall not serve to relieve the ocntractor of his responsibility in the design and manufacture of such gages as may be required for the satisfactory fulfillment of the contract requirements, but is intended to facilitate acceptance of all components and assemblies by Navy Final Inspection Gages.

3.2.7 Threads. Unless otherwise specified, all threads shall be in accordance with National Bureau of Standards Handbook H28. The class or fit for threads shall be as specified on the applicable drawings.

3.2.8 Conflicting requirements. Conflicting requirements arising between this specification or any specifications, publications, or drawings listed herein shall be referred in writing to the procuring agency or appointed agent for interpretation, clarification, and resolution (or correction).

3.3 Performance requirements and product characteristics. The VAND System shall meet the following performance requirements and product characteristics:

3.3.1 Pressure. The equipment shall be capable of supplying air, from a source of 800 pounds per square inch, at pressures ranging from O to 750 pounds per square inch, when tested as in 4.5.4.1.

3.3.2 Vacuum. The equipment shall be capable of evacuating the air to obtain a vacuum of 25 inches of mercury, when tested as in 4.5.4.3.

4.3.3 Nitrogen. The equipment shall be capable of replacing the evacuated air with nitrogen as required in the applicable weapons Ordnance Pamphlets. (See 4.5.4.4.) The source of nitrogen shall not exceed 50 to 400 pounds per square inch.

3.4 Environment requirements

3.4.1 Vibration

3.4.1.1 Operating and nonoperating. The Vacuum-Air-Nitrogen Distribution System, mounted rigidly on a vibration testing device in a manner to simulate its service installation, shall be capable of withstanding vibrations of frequency varying between 10 and 33 cycles per second (cps) with a total excusion of 0.06 plus or minus 0.006 inch, between 10 and 55 cps with a total excursion of 0.03 plus or minus 0.006 inch, and at the four most severe resonant frequencies (see 4.4.1). Thereafter, the system shall meet all performance requirements and product characteristics of this specification.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

3.4.1.2 Vibration; transportation. The system, after being subjected to the tests specified in 4.4.1.5, shall show no damage and shall meet all the requirements of Section 3.

3.4.2 Shock

3.4.2.1 Operating and nonoperating. With the Vacuum-Air-Nitrogen Distribution System mounted in a manner to simulate its service installation, it shall be subjected to three blows in each of the three principal axes (see 4.4.2). Thereafter, the system shall show no damage and meet all performance requirements and product characteristics of this specification.

3.4.2.2 Shock; transportation, storage, and handling. The system, after being subjected to the test specified in 4.4.2.2, shall show no damage and shall meet all the requirements of Section 3.

3.4.3 Temperature and humidity. The Vacuum-Air-Nitrogen Distribution System shall be subjected to temperatures of 77 degrees F (with a humidity of up to 95 percent relative maximum), 32 degrees F, and 131 degrees F, (see 4.4.3). Thereafter, the system shall show no corrosion or damage and meet the performance requirements and product characteristics of this specification.

3.4.4 Tropical environment. The Vacuum-Air-Nitrogen Distribution System shall be capable of meeting all the performance requirements and product characteristics of this specification after being subjected to the tropical environment test of 4.6.4.

3.4.5 Storage life. The Vacuum-Air-Nitrogen Distribution System shall be capable of being stored for a period of at least five years when packed in accordance with Method II of MIL-P-116 under temperature and humidity conditions as follows:

3.4.5.1 Temperature: Minus 65 degrees F to plus 160 degrees F.

3.4.5.2 Humidity: Up to 95 percent relative maximum.

3.5 Cleaning. Prior to and after final assembly all parts, components, and the assembly shall be thoroughly cleaned of loose, spattered, or excess solder, metal chips, and other foreign matter. Burrs and sharp edges as well as rosin flash shall be removed.

3.8 Workmanship. The equipment, including all parts and accessories, shall be constructed and finished in a manner to ensure compliance with all requirements of this specification. Particular attention shall be paid to neatness and thoroughness of soldering, wiring, impregnation of



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

coils, marking of parts and assemblies, plating, riveting, machine screw assemblies, welding, brazing, and freedom of parts from burrs and sharp edges. The standards of workmanship exhibited in any approved preproduction sample, subject to any qualification stated in the Government's notice of approval, shall be determinative of the requirements of the contract relative to workmanship insofar as not specifically covered by applicable specifications.

## 4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure that supplies and services conform to prescribed requirements.

4.2 Classification of inspections. Inspection of the VAND System shall be classified as follows:

a. Preproduction inspection (paragraph 4.4)

b. Periodic production inspection (paragraph 4.4)

c. Acceptance inspection (paragraph 4.5)

4.3 Sampling. Unless otherwise specified, and when applicable, the sampling plans and procedures used by the Government inspector in the determination of the acceptability of products submitted by a supplier for Government inspection, shall be in accordance with the provisions , set forth in MIL-STD-105.

4.3.1 Preproduction sample. A preproduction sample of three VAND Systems manufactured in accordance with 3.2 shall be subjected to the preproduction tests detailed in 4.4 at an activity designated by the procuring activity. Acceptance of the preproduction sample shall be based on no defects in the sample. Further production of the system by the supplier, prior to the approval of the preproduction sample, shall be at the supplier's risk. Failure of the preproduction sample to comply with requirements shall be cause for rejection of the sample and its resubmission, as determined by the procuring activity.

4.3.2 Periodic production samples. From each succeeding lot or grand lot of one hundred or less, a random sample of three Vacuum-Air-Nitrogen Distribution Systems will be selected by the Government inspector for submission to a Naval Ordnance Systems Command assigned activity to



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

determine compliance of the samples with the requirements of the contract, specifications, and drawings. The VAND System shall be considered satisfactory if it meets all specifications and pertinent drawing requirements, and withstands the tests specified in 4.4 and 4.5 inclusive. Failure of a periodic production sample to comply with requirements will result in rejection of the lot and cessation of production, as determined by the procuring activity.

4.3.2.1 Lot size. As applied to Government inspection of units of product, the term "lot" shall mean "inspection lot", i.e., a collection of units of product submitted by a supplier for Government inspection. Unless otherwise specified, the number of units of product in "inspection lots" will be as determined by the Government inspector and may differ from the quantity designated in the contract or order as a lot for production, shipment, or other purpose.

4.3.3 Acceptance sampling. The tests and examinations detailed in 4.5 shall be conducted on each VAND System to be delivered; therefore, there shall be no sampling for acceptance. Defective units shall be rejected.

4.4 Preproduction and periodic production inspection. The preproduction and periodic production samples, after satisfactorily passing the acceptance inspections detailed in 4.5, shall be subjected to the following tests and examinations. Failure to meet any requirement specified herein shall be considered cause for rejection of the lot represented and units tested.

4.4.1 Vibration. The Vacuum-Air-Nitrogen Distribution System, mounted *as* specified in 3.4.1.1, shall be subjected to the following tests:

4.4.1.1 Test 1. The equipment shall be vibrated with a frequency varying between 10 and 33 cycles per second at a total excursion of 0.06 plus or minus 0.006 inch. The frequency shall vary uniformly from 10 to 33 cycles per second and return to 10 cycles per second in approximately one-half minute.

4.4.1.2 Test 2. The equipment shall be vibrated with a frequency varying between 10 and 55 cycles per second at a total excursion of 0.03 plus or minus 0.006 inch. The frequency shall vary uniformly from 10 to 55 cycles per second and return to 10 cycles per second in approximately one minute.

NOTE: Application of vibration specified in the above two tests shall be in each of the three major axes for a period of fifteen minutes each.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

4.4.1.3 Fixed frequency vibration. The equipment shall then be vibrated for a period of three minutes at each of the four most severe resonant frequencies at the amplitude specified above and in a plane observed to give the most severe reaction.

4.4.1.4 The equipment shall be inspected to ascertain that no fixed parts have become loose or damaged. The equipment shall then be operated to demonstrate that the performance required in this specification is maintained.

4.4.1.5 Vibration; transportation. The system, packaged and packed as specified in Section 5, shall be vibration tested as specified in Weapons Requirement WR-11.

4.4.2 Shock test. The Vacuum-Air-Nitrogen Distribution System shall be tested in accordance with the following procedure:

4.4.2.1 Mount the system on a shock testing machine (NSSC Drawing 10-T-2I45) as specified in 3.4.2.1, and subject it to a total of nine blows. Three blows shall be applied parallel to each of the three principal axes of Panel 1874290. Hammer drop heights for the back blow and side blow shall be one foot, two feet, and three feet. For the top blow, the height of hammer drop shall be two feet, three feet, and four feet. After each blow, the panel shall continue to perform in accordance with the requirement of this specification.

4.4.2.2 Shock; transportation, storage, and handling. The system packaged and packed as specified in Section 5, shall be subjected to the appropriate shock isolation tests specified in Weapons Requirements WR-11.

4.4.3 Temperature and humidity tests. The VAND System shall be subjected to the following temperature and humidity tests:

4.4.3.1 With the equipment stabilized at an ambient temperature of 77 degrees F, and with a humidity of up to 95 percent relative maximum, the system shall be operated for a twenty-minute period. At the conclusion of this period the Vacuum-Air-Nitrogen Distribution System shall meet the performance and other requirements specified in this specification.

4.4.3.2 The ambient temperature of the equipment shall be lowered to 32 degrees F and sufficient time for temperature stabilization shall be allowed. At the conclusion of this period all controls shall be readily manipulated and the Vacuum-Air-Nitrogen Distribution System shall meet the performance and other requirements specified in this specification.

4.4.3.3 The ambient temperature shall be raised to 131 degrees F and sufficient time for temperature stabilization shall be allowed. At the conclusion of this period all controls shall be readily manipulated and VAND System shall meet the performance and other requirements specified in this specification.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

4.4.4 Tropical environment. The VAND System, including applicable external connections, shall be placed in a mold chamber in which are maintained a temperature of 86 degrees F plus or minus 5 degrees F and a relative humidity of 90 percent plus or minus 5 percent, and the system shall then be sprayed with a suspension of mixed spores. These conditions shall be maintained for twenty-eight days. At the conclusion of this period, the VAND System shall be allowed to return to room temperature before its performance is checked. At least five groups of fungi shall be used in the system's inoculation. These five groups are listed below, and one type of fungus from each group shall be used. In preparing the spore suspension, distilled water (having a pH value between 5.8 and 7.2 degrees F) shall be prepared by sterilization in convenient containers (approximately 100 milliliters each). Approximately 10 milliliters of the solution shall then be introduced directly into a stock culture of one fungus and shaken vigorously in order that a well sporulated suspension will result without disturbing the agar. This process shall be repeated for each type fungus. The separate spore suspensions from the types of fungi shall then be mixed together in an atomizer to provide a composite suspension. Actively growing cultures in ripe fruiting condition shall be used for each inoculation and under no condition will the inoculum be kept for more than an 8 hour period.

| | |
|---|---|
| Group I | Chaetomium globosum USDA 1042.4, ATCC 6205, or<br>Myrothecium verrucaria USDA 1334.2, ATCC 9095. |
| Group II | Rhizopus nigricans S.N. 32, ATCC 10404, or<br>Aspergillus niger USDA TC215-4247, ATCC 6275. |
| Group III | Aspergillus flavus AMC No. 26, ATCC 10836, or<br>Aspergillus terreus PQMD 82J, ATCC 10690. |
| Group IV | Penicillium luteum USDA 1336.1, ATCC 9776<br>Penicillium sp. USDA 1336.2, ATCC 9112, or<br>Penicillium citrinum ATCC 9849. |
| Group V | Memnoniella echinata AMC No. 37, ATCC 9597, or<br>Fusarium moniliforme USDA 1004.1, ATCC 10052. |

4.4.5 Functional tests. At the conclusion of the tests specified in 4.4.1.5 and 4.4.2.2 above, functional and other tests, as applicable, shall be conducted on the system to determine freedom from operational malfunction and compliance with all requirements of Section 3.

4.4.6 Waiver of tests. Tests specified in 4.4.1.5 and 4.4.2.2 above may be waived by the procuring agency for Level C packs only, provided the contractor guarantees safe delivery to the using activity.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

4.5 Acceptance inspection. Each Vacuum-Air-Nitrogen Distribution System delivered under contract shall be subjected to the following tests and l xaminations. Failure to meet any requirement specified herein shall be considered cause for rejection.

4.5.1 Test conditions. Unless otherwise specified, the Vacuum-Air-Nitrogen Distribution System shall be subjected to acceptance tests under the following conditions:

4.5.1.1 Temperature: Room ambient 65 degrees F to 95 degrees F.

4.5.1.2 Altitude: Normal ground.

4.5.1.3 Vibration: None.

4.5.1.4 Humidity: 95 percent relative maximum at l n ambient temperature of 40 degrees C plus or minus 2 degrees, dry bulb.

4.5.2 Test and inspection equipment and facilities. The manufacturer shall furnish and maintain all necessary test equipment and facilities and shall provide personnel for performing all acceptance tests. The test equipment shall be adequate in quantity and, unless definite requirements are specified, shall be of sufficient accuracy and quality to permit performance of the required acceptance tests.

4.5.3 Test equipment. The following items of test equipment are required to perform the acceptance tests set forth in this specification:

4.5.3.1 Manometer capable of reading 30 inches of mercury vacuum to 30 pounds per square inch pressure.

4.5.3.2 Source of clean, dry air at 800 pounds per square inch pressure.

4.5.3.3 Source of nitrogen at 50 to 400 pounds per square inch pressure.

4.5.3.4 Source of 115 volts 60 cycles per second power.

4.5.3.5 An 800 pounds per square inch air-pressure gage calibrated in one pound per square inch increments.

4.5.3.6 A shock testing machine as shown on Naval Ships Systems Command Drawing 10-T-2145.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

4.5.4 Test procedure

4.5.4.1 Pressure test. Connect a supply of regulated clean, dry air at 800 pounds per square inch pressure to the high-pressure air inlet of Vacuum-Air-Nitrogen Distribution Panel 1874090. To one of four Sockets 1390590 of Pressure Hose Assembly 1443812, connect an 800 pounds per square inch air gage calibrated in one pound per square inch increments. With the regulator valve closed (spindle backed out), open the inlet valve. No pressure should register at the outlet. Slowly open the regulator valve, and check the following:

4.5.4.1.1 Pressure change. The pressure shall increase evenly and smoothly.

4.5.4.1.2 Maximum pressure. With regulator fully opened, 800 pounds per square inch shall be registered at the outlet.

4.5.4.1.3 Leakage. There shall be no drop in pressure with the inlet valve closed.

4.5.4.1.4 Gage 2482217, shown on Drawing 1874090, shall be recalibrated for accuracy at end of above test.

4.5.4.2 Vacuum and nitrogen test preparation. Connect a 50 to 400 pound per square inch supply of nitrogen to the nitrogen inlet, and connect a differential manometer to Socket 1390590 of Vacuum Hose Assembly 1263337.

4.5.4.3 Vacuum test. With Regulator Valve 1263313 closed, Toggle Valve 1390811 closed, and Toggle Valve 1263617 open, start the vacuum pump and draw a vacuum of 25 inches of mercury, as read on the manometer. The compound gage shall register the same as the manometer within plus or minus 0.1 percent. The time required for the pump to draw this vacuum shall not exceed five seconds.

4.5.4.3.1 Leakage. Toggle Valve 1263617 and stop the pump. After a time lapse of five minutes there shall be no change in the manometer reading.

4.5.4.4 Nitrogen test. With Toggle Valve 1390811 open and Toggle Valve 1263617 closed, open the nitrogen inlet valve and operate the regulator until O pounds per square inch is registered on the manometer. The pressure change shall be smooth and even.

4.5.4.4.1 Relief valve operation. Increase the nitrogen pressure until Relief Valve 1390424 operates. Operating pressure shall be 25 plus or minus one pound per square inch.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

4.5.4.5 Visual and dimensional examination. Each VAND System shall be examined to determine conformance with the requirements for workmanship and dimensions.

4.5.4.6 Packaging and packing. The VAND System shall be examined to ensure that it complies fully with the requirements of Section 5.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging

5.1.1 Level A. In addition to the following, Level A packaging shall be in accordance with MIL-E-1755S.

5.1.1.1 Cleaning, drying, and preservative application. Not applicable.

5.1.1.2 Unit packaging. Unit packaging of the system shall be in accordance with Method IIa of MIL-P-116. The unit package shall contain one VAND System.

5.1.1.3 Intermediate package. Not applicable.

5.1.2 Level B. Not applicable.

5.1.3 Level C

5.1.3.1 Unit packaging. Unit packaging of system shall be in accordance with Method III of MIL-P-116.

5.1.3.2 Intermediate package. Not applicable.

5.2 Packing

5.2.1 Level A. In addition to the following, Level A packing shall be in accordance with MIL-E-175S5.

5.2.1.1 Exterior containers. One system, packaged as described in 5.1.1.2, shall be packed in a wood box in accordance with PPP-B-621, Class 2, or PPP-B-601, overseas type, plywood modified to include a removal door for view of humidity indicator.

5.2.2 Level B. In addition to the following, Level B packing shall be in accordance with MIL-E-17555.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

5.2.2.1 Exterior containers. One system, packaged as described in 5.1.1.2, shall be packed in a wood box in accordance with PPP-B-621, Class 1, or PPP-B-601, Domestic type.

5.2.3 Level C. Systems packaged in accordance with 5.1.3.1 shall be packed to afford protection against damage during shipment from the supply source to the first receiving activity for immediate use. Containers shall comply with Consolidated Freight Classification Rules or other common carrier regulations applicable to the mode of transportation.

5.3 Levels A, B, or C cushioning. The unit package or pack shall incorporate sufficient cushioning material, bracing, or other adequate shock absorbing devices to ensure that the system will meet all the requirements of Section 3 after being tested in accordance with 4.4.1.5 and 4.4.2.2. At the time of packaging or packing, the moisture content of the cushioning material shall not exceed five percent.

5.4 Marking

5.4.1 Special markings. None unless otherwise specified.

5.4.2 Normal markings. In addition to the markings required by contract or order, unit packages, intermediate packages (when used), and shipping containers shall be marked in accordance with the requirements of MIL-STD-129, including serial numbers.

6. NOTES

6.1 Intended use and descriptions

6.1.1 Intended use. The VAND System is used with the following torpedoes: Mk27 Mod 4, Mk 34 Mod 1, Mk 35 Mod 3, Mk 37 Mods 0 and 1, Mk 43 Mods 1 and 3, Mk 44 Mods 0 and 1, Mk 45 Mods 0 and 1, Mk 46 Mods 0 and 1, and Mine Vehicle Mk 1 Mods 0, 1 and 2.

6.1.2 Description. The VAND System consists essentially of a vacuum pump, hoses, panel-mounted valves, pressure gages, and air regulators. The system provides pneumatic testing facilities for the advanced undersea weapons. The equipment is also capable of controlling the nitrogen supply for the various weapons of this group which are to be filled with an inert gas.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.

(b) Any exceptions to this specification.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

(c) Required level of preservation and packaging.

(d) Required level of packing.

(e) Assigned activity for preproduction and periodic production tests.

(f) That all additional samples required shall be provided and inspected at the expense of the supplier, when such additional samples are required because of failure of any sample(s) to pass the prescribed inspections.

(g) That certified inspection data covering the results of preproduction and periodic production inspections shall be forwarded to the Naval Ordnance Systems Command when testing is accomplished at other than a Government activity.

6.2.1 The attention of the contracting officer is invited to the Quality Assurance Provisions and options in MIL-P-116 and to 4.4.6 of this specification.

6.3 Preparation for delivery criteria. Criteria for use of the proper level of preservation, packaging, and packing shall be as follows:

Level A. This level shall be used for those items which are to be shipped to indeterminate destinations or stored under indeterminate conditions for redistribution anywhere.

Level B. This level shall be used only when it is definitely known that the item will be held in covered storage in overseas locations for six months or less or in domestic locations for an indefinite period.

Level C. This level shall be used only when it is definitely known that the packaged items are to be shipped to domestic installations for immediate use at the first receiving activity.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

# SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

**INSTRUCTIONS**

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specifications in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity (as indicated on reverse hereof).

SPECIFICATION

MIL-V-82466(OS) VACUUM-AIR-NITROGEN DISTRIBUTION SYSTEM

| ORGANIZATION (of submitter) | CITY AND STATE |
|---|---|
| | |

| CONTRACT NO. | QUANTITY OF ITEMS PROCURED | DOLLAR AMOUNT |
|---|---|---|
| | | $ |

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

   ☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS (Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)

| SUBMITTED BY (Printed or typed name and activity) | DATE |
|---|---|
| | |

DD, FORM 1 APR 63 1426

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY
Naval Ordnance Systems Command
Washington, D.C. 20360

POSTAGE AND FEES PAID
NAVY DEPARTMENT

OFFICIAL BUSINESS

NAVAL ORDNANCE SYSTEMS COMMAND (ORD 9343)
DEPARTMENT OF THE NAVY
WASHINGTON, D. C. 20360

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:11Z
Check the source to verify that this is the current version before use.