INCH-POUND

MIL-P-52284C
7 April 1992
SUPERSEDING
MIL-P-52284B
21 September 1983

MILITARY SPECIFICATION

POST, HANDRAIL, FOOTBRIDGE

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a handrail post to be used with the treadway of the aluminum floating footbridge.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications and standards form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2)

SPECIFICATIONS

FEDERAL

PPP-B-621 - Boxes, Wood, Nailed and Lock-Corner.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-T-704 - Treatment and Painting of Materiel.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129 - Marking for Shipment and Storage.
MIL-STD-889 - Dissimilar Metals.
MIL-STD-1190 - Minimum Guidelines for Level C Preservation, Packing and Marking.

(Unless otherwise indicated, copies of federal and military specifications and standards are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other drawings and publications. The following other drawings and publications form a part of this specification to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

DRAWINGS

ME

TA13217E9313 - Post Handrail, Footbridge.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the US Army Belvoir Research, Development and Engineering Center, ATTN: STRBE-JBS, Fort Belvoir, VA 22060-5606.)

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME - Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers and Welding and Brazing Operators.

(Applications for copies should be addressed to the American Society of Mechanical Engineers, Inc., 345 East 47th Street, New York, NY 10017.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

AMERICAN WELDING SOCIETY (AWS)

AWS A5.10	-	Bare Aluminum and Aluminum-Alloy Welding Electrodes and Rods.
AWS D1.2	-	Structural Welding Code - Aluminum.

(Application for copies should be addressed to the American Welding Society, Inc., 550 N.W. LeJeune Road, P.O. Box 351040, Miami, FL 33135.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D 3953	-	Strapping, Flat Steel and Seals.
D 4675	-	Selection and Use of Flat Strapping Materials.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, (except for related associated detail specifications, specification sheets or MS standards), the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The handrail post shall be as shown on Top Assembly TA13217E9313 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviations from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operating of the handrail post. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or the designated representative.

3.2 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 4.3 and 6.3).

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

contractor and shall be subject to all provisions of this specification. Material shall be new and unused.

3.3.1 Material deterioration and control. The items shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable storage and operating environment to which the item may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with components and sub-components, and shall make information available, upon request, to the contracting officer or designated representative.

3.4 Welding electrodes. Welding electrodes shall conform to AWS A5.10, classification ER4043, size as required.

3.5 Identification marking. The handrail post shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.6 Treatment and painting. The handrail post shall be cleaned, treated, and painted in accordance with MIL-T-704, type B.

3.7 Workmanship.

3.7.1 Welders and welding.

3.7.1.1 Welders or welding operator . Before assigning any welder or welding operator to welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder or welding operator has passed qualification tests as prescribed by either of the following listed codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

ASME Boiler and Pressure Vessel Code, Section IX.
AWS D1.2, Structural Welding Code-Aluminum.

Contractors who make only horizontal welds need not qualify welders for "all position welding". In the event of evidence of poor welds, the Government reserves the right to require retesting of any welder or welding operator.

3.7.1.2 Welding. The surfaces of parts to be welded shall be free from scale, paint, grease, and other foreign matter. Welding shall be done by the shielded metal-arc or gas metal-arc (MIG) process and shall conform to the

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:12Z
Check the source to verify that this is the current version before use.

provisions of either ASME or AWS Code. All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit and adjoining base metal shall be wirebrushed clean. Welding procedures shall be qualified in accordance with applicable ASME or AWS code, and all welding and welds shall be in accordance with ASME or AWS code.

3.7.2 Metal fabrication. Metal used in fabrication shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause damage to the material. Corners shall be square and true. All bends shall be made with controlled means to insure uniformity of size and shape. External surfaces shall be clean, free from rust, burrs, sharp edges and corners, tool marks, pits and other injurious defects.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards, as applicable.

4.2 Classification of inspections. Inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:12Z
Check the source to verify that this is the current version before use.

c. Inspection of packaging (see 4.6).

4.3 First article inspection.

4.3.1 Examination. The first article handrail post shall be examined for the defects specified in 4.5.1. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when 0 defects are found and rejected when 1 or more defects are found.

4.4.2 Examination. Samples selected in accordance with 4.4.1 shall be examined for the major and minor defects specified in 4.5.1. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.5 Inspection procedure.

4.5.1 Examination. The handrail post shall be examined as specified for the following defects.

Major

101. Nonconformance to the dimensions shown on the drawings (see 3.1.1).
102. Material not as specified (see 3.3).
103. Materials not resistant to corrosion or treated to be made corrosion resistant for the applicable storage and operating environment (see 3.3.1).
104. Dissimilar metals as defined in MIL-STD-889 or not effectively insulated from each other (see 3.3.1.1).
105. Contractor does not have documentation available for identification of material, material finishes or treatments (see 3.3.1.2).
106. Workmanship not as specified (see 3.7).
107. Welding and welds not as specified (see 3.7.1).
108. Welders and welding operators not certified as specified (see 3.7.1.1).

Minor

201. Identification marking incorrect, missing, or illegible (see 3.5).
202. Treatment and painting not as specified (see 3.6).

4.6 Inspection of packaging.

4.6.1 First article pack inspection.

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:12Z
Check the source to verify that this is the current version before use.

4.6.1.1 Examination. Examine the first article pack for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.2.2 Sampling. Sample size shall be determined by using MIL-STD-105, table I or table IIa. A lot shall be accepted when 0 defects are found and rejected when 1 or more defects are found.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following defects. Presence of one or more defects shall be cause for rejection.

109.	Posts not packed in a box as specified for level A (see 5.2.1).
110.	Quantities not as specified for level A (see 5.2.1).
111.	Ends of boxes not reinforced as specified for level A (see 5.2.1).
112.	Posts not positioned in the box as specified for level A (see 5.2.1).
113.	Strapping not as specified for level A (see 5.2.1).
114.	Packing not in accordance with the referenced document for level C (see 5.2.3).
115.	Marking missing, illegible, incorrect, or incomplete for level A or level C (see 5.3).

5. PACKAGING

5.1 First article pack. Unless otherwise specified (see 6.2), the contractor shall furnish a first article pack for examination within the time frame specified (see 6.2) to prove prior to starting production packaging that the applied packing, and marking comply with the packaging requirements of this specification. Examination shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The first article pack may be prepared utilizing either the first article posts or production posts. When the first article posts are utilized, any packing shall be removed by the contractor at no expense to the Government, when requested by the Government, to facilitate comparison between the first article posts and production posts.

5.2 Packing. Packing shall be level A, B, or C as specified (see 6.2).

5.2.1 Level A. The posts shall be packed in quantities of 42 in a box conforming to PPP-B-621, class 2, style 2, for type 3 load. The boxes shall be constructed with lumber of any species of groups I or II wood for weight of contents of 250 to 400 pounds. The ends of the box shall be reinforced by the addition of boards covering the entire inner face of each end. The reinforcing boards shall be the same thickness as the end boards, shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

placed with grain direction at right angles to that of the end boards, and shall be nailed to them with the nails clinched. The sides, top, and bottom of the box shall be nailed to the reinforcing boards in addition to the nailing required by the box specification. The box shall be close fitting to prevent movement of the posts and shall be approximately 44-3/4 inches long by 11-1/2 inches wide by 15-1/4 inches high. The posts shall be tightly nested in the box seven posts wide and six layers high, with the ends of each post alternated with respect to adjacent posts. The boxes shall be strapped in accordance with ASTM D 3953, type 1 or 2, zinc coated, size as applicable and ASTM D 4675.

5.2.2 Level B. Posts shall be packaged as specified in 5.2.1 except that the box shall be domestic type.

5.2.3 Level C. Posts shall be packed to level C requirements in accordance with MIL-STD-1190.

5.3 Marking (see 6.5). In addition to any special marking specified in the contract or purchase order (see 6.2), marking shall be in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The handrail posts are to be used with the treadways of the aluminum floating footbridge as support for the handrail rope. This item is a component of the following supply catalog: SC5420-97CL-E28.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.2.1 and 2.2).
c. When a first article is required for inspection and approval and the number of units required (see 3.2 and 4.3).
d. When a first article pack is not required (see 5.1).
e. Time frame required for submission of the first article pack (see 5.1).
f. Level of packing required (see 5.2).
g. Any special marking required (see 5.3).

6.3 First article. When a first article inspection is required, the contracting officer should provide specific guidance to offerors whether the item(s) should be a preproduction item (see 3.2), and the number of items to be tested specified in 4.3. The contracting officer should also include specific instructions in acquisition documents regarding arrangements for

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

examinations, approval of the first article test results and disposition of the first articles. Invitations for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 First article pack. Any changes or deviations of production packs from the approved first article pack will be subject to the approval of the contracting officer. Approval of the preproduction pack will not relieve the contractor of his obligation to pack and mark the handrail posts in accordance with this specification.

6.5 Level of preservation. Levels of preservation have not been included as the posts do not require additional preservation. For purposes of marking, the preservation shall be designated as level A.

6.6 International standardization agreement. Certain provisions of this specification are the subject of International Standardization Agreement QSTAG 88. When amendment, revision, or cancellation of this specification is proposed which will modify the international agreement concerned, the preparing activity will take appropriate action through international standardization channels, including departmental standardization offices, to change the agreement or make other appropriate accommodations.

6.7 Subject term (key word) listing.

Handrail support
Railing
Railing footbridge

6.8 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:
Army - ME

Preparing activity:
Army - ME

Review activity:
Navy - MC
DLA - CS

Project 5420-0199

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-P-52284C	2. DOCUMENT DATE (YYMMDD) 920407

3. DOCUMENT TITLE: Post, Handrail, Footbridge

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (if applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME Gerry Harlow	b. TELEPHONE (Include Area Code) (1) Commercial (703) 704-3469 (2) AUTOVON 654-3469
c. ADDRESS (Include Zip Code) US Army Belvoir RDE Center ATTN: STRBE-TSE Fort Belvoir, VA 22060-5606	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

DD Form 1426, OCT 89 Previous editions are obsolete

Source: https://assist.dla.mil -- Downloaded: 2026l0-22T21:12Z
Check the source to verify that this is the currentversion before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:12Z
Check the source to verify that this is the current version before use.