MIL–F–11247A (MU)
15 OCTOBER 1963
SUPERSEDING
MIL–F–11247(ORD)
28 JUNE 1951

MILITARY SPECIFICATION

FUZE, MINE, AT, M603
FUZE, MINE, AT, PRACTICE, M604
METAL PARTS FOR

1. SCOPE

1.1 This specification covers the metal parts for two fuzes designated as Fuze, Mine, AT, M603 and Fuze, Mine, AT, Practice, M604.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL–A–2550 —Ammunition and Special Weapons, General Specification for

MIL–P–10025 —Packaging, Packing and Marking for Interplant Shipment of Inert Ammunition Components; General Specification for

MIL–I–45208 —Inspection Requirements, General Specification for

MIL–I–45607 —Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

MIL–STD–105 —Sampling Procedures and Tables for Inspection by Attributes

MIL–STD–109 —Quality Assurance Terms and Definitions

MIL–STD–1235 —Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

ORDNANCE CORPS

73–9–55—Fuze, Mine, AT, M603 Assembly

73–9–85—Fuze, Mine, AT, Practice M604

PUBLICATIONS

ORDNANCE CORPS

IEL–73–9–85—Index of Inspection Equipment Lists

(Copies of specifications, standards, drawing and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:46Z
Check the source to verify that this is the current version before use.

FSC: 1390

3. REQUIREMENTS

3.1 Material. Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Metal parts. The metal parts shall comply with all requirements specified on Drawing (dwg.) 73–9–55 and dwg. 73–9–85 and with all requirements specified in applicable specifications.

3.3 Cover assembly. The solder joint of the cover assemblies shall withstand a tensile load of at least 50 pounds without failure when tested as specified in 4.4.1.

3.4 Air pressure test. The metal parts assemblies shall evidence no drop in pressure when subjected to an internal air pressure of not less than 10 pounds per square inch gage (p.s.i.g.) for not less than 3 seconds when tested as specified in 4.4.3.

3.5 Body crimp. The crimp of the body to the cover assembly shall show no evidence of leakage following a pull of 15 pounds when tested as specified in 4.4.4.

3.6 Recovery of firing pin assembly. The firing pin shall return to a minimum of 0.002 inches above the detonator well shoulder after a load of not less than 134 pounds and not more than 135 pounds is applied and released when tested as specified in 4.4.5.

3.7 Functioning. The fuze assembly shall require an axial load of not less than 140 pounds nor more than 240 pounds to cause sudden reversal of the spring when tested as specified in 4.4.6.

3.8 Workmanship. All parts shall be fabricated and finished in a thorough workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. All required markings shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions. The supplier is responsible for the performance of *all* inspection requirements specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL–STD–109 in order to define terms used herein. The provisions of Specification MIL–A–2550 shall apply.

4.1.1 *Contractor quality assurance system.* The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL–I–45208.

4.1.2 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

(a) A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.

(b) Number of units of product inspected.

(c) Results obtained for all inspection performed.

(d) Drawing, specification number and date, together with an identification and date of changes.

(e) Certificates of analyses on all material purchased by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

(f) Number of items in the lot.

(g) Date submitted.

Source: https://assistdla.mil - Downloaded: 2026-10-17 11:46.46Z
Check this source to verify that this is the current version before use.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificates submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.3 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector will verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL–I–45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Initial production inspection.

4.2.1 *Submission.* Prior to normal production the contractor shall submit an initial production sample consisting of 50 consecutively produced assemblies and complete sets of parts (i.e. 50 each of every individual component and every subassembly), which have been produced by the production process which the contractor will use in fulfilling the contract, to a Government-approved facility designated by the contracting officer. All parts and materials shall be obtained from the same source of supply as will be used in regular production. The initial production sample shall be accompanied by certificates of analyses for all materials. A sample shall also be submitted whenever a change occurs in manufacturing process, material used, drawing, specification, or source of supply such as to significantly affect product uniformity as determined by the Government.

4.2.2 *Inspections to be performed.* Each assembly and component shall be inspected by the Government for all the inspections specified in 4.3.2 and 4.3.3 of this specification and for all additional requirements of the applicable drawings.

4.2.3 *Rejection.* If any assembly or component fails to comply with the applicable requirements, the initial production sample shall be rejected. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit new or supplemental quantities until such time as an acceptable sample is submitted, or until otherwise directed by the contracting officer.

4.3 Inspection provisions.

4.3.1 *Lot formation.* A lot shall consist of fuze parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification and process changes not affecting safety, performance or fit, as determined by the Government shall not necessitate changing the lot number.

4.3.2 *Examination.* Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL–STD–105 except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with Standard MIL–STD–1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.25 percent for each major defect and an AQL of 0.40 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 *Workmanship.* Applies to all components and subassemblies not specifically listed in 4.3.2.2–4.3.2.13 (see applicable drawings).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:46Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of inspection
Critical:	None defined.	
Major:	AQL 0.25 percent per defect	
101.	Operation missing or improperly performed	Visual
102.	Bur or chip on or at intersection of sliding or other functional surfaces	Visual
103.	Finish of sliding or other functional surface improper	Visual
104.	Component missing or improperly assembled	Visual
105.	Protective finish inadequate	Visual
Minor:	AQL 0.40 percent	
201.	Evidence of poor workmanship other than that covered under Major Category above (see 3.8).	Visual

4.3.2.2 Pin, firing (see dwg. 73-9-57 covering details of dwg. 73-9-55 and dwg. 73-9-85).

Categories	Defects	Method of inspection	Code No. (see 6.2).
Critical:	None defined.		
Major:	AQL 1.00 percent		
101.	Profile of point	Gage	01001
102.	Diameter of shank	Gage	01002
103.	Length of shank	Gage	01003
104.	Diameter of retainer mating surface	Gage	01004
105.	Length of retainer mating surface	Gage	01005
106.	Diameter of head	Gage	01006
107.	Length of head	Gage	01007
108.	Diameter of cover locator	Gage	01008
109.	Taper of cover locator	Gage	01009
110.	Total length	Gage	01010
Minor:	AQL 1.00 percent		
201.	Finish improper	Visual	01011
202.	Evidence of poor workmanship (see 3.8)	Visual	01012

4.3.2.3 Retainer (see dwg. 73-9-57 covering details of dwg. 73-9-55 and dwg. 73-9-85).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Total height	Gage	02001
102.	Height to taper	Gage	02002
103.	Taper to flange	Gage	02003
104.	Outside diameter of flange	Gage	02004
105.	Outside diameter to taper	Gage	02005
106.	Inside diameter	Gage	02006
107.	Countersink missing or inadequate	Visual	02007
Minor:	AQL 1.00 percent		
201.	Finish improper	Visual	02008
202.	Evidence of poor workmanship (see 3.8)	Visual	02009

4.3.2.4 Spring (see dwg. 73-9-57 covering details of dwg. 73-9-55 and dwg. 73-9-85).

Categories	Defects	Method of inspection	Code No. (see 6.2).
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Outside diameter	Gage	03001
102.	Hole diameter	Gage	03002
103.	Concentricity of hole with outside diameter	Gage	03003
104.	Thickness	Gage	03004
105.	Height after heat treatment	Gage	03005
106.	Identification mark missing or improperly located	Visual	03006
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.8)	Visual	03007

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:46Z
Check the source to verify that this is the current version before use.

4.3.2.5 Firing Pin Assembly (see dwg. 73–9–57 covering details of dwg. 73–9–55 and dwg. 73–9–85).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Height to cocked springs	Gage	04001
102.	Crimp not 360 degrees	Visual	04002
103.	Springs incorrectly assembled	Visual	04003
Minor:	AQL 1.00 percent		
201.	Lacquer missing or inadequate	Visual	04004
202.	Evidence of poor workmanship (see 3.8)	Visual	04005

4.3.2.6 Cover (see dwg. 73–9–57 covering details of dwg. 73–9–55 and dwg. 73–9–85).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.00 percent		
101.	Height to plate shoulder	Gage	05001
102.	Height of plate dimple	Gage	05002
103.	Radius of plate dimple	Gage	05003
104.	Outside diameter	Gage	05004
105.	Width of flange	Gage	05005
106.	Thickness of flange	Gage	05006
107.	Radius between plate dimple and plate shoulder	Gage	05007
108.	Other radii missing	Visual	05008
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.8)	Visual	05009

4.3.2.7 Plate, pressure (see dwg. 73–9–57 covering details of dwg. 73–9–55 and dwg. 73–9–85).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Flange thickness	Gage	06001
102.	Height of dimple	Gage	06002
103.	Radius of dimple	Gage	06003
104.	Radius to dimple	Gage	06004
Minor:	AQL 1.50 percent		
201.	Outside diameter	Gage	06005
202.	Marking improper or misleading	Visual	06006
203.	Evidence of poor workmanship (see 3.8)	Visual	06007

4.3.2.8 Cover Assembly (see dwg. 73–9–57 covering details of dwg. 73–9–55 and dwg. 73–9–85).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.25 percent		
101.	Height between flanges	Gage	07001
102.	Soldering inadequate	Visual	07002
Minor:	AQL 1.50 percent		
201.	Excess solder	Visual	07003
202.	Evidence of poor workmanship (see 3.8)	Visual	07004
203.	Marking improper or misleading	Visual	07005

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:46Z
Check the source to verify that this is the current version before use.

4.3.2.9 Body (see dwg. 73-9-57 covering details of dwg. 73-9-55 or dwg. 73-9-85).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 2.50 percent		
101.	Diameter of detonator well	Gage	08001
102.	Height of detonator well	Gage	08002
103.	Height of detonator well crimp projection	Gage	08003
104.	Radius at shoulder of detonator well	Gage	08004
105.	Diameter of firing pin shank hole	Gage	08005
106.	Diameter of spring counterbore	Gage	08006
107.	Radius to start of spring taper	Gage	08007
108.	Depth to start of spring taper	Gage	08008
109.	Diameter at start of spring taper	Gage	08009
110.	Width of detonator well crimp projection	Gage	08010
111.	Taper of detonator well crimp projection	Gage	08011
112.	Diameter at end of spring taper	Gage	08012
113.	Angle of spring taper	Gage	08013
114.	Diameter of cover counterbore	Gage	08014
115.	Depth of cover groove	Gage	08015
116.	Width of cover groove	Gage	08016
117.	Total height	Gage	08017
118.	Profile of exterior	Gage	08018
119.	Concentricity of spring counterbore with firing pin shank hole	Gage	08019
120.	Chamfer to firing pin shank hole missing	Visual	08020
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.8)	Visual	08021

4.3.2.10 Cushion (see dwg. 73-9-57 covering details of dwg. 73-9-55).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Outside diameter	Gage	09001
102.	Inside diameter	Gage	09002
103.	Thickness	Gage	09003
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.8)	Visual	09004

4.3.2.11 Fork, safety (see dwg. 73-9-57 covering details of dwg. 73-9-55 and dwg. 73-9-85).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Height	Gage	10001
102.	Thickness	Gage	10002
103.	Diameter at closed end	Gage	10003
104.	Diameter of mid portion	Gage	10004
105.	Width of opening	Gage	10005
Minor:	AQL 1.50 percent		
201.	Radii improper	Gage	10006
202.	Distance between diameter centers	Gage	10007
203.	Distance to ends	Gage	10008
204.	Evidence of poor workmanship (see 3.8)	Visual	10009

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:46Z
Check the source to verify that this is the current version before use.

4.3.2.12 Cup, Body (see dwg. 73-9-85).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Height	Gage	11001
102.	Inside diameter	Gage	11002
103.	Thickness at bottom	Gage	11003
104.	Diameter of bottom hole	Gage	11004
105.	Radius at bottom	Gage	11005
106.	Outside diameter	Gage	11006
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.8)	Visual	11007

4.3.2.13 Disc, Body (see dwg. 73-9-85).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.25 percent		
101.	Diameter	Gage	12001
102.	Thickness	Gage	12002
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.8)	Visual	12003

4.3.2.14 Assembly (see dwg. 73-9-55 or dwg. 73-9-85).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Total height	Gage	13001
102.	Distance from pressure plate flange to top of body	Gage	13002
103.	Distance from bottom of detonator to tip of firing pin	Gage	13003
104.	Crimp fractured or not for 360 degrees	Visual	13004
105.	Lining compound missing or incomplete	Visual	13005
Minor:	AQL 1.00 percent		
201.	Marking incorrect or misleading	Visual	13006
202.	Evidence of poor workmanship (see 3.8)	Visual	13007

4.3.2.15 Carton, sealed (see section 5).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Contents move when carton is shaken	Manual	14001
102.	Carton damaged so that contents are exposed or liable to become exposed	Visual	14002
103.	Sealing strip incomplete, badly wrinkled or not in contact with surface for at least ½ inch around entire carton	Visual	14003
Minor:	AQL 0.40 percent		
201.	Marking misleading or unidentifiable	Visual	14004

4.3.3 *Testing.*

07006

4.3.3.1 *Cover assembly (see 3.3) Major defect.* A sample of 25 assemblies shall be selected for this test. The test shall be performed as specified in 4.4.1 using equipment in accordance with 4.3.4. If two or more samples do not comply with 3.3 the lot shall be re-

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:46Z
Check the source to verify that this is the current version before use.

jected. If one sample does not comply with 3.3 the lot shall be rejected unless the supplier requests, and the lot passes, a retest. A sample of additional 50 assemblies shall be selected for the retest and failure of one assembly to comply with 3.3 during the retesting shall cause the lot to be rejected.

03008

4.3.3.2 *Reversed height, snap back load and travel.* Free position height after snap back and enamel of spring (see dwg. 73–9–57) major defect. The sampling plan for this test shall be in accordance with Standard MIL–STD–105 using inspection level I and an AQL of 0.25 percent. This test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4. Any spring which does not comply with all applicable requirements shall be classed defective.

13008

4.3.3.3 *Air pressure test (see 3.4) major defect.* This test shall be performed 100 percent and as specified in 4.4.3. Assemblies which do not comply with 3.4 shall be classed defective and removed from the lot.

13009

4.3.3.4 *Body crimp (see 3.5) major defect.* A sample of 25 assemblies shall be selected for this test. The test shall be performed as specified in 4.4.4. using equipment in accordance with 4.3.4. If two or more samples do not comply with 3.5 the lot shall be rejected. If one sample does not comply with 3.5 the lot shall be rejected unless the supplier requests, and the lot passes, a retest. A sample of 50 additional assemblies shall be selected for the retest and failure of one assembly to comply with 3.5 during the retesting shall cause the lot to be rejected.

13010

4.3.3.5 *Recovery of firing pin assembly (see 3.6).* major defect, initial production. Beginning with the first lot produced and continuing until three consecutive lots have complied with the acceptance criteria specified, the sampling plan for this test shall be in accordance with Standard MIL–STD–105 using inspection level II and an AQL of 0.10 percent. The test shall be performed as specified in 4.4.5 using equipment in accordance with 4.3.4. Any fuze assembly which does not comply with 3.6 shall be classed defective.

4.3.3.5.1 Recovery of firing pin assembly (see 3.6) major defect, normal production. After three consecutive lots have met the criteria of 4.3.3.5, the sampling plan for this test shall be in accordance with Standard MIL–STD–105 using inspection level I and an AQL of 0.25 percent.

13011

4.3.3.6 Functioning (see 3.7) major defect, initial production. Beginning with the first lot produced and continuing until three consecutive lots have complied with the acceptance criteria specified, the sampling plan for this test shall be in accordance with Standard MIL–STD–105 using inspection level II and an AQL of 0.10 percent. The test shall be performed as specified in 4.4.6 using equipment as specified in 4.3.4. Any fuze assembly which does not comply with 3.7 shall be classed defective.

4.3.3.6.1 Functioning (see 3.7) major defect, normal production. After three consecutive lots have met the criteria of 4.3.3.4, the sampling plan for this test shall be in accordance with Standard MIL–STD–105 using inspection level I and an AQL of 0.25 percent.

4.3.4 *Inspection equipment.* Index of Inspection Equipment Number IEL 73–9–85 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on

Source: https://assistdla.mil — Downloaded: 2026-10-07 15:46:42
Check the source to verify that this is the current version before use.

the IEL shall be in accordance with Specification MIL–I–45607.

4.3.4.3 *Government use of contractor's inspection equipment.* The contractor shall as required make available to the Government all inspection equipment necessary for determining conformance with contract requirements. Operation of the equipment and verification of its accuracy shall be supplied by the contractor, as required by the Government in performance of its examination or test.

4.4 Test methods and procedures.

4.4.1 *Cover assembly.* The asembly shall be subjected to a tensile load applied between the pressure plate and the fully supported cover. Th load shall be applied at such a rate that the pull fixture moves ½ to 1 inch per minute until the solder joint is destroyed. Observation shall be made for a failure load of 50 pounds minimum, and evidence of 360 degree solder contact in the soldered joint for compliance with 3.3.

4.4.2 *Reversed height, snap back load and travel, free position height after snap back and enamel of spring.* The spring shall be subjected to an axial load at the rate of ½ to 1 inch per minute to cause it to snap through and then to snap back. Observation shall be made that the reversed height is 0.068 plus .010 inch, a load of 60 to 90 pounds is required to snap back, the travel during snap back is 0.032 plus .015 inch, the height after snap back is 0.070 inch minimum and no enamel is flaked off during the testing to determine compliance with the requirements. Springs so tested shall be scrapped.

4.4.3 *Air pressure test.* The assembly shall be subjected to an internal air pressure of 10 psig for not less than 3 seconds applied through the detonator well cavity. Observation shall be made for leaks as evidences by a loss of pressure to determine compliance with 3.4.

4.4.4 *Body crimp.* The assembly shall be subjected to a tensile load of 15 pounds applied between the pressure plate and the lower portion of the body. The load shall be applied at such a rate that the pull fixture moves at a speed of ½ to 1 inch per minute. An air pressure shall then be applied and observation made for leaks as specified in 4.4.2 to determine compliance with 3.5.

4.4.5 *Recovery of firing pin assembly.* The lower portion of the body shall be supported securely and the safety fork removed. A load of 134 plus one pounds shall be applied to the assembly at such a rate that the load fixture moves at a rate of ½ to 1 inch per minute and then released. Observation shall be made that the firing pin returns sufficiently that the firing pin point is at least 0.002 inches above the detonator well shoulder to determine compliance with 3.6. If a load sufficient to cause sudden reversal of the firing pin assembly is advertantly applied and the spring snaps through, that assembly shall be replaced with another test sample. Fuzes so tested shall be used in the functioning test (see 4.4.6) or scrapped.

4.4.6 *Functioning.* This test may be performed on the same assemblies as those subjected to the recovery of firing pin assembly test (see 4.4.5). The lower portion of the body shall be supported securely and the safety fork removed. A load shall be applied to the pressure plate at such a rate that the load fixture moves at a rate of ½ to 1 inch per minute. Observation shall be made that the load at which sudden reversal of the spring occurs in 140 pounds minimum, 240 pounds maximum and the average is 170 to 220 pounds for all assemblies tested to determine compliance with 3.7. Assemblies so tested shall be scrapped.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 *Level C.* The parts and assemblies for Fuze, Mine, AT, M603 and Fuze, Mine, AT, Practice, M604 shall be packaged in accordance with Specification MIL–P–10025 in such a manner that no damage will occur during shipment.

5.2 Packing.

5.2.1 *Level C.* The parts and assemblies for Fuze, Mine, AT, M603 and Fuze, Mine, AT, Practice, M604 shall be packed in accordance

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:46Z
Check the source to verify that this is the current version before use.

with Specification MIL-P-10025. Separately designated items shall not be packed together as a single assembly.

5.3 Data cards. Data card information shall be as specified in Specification MIL-A-2550.

5.4 Shipping. When component parts and assemblies from more than one lot are shipped as a carload, each lot must be kept separate and the division between lots clearly indicated to prevent mixing of lots in transit.

5.5 Marking. Marking of the cartons shall comply with Specification MIL-P-10025. Printing shall be in bold type, with black ink on white paper labels.

6. NOTES

6.1 Ordering data. Procurement documents shall specify the following:

(a) Title, number and date of this specification.

6.2 Inspection code numbers. The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor will design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1243-3) the numbers of drawings of existing equipment designs or codes as indicated in 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "contractor design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5, and 6.3.6 will be designated in the Inspection Equipment List by the following codes:

CDOF	—Contractor's design responsibility on Ordnance format; ORDM-608-12.
CDCF	—Contractor's design responsibility on contractor format.
OD	—Ordnance design.
ODMU	—Ordnance design, mandatory for use.
CE	—Commercial equipment.
SCD	—Specification Control Drawing.

6.3.3 *Ordnance designs.* Ordnance designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Ordnance design is listed for an item of inspection equipment. Ordnance designs fall into two basic classifications; mandatory and nonmandatory. When an inspection equipment list references mandatory Ordnance designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with nonmandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawings.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic, or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings.

Source: https://assist.dla.mil - Downloaded: 2026-01-01 11:47
Check the source to verify that this is the current version before use.

These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Design shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and government. Contractors are not required to furnish drawings of commercial inspection equipment but a list of such equipment must be approved by the Government. Lists will be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDOF shall comply with the format and requirements of ORDM-608-12, and, in addition, contain the detail and information specified above.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 A functioning load is that load which requires no further augmentation to continue to deflect the spring until it snaps.

Notice. When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way, be related thereto.

Custodian:
Army—MU

Preparing activity:
Army—MU
Project No. 1345-A112

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:46Z
Check the source to verify that this is the current version before use.