MIL-G-11248A (MU)
7 August 1967
SUPERSEDING
MIL-G-11248 (ORD)
28 June 1951

MILITARY SPECIFICATION

GRENADE, RIFLE, SMOKE, COLORED STREAMER, M23A1, METAL PARTS FOR

1. SCOPE

1.1 This specification covers the inspection of the parts for one type of smoke rifle grenade designated as Grenade, Rifle, Smoke, Colored Streamer, M23A1.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification for
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of

STANDARDS

FEDERAL

FED-STD-151 - Metals; Test Methods

FSC: 1330

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1169 - Packaging, Packing, and Marking for Shipment of Inert Ammunition Components
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U. S. ARMY MUNITIONS COMMAND

82-2-44 - Grenade, Rifle, Smoke, Metal Parts Arrangement and Details
82-2-48 - Stabilizer and Fuze, Grenade, Rifle, Metal Parts Assembly and Details
9216145 - Clip, Launcher Positioning

PUBLICATIONS

U. S. ARMY MUNITIONS COMMAND

IEL - 7298890 - Index of Inspection Equipment

(Copies of specifications, standards, drawings and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

3. REQUIREMENTS

3.1 Material.- The materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Metal parts assemblies.- The metal parts assemblies shall comply with all requirements specified on Drawings (dwgs.) 82-2-44, 82-2-48, and 9216145 as applicable, and with all requirements specified in this and other referenced specifications.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

3.3 Strength of stabilizer tube brazed joint.- The brazed joint of the stabilizer tube and the fuze body shall not crack or show evidence of separation when tested as specified in 4.4.1.

3.4 Strength of stabilizer tube and fin assembly welds.- The spot welds shall leave a button of fin material on the stabilizer tube, which is the thickness of the fin material and has an area at the base of at least one-half the area of the specified weld diameter, when tested as specified in 4.4.2.

3.5 Workmanship.- All parts shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. All required markings shall be neat and sharply defined.

3.6 First article inspection.- This specification makes provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define the terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Submission of product.- At the time of the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

a. A statement that the lot complies with all quality assurance provisions specified within this specification.
b. Number of units of product inspected.
c. Results obtained, by defect code, for all inspections performed.
d. Drawing, specification number and date, together with an identification and date of changes.
e. Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.
f. Number of items in the lot.
g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 Government verification.- Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 First article inspection.

4.2.1 Submission.- The contractor shall submit a first article sample as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2. The first article sample shall consist of 25 assemblies and 25 complete sets of parts (i.e. 25 each of every component and every subassembly) which have been produced by the contractor or furnished by a supplier and which have

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials, (see 4.1.1e). A sample containing known defects will not be submitted unless specifically authorized, by the Contracting Officer. A first article sample, or portion thereof, as directed by the Contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government.

4.2.2 Inspections to be performed.- Assemblies and components will be subjected by the Government to any or all of the examinations or tests specified in 4.3.2 and 4.3.3 of this specification and any or all requirements of the applicable drawings.

4.2.3 Rejection.- If any assembly or component fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component to comply with any of the stated requirements.

4.3 Inspection provisions.

4.3.1 Lot formation.- The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, specification, or revision thereof. Changes to either the process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

Government inspector, shall not be deemed to alter the homogeneity of the lot. Each lot shall contain parts of one kind from one manufacturer.

Inspection lots shall comply with MIL-STD-105 and shall be numbered in accordance with MIL-STD-1168.

Unless otherwise approved by the contracting officer, the inspection lot size of end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period nor more than the largest quantity contractually scheduled for delivery during any month of the contract period. Inspection lots for components or sub-assemblies, other than the items of delivery, shall be homogeneous and of a size convenient to the contractor.

4.3.2 Examination.- Sampling plans and procedures for the following classification of defects shall be in accordance with Standard MIL-STD-105 except that inspection for critical defects, (and Majors, when so specified), shall be 100 percent. Contractor's sampling plans, if used, shall be approved by the Government and shall provide, as a minimum, the protection afforded the Government by the sampling plans in Military Standard MIL-STD-105. Continuous sampling plans in accordance with Standard MIL-STD-1235 for defects other than critical may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each Major defect and an AQL of 0.65 percent for each Minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Body (see dwg. 82-2-48).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Intermediate outside diameter....	Gage	01001
102.	Pitch diameter of thread, minimum (min.).....	Gage	01002
103.	Major diameter of thread, min....	Gage	01003
104.	Diameter of counterbore.....	Gage	01004
105.	Depth of counterbore.....	Gage	01005

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.50 percent		
201.	Length of body	Gage	01006
202.	Flash hole missing or obstructed.	Visual	01007
203.	Evidence of poor workmanship (see 3.5)	Visual	01008

4.3.2.2 Holder, Igniting Charge (see dwg. 82-2-48).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Outside diameter	Gage	02001
Minor:	AQL 1.00 percent		
201.	Length of holder	Gage	02002
202.	Evidence of poor workmanship (see 3.5)	Visual	02003

4.3.2.3 Tube, Stabilizer (see dwg. 9216144 covering a detail of dwg. 82-2-48).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Wall thickness, min	Gage	03001
102.	Inside diameter	Gage	03002
Minor:	AQL 1.50 percent		
201.	Length	Gage	03003
202.	Flared flange missing	Visual	03004
203.	Evidence of poor workmanship (see 3.5)	Visual	03005

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

4.3.2.4 Fin (see dwg. 9216137 covering a detail of dwg. 82-2-48).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Thickness, min.....	Gage	04001
102.	Crack or fracture.....	Visual	04002
103.	Spot weld missing (when applicable).....	Visual	04003
Minor:	AQL 1.50 percent		
201.	Inside diameter, min.....	Gage	04004
202.	Width of ring either side of formed section.....	Gage	04005
203.	Total length.....	Gage	04006
204.	Evidence of poor workmanship (see 3.5).....	Visual	04007

4.3.2.5 Baffle, Stabilizer Tube (see dwg. 82-2-48).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Thickness of baffle at bottom of slot, max.....	Gage	05001
Minor:	AQL 1.50 percent		
201.	Location of flash holes.....	Gage	05002
202.	Width of slot.....	Gage	05003
203.	Flash holes obstructed.....	Visual	05004
204.	Evidence of poor workmanship (see 3.5).....	Visual	05005

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

4.3.2.6 Stabilizer Assembly (see 82-2-48).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Inside diameter of tube (functional)	Gage	06001
102.	Outside diameter of fin	Gage	06002
103.	Crimp missing or length insufficient	Visual	06003
104.	Sealing disc missing or improperly installed	Visual	06004
105.	Spot weld missing	Manual	06005
Minor:	AQL 1.50 percent		
201.	Total length	Gage	06006
202.	Marking missing or improper	Visual	06007
203.	Evidence of poor workmanship (see 3.5)	Visual	06008

4.3.2.7 Body (see dwg. 82-2-44).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Inside diameter of flange	Gage	07001
102.	Inside diameter of forward hole	Gage	07002
Minor:	AQL 1.50 percent		
201.	Length of body to flange	Gage	07003
202.	Wall thickness	Gage	07004
203.	Evidence of poor workmanship (see 3.5)	Visual	07005

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

4.3.2.8 Union, Body (see dwg. 82-2-44).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Pitch diameter of thread.....	Gage	08001
102.	Outside diameter of flange.....	Gage	08002
Minor:	AQL 2.50 percent		
201.	Total length.....	Gage	08003
202.	Outside diameter of neck.....	Gage	08004
203.	Minor diameter of thread, max....	Gage	08005
204.	Perpendicularity of flange face with pitch diameter of thread including parallelism.....	Gage	08006
205.	Presence of smoke vents.....	Visual	08007
206.	Evidence of poor workmanship (see 3.5).....	Visual	08008

4.3.2.9 Clip, Launcher Positioning (see dwg. 9216145).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Clip failure, functional.....	Gage	09001
Minor:	AQL 1.50 percent		
201.	Length after forming, max.....	Gage	09002
202.	Width.....	Gage	09003
203.	Evidence of poor workmanship (see 3.5).....	Visual	09004

4.3.3 Testing.

4.3.3.1 Strength of stabilizer tube brazed joint.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

4.3.3.1.1 1000 pound load test (see 3.3) - Major defect - Code No. 10001.- This test shall be performed one hundred percent. Any brazed joint which shows evidence of failure shall cause the assembly to be classed defective. The test shall be performed as specified in 4.4.1.1 using equipment in accordance with 4.3.4.

4.3.3.1.2 7500 pound load test (see 3.3) - Major defect - Code No. 10002.- The sampling plan for this test shall be in accordance with Standard MIL-STD-105 using code letter G and an AQL of 0.40 percent. Any stabilizer tube assembly which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.4.1.2 using equipment in accordance with 4.3.4.

4.3.3.2 Strength of stabilizer tube and fin assembly welds (see 3.4) - Major defect - Code No. 06008.

4.3.3.2.1 Beginning with the first lot produced and continuing until three (3) consecutive lots have been found to be acceptable, eighty (80) assemblies shall be selected from each lot for test. If two (2) or more assemblies show evidence of failure, the lot shall be rejected. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4.

4.3.3.2.2 After three (3) consecutive lots have complied with the criteria of 4.3.3.2.1, the sampling plan for this test shall be in accordance with Standard MIL-STD-105 using code letter G and an AQL of 0.40 percent. Any stabilizer tube and fin assembly spot weld which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4.

4.3.3.3 Hydrostatic test of stabilizer tube (see dwg. 9216144) - Major Defect - Code No. 03006.- This test shall be performed 100 percent (see 6.4). If any stabilizer tubing fails to comply with the applicable requirement, it shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.3 using equipment in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

4.3.3.4 Hardness of launcher positioning clip (see dwg. 9216145) - Major defect.- Code No. 09005.- Twenty (20) launcher positioning clips shall be selected from each heat treated batch for test. If any clip fails to comply with the applicable requirement, the heat treated batch represented by the sample shall be rejected. The test shall be performed as specified in 4.4.4 using equipment in accordance with 4.3.4.

4.3.4 Inspection Equipment.- Index of Inspection Equipment Number IEL -7298890 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 Government rights to documentation.- Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 Supply and maintenance.- Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL-I-45607.

4.3.4.3 Government use of contractor's inspection equipment.- The contractor shall make available to the Government all inspection equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

4.4 Test methods and procedures.

4.4.1 Strength of stabilizer tube brazed joint.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

4.4.1.1 1000 pound load test.- The brazed joint of the stabilizer tube assembly shall be tested by applying a load of 1000 pounds, minimum, to the inside of the brazed joint. The load shall be applied in a direction parallel to the axis of the tube at the rate of from 0.100 to 0.125 inch per minute, inclusive. Observation shall be made to determine compliance with the applicable requirement. Test equipment shall be in accordance with 4.3.4.

4.4.1.2 7500 pound load test.- The stabilizer tube assembly shall be tested by applying a load in a direction parallel to the axis of the tube sufficient to cause failure in tension of the tube, or a load of 7,500 pounds (whichever is reached first). The load shall be applied at a rate of 0.100 to 0.125 inch per minute, inclusive. The sides of the tube may be flattened, if necessary, for attachment to the testing machine. Observation shall be made to determine compliance with the applicable requirement. Test equipment shall be as specified in 4.3.4.

4.4.2 Strength of stabilizer tube and fin assembly welds.- The spot welded assemblies shall be pulled apart utilizing equipment in accordance with 4.3.4. Observation shall be made to determine compliance with the applicable requirement.

4.4.3 Hydrostatic test of stabilizer tube. Prior to machining, the stabilizer tubing shall be tested for not less than five (5) seconds at the minimum hydrostatic pressure as specified on the drawing. Observation shall be made for rupture, indication of flaws as evidenced by leaks, and for permanent deformation beyond the drawing requirements. Test equipment shall be as specified in 4.3.4.

4.4.4 Hardness of launcher positioning clip.- The launcher positioning clip shall be tested for hardness as specified in Federal Standard No. 151, Method 243.

5. PREPARATION FOR DELIVERY

5.1 Packaging, packing and marking.- Packaging, packing and marking shall be in accordance with Standard MIL-STD-1169.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Ordering data.- Procurement documents should specify the following:

a. Title, number and date of this specification.

b. Ammunition data cards shall be prepared for each lot in accordance with Standard MIL-STD-1167.

c. Submission of first article quantity.- Instructions as to the location of the facility at which the evaluation of the first article quantity shall be carried out, may be obtained from the contracting officer.

6.2 Inspection code numbers.- The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.- The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 Inspection equipment lists.- Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (OO Form 1242-3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Two copies of the designs shall be submitted for approval as specified in 6.3.7.

6.3.2 Inspection equipment list codes.- The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designated in the IEL by the following codes:

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

CDAF - Contractor's design responsibility on Army format in accordance with MIL-D-45608.
CDCF - Contractor's design responsibility on contractor format.
AD - Army design.
ADMU - Army design, mandatory for use.
CE - Commercial equipment.
SCD - Specification control drawing.

6.3.3 Army designs.- Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 Specification control drawing.- Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagramatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

6.3.5 Commercial equipment.- Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 Contractor designs.- Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspectior equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL-D-45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electrostatic full size prints of top quality with black lines on white background, and shall provide a legible print produced via the 35MM microfilm process. The contractor shall submit one rolled or flat set copy of the final approved design.

6.3.7 Submission of contractor designs.- Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.

6.4 Hydrostatic test.- If the stabilizer tubing procured under the specification has been previously subjected to the hydrostatic test specified in this specification, a second hydrostatic test will not be required.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project No. 1330-A-074

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:47Z
Check the source to verify that this is the current version before use.