MIL-U-43263E
5 May 1986
SUPERSEDING
MIL-U-43263D
1 December 1976

MILITARY SPECIFICATION

URNS, COFFEE, TWIN AND SINGLE, AUTOMATIC (ELECTRIC, STEAM, AND GAS)

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This document covers automatic twin coffee urns for installation under a counter and twin and single urns for installation on a countertop or stand.

1.2 Classification. Twin or single coffee urns covered herein shall be of the following styles, sizes, types, and classes as specified (see 6.2):

Style 1 - Under-counter (countertop dispensing)

- Size 1 - 3-gallon capacity each compartment
- Size 2 - 6-gallon capacity each compartment
- Type I - Electric heated
- Type II - Steam heated
- Class 1 - Caster mounted
- Class 2 - Leg mounted

Style 2 - Counter or stand mounted (twin or single urns)

- Size 1 - 3-gallon capacity each compartment
- Size 2 - 6-gallon capacity each compartment
- Size 3 - 8-gallon capacity (single only)

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to U.S. Army Natick Research, Development, and Engineering Center, Natick, MA 01760-5014, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 7310

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:02Z
Check the source to verify that this is the current version before use.

Size 4 - 4-gallon capacity each compartment
Size 5 - 2-gallon capacity (single only)
Type I - Electric heated
Type II - Steam heated
Type III - Gas heated (not applicable to single units)

2. APPLICABLE DOCUMENTS

* 2.1 Government documents. Unless otherwise specified, the following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this document to the extent specified herein.

SPECIFICATIONS

FEDERAL

FF-C-77	- Casters, Rigid and Swivel (Institutional Duty)
QQ-C-320	- Chromium Plating (Electrodeposited)
CCC-C-446	- Cloth, Muslin, Cotton
PPP-B-591	- Boxes, Shipping, Fiberboard, Wood-Cleated
PPP-B-601	- Boxes, Wood, Cleated-Plywood
PPP-B-636	- Boxes, Shipping, Fiberboard
PPP-T-60	- Tape: Packaging, Waterproof

MILITARY

MIL-M-14	- Molding Plastics and Molded Plastic Parts, Thermosetting

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	- Marking for Shipment and Storage
MIL-STD-130	- Identification Marking of US Military Property

(Copies of documents required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

* 2.2 Other publications. Unless otherwise specified, the following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this document to the extent specified herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

AMERICAN GAS ASSOCIATION (AGA)

Directory of Certified Appliances and Accessories

(Application for copies should be addressed to the American Gas Association Laboratories, 8501 East Pleasant Valley Road, Cleveland, OH 44131.)

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

Standard Z83.14 - American National Standards for Gas Counter Appliances

(Application for copies should be addressed to the American National Standards Institute, 1430 Broadway, New York, NY 10018; or the American Gas Association Laboratories, 8501 East Pleasant Valley Road, Cleveland, OH 44131.)

NATIONAL BUREAU OF STANDARDS

Simplified Practice Recommendation R231-48 - Coffee Grinds

(Application for copies should be addressed to National Coffee Association, 120 Wall Street, New York, NY 10005.)

PAN AMERICAN COFFEE BUREAU (PACB)

Publication No. 15 - Coffee Brewing Control Chart
Publication No. 27 - Coffee Solubles and Beverage Acceptance
Publication No. 43 - The Coffee Hydrometer
Publication No. 61 - The Direct Reading Coffee Hydrometer

(Copies may be obtained from the National Coffee Association, 120 Wall Street, New York, NY 10005.)

NATIONAL SANITATION FOUNDATION (NSF)

Standard No. 2 - Food Service Equipment
Standard No. 4 - Commercial Cooking and Hot Food Storage Equipment

Listing of Food Service Equipment

(Application for copies should be addressed to the National Sanitation Foundation, NSF Building, Ann Arbor, MI 48105.)

Source: https://assist.dla.mil -- Downloaded: 20260-21T21:02Z
Check the source to verify that this is the current version before use.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A 167	- Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
D 1457-TFE	- Fluorocarbon Resin Molding and Extrusion Materials
D 3951	- Standard Practice for Commercial Packaging

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

UNDERWRITERS LABORATORIES INC. (UL)

UL 197 - Commercial Electric Cooking Appliances

(Application for copies should be addressed to the Underwriters Laboratories, Inc., 333 Pfingston Rd., Northbrook, IL 60062; 1285 Walt Whitman Road, Melville, Long Island, NY 11746; 1655 Scott Blvd., Santa Clara, CA 95050; or 2602 Tampa East Blvd., Tampa, FL 33619.)

NATIONAL ELECTRICAL MANUFACTURERS' ASSOCIATION (NEMA)

ICS-1-1983 - Industrial Controls and Systems

(Application for copies should be addressed to the National Electrical Manufacturers' Association, 155 East 44th Street, New York, NY 10017.)

(Technical society and technical association documents are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

* 2.3 Order of precedence. In the event of conflict between the text of this document and the references cited herein (except for associated detail specifications, specification sheets, or MS standards), the text of this document shall take precedence. Nothing in this document, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Standard product. The coffee urns shall, as a minimum, be in accordance with the requirements of this document and shall be the manufacturer's standard commercial product with any added features needed to comply with the requirements of this document. Modifications to add features shall not incorporate different parts unless such parts are used on other

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

current commercial models. Standard or modified commercial products furnished in accordance with this document shall be identifiable by all regular manufacturer's or commercial service organizations servicing the brand involved. Service organizations shall be capable of providing complete parts and repair services on models furnished to the Government consistent with their normal commercial practices.

3.2 Codes and standards. The coffee urns shall comply with the applicable requirements of NSF Standard No. 4, UL 197, and ANSI Z83.14, as applicable. The urn stands shall comply with the applicable requirements of NSF Standards Nos. 2 and 4 (see 4.1.1.2.1, 4.1.1.2.2, and 4.1.1.2.3).

* 3.3 Materials and components. Materials and components shall be as specified herein. Materials not definitely specified shall be of the quality normally used by the manufacturer for coffee urns and stands, provided the finished item complies with all provisions of this document. Recycled material may be used (see 6.4).

3.3.1 Stainless steel. Stainless steel shall conform to any steel in the 300 series specified in ASTM A 167.

3.3.2 Plastic. Plastic for handles and knobs shall be black conforming to type CFI-5 of MIL-M-14. Plastic materials for fabricating dispensing lines for style 1 urns shall be type III, class 1 or 2 of ASTM D 1457.

* 3.3.3 Paper. Paper for leacher filters shall be of the quality normally used by the manufacturer provided that it meets all the provisions of this document.

3.3.4 Muslin. Muslin for leacher bags shall conform to type II of CCC-C-446.

3.4 Design. The coffee urns shall be electrically, steam, or gas heated, as applicable, and shall automatically brew coffee by push button control. The urns shall perform the following operations automatically: heat water, spray a measured amount of water over ground coffee, refill the water compartment, maintain brewed coffee temperature, and deliver brewed coffee and hot water to faucets. Urns shall automatically brew one-half compartment capacity when tested as specified in 4.4.1(i). Urns shall be provided with a separate leacher or adapter if required for brewing half batches. All urns shall have a nonpressurized water compartment. Unless otherwise specified (see 6.2 and 6.6), electric characteristics shall be as follows:

a. Type I - 120/208 volt, 3 phase, 4 wire convertible to 120/208 volt, single phase, 3 wire by means of jumpers provided with the urn.

b. Types II and III - 120 volts, 60 hertz (Hz), 1-phase system.

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:02Z
Check the source to verify that this is the currentversion before use.

All urns shall be electrically grounded. When intended for shipboard use (see 6.2), the urns shall be designed so that, when filled with the specified amount of brew, the brew will not spill or come in contact with the leacher when tilted at a 15 degree angle (see 4.4.3).

3.4.1 Dispensing.

3.4.1.1 Style 1. Unless otherwise specified (see 6.2), the style 1 urns shall be provided with one coffee faucet and one hot water faucet for countertop use, and one coffee faucet per coffee compartment and one hot water faucet at the urn body. Coffee and hot water for tea shall be fed to the countertop faucets through flexible lines by means of pumps. Coffee and hot water faucets at the urn body shall be gravity fed.

3.4.1.2 Style 2. Style 2 urns shall be provided with one coffee faucet per coffee compartment and one water faucet. The faucets shall be located on the attendant's side. Coffee faucets shall be gravity fed and hot water faucets shall be gravity fed or tap water pressure fed. When specified (see 6.2), each coffee compartment of style 2 urns, except single urns, shall have two coffee faucets, one on the attendant's side and one on the service side; and two water faucets, one on the attendant's side and one on the service side.

3.4.2 Dimensions.

3.4.2.1 Style 1. The style 1 urns shall be not greater than 45 inches wide by 28 inches deep by 33 1/2 inches high.

3.4.2.2 Style 2. The style 2 twin urns shall be not greater than 43 inches wide by 22 inches deep by 40 inches high. Style 2 single urns shall be not greater than 27 inches wide by 18 inches deep by 40 inches high. When faucets are supplied on both sides of the urn, the depth shall be not less than 26 1/2 inches.

3.4.3 Coffee brewing. Coffee brewing components shall consist of two coffee compartments or one coffee compartment, as applicable; one water-heating compartment; and either a spray-over pump or a heat-exchanger using water-supply pressure instead of a pump to spray hot water over a leacher containing ground coffee. Spray-over temperature of the water shall be not less than 195°F nor more than 210°F when tested as specified in 4.4.1(b). The spray-over device and connecting piping shall be capable of delivering the required volume of water to accomplish brewing in 6 minutes maximum when urn-grind coffee (also termed drip or universal grind) is used, and 13 minutes maximum if regular grind coffee is used when the urn is tested as specified in 4.4.1(c). Urns may be furnished with a spray-water bypass. When tested as specified in 4.4.2, the solids in the brewed coffee shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

not less than 1.15 percent nor more than 1.32 percent of the total weight of the brew in each compartment. The coffee urn shall maintain the brewed coffee at a temperature of 180° to 190°F for a minimum of one hour when tested as specified in 4.4.1(f).

3.4.4 Initial heat-up and recovery. Initial heat-up time shall be not more than 50 minutes for all urns when tested as specified in 4.4.1(a). Recovery time between brews shall be not more than 15 minutes for urns when tested as specified in 4.4.1(a). The temperature of the incoming water supply to gas urns with a total capacity of more than 6 gallons shall be 160°F minimum and for all other urns shall be 70°F minimum, when tested as specified in 4.4.1.

3.5 Construction. The coffee urn shall conform to the construction requirements specified herein. When tested as specified in 4.4.1(g), the coffee compartments, water compartment, faucets, and all joints, piping, and fittings shall not leak. All exposed metal fittings and hardware shall be stainless steel or brass with chrome-nickel plating.

3.5.1 Outer shell. The outer shell shall be fabricated of stainless steel specified in 3.3.1, either 18 gage (0.048 inch) or 20 gage (0.036 inch) as required (see 3.5.4). Finish shall be as specified in 3.8.1.

3.5.2 Coffee compartments. When tested as specified in 4.4.1(h), the coffee compartments shall have capacities as specified in 1.2 for the size of urn specified. The compartments shall be formed of minimum 20 gage (0.036 inch) thick stainless steel specified in 3.3.1. The compartments shall be die-drawn from a single piece of material or fabricated by welding. Each compartment shall be provided with gravity-fed faucets as specified in the applicable subparagraph of 3.4.1 and an outlet to the countertop coffee faucets for style 1 urns. A cover fabricated of minimum 20 gage (0.036 inch) thick stainless steel shall be provided for each coffee compartment. Covers shall be provided with a handle of the plastic specified in 3.3.2. The coffee faucets attached to the compartments shall be located to provide complete drainage of the compartments, as verified by the test specified in 4.4.1(h).

3.5.3 Leacher assembly. A stainless steel leacher assembly shall be furnished with each coffee urn. The leacher shall be sized so that, when using 7.1 ounces of drip-grind coffee per gallon of water, the depth of coffee shall be not more than 2 inches nor less than 1 inch when spread uniformly in the filter bag at the bottom of the leacher (see 4.4.2). The diameter and depth of the leacher shall be such that no overflowing will occur during the normal spraying cycle, which shall be verified during the test specified in 4.4.2.

Source: https://assist.dla.mil -- Downloaded: 202640-21T21:02Z
Check the source to verify that this is the current version before use.

* 3.5.3.1 Leacher filters. Unless permanent metal filters or paper filters are specified (see 6.2), each urn shall be furnished with 25 muslin leacher bags (see 3.3.4) to fit the leacher and 1 stainless steel bag ring to be used with muslin leacher bags. For Navy use, paper filters are required (see 3.3.3).

3.5.4 Water compartment. The water compartment shall be fabricated of minimum 18 gage (0.048 inch) thick stainless steel or minimum 21 gage (0.034 inch) thick copper. The outer wall of the stainless steel water compartment may be utilized as the outer shell. When a copper water tank is provided, the tank shall be enclosed by a minimum 20 gage (0.036 inch) thick stainless steel outer shell. The exposed water contact surfaces of the copper water tank shall be plated to comply with NSF requirements. The compartment shall be sized for the heating element or steam coil, as applicable, and not less than 4 gallons of available hot water for size 5 urn, not less than 8 gallons for size 1 urn, not less than 12 gallons for size 2 urn, not less than 16 gallons for size 3 urn, and not less than 10 gallons for size 4 urn. The compartment shall be provided with an electric heating element (type I) or steam coil (type II), water gage (see 3.5.4.1), low water cutoff (type I and III), a 3/8-inch or 1/2-inch water inlet with strainer, and an outlet to the hot water dispensing pump for style 1 urns. A means for complete drainage and cleaning of the water compartment shall be provided. Unless otherwise specified (see 6.2), style 1 urns shall be provided with at least 5 feet of flexible tubing or hose and necessary service connections for use with water.

3.5.4.1 Gage glasses. The water compartment and each coffee compartment shall be furnished with a sight glass to show liquid level in each compartment. The gage glasses shall be attached to the faucet shanks on the attendant's side. Glasses shall be provided with a stainless steel, chromium-plated brass, or anodized aluminum guard.

3.5.4.2 Low water protection. The water compartment shall be provided with a low water cutoff for protecting the water compartment and heating element for type I urns and water compartment for type III urns. The cutoff shall be positioned and adjusted to maintain a water level in the compartment of type I and type III urns to prevent burn-out. When tested as specified in 4.4.1(d), the cutoff shall shut off the electric supply to the heating element for type I urns when the water level drops to within 1 1/2 inches of the top of the immersion electric heaters or shut off the gas supply for type III urns when the water level drops to within 3 inches of the bottom of the water compartment. The cutoff shall be an electric-probe-type or float-type that is not affected by water turbulence.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

3.5.5 Spray-head and piping. When a spray-head is furnished, the coffee urn shall be provided with two individual spray-heads or one swivel-type spray-head. Spray-heads shall be chrome-plated brass or stainless steel. The spray-heads shall evenly distribute water over the ground coffee without overspraying or pocketing. Piping or tubing from the water compartment to the spray-heads shall be stainless steel, or copper, or brass plated to comply with NSF requirements.

3.5.6 Type I urns. The heating element(s) for the water compartment shall be an immersion type and shall be removable for replacement or servicing. Heating element(s) shall be provided with a stainless steel sheath welded to a stainless steel screw plug, or copper-sheathed heaters with the tubing brazed to a bronze plug or mounting boss. Terminals shall be sealed with a moisture barrier sealing material. The heater terminals shall be enclosed in a removable box. A toggle switch or push button shall be provided for complete cutoff of all electrical components and for energizing the entire electrical system. Individual push buttons to control automatic brewing for each coffee compartment shall be provided if two individual spray heads are provided. A signal light shall be provided to indicate which coffee compartment is dispensing. Signal lights to indicate when individual pumps for style 1 urns are energized may be provided if they are furnished on the manufacturer's standard product. The push buttons, indicators, and signals shall be readily accessible for servicing and visible to the attendant. Other electrical controls necessary for safe and efficient operation of the urn shall be provided. All terminal connections and wiring to switches shall be such that repairs can be made without disassembly of switch structure or other components. Electric cord or cable on style 1 urns shall be provided with a metal clamp-like strain-relief connector and shall be at least 8 feet long to allow the urn to be moved from under the counter without disconnection.

3.5.6.1 Thermostat. The water temperature shall be thermostatically controlled. The thermostat shall have an operating range of 175° to 220°F. Variations from the thermostat settings shall not vary more than plus or minus 5°F when tested as specified in 4.4.1(b).

3.5.6.2 Contactor. The type I urn shall be provided with a 3 or 4 pole magnetic contactor for operation within the specified voltage range. The contactor shall conform to the requirements of NEMA ICS-1-1983.

* 3.5.6.3 Wiring diagram. A wiring diagram showing all electrical connections between components and terminal location shall be securely attached to the urn in a readily visible location.

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:02Z
Check the source to verify that this is the current version before use.

3.5.7 Type II urns.

* 3.5.7.1 Steam coil. The steam coil shall be of one continuous piece and of sufficient size and length to heat the necessary volume of water. The coil shall be copper tubing rated for at least 100 pounds per square inch (psig) steam working pressure, and the coils shall be spaced to allow for maximum circulation of water around the coil. Operating steam pressure shall be a minimum of 10 psig to a maximum of 15 psig. When tested as specified in 4.2.2.2, the coil shall not leak.

3.5.7.2 Steam trap. A steam trap, of the type normally furnished by the manufacturer on his standard product, shall be supplied with each steam-heated coffee urn.

3.5.7.3 Thermostat. Each steam-heated urn shall be equipped with a steam thermostat of the throttle or snap-action type (capillary bulb). The thermostat shall be designed to automatically control the steam supply as temperature variations occur within the water compartment. The thermostat shall be so installed that the sensing tube does not come in contact with the heating coils. The thermostat shall have an operating range of 175° to 220°F. Variations from the thermostat setting shall not exceed plus or minus 5°F when tested as specified in 4.4.1(b).

3.5.7.4 Steam hose. Style 1, type II urns shall be provided with at least 5 feet of flexible hose and necessary service connections for steam supply and condensate return lines. Steam hose suitable for a working pressure of 50 psig shall be butyl rubber or teflon protected by a flexible, braided stainless steel cover. A strainer shall be provided in the steam line between the hose and the valve.

3.5.8 Type III urns.

3.5.8.1 Fuel system. The fuel system shall be designed to burn natural gas and liquified petroleum gas. Pilot gas-valves shall be of the fixed-orifice type with interchangeable orifice hoods or bushings. Fixed-orifice type with interchangeable hoods or bushings may be located at the burner or at the burner gas valve. Each burner valve shall be provided with two orifice hoods or bushings, one drilled for natural gas and the other drilled for liquified petroleum gas. The manufacturer shall provide instructions for conversion from one type of gas to the other. The valve hoods or bushings shall be color-coded as follows:

a. natural gas - unpainted brass, and
b. liquified petroleum gas - black.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

3.5.8.2 Thermostat. The water temperature shall be thermostatically controlled. The thermostat shall have an operating range of 175° to 220°F. Variations from the thermostat setting shall not exceed plus or minus 5°F when tested as specified in 4.4.1(b).

3.5.8.3 Solenoid valve. A solenoid gas valve, wired for automatic restart, shall be installed in the electrical circuit of the low-water cutoff.

3.5.8.4 Automatic pilot. An automatic pilot shall be provided, equipped with an automatic safety shutoff device to interrupt the flow of gas to both the main burner and the pilot, in the event the source of ignition fails.

3.5.9 Faucets. Coffee urns shall be provided with faucets in accordance with the applicable subparagraph of 3.4.1. Faucets shall be antisplash, self-closing type with replaceable seat cups or washers, and shall be suitable for temperatures up to 220°F. The faucets shall be provided with wing nut shanks to allow removal of the delivery tube system without the use of tools for cleaning, or the faucet may be provided with a direct cleanout feature to permit the cleanout brush specified in 3.5.13 to be inserted through the faucet. Faucets shall be constructed to enable complete disassembly for cleaning and replacement without the use of tools and shall be chrome-plated brass as specified in 3.8.2 with handles of non-heat-absorbing plastic. Clearance between countertop and bottom of faucets on style 1 urns shall be not less than 6 1/4 inches nor more than 8 inches. Clearance between bottom of compartment faucets and drip trough splash cover on the style 1 urns shall be not less than 5 1/8 inches nor more than 9 3/8 inches, and on the style 2 urns shall be not less than 11 inches nor more than 13 1/4 inches.

3.5.10 Drip trough. A stainless steel drip trough with a removable antisplash cover shall be furnished on style 1 urns. The drip trough for style 1 urns shall be secured to the outer shell. The drip trough shall be centered directly below the compartment coffee and water faucets and shall be designed for complete drainage with a drain suitable for connection to drainage piping. The distance between the bottom of the faucets and the top of the splash cover shall be as specified in 3.5.9.

3.5.11 Dispensing system. Coffee compartments and the water compartments on style 1 urns shall be provided with sanitary pumps to raise the brewed coffee and hot water under pressure to the dispensing faucets. The pumps shall provide sufficient liquid under pressure to the dispensing faucets. The pumps shall provide sufficient liquid under pressure to fill a 5-ounce cup in not more than 6 seconds without excessive splashing when tested as specified in 4.4.1(e). Pumps shall be suitable for operation with the specified electrical characteristics. Feed lines and return lines between the pumps and dispensing faucets shall be nontoxic plastic tubing fabricated from the plastic specified in 3.3.2 and approved by NSF. Plastic tubes shall be

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:02Z
Check the source to verify that this is the current version before use.

protected with a flexible, braided, stainless steel covering. Feed and return lines shall be arranged so that coffee and hot water are recirculated between the compartments and the dispensing faucets to maintain proper liquid temperature. Unless otherwise specified (see 6.2), the length of dispensing lines shall be 8 feet. Where applicable, a hand operated selector valve or motor operated selector valve shall be furnished to select right or left compartments for the dispensing faucet. The motor operated valve shall have a selector switch and a pilot light to indicate when the urn is in use.

3.5.12 Method of mounting urn.

3.5.12.1 Style 1 urns. Style 1, class 1 urns shall be mounted on four casters and service connections shall be flexible. Style 1, class 2 urns shall be mounted on four adjustable legs.

* 3.5.12.2 Casters. Casters shall conform to the requirements of type I, rigid type or type II, swivel type, class A, wheel diameter - 3 inches minimum, style 3, mounting optional of FF-C-77. Type II casters shall be provided with brakes.

3.5.12.3 Legs. When legs are required, an adjustable stainless steel leg assembly shall be provided on each corner of the style 1 urns. The legs shall be secured to the urn frame or body and shall have a minimum adjustment of 1/2 inch.

3.5.12.4 Style 2 urns. The style 2 urns shall be suitable for mounting either on a countertop or, when specified (see 6.2), furnished with the stand described in 3.5.12.5. The urn shall be provided with four legs conforming to 3.5.12.3. When specified for shipboard use (see 6.2), legs shall be provided with hold-down means. When specified (see 6.2), the stand shall be furnished with tray rails and with key slots for vertical adjustment of the rails.

3.5.12.5 Urn stand. The urn stand for style 2 twin urns shall be 48 inches wide by 36 inches deep and 34 inches high. The stand for single urns shall be 30 inches wide by 28 inches deep and 34 inches high. The stand shall be constructed of carbon steel angles welded to form a rigid base for the urn and shall be enclosed by a minimum 20 gage (0.0375 inch) thick stainless steel skin. The top shall have a 3/8-inch minimum raised edge on all four sides. A drip trough specified in 3.5.10 shall be provided for style 2 urns and shall be built into the stand. The stand shall be furnished with a bottom steel shelf with two doors on the attendant's side and shall be equipped with four stainless steel or chrome-plated brass adjustable bullet-shaped feet. The sink shall be provided with a water inlet connection and a standing water overflow.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

3.5.13 Cleaning brush. A flexible brush suitable for cleaning faucets, pipes, shank connections, and gage glasses shall be furnished with each urn.

3.5.14 Handles and knobs. All handles and knobs subject to a temperature of 120°F or more shall be formed of plastic specified in 3.3.2.

3.6 Repair and maintenance. The coffee urn shall be constructed to allow for ready inspection, adjustment, service, and replacement of controls, plumbing fixtures, fittings, and electrical apparatus without requiring disassembly of any components other than panels or access covers.

3.7 Data name plate. The coffee urn shall be furnished with a data name plate in accordance with the applicable requirements of MIL-STD-130 except the requirements for; (a) Methods of applying, (b) Identification tags, (c) Information not required, and (d) Optional marking information shall not apply. The data name plate shall be made of minimum 20 gauge corrosion resisting metal, and attached to coffee urn by rivets, screws, or by welding, in such a manner as to meet the applicable National Sanitation Foundation requirements for this equipment. The plate shall bear the following information which shall be stamped, engraved, or applied by photosensitive means:

National Stock Number
Procurement Instrument Identification Number
Specification Data
Manufacturer's Name, Address, and Telephone Number
Supplier's Name, Address, and Telephone Number (List only if different from Manufacturer)
Manufacturer's Model Number
Government Approved Manual Number (see 6.2)

Each plate shall be placed so as to be readily visible to the operator during normal operation and use, and so as to not adversely affect the life or utility of the coffee urn.

3.8 Finish. All burrs, slivers, and sharp edges shall be removed.

3.8.1 Stainless. All exposed stainless steel surfaces of the complete coffee urn assembly shall have a No. 4 or better standard commercial polish and shall be free of scratches, discoloration, stains, pits, or scales. Surfaces of the coffee containers in contact with brewed coffee shall have a No. 8 mirror finish or electropolish finish.

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:02Z
Check the source to verify that this is the current version before use.

3.8.2 Plating. Exterior hardware, piping, fittings, spouts, and valves not fabricated of stainless steel shall be chrome plated conforming to class 1, type 1 of QQ-C-320, with a nickel-copper undercoating.

3.9 Workmanship. All components and assemblies of the urn shall be free from dirt and other harmful extraneous material, burrs, slivers, rough die, tool and grind marks, dents, and cracks. Castings, molded parts, and stampings, if used, shall be free of sand, fins, pits, blow holes, and sprues. External surfaces shall be free from sharp edges and sharp corners, except when corners are required. No component shall be fractured, buckled, warped, loose, dented, punctured, or malformed.

3.9.1 Metal fabrication. Metal used in the fabrication of the urn shall be free from kinks. Forming and shearing shall not cause damage to the metal and shall be free of trim marks.

3.9.2 Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, and other foreign matter. Welds shall be smooth and free of cracks, burn holes, undercuts, or incompleted fusion. All scale and flux shall be removed from the finish weld area.

3.9.3 Fastening devices. Threaded fastener and rivet holes shall have burrs removed. Threaded fasteners shall not be missing, broken, cracked, or stripped, and shall be drawn tight. Rivets shall fill the hole completely, and the heads shall be in full contact with the surface of the member and concentric with the hole. Spring clips, when required, shall not be missing.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable under the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the document where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

* 4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this document shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the document shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.1.2 Compliance. Prior to commencing production, the contractor shall submit to the contracting officer, or his authorized representative, satisfactory evidence that the coffee urns and stands he proposes to furnish under this document meet the applicable requirements of ANSI, NSF, and UL as indicated in 4.1.1.2.1, 4.1.1.2.2, and 4.1.1.2.3.

4.1.1.2.1 UL. Acceptable evidence of meeting the applicable requirements of UL standards shall be the UL label, the UL listing mark, or a certified test report from a recognized independent testing laboratory, acceptable to the Government, indicating that the offered electric urns have been tested and conform to the applicable requirements of UL 197.

4.1.1.2.2 NSF. Acceptable evidence of meeting the requirements of NSF shall be one of the following:

a. A listing in the current edition of the NSF "Listing of Food Service Equipment" and display of the NSF seal on the finished urn and stand.

b. A certification for the urn and urn stand issued by NSF under their special one-time contract evaluation/certification service.

c. A certified test report from a recognized independent testing laboratory acceptable to the medical department of the service for which the urn stand and urn are being procured indicating that the urn stand and urn have been tested and conform to NSF Standards Nos. 2 and 4, respectively.

4.1.1.2.3 ANSI. Acceptable evidence of meeting the applicable requirements of ANSI Standard Z83.14 shall be a reproduced copy of the AGA Appliance Certificate; a listing of the urn in the AGA Directory of Certified Appliances and Accessories; or a certified test report from a recognized, independent testing laboratory acceptable to the Government stating that the urns have been tested and conform to ANSI Z83.14.

Source: https://assist.dla.mil -- Downloaded: 202640-21T21:02Z
Check the source to verify that this is the currentversion before use.

4.2 Quality conformance inspection. Unless otherwise specified, sampling for inspection shall be performed in accordance with MIL-STD-105.

4.2.1 Component and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents unless otherwise excluded, amended, modified, or qualified in this document or applicable purchase document.

4.2.2 In-process inspection. Inspection of sub-assemblies shall be made to ascertain that construction details which cannot be examined in the finished product are in accordance with specified requirements. The Government reserves the right to exclude from consideration for acceptance, any material or service for which in-process inspection has indicated nonconformance.

4.2.2.1 In-process visual examination. Plated exposed surfaces and food contact surfaces shall be examined as follows:

a. Exposed water-food surfaces of the copper water tank shall be plated, when applicable (see 3.5.4).

b. Exposed food contact surfaces of hot water copper coil, when provided, shall be plated to comply with NSF requirements.

4.2.2.2 In-process testing of steam and water coil. Tests shall be made to determine compliance with the following requirements:

a. The steam coil on type II urns shall be hydrostatically tested with 100 psig air pressure with the coil submerged in water. The pressure shall be held for a period of 15 minutes and the coil examined for leaks in accordance with 3.5.7.1. Failure of the test shall be cause for rejection of the steam coil.

b. The water coil, when applicable, shall be hydrostatically tested with 60 psig air pressure with the coil submerged in water. The pressure shall be held for a period of 15 minutes and examined for leaks. Failure of the test shall be cause for rejection of the hot water coil.

* 4.2.3 End item visual inspection. The end item shall be examined for the defects listed in table I. The lot size shall be expressed in units of coffee urns of one style, size, type (and class, if applicable). The sample unit shall be one completely fabricated coffee urn and urn stand, as applicable. The inspection level shall be II and the acceptable quality level (AQL), expressed in terms of defects per hundred units, shall be 2.5 for major defects and 6.5 for total defects.

Source: https://assist.dla.mil -- Downloaded: 202640-21T21:02Z
Check the source to verify that this is the currentversion before use.

TABLE I. End item visual defects

Examine	Defect	Classification	
		Major	Minor
Finish	Any sliver, burr, or sharp edge	101	
(1) Chrome plating	Blistered, peeled, chipped, or area of no plating	102	
	Scratched to base metal		201
(2) Stainless steel	Exterior surfaces not No. 4 or smoother finish	103	
	Scratched, discolored, stained, pitted, or scaly	104	
	Interior surfaces of coffee compartments not a No. 8 mirror finish or electropolish finish	105	
Construction and workmanship (applicable to all assemblies)	Component not fabricated of specified material (i.e., stainless steel, copper etc., as applicable)	106	
	Missing components including paper filters, bolts, screws, nuts, or rivets	107	
	Any component dented or buckled	108	
	Dirt or other foreign matter inside compartments	109	
	Cracked or fractured component or metal	110	
	Assembly not rigid	111	
	Component not accessible for servicing where required	112	
	Tool or forming marks	113	
Welding (where applicable)	Incomplete, burn holes, cracked, or fractured	114	
	Any slag inclusion, undercut, rust, paint, grease, or other foreign matter	115	
	All scale or flux not removed from the finished weld	116	

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects - Continued

Examine	Defect	Classification	
		Major	Minor
Soldering (where applicable)	Not adherent or incomplete	117	
Electrical equipment	Not enclosed in flexible metallic conduit where required	118	
(1) Wiring	Connection loose	119	
	Wiring diagram missing	120	
	Wiring diagram not located as specified	121	
	Signal lights and push-button controls not provided as applicable	122	
(2) Thermostat	Range not as specified	123	
	Knob cannot be turned	124	
	Loose knob	125	
	Not securely mounted (loose)	126	
(3) Heating element	Element not removable	127	
	Terminals not enclosed in removable box	128	
	Terminals not sealed	129	
Piping and tubing	Cross threaded (piping)	130	
Valves	Missing, where required	131	
	Handle missing	132	
	Loose handle	133	
Stand	Not provided with bag sink (when required)	134	
	Tray rails missing (Navy, if required)	135	
Outer shell	Steam vents not provided (if applicable)	136	

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

TABLE I. End item visual defects - Continued

Examine	Defect	Classification	
		Major	Minor
Coffee compartments	Gage glass missing or not as specified	137	
	Compartment faucets not located as specified	138	
	Cover missing	139	
	Handle or cover not as specified	140	
Leacher	Handle not provided	141	
	Filters missing, not as specified	142	
Water compartment	Water gage not located as specified	143	
	Faucets not as specified	144	
Legs	Not provided with holddown means (Navy)	145	
	Nonadjustable (when required)	146	
Spray-head	Spray-head not type specified (swivel or individual)	147	
Pump	Pump not as specified, or missing	148	
Casters	Not as specified	149	
	Brakes missing	150	
Dispensing faucets	Not correct number, not specified type, not located as specified	151	
	Cannot disassemble without tools	152	
Data name plate	Omitted or not as specified		202
	Information incomplete or illegible		203
	Not located so as to be readily visible to the operator		204

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:02Z
Check the source to verify that this is the current version before use.

* 4.2.4 End item dimensional examination. The end item shall be examined for the defects listed below. The lot size shall be expressed in units of coffee urns and urn frames, as applicable. The sample unit shall be one coffee urn and urn frame. The inspection level shall be S-2, and the AQL, expressed in terms of defects per hundred units, shall be 4.0. Any nonconformance shall constitute a defect.

TABLE II. End item dimensional examination

Dimension	Requirement paragraph
Height, weight, and depth	3.4.2.1 and 3.4.2.2
Electric cord length	3.5.6
Flexible hose length	3.5.7.4
Faucet clearance	3.5.9
Casters	3.5.12.2
Stand	3.5.12.5

4.2.5 End item testing. Sample coffee urns shall be tested as specified in 4.4.1. The inspection level shall be S-4, and the AQL, expressed in terms of defects per hundred units, shall be 4.0. The tests as specified in 4.4.2 and 4.4.3, when applicable, shall be performed on one representative production unit. Failure of any test shall be cause for rejection of the inspection lot.

* 4.2.6 Packaging examination. The fully packaged end items shall be examined for the defects listed below. The lot size shall be expressed in units of shipping containers. The sample unit shall be one shipping container fully packaged. The inspection level shall be S-2 and the AQL, expressed in terms of defects per hundred units, shall be 2.5.

Examine	Defect
Marking (exterior and interior)	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application
Materials	Any component missing, damaged, or not as specified

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

Workmanship	Inadequate application of components, such as: incomplete sealing or closure of flap, improper taping, loose strapping or inadequate stapling Bulged or distorted container
Content	Number per container is more or less than required

4.3 Certification examination. Certificates of compliance, certified test reports, approval labels or listing marks for codes and standards, as applicable, that are submitted as proof of compliance with the document requirements shall be examined and validated.

4.4 Tests.

4.4.1 Operational test. The urn shall be tested to determine proper operation, that it does not leak, and that it is capable of brewing coffee. Any nonconformance shall constitute failure of this test. The water compartment shall be filled to the "stop" mark of the water gage. The steam, electricity, or gas, as applicable, shall be turned on and the following checks shall be made:

a. The initial heatup time and recovery time shall be checked for conformance with the time requirements of 3.4.4.

b. The temperature of the spray-over water and the thermostat setting shall be checked to determine conformance with the applicable requirements of 3.4.3 (for spray-over) and 3.5.6.1, 3.5.7.3, and 3.5.8.2 (for thermostat).

c. The time required to spray-over the required amount of water shall be checked for conformance with the brewing time requirements of 3.4.3.

d. The water compartment shall be drained until the low water cutoff operates, and the water level shall be checked to determine conformance with the low water cutoff requirements of 3.5.4.2.

e. The pump delivery to the countertop (style 1) shall be checked to determine conformance with the pump electricity requirements of 3.5.11.

f. The urn shall be allowed to stand for 1 hour after brewing, and the brewed coffee temperature shall be checked upon emergence from the countertop faucets on style 1 urns and the gravity fed faucets on style 2 urns, as applicable, to determine conformance with the temperature-holding requirements of 3.4.3.

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:02Z
Check the source to verify that this is the currentversion before use.

g. The urn and connecting piping shall be checked for leakage (see 3.5).

h. The amount of brewed coffee in the coffee compartments shall be checked to determine conformance with capacity requirements of 3.5.2. Check shall be made to determine that coffee faucets are located to allow complete drainage as required by 3.5.2.

i. The urn shall be tested to determine conformance with the automatic refill of the water compartment and 1/2-brew requirements of 3.4.

4.4.2 Brew test. The brewed coffee shall be tested during the operational test to determine that the percent of solids conforms to the requirements of 3.4.3. The test shall be conducted using 7.1 ounces of drip grind coffee (conforming to Simplified Practice Recommendation R231-48 of the National Bureau of Standards) per gallon of water for the size urn specified. The depth of the ground coffee shall be measured to determine conformance with the requirements of 3.5.3. All of the volume of hot water shall pass through the coffee bed and none shall be repoured. During the brew test the spray-over water shall be checked to determine that it does not overflow the leacher (see 3.5.3). The test to determine solids percentage shall be made with a coffee hydrometer as described in PACB Publication No. 43 or No. 61; or the contractor may have the brew analyzed by an independent laboratory in accordance with PACB Publication Nos. 15 and 27. Any nonconformance shall constitute failure of this test.

4.4.3 Tilt test. The urn shall be filled with the specified amount of brew and tilted 15 degrees each side of the vertical in each of two vertical planes at right angles to each other for a period of 2 minutes in each position. There shall be no spillage or contact of brew with the leacher as required by 3.4. Any nonconformance shall constitute failure of this test.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or Commercial, as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Disassembly. Protruding and detachable components shall be disassembled from the coffee urn, as necessary, in order to prevent damage while in transit.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

5.1.1.2 Sealing. All openings into the urn, including the cover-closure seam, shall be sealed with tape conforming to PPP-T-60.

5.1.1.3 Securing. Parts of the urn that are free to move shall be secured in a manner to prevent movement and damage while in transit.

* 5.1.1.4 Paper filters and detached components. The disposable paper filters and detached components shall be unit packed in a snug-fitting, fiberboard box conforming to style RSC, grade W5c, of PPP-B-636. Each fiberboard box shall be closed in accordance with method IV as specified in the appendix of PPP-B-636.

5.1.1.5 Cleaning brush. Cleaning brush shall be unit packed in the same box as the filters or secured to the coffee urn. Care shall be exercised that the brush is not bent or coiled.

* 5.1.2 Commercial. Urns shall be preserved in accordance with ASTM D 3951.

5.2 Packing. Packing shall be level A, B, or Commercial, as specified (see 6.2).

5.2.1 Level A packing. Each urn, preserved as specified in 5.1, shall be packed in a snug-fitting shipping container conforming to overseas type, style A or J, grade optional, type 3 load of PPP-B-601. Each shipping container shall be provided with skids in accordance with PPP-B-601. The fiberboard box, containing the paper filters, and detached components shall be secured in an unused portion of the shipping container. The contents shall be secured by lumber blocking and bracing or by bolting the container base through the skids. Lumber blocking and bracing shall not depend on end-grain nailing alone, but supplemental supporting cleats shall be provided to reinforce and prevent splitting of the blocking and bracing. Cushioning material shall be used between the lumber blocking and coffee urn. Each shipping container shall be closed and strapped in accordance with the appendix of PPP-B-601.

5.2.2 Level B packing. Each urn, preserved as specified in 5.1, shall be packed as specified in 5.2.1.1, except that shipping containers shall conform to domestic type, style A or J of PPP-601 or class II, style A or J, of PPP-B-591.

* 5.2.3 Commercial packing. Urns, preserved as specified in 5.1, shall be packed in accordance with ASTM D 3951.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

* 5.3. Marking. In addition to any special marking required by the contract or purchase order, unit packs and shipping containers shall be marked in accordance with MIL-STD-129 or ASTM D 3951, as applicable.

6. NOTES

6.1 Intended use. The automatic coffee urns are intended for dispensing of coffee and hot water for tea in hospitals, cafeterias, galleys, and dining facilities.

* 6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this document.
b. Style, size, and type (and class, if applicable) of coffee urn required (see 1.2).
c. Electrical requirements, if other than specified (see 3.4).
d. When urn is intended for shipboard use (see 3.4).
e. When style 1 urns shall be provided with 3 faucets at countertop level, two coffee and one water (see 3.4.1.1).
f. When style 2 urns shall be provided with two coffee faucets and one water faucet per coffee compartment for double service (see 3.4.1.2).
g. When permanent metal filters or paper filters are required (see 3.5.3.1).
h. Length of water tubing or hose if other than specified (see 3.5.4).
i. Length of dispensing lines for style 1 urns if other than specified (see 3.5.11).
j. When stand is required for style 2 urn (see 3.5.12.4).
k. For shipboard use, when stand shall be furnished with tray rails and hold-down means (see 3.5.12.4).
l. Government approved manual number to be included on data name plate (see 3.7).
m. Selection of the applicable level of preservation and packing (see 5.1 and 5.2).

6.3 Contract data requirements. Any data items to be delivered under any contract for the items covered by this document should be specifically called for in the contract in accordance with the applicable regulations of the contracting activity.

* 6.4 Recycled material. The contractor is encouraged to use recycled material, provided that it meets the requirements of this document (see 3.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

6.5 Facilities. Electric urns and gas urns may be expected to require the following facilities:

	Electric*	Gas
Size 1	12 kW	45,000 BTU per hour
Size 2	15 kW	* * 45,000 BTU per hour
Size 3	15 kW	N/A
Size 4	12 kW	* * 45,000 BTU per hour

* Electric voltages shall be as specified in 3.4 for each size urn.
* * Gas urns above 6-gallon total capacity require a 160°F minimum water supply in addition to the installed gas capacity shown.

* 6.6 Shipboard voltages. Type I urns for shipboard use shall operate on 120 volts, direct current (dc); 230 volts, dc; 250 volts, dc; 115 volts, 1 phase, 60 Hz; 230 volts, 3 phase, 60 Hz; or 440 volts, 3 phase, 60 Hz.

6.7 Changes from previous issue. The margins of this document are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only, and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodians:

Army - GL
Navy - YD
Air Force - 99

Preparing activity:

Army - GL

Project No. 7310-0704

Review activities:

Army - MD, TS
Navy - MS, MC
Air Force - 82, 84
DLA - GS

User activities:

Navy - CG

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY
US Army Natick Research and Development Center
Natick, Massachusetts 01760

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300
STRNC-ES

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
US Army Natick Research and Development Center
ATTN: STRNC-ES
Natick, MA 01760

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:02Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-U-43263E	Urns, Coffee, Twin and Single, Automatic (Electric, Steam & Gas

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR ☐ USER ☐ MANUFACTURER ☐ OTHER *(Specify)*: _____
b. ADDRESS *(Street, City, State, ZIP Code)*	

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

NATICK OP, 1 Apr 84

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:02Z
Check the source to verify that this is the current version before use.