MIL-T-38646B(USAF)
5 February 1976
SUPERSEDING
MIL-T-38646A(USAF)
8 March 1972

MILITARY SPECIFICATION

TRUCK, LIFT, AERIAL STORES, 7000 POUND CAPACITY MHU-83A/E

1. SCOPE

1.1 This specification covers one type of Aerial Stores Lift Truck designated MHU-83A/E.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on the date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

STANDARDS

Military

MIL-STD-129	Marking for Shipment and Storage
MIL-STD-130	Identification Marking of U.S. Military Property
MIL-STD-143	Standards and Specifications, Order of Precedence for the Selection of
MIL-STD-162	Material Handling Equipment, Storage, Cyclic Maintenance, Outline Testing and Process
MIL-STD-461	Electromagnetic Interference Characteristics Requirements for Equipment
MIL-STD-794	Parts and Equipment, Procedures for Packaging and Packing of
MIL-STD-808	Finish, Protective and Codes for Finishing Schemes for Ground and Ground Support Equipment
MIL-STD-810	Environmental Test Methods
MIL-STD-889	Dissimilar Metals

FSC 1730

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

Military

MIL-D-1000	Drawing, Engineering and Associated List
MIL-L-2104	Lubricating Oil, Internal Combustion Engine, Heavy Duty
MIL-L-2105	Lubricating Oil, Gear, Multi-Purpose
MIL-A-2550	Ammunition and Special Weapons, General Specification for
MIL-F-3541	Fittings, Lubrication
MIL-G-5514	Gland Design, Packings, Hydraulic, General Requirements for
MIL-G-7711	Grease, Aircraft, General Purpose
MIL-S-7742	Screw Threads, Standard, Optimum Selected Series, General Specification for
MIL-B-8565	Battery and Cell, Storage Aircraft
MIL-R-12144	Reflector, Indicating, Clearance
MIL-G-23827	Grease, Aircraft and Instrument, Gear and Actuator Screw
MS27766	Shroud for Aerospace Ground Equipment

DRAWINGS

Air Force

65F35339	Strap, Quick Release, Tie-down MHU-98/E
65E35468	Fork, Adapter Assembly MHU-101/E
65D35518	Specification, Welding
65C35569	Roller Assembly, Bomb Support MHU-100/E
65E35736	Engine
69B4922	Filter
69J4983	Truck, Lift, Aerial Stores, 7000 Pound Capacity MHU-83A/E

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

(Copies of documents required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Major component list. The major components of the lift truck are:

a. Body
b. Chassis
c. Engine
d. Hydraulic lift system
e. Hydraulic drive system

3.2 Performance. The lift truck shall perform as described below without structural, mechanical, or hydraulic failure.

3.2.1 Structural strength. There shall be no mechanical failure or structural deformation as a result of a 1400 pound load on the table.

3.2.2 Environmental conditions. The lift truck shall withstand the following environmental conditions without detrimental effects on its operation.

a. Operational temperature from -40°F to +125°F.
b. Storage temperatures from -65°F to +154°F.
c. Thirty minute sand and dust conditions as outlined in MIL-STD-810.
d. Thirty minute rain cycles as defined in MIL-STD-810.

3.2.3 Engine. The lift truck shall be powered by an air-cooled, gasoline engine conforming to USAF Drawing No. 65E35736.

3.2.3.1 The engine, when operating at 2400 revolutions per minute (rpm), shall provide a speed capability on a hard level surface of 13 miles per hour (mph) unloaded and 8 mph loaded. It shall have the capability of withstanding not less than 1000 stop and go cycles without failure.

3.2.3.2 The engine shall provide sufficient power for the lift truck to climb a 20 percent grade unloaded and a 10 percent grade loaded.

Source: https://assist.dla.mil -- Downloaded: 202610-21T15:16Z
Check the source to verify that this is the current version before use.

3.2.4 Electrical system. The lift truck shall have a 24 volt electrical system. The electrical system shall incorporate an external alternator system to produce not less than 8 amps at idle engine rpm and not less than 15 amps at maximum engine rpm.

3.2.4.1 Starting system. The starting system shall have a lead-acid battery conforming to MIL-B-8565, a starting switch, an alternator, and a voltage regulator.

3.2.4.2 Lighting system. The lift truck shall have two swivel floodlights, a backup light, and reflectors that conform to MIL-R-12144.

3.2.5 Transmission. The lift truck shall have a hydrostatic transmission of sufficient size to effectively transmit power from the engine to the rear axle.

3.2.5.1 Heat exchanger. The lift truck shall have a heat exchanger of sufficient size to keep the transmission fluid below +200°F under normal operating conditions.

3.2.6 Brakes. The brakes shall hold the loaded lift truck on a 10 percent grade.

3.2.6.1 Service brake. The lift truck shall have hydraulic brakes on the two rear wheels and the two inside front wheels. The brakes shall be foot pedal controlled and capable of stopping the fully loaded lift truck traveling at 8 mph within a maximum distance of 16 feet.

3.2.6.2 Emergency brakes. The lift truck shall have a mechanical emergency brake that is easily accessible to the operator.

3.2.7 Instrument panel. The instrument panel shall be located in a position that is easily observed by the operator. The gages shall be color coded to indicate above and below normal ranges of operation of the hydraulic, electrical, and automotive systems. The panel shall include a tach-hourmeter, an oil pressure gage, an ammeter, a temperature indicator, an accumulator pressure gage, and the hydraulic control valves (3.2.8.7). All gages shall be raintight.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

3.2.8 Hydraulic system. The hydraulic system shall include a 10 micron filter located such that it will not cause cavitation or other adverse effects in the system. All hydraulic fluid leaving the reservior shall pass through the filter before returning to the reservior. The differential pressure drop shall not exceed 50 pounds per square inch (psi) between the inlet and outlet of the filter housing at 30 gallons per minute (gpm) flow and oil temperature at 100°F. The hydraulic system shall have an accululator for maintaining pressure and various hydraulic control valves, cylinders, and other mechanisms to perform under operating and functional conditions stated herein.

3.2.8.1 Steering. The lift truck shall have rear wheel, hydraulic power steering. The steering shall ensure positive control of the lift truck when traveling at maximum speed and be capable of turning the wheels when the lift truck is stationary with the engine idling. No more than three turns of the steering wheel shall be required to turn from lock to lock. The lift truck shall have a turn radius of 20 feet.

3.2.8.2 Accumulator. The hydraulic system shall have an accumulator that is precharged with nitrogen to 700 psi± 50 psi. The hydraulic system pump shall be capable of further charging the accumulator to capacity when the engine is operating at 1000 rpm.

3.2.8.3 Control valve. The hydrualic system shall have a control valve for positive metering of the hydraulic fluid to ensure a smooth operation.

3.2.8.4 Unloader valve. The hydraulic system shall have a valve in the pump circuit to permit a continuous flow of fluid through the pump when there is no demand on the system. Operating pressure shall be maintained in the pump line only when there is a demand on the hydraulic system.

3.2.8.5 Packings. Packing installation shall conform to MIL-G-5514.

3.2.8.6 Hydraulic filter. The hydraulic filter shall be of the 10 micron type per USAF Drawing 69B4922.

3.2.8.7 Control valve locations. Control valves for operation of the lift boom and azimuth, tilt and yaw mechanisms shall be located on the instrument panel and on the lift boom near the manipulator head. The longitudinal control valve shall be located on the lift boom near the manipulator head along with the other control valves.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

3.2.8.8 Front wheel adjustments. The wheelbase of the lift truck and the spacing of the front sheels shall be variable. To provide additional stability in handling bulky items, provision shall be made for extending the wheelbase from 89 3.4 inches to 113 3/4 inches in 12 inch increments. The side frame width shall hydraulically be adjustable to allow a minimum width between the inside front wheels of 24 1/2 inches and a maximum of 94 inches. The position of the wheels shall be individually adjustable within this range. The control valves for side frame width movement shall be located on the instrument panel. The boom shall be capable of being lowered below wheel/ground contact line to allow raising of wheels for extending the front wheels. The side frame width adjusting mechanism shall be capable of operating through 250 cycles, from 24 1/2 inches to 94 inches, without failure.

3.2.8.9 Main lift system.

3.2.8.9.1 Lift system. The lift truck shall have a 7000 pound lift capability consisting of a hydraulic system, lift mechanism, lift boom, and cradle. The unloaded boom shall have a vertical reach of 96 inches, measured from the ground to the top and center of the lift cradle. The lifting rate of the lift boom, full loaded or empty, and with the engine operating at 2400 rpm, shall be an average minimum of 14 feet per minute for a complete cycle. The lift shall be fully controlled in increments of 1/8 inch from minimum to maximum lift position, up or down, under a capacity load. The lift mechanism shall insure that the vertical boom drift, measured at the front of the manipulator head, does not exceed 1/2 inch for one hour. The lift or lower time of the auxiliary hand pump system, under capacity load, shall be not more than 5 minutes through the range of maximum and minimum lift. The lifting mechanism shall be such that stores being lifted shall remain in a given attitude during lifting operation. Provisions shall be made to prevent binding of the lifting mechanism while lifting with the lift truck sitting on an uneven surface. It shall be capable of operating 1000 cycles without failure.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

3.2.8.9.2 Azimuth. The lifting boom shall be provided with an azimuth mechanism for positioning weapon or store by horizontally moving the boom 20 ± 2 degrees to each side of center. Provisions shall be made to hydraulically control this movement in increments of not more than 1/8 inch. The azimuth mechanism shall insure that the horizontal boom drift, measured at the front of the manipulator head, does not exceed 1/2 inch for one hour. The mechanism shall be capable of operating 250 cycles without failure.

3.2.8.9.3 Failsafe. The lifting mechanism shall be equipped with a hydraulically actuated "failsafe" device which prevents the boom from falling in the event of hydraulic failure.

3.2.8.10 Manipulator head. The lifting boom shall be provided with a manipulator head for restraining and positioning the weapon or store and shall be so designed that the rams will always be lower than the underside of stores during loading and unlaoding operations. The manipulator head shall have the capability of operating with rated load through 250 cycles without failure. This head shall be equipped in such a manner as to have four separate motions.

3.2.8.10.1 Yaw. The manipulator head shall impart to the weapon or store a yaw movement of 104 ± 3 degrees to either side of center.

3.2.8.10.2 Tilt. The manipulator head shall impart to the weapon or store a tilt movement of 5 ± 1 degrees, nose up, or nose down and shall insure that the tilt drift, measured at the tilt cylinders, does not exceed 1/2 inch for one hour.

3.2.8.10.3 Roll. The manipulator head shall impart to the weapon or store a total roll movement of 7 ± 1 degrees up or down from the level position and shall insure that the roll drift, measured at the roll cylinders, does not exceed 1/2 inch for one hour.

3.2.8.10.4 Longitudinal. The manipulator head shall impart to the weapon or store a total longitudinal movement of 2 ± 1/2 inches fore or aft of center and shall insure that the longitudinal drift, measured at the longitudinal cylinders, does not exceed 1/2 inch for one hour.

3.3 Accessories. The lift truck shall be designed to accommodate the accessories noted below.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

3.3.1 Fork adapter plate and forks. The adapter plate and forks (USAF Drawing 65E35468) shall be quickly and easily secured on the manipulator head for the handling of triple ejection bomb racks (TER), multiple ejection bomb racks (MER), and aerial stores which are positioned with a minimum ground clearance. The placement of the adapter on the head and forks on the adapter shall be variable so that ground clearance may be 2 1/4 inches, 6 7/8 inches, 18 inches, or 22 5/8 inches. The fork shall be capable of supporting a load of 6000 pounds.

3.3.2 Bomb support rollers. Bomb support rollers (USAF Drawing 65C35569) shall be used on the manipulator head or the forks of the lift truck. The rollers shall provide accommodation for aerial stores with diameters ranging 6 inches to 31 inches on the forks or 44 inches on the head. A set of four rollers shall be capable of supporting 7000 pounds.

3.3.3 Tie-down straps. Removable tie-down straps (USAF Drawing 65F35339) shall be used to secure aerial stores to the forks or manipulator head during transport. Each strap shall be at least 85 inches long and shall be equipped with a tension device to facilitate handling. A set of two straps shall be capable of restraining 7000 pounds.

3.4 Design and construction.

3.4.1 Production drawings. The design and construction of the lift truck shall conform to USAF Drawing 69J4983. If this specification and the drawing conflict, the specification shall govern.

3.4.2 Metals. Metals shall be corrosion-resistant or suitably treated to resist corrosion due to fuels, salt spray, or atmospheric conditions likely to be met in storage or service. When non-corrosion resistant materials are used, they shall be treated in a manner that will not prevent compliance with the performance requirements of this specification. Protective coatings that crack, chip, or scale with age or extremes of atmospheric conditions shall be avoided.

3.4.3 Dissimilar metals. Dissimilar metals are defined in MIL-STD-889. They shall not be used in contact with each other unless suitably protected against electrolytic corrosion.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

3.4.4 Selection of specifications and standards. Specifications and standards for necessary commodities and services not specified herein or on the applicable drawings shall be selected according to MIL-STD-143, except as provided in 3.4.4.1 and 3.4.4.2.

3.4.4.1 Commercial parts. Commercial parts having identical or better design properties and parameters may be used where, on the date of invitation for bids, there are no equivalent standard parts. In any case, commercial utility parts, like screws, bolts, nuts, and cotter pins, having identical or better design properties may be used provided:

a. They are completely interchangeable with standard parts (MS or AN) without alteration.

b. The corresponding standard part numbers are referenced in the parts list and, if practical, on the drawings.

3.4.4.2 Standard parts. With the exception of 3.4.4.1, MS and AN standard parts shall be used where suitable. They shall be identified on the drawings by their part numbers.

3.4.5 Screw threads. Screw threads shall be in accordance with MIL-S-7742.

3.4.6 Welding. Welding shall conform to USAF Drawing 65D35518.

3.4.7 Electromagnetic interference. The lift truck shall be radio suppressed as required by MIL-STD-461.

3.4.8 Painting. Treatment and painting shall be in accordance with MIL-STD-808.

3.4.9 Greases and grease fittings. Greases for general chassis lubrication shall conform to MIL-G-7711. Greases for lubrication of anti-friction bearings shall conform to MIL-G-23827. All grease fittings shall be accessible for pressure type lubrication without disassembly of any part of the vehicle and shall conform to MIL-F-3541.

3.4.10 Oils. Engine oil shall conform to MIL-L-2104. Gear oil shall conform to MIL-L-2105.

3.4.11 Hydraulic fluid. Type A, Suffix A automatic transmission fluid shall be used in the hydraulic lift system.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

3.4.12 Transmission fluid. Type A, Suffix A automatic transmission fluid shall be used in the hydrostatic transmission.

3.4.13 Identification of product. Except as noted in the procuring document, equipment, assemblies, and parts shall be marked for identification in accordance with MIL-STD-130 and applicable drawings.

3.4.14 Interchangeability. All parts having the same part number shall be functionally and dimensionally interchangeable. MIL-D-1000 shall govern changes in the part number.

3.4.15 Workmanship. Workmanship shall conform to MIL-A-2550. The lift truck, including all parts and accessories, shall be fabricated in a manner that will insure that the criteria of appearance, fit, and adherence to specified tolerances shall be observed. Particular attention shall be given to neatness and thoroughness of marking of parts and assemblies, plating, printing, riveting, machine screw assemblage, and welding. All parts shall be free from burrs and sharp edges which may mar associated equipment or cause injury to using personnel.

3.5 First article testing. Unless otherwise specified (see 6.2), the contractor shall submit a first article sample for testing.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reservies the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of tests. The inspection and testing of the lift truck shall consist of the following.

4.2.1 First article tests. The first article tests are those tests performed on a production lift truck of each new production run to determine if that truck meets the requirements of this specification. First article tests consist of all tests described under 4.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

4.2.1.1 Test sample. The first production lift truck, as specified in the contract, shall be tested for approval by the procuring activity, or, when so specified in the contract, at the contractor's plant under the supervision of the procuring activity.

4.2.2 Acceptance tests. Acceptance tests are those tests performed on production units which have been submitted for test. They consist of those tests described in 4.2.2.1 and 4.2.2.2.

4.2.2.1 Production tests. Production tests shall be performed on each lift truck and consist of all tests described in 4.4.4.1.4, 4.4.4.1.5, 4.4.4.2, 4.4.4.3 for five cycles only; 4.4.5.1 for one mile unloaded only; and 4.4.5.5 and 4.4.5.6.

4.2.2.2 Periodic sampling tests. One lift truck shall be selected from each 50, or fraction thereof, on the contract or order and subjected to sampling tests. The test sample shall be selected by the procuring activity from production lift trucks which have successfully completed all production tests. The sampling tests shall consist of all tests described under 4.4 except for the following:

a. Delete 4.4.2
b. Reduce 4.4.4.1.1 to 250 cycles
c. Reduce 4.4.4.1.4, 4.4.4.2, and 4.4.4.3 to 50 cycles
d. Reduce 4.4.5.1 to 100 miles loaded and 0 miles unloaded with 200 stop and go cycles.

4.2.2.2.1 Rejection and retest. When a lift truck selected for periodic sampling tests fails to meet this specification, no items still on hand or produced later shall be accepted until the extent and cause of the failure are determined.

4.2.2.2.2 Continuance of individual tests. Individual tests may be continued at the discretion of the procuring activity pending the investigation of the periodic sampling test failure. However, final acceptance of items on hand or produced later shall not be made until it is determined that the lift trucks meet all the requirements of this specification.

4.2.2.2.3 Defects in items already received. The investigation of a periodic sampling test failure may indicate that defects exist in items previously accepted. The contractor shall be responsible for correcting the defect in all items back to the previous test, first article or periodic sampling as applicable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

4.3 Test conditions. Unless otherwise specified herein, tests shall be performed under normal ambient temperatures and atmospheric conditions.

4.4 Test methods and procedures. Upon completion of each test there shall be no evidence of structural or hydraulic failure.

4.4.1 Examination of product. Each lift truck shall be completely inspected to insure conformance with this specification and all applicable drawings with respect to workmanship, material, dimensions, weight, and markings.

4.4.2 Environmental testing. The lift truck, with a 7000 pound load on the table shall be subjected to the following environmental tests in accordance with MIL-STD-810.

4.4.2.1 High Temperature Test, Method 501, Procedure II. The lift truck shall be operated +125°F for 30 minutes.

4.4.2.2 Low Temperature Test, Method 502, Procedure I. The storage temperature shall be -65°F. The lift truck shall be operated at -40°F for 30 minutes.

4.4.2.3 Rain Test, Method 506, Procedure I. The lift truck shall be operated the last 10 minutes of each of the four 30 minute rain cycles.

4.4.2.4 Sand and Dust Test, Method 510, Procedure I. The lift truck shall be operated for 30 minutes.

4.4.3 Structural overload tests. The lift truck shall be subjected to the following static load tests with a 14,000 pound load on the table.

4.4.3.1 The lifting boom shall be set such that the top of the table is 48 inches above the ground. The load shall be placed on the table and held in that position for three minutes. Upon removal of the load, the table shall not have dropped more than 1/2 inch. This test shall be repeated with the lifting boom set such that the top of the table is 96 inches above the ground.

4.4.4 Functional tests. The lift truck shall be subjected to the following functional tests.

4.4.4.1 The following tests shall be performed with a 7000 pound load on the table.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

4.4.4.1.1 Cycle test. The boom shall be raised and lowered through the maximum lift range for 1000 cycles. During this test it shall be demonstrated that, with the engine operating at 2400 rpm, the lift rate is not less than an average of 14 feet per minute for a complete cycle.

4.4.4.1.2 Failsafe test. The table shall be raised off the ground. It shall be demonstrated by causing a hydraulic failure that the "failsafe" features of the main lift mechanisms are functioning.

4.4.4.1.3 Incremental control test. The lifting mechanism shall demonstrate an incremental control capability of not more than 1/8 inch through the vertical lift range.

4.4.4.1.4 Azimuth test. The lifting boom shall be moved horizontally 20 ± 2 degrees to each side of center for 250 cycles. It shall also be demonstrated once that there is an incremental control capability of not more than 1/8 inch through the horizontal range.

4.4.4.1.5 Manual lift rate test. The auxiliary hand pump shall demonstrate that the lift boom can be raised or lowered through its maximum range in five minutes.

4.4.4.1.6 Accumulator test. The hydraulic system accumulator shall demonstrate its capability of being charged to capacity while the engine is running at a maximum of 1000 rpm. Further, the unloader valve shall demonstrate that there is a continuous flow of fluid through the pump when there is no demand on the hydraulic system. When the engine is shut down, the accumulator pressure may leak down to a minimum of 700 psi ± 50 psi.

4.4.4.1.7 Hydraulic filter test. The pressure differential between the inlet and outlet of the filter housing shall be checked to insure that the differential does not exceed 50 psi at 30 gpm oil flow at an oil temperature of 100°F.

4.4.4.1.8 Boom drift test. This test shall demonstrate that, with the engine operating at 1800 rpm, the vertical and horizontal boom drift, measured at the front of the manipulator head, does not exceed 1/2 inch for one hour.

4.4.4.2 Manipulator head cycle test. The following tests shall be performed with a 6000 pound load on the forks for 250 cycles.

4.4.4.2.1 Yaw test. The yaw mechanism on the manipulator head shall move (yaw) the longitudinal centerline of the table 104 ± 3 degrees to the right and left of center.

Source: https://assist.dla.mil -- Downloaded: 202610-21T15:16Z
Check the source to verify that this is the current version before use.

4.4.4.2.2 Roll test. The roll cylinders on the manipulator head shall move (roll) the longitudinal centerline of the table 7 plus 1 minus zero degrees up and down from the level position. It shall be demonstrated by causing a hydraulic failure that the "failsafe" features of the roll mechanism are functioning. During this test it shall be demonstrated that, with the engines operating at 1800 rpm, the roll drift, measured at the roll cylinders, does not exceed 1/2 inch for one hour.

4.4.4.2.3 Tilt test. The tilt cylinders on the manipulator head shall move (tilt) the longitudinal centerline of the load 5 plus 1 minus zero degrees up and down from level position. During this test it shall be demonstrated that, with the engine operating at 1800 rpm, the longitudinal drift, measured at the longitudinal cylinders, does not exceed 1/2 inch for one hour.

4.4.4.3 Boom and outrigger cycle test. The following tests shall be performed with no load on the lift truck for 250 cycles.

4.4.4.3.1 Boom cycle test. The boom shall be raised and lowered through the maximum lift range. During this test it shall be demonstrated that, with the engine operating at 2400 rpm, the lift rate is not less than an average of 14 feet per minute for a complete cycle.

4.4.4.3.2 Outrigger test. The outriggers shall be fully extended laterally so that the inside front wheels are 94 inches apart and then retracted to 24 1/2 inches.

4.4.4.3.3 Front wheel adjustment test. The front wheels shall be extended longitudinal to provide a wheelbase of not less than 89 3/4 inches to not greater than 113 3/4 inches in 12 inch increments.

4.4.5 Mobility tests. The lift truck shall be subjected to the following mobility tests with a 7000 pound load on the table unless otherwise specified.

4.4.5.1 Road test. The lift truck shall be driven 500 miles loaded and 100 miles unloaded. The test shall include not less than 1000 stop and go cycles.

4.4.5.2 Heat Exchanger test. During the road test the transmission fluid shall not exceed 200°F.

Source: https://assist.dla.mil -- Downloaded: 202610-21T15:16Z
Check the source to verify that this is the current version before use.

4.4.5.3 Grade test. The loaded lift truck shall be stopped on a 10 percent slope. From this position the lift truck shall climb the slope. This test shall be repeated on a 20 percent slope with the lift truck unloaded.

4.4.5.4 Speed test. The lift truck, with the engine operating at 2400 rpm, shall demonstrate a minimum speed of 8 mph loaded and 13 mph unloaded.

4.4.5.5 Service brake test. The service brake shall hold the loaded lift truck on a ten percent slope. In addition, the service brakes shall stop the fully loaded lift truck traveling at 8 mph within a maximum distance of 16 feet.

4.4.5.6 Emergency brake test. The emergency brake shall hold the loaded lift truck on a 10 percent slope.

4.4.5.7 Steering test. The lift truck shall demonstrate a maximum turning radius of 20 feet. It shall also be demonstrated that no more than three turns of the steering wheel are required to turn from lock to lock.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging shall be level A or C as specified (see 6.2).

5.1.1 Level A. The lift truck shall be preserved and packaged in accordance with MIL-STD-162, Level A, Type I and II requirements.

5.1.2 Level C. The lift truck shall be preserved and packaged in accordance with MIL-STD-162, Level C, Type I requirements.

5.2 Packing. Packing shall be Level A, B, or C as specified (see 6.2).

5.2.1 Level A. The lift truck, preserved and packaged in accordance with 5.1.1, shall be packed in accordance with MIL-STD-162, Level A. Type I, Level A or Type II, Level A requirements shall apply as specified by the procuring activity (see 6.2). When MIL-STD-162, Level A, Type I, Mobile requirements are specified, the control cab and manipulator head shall be shrouded in accordance with MS27766.

5.2.2 Level B. The lift truck, preserved and packaged in accordance with 5.1.1, Type I, shall be packed in accordance with MIL-STD-162, Level B, unboxed. The control cab and manipulator head shall be shrouded in accordance with MS27766.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

5.2.3 Level C. The lift truck, preserved and packaged as specified in 5.1.2, shall be prepared for shipment in accordance with MIL-STD-162, Type I, Mobile requirements.

5.3 Marking. In addition to any special marking required by the contract or order, mobile packs and shipping containers shall be marked in accordance with the requirements of MIL-STD-129.

5.4 Dangerous material requirements. The lift truck with hydraulic system accumulator installed and charged with compressed nitrogen gas shall be prepared for shipment in accordance with dangerous material shipment requirements of MIL-STD-794.

6. NOTES

6.1 Intended use. The lift truck described herein is intended for use by the US Air Force on, or around, hardstands, pierced steel planking, and landing mats to lift, transport, position, and load single aerial stores on preloaded MERs and TERs onto tactical aircraft.

6.2 Ordering data. Procurement documents should include:

a. Title, number, and date of this specification.
b. Level or preservation and packaging (see 5.1).
c. Level and type of packing (see 5.2 and 5.2.1).
d. Site of First Article Test.
e. Whether contractor is responsible for all tests.

Custodian:
Air Force 18

Reviewer:
Air Force 82

Preparing Activity:
Air Force 18

Project Number 1730-F219

328

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T15:16Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

C16061

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 202610-21T15:16Z
Check the source to verify that this is the current version before use.