MIL-C-23994(SHIPS)
AMENDMENT-2
14 December 1964
SUPERSEDING 1/
Amendment-1
4 November 1964

MILITARY SPECIFICATION

CONTROLLERS, STATIC, NAVAL SHIPBOARD

This amendment forms a part of Military Specification MIL-C-23994(SHIPS), 7 July 1964.

Page 2, paragraph 3.1: Delete and substitute:

"3.1 Preproduction sample. - Prior to beginning production, samples shall be tested as specified 4.3 (see 6.3)."

Page 4, paragraph 3.3.10: Add "Forced draft cooling is not permitted."

Page 5, paragraph 3.3.11.4: Delete and substitute:

"3.3.11.4 Undervoltage and overvoltage. - Controllers shall be designed to interrupt the load between 80 and 70 percent (undervoltage limits) and 120 and 130 percent (overvoltage limits) of rated input voltage, unless otherwise specified (see 6.1). Controllers shall not interrupt the load due to transients of a 5 second duration or less."

Page 5, Add as paragraph 3.3.11.7:

"3.3.11.7 Electromagnetic interference. The equipment shall be designed to insure a minimum amount of electromagnetic interference."

Pages 8 and 9, paragraph 3.6.1, cont'd, item (6), a through g: Delete and substitute:

"(6) Silicon controlled rectifiers.

a. Similar information to transistor data, as applicable.

"(m) List of exceptions to this specification.
"(n) Descriptive data of the equipment which shall include rating, degree of enclosure and catalog number. Include derating due to starting characteristics (see 3.3.5.2).

1/ CHANGES FROM PREVIOUS ISSUE. THE OUTSIDE MARGINS OF THIS DOCUMENT HAVE BEEN MARKED "#" TO INDICATE WHERE CHANGES (DELETIONS, ADDITIONS, ETC.) FROM THE PREVIOUS ISSUE HAVE BEEN MADE. THIS HAS BEEN DONE AS A CONVENIENCE ONLY AND THE GOVERNMENT ASSUMES NO LIABILITY WHATSOEVER FOR ANY INACCURACIES IN THESE NOTATIONS. BIDDERS AND CONTRACTORS ARE CAUTIONED TO EVALUATE THE REQUIREMENTS OF THIS DOCUMENT BASED ON THE ENTIRE CONTENT AS WRITTEN IRRESPECTIVE OF THE MARGINAL NOTATIONS AND RELATIONSHIP TO THE LAST PREVIOUS ISSUE.

Source: https://assist.dla.mil -- Downloaded: 202640-19T18:40Z
Check the source to verify that this is the current version before use.

"(o) Actual weight of the equipment and an unboxed set of repair parts.

"(p) List of repair parts with piece numbers for each item, the name of each item, the quantity of each item recommended for one set of repair parts and the manufacturer's identification for the item. This list shall conform to 3.5.2.

"(q) Table of revisions including a brief description of each revision of the drawing.

"(r) Title block."

Page 9, paragraph 4.2, line 1: Delete "Qualification, comparison" and substitute "Preproduction."

= Page 10, table II, column 2, heading: Delete "Qualification inspection" and substitute "Preproduction inspection" and delete entire column 3.

= Page 10, table II, columns 1 and 5: Delete "Explosionproof" and "3.4" and substitute "Enclosure" and "3.4.1" respectively.

Page 10, table II, column 5, opposite "Effectiveness of enclosure": Delete "3.4" and substitute "3.4.1".

Page 10, paragraph 4.3: Delete and substitute:

"4.3 Preproduction inspection. - Preproduction inspection shall consist of the examination and tests specified in table II. A proposed test agenda shall be forwarded for Bureau of Ships approval. The preproduction samples shall be approved by the Bureau of Ships."

= Page 10, paragraph 4.3.1: Delete and substitute:

"4.3.1 Samples for preproduction. - Two samples each of the basic controller types specified in 3.3.1 shall be submitted for test. Otherwise, tests on two adjustable voltage types will cover all a.c. types and tests on two armature and field control types will cover all d.c. types. The samples shall be rated at the maximum horsepower offered. Three equipment samples, of other than complete controllers, shall be submitted for their applicable preproduction tests. Class C drawings shall be submitted with the samples."

Page 10: Delete footnote 1 at bottom of page.

Page 11, paragraph 4.4: Delete.

Page 11, paragraph 4.7.3, fifth sentence: Delete and substitute "The controller shall be tested in a 50°C ambient for 48 hours with a load of maximum current rating."

= Page 11, paragraph 4.7.3.1, second sentence: Delete.

Source: https://assist.dla.mil -- Downloaded: 20260-19T18:40Z
Check the source to verify that this is the current version before use.

Page 13, paragraph 4.7.12.1: Delete and substitute:

"4.7.12.1 Preproduction tests. Preproduction tests are required only on explosionproof enclosures and enclosures included with complete equipments submitted for preproduction tests. Explosionproof enclosures shall be tested by the Bureau of Mines."

Page 14, paragraph 4.7.12.2: Delete.

Page 15, paragraphs 6.3 and 6.3.1: Delete and substitute:

"6.3 Preproduction. - Invitations for bids should provide that the Government reserves the right to waive the requirement for preproduction samples as to those bidders offering a product which has been previously procured or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending procurement."

Preparing activity:
Navy - SH
(Project 6110-NO77SH)

Source: https://assist.dla.mil -- Downloaded: 202610-19T18:40Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T18:40Z
Check the source to verify that this is the current version before use.