| NOT MEASUREMENT |
| SENSITIVE |

MIL-R-24005F
29 June 1992
SUPERSEDING
MIL-R-24005E
5 June 1985

MILITARY SPECIFICATION

ROLLERS, MOTORIZED, VIBRATING, TANDEM

This specification is approved for use by the Naval Facilities Engineering Command, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers motorized, two-drum, vibrating rollers.

1.2 Classification. The roller shall be one of the following types, as specified (see 6.2):

Type I - Single-drum-driven, single vibrating drum.
Type II - Double-drum-driven, double vibrating drums.

* 2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

| Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, 621 Pleasant Valley Road, Port Hueneme, CA 93043-4300, by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter. |

AMSC N/A FSC 3895

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T18:42Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

MILITARY

MIL-V-173 - Varnish, Moisture- and Fungus-Resistant (For Treatment of Communications, Electronic, and Associated Equipment).
MIL-R-3075 - Roller, Motorized, Road, Diesel- or Gasoline-Engine-Driven, Packaging of.

STANDARDS

MILITARY

MIL-STD-209 - Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Bldg. 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

* 2.2 Non-Government publications. Non-Government publications adopted by the Department of Defense (DoD) shall be listed in the current DODISS. The referenced publications, listed as follows, become a part of this document to the extent specified herein. Unless otherwise specified (see 6.2), the issue listed in the DODISS as current on the date of solicitation, shall be issue of record for procurement purposes.

ASTM

ASTM D 1557 - Standard Test Methods for Moisture-Density Relations of Soils and Soil-Aggregate Mixtures Using 10-Lb Rammer and 18-Inch Drop.
ASTM D 2487 - Standard Test Method for Classification of Soils for Engineering Purposes.

(Application for copies should be addressed to the ASTM, 1916 Race Street, Philadelphia, PA 19103.)

(Non-Government standards are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, Inc., 400 Commonwealth Drive, Warrendale, PA 15096.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T18:42Z
Check the source to verify that this is the current version before use.

* 2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

* 3.1 Description. The roller shall consist of a steel vibrating drum(s), self contained power source and drive system, sprinkler system, and an operator's station.

* 3.2 First article. When specified (see 6.2) a first article test and report shall be required. The contractor shall provide a roller and demonstrate performance tests as specified herein. The contractor shall have full responsibility for providing any equipment, gear or tools as may be necessary, personnel, and operation of equipment. The roller may be a sample product (manufacturer's standard model) with same features as specified, or the first production item.

* 3.3 Standard commercial product. The roller shall, as a minimum, be in accordance with the requirements of this specification and shall be the manufacturer's standard commercial product. Additional or better features which are not specifically prohibited by this specification but which are a part of the manufacturer's standard commercial product, shall be included in the roller being furnished. A standard commercial product is a product that has been sold as a standard or optional product, and listed in manufacturer's catalog(s), brochures, and advertisements for not less than six months prior to date of solicitation, and is a standard production model.

* 3.4 Materials. Materials used shall be free from defects which would adversely affect the performance or maintainability of individual components or of the overall assembly. Materials not specified herein shall be of the same quality used for the intended purpose in commercial practice. Unless otherwise specified herein, all equipment, material, and articles incorporated in the work covered by this specification are to be new and fabricated using materials produced from recovered materials to the maximum extent possible without jeopardizing the intended use. The term "recovered materials" means materials which have been collected or recovered from solid waste and reprocessed to become a source of raw materials, as opposed to virgin raw materials. None of the above shall be interpreted to mean that the use of used or rebuilt products are allowed under this specification unless otherwise specified.

3.5 Interchangeability. All units of the same classification furnished with similar options under a specific contract shall be identical to the extent necessary to insure interchangeability of component parts, assemblies, accessories, and spare parts.

* 3.6 Ease of maintenance. Design of the roller shall permit ready accessibility to all parts for maintenance and repair by the use of tools commonly associated with equipment of this nature. Ease of maintenance provisions shall incorporate features insuring clearances between adjacent components to facilitate maintenance and servicing operations. Components containing liquids shall be provided with an accessible means for draining by gravity, without contacting any part of vehicle chassis or components.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T18:42Z
Check the source to verify that this is the current version before use.

* 3.7 Safety. Rollers shall meet safety requirements of OSHA in effect on date of manufacture. All components which may be hazardous to operating personnel shall be furnished with safety guards. The roller shall be furnished with a backup alarm which may include a timed shut down switch to limit continuous operation. A roll-over-protection (ROP) device shall be furnished, when available, either as standard or optional equipment by manufacturer.

3.8 Dimensions and weights.

3.8.1 Dimensions. Roller shall meet the dimensional requirements specified in table I.

* TABLE I. Dimensions.

ITEM (dimensions in inches)	Type I	Type II
Width: maximum overall	46	56
Length: maximum overall	98	130
Height: maximum, excluding: ROP and exhaust	98	98
Wheelbase:	N/A	N/A
Turning radius, inside maximum diameter	100	140
Drum(s), diameter, minimum	20	24
Drum(s), width, minimum	26	36

3.8.2 Weights. Type I roller shall have a shipping weight of not less than 1,800 pounds (lb). Type II roller shall have a shipping weight of not less than 3,600 lb.

* 3.9 Performance. When on a firm level surface, the roller shall have a maximum travel speed of not less than 1.5 miles per hour (mph) in both forward and reverse directions. The roller shall be able to negotiate a 15 percent slope. The roller shall have the capability of loading and unloading from standard transport (a gross gradeability of 30 percent). When tested as described in 4.4.2.1 and 4.4.2.2, the roller, with the vibrating mechanism(s) operating at not less than 1,400 vibrations per minute (vpm), shall be capable of compacting hot and cold mixed asphaltic concrete and both fine and coarse grained soils as classified in accordance with ASTM D2487. Not more than five passes (see 6.5) over the same area with the roller shall be required to compact asphaltic concrete having a loose depth thickness of 3 inches. Not more than six passes with the roller shall be required to compact the fine grained soil, and not more than four passes to compact the coarse grained soil when spread to a depth of 3 inches. Maximum density, as determined by ASTM D1557, shall be not less than 95 percent for both soils. Roller shall withstand the strains imposed upon it without receiving any damage or deformation when operating at maximum frequency and as specified herein.

3.10 Roller components.

3.10.1 Frame. Frame shall be fabricated of structural steel sections or steel plates with members joined using one of the arc-welding processes. To withstand the stresses imposed, and to prevent permanent deformation or damage to the roller, the frame shall be braced and reinforced wherever necessary.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T18:42Z
Check the source to verify that this is the current version before use.

* 3.10.2 Power plant. The roller shall be furnished with an engine providing horsepower and torque characteristics as required to meet performance requirements as specified herein. Unless otherwise specified (see 6.2), the engine shall operate on diesel fuel. The engines shall have not less than 12 horsepower for Type I, and not less than 30 horsepower for Type II rollers. Each roller shall be furnished with the following:

a. Fuel tank with capacity for not less than 5 hours' operation.
b. Dry type air cleaner, meeting engine manufacturer's requirements.
c. Exhaust system with muffler, including means to prevent water from entering when raining.
d. Electrical starting and charging system including lead acid battery of either 12 or 24 volts direct current (Vdc) design.
e. Either a weather resistant enclosed battery box, or secured location within the roller body. The battery location shall be painted with acid resistant paint.
f. Key type ignition switch and starter control.
g. Diesel engines shall be furnished with a positive means of securing engine, such as an electric or manually operated fuel shut-off.
h. Operator controlled throttle.
i. Hour meter with capacity of not less than 9,999 hours.
j. Manufacturer's standard instrument(s) panel with visual or electrical/audio type devices which will warn operator of low engine oil pressure, and excessive high engine operating temperature.

* 3.10.3 Power train. Roller(s) vibratory action shall be hydraulic powered and operator controlled at choice of speed. Motivation of drive roll(s) on Type I rollers may be either hydrostatic or mechanical, but Type II shall be hydrostatic drive. Drive train system shall be capable of withstanding maximum torque of engine furnished while operating under the most adverse conditions which may be encountered during compaction operations. Direction of travel shall be controlled by a single device, with a detent at neutral position or include a self centering to neutral feature. Movement shall be in the same direction as the control device.

* 3.10.4 Drums. Drums shall be fabricated of steel plates with seams and heads joined using one of the arc-welding processes. Drums shall have a smooth surface and chamfered peripheral edges. Plate thickness shall be not less than 1/4 inch for Type I, and 3/8 inch for Type II rollers. Drums shall be mounted utilizing heavy duty axle stubs and anti-friction type bearing.

3.10.5 Scrapers. Roller shall have scrapers, located in the front and rear of each drum. All scrapers shall extend across the full width of each drum, and shall be capable of preventing the accumulation of material on the drums when roller operates in either the forward or reverse direction.

* 3.10.6 Sprinkler system. Roller shall be equipped with a self-contained sprinkler system for wetting and cleaning of the drums. Sprinkler system shall consist essentially of a water tank, lines, wiper mats, spray headers, and valves. Tank shall have a capacity of not less than 30 gallons, a filler opening with cap having a diameter of not less than 1-1/2 inches, and a petcock for draining. Piping shall be rigidly affixed to the frame; flexible lines

Source: https://assist.dla.mil -- Downloaded: 202610-19T18:42Z
Check the source to verify that this is the current version before use.

shall be supported at 2-foot intervals or less. Wiper mats and spray headers shall be furnished on each drum and shall extend across the full width of each drum and shall completely wet the surface of the drums.

* 3.10.7 Vibrating mechanism(s). The rollers shall be furnished with the manufacturer's standard vibratory mechanism. The Type I roller shall include one vibratory mechanism as a minimum, but may have one in each roll if manufacturer's standard design. The Type II roller shall include a vibratory mechanism in each roller. The vibratory action shall be at the operator's choice of intensity and include a frequency of not less than 2,400 vpm at full engine revolutions per minute. The dynamic force of the roller (including weight and vibratory action) shall be not less than 5,000 lb for each vibratory drum. The roller design shall provide maximum insulation for the operator against the vibratory actions.

3.10.8 Brakes. The manufacturer's standard brake system, including service and park system shall be furnished. The brakes shall be capable of stopping the roller within 4 feet when traveling on a level hard surface at 1.5 miles per hour. The parking brake shall be capable of stopping and holding the roller stationary when moving either up or down a 15 degree slope with a hard surface.

3.10.9 Operator's station. Operator's station shall be equipped with a seat and backrest, instrument panel, and operating controls. All controls necessary for normal operation of the roller shall be located within easy reach of the operator while seated. All instruments shall be visible and all hand and foot operated controls, including brake, forward/reverse lever, steering wheel, vibrating mechanism(s) lever, and sprinkler valves shall be within easy reach of the operator while sitting in his normal operating position. Instruments, gauges, and switches, shall be protected against moisture and inclement weather conditions. All controls and instruments shall be clearly identified for their intended operation and function with permanently affixed identification plates.

3.11 Tool storage. When specified (see 6.2), a weatherproof compartment or box shall be furnished for storage of tools and accessories required for normal daily operation of the roller.

3.12 Lifting and tiedown attachments. When specified (see 6.2), the roller shall be equipped with lifting and tiedown attachments.

* 3.13 Lubrication. Means for lubrication shall be in accordance with the manufacturer's standard practice. The lubricating points shall be easily visible and accessible. Hydraulic lubrication fittings shall be in accordance with SAE J534. Where use of high pressure lubricating equipment, 1,000 pound-force per square inch or higher, will damage grease seals or other parts, a suitable warning shall be affixed to the equipment in a conspicuous location.

* 3.14 Cleaning, treatment, and painting. Surfaces normally painted in good commercial practice shall be cleaned, treated, and painted as specified herein. Unless otherwise specified (see 6.2), the finish color shall be manufacturer's standard yellow, nearest match to No. 13538 of FED-STD-595. Surfaces to be painted shall be cleaned and dried to insure that they are free from contaminants such as oil, grease, welding slag and spatter, loose mill scale,

Source: https://assist.dla.mil -- Downloaded: 202610-19T18:42Z
Check the source to verify that this is the current version before use.

water, dirt, corrosion product, or any other contaminating substances. As soon as practicable after cleaning, and before any corrosion product or other contamination can result, the surfaces shall be prepared or treated to insure the adhesion of the coating system. The painting shall consist of at least one coat of primer and one finish coat. The primer shall be applied to a clean, dry surface as soon as practicable after cleaning and treating. Painting shall be with manufacturer's current materials according to manufacturer's current processes and the total dry film thickness shall be not less than 2.5 mils over the entire surface. The paint shall be free from runs, sags, orange peel, or other defects.

3.15 Workmanship.

3.15.1 Steel fabrication. The steel used in fabrication shall be free from kinks, sharp bends, and other conditions which would be deleterious to the finished product. Manufacturing processes shall not reduce the strength of the steel to a value less than intended by the design. Manufacturing processes shall be done neatly and accurately. All bends shall be made by controlled means to insure uniformity of size and shape.

3.15.2 Bolted connections. Boltholes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in accordance with good commercial practice, and all bolts, nuts, and screws shall be tight.

3.15.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of approved shape and of uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the metal.

3.15.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Welds shall be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the weld are subjected to proof and service loadings.

3.15.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping, or any other defect which reduces the casting's ability to perform its intended function.

4. QUALITY ASSURANCE PROVISIONS

* 4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government.

Source: https://assist.dla.mil -- Downloaded: 202610-19T18:42Z
Check the source to verify that this is the current version before use.

The Government reserves the right to perform any of the inspections set forth in this document where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

* 4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this document shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in this document shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.1.2 Component and material inspection. Components and materials shall be inspected in accordance with all the requirements specified herein and in applicable referenced documents.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

4.2.1 First article inspection. The first article inspection shall be performed on one roller when a first article is required (see 3.2 and 6.2). This inspection shall include the examination of 4.3, and the tests of 4.4. The first article may be either a first production item or a standard production item from the supplier's current inventory provided the item meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining items to be furnished under the contract.

4.2.2 Quality conformance inspection. The quality conformance inspection shall include the examination of 4.3, and the tests of 4.5.

4.3 Examination. Each roller shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any necessary redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

4.4 First article tests. The first article shall be subjected to the tests specified in 4.4.1 through 4.4.3.

4.4.1 Performance test. Roller shall be measured and weighed to verify conformance to 3.8.2. Before starting tests, the manufacturer shall present calculations to verify conformance to dynamic force requirements of 3.10.7. Roller shall be operated continuously at full rated engine speed, with vibrating

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T18:42Z
Check the source to verify that this is the current version before use.

mechanism(s) engaged, for a period of 4 hours. At the conclusion of the 4-hour test, the roller shall be checked for lubrication and any signs of damage or deformation. Roller shall be operated for an accumulated period of 16 hours, including the specified 4-hour run in test period. Tests 4.4.2 and 4.4.3 may be performed at the same time. Roller shall be tested for the following:

a. Travel speed (see 3.9).
b. Negotiating a 15 percent grade (see 3.9) and 30 percent grade in loading and unloading on transport (see 3.9).
c. Vibratory frequency measured with gauge or meter (see 3.10.7).
d. Service and parking brake demonstration (see 3.10.8).

Every 4 hours the roller shall be examined for excessive wear, overheating, and any signs of damage or deformation. Throughout the test, roller shall be observed to verify compliance with:

e. Safety requirements as specified (see 3.7).
f. Frame capability to resist deformation or damage (see 3.10.1).
g. Fuel tank operational capacity (see 3.10.2).
h. Excessive vibratory action transfer to operator station (see 3.10.7).
i. Operational controls and instruments (see 3.10.9).

4.4.2 Compaction.

4.4.2.1 Asphalt. A level test area of not less than three times the length and width of roller shall be prepared. Asphalt of either hot or cold mix shall be spread evenly not less than three inches thick over test area. When operated as described in 3.9, the roller shall compact the complete area while making not more than five passes over any specific location. During this operation the roller shall demonstrate the sprinkler system described in 3.10.6. A section of the compacted area shall be removed for inspection of compaction capability.

4.4.2.2 Soil. Two level test areas of not less than three times the length and width of roller shall be prepared. A layer of fine grained soil shall be spread evenly over one area to not less than 4, or more than 6 inches depth. The second area shall be spread evenly with coarse grained soil to not less than 6 inches, or not more than 8 inches depth. The roller shall compact each area separately by making not more than six passes over the fine grained soil and four passes over the coarse grained soil. The contractor shall verify compaction to requirements of 3.9, utilizing any certified method of their choice which may be available.

4.4.3 Lifting and tying down attachment tests. Lift and tiedown devices shall be tested to verify conformance to MIL-STD-209 requirements. Contractor may request substitution of certified engineering drawings and calculations in lieu of actual demonstration. Request shall be made far enough in advance of first article test date to allow for acceptance or requirement of actual test performance.

4.5 Operational test. Each production roller shall be completely assembled, properly adjusted, and serviced for operation. Engine shall be started and subjected to a warm up period as recommended by the manufacturer. Roller shall be operated for not less than 30 minutes. During this operation period the roller shall be function tested utilizing all controls. All controls and

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T18:42Z
Check the source to verify that this is the current version before use.

switches shall be operated as many times as necessary to determine ease of operation, effectiveness, responsiveness, and that mechanism actuated by the controls operate promptly, fully, and without restriction, malfunction, or excessive vibration. During and after completion of this function the roller shall be inspected for any malfunction, leaks, or damage. Failure to pass any phase of this test shall be cause for rejection. The contractor's standard final quality test and examination will be acceptable if approved in advance by the purchasing agency.

5. PACKAGING

* 5.1 Commercial. The equipment shall be preserved in accordance with the contractor's standard practice in a manner to prevent deterioration and damage. The equipment shall be lubricated for operational service as required in the operator's manual.

6. NOTES

6.1 Intended use. The rollers covered by this specification are intended for use in compacting bases for road patches, concrete slabs, sidewalks, and compacting hot and cold asphaltic concrete.

* 6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Type of roller required (see 1.2).
c. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
d. When a first article roller is required for inspection and approval (see 3.2, 4.2.1, and 6.4).
e. When gasoline engine is required (see 3.10.2).
f. When a tool storage compartment is needed (see 3.11).
g. When lifting and tying down attachments are required (see 3.12).
h. Color of finish paint other than Yellow No. 13538 of FED-STD-595 (see 3.14).

6.3 Data requirements. When this specification is used in an acquisition which incorporates a DD Form 1423, Contract Data Requirements List (CDRL) and invokes the provisions of paragraph 52.227-7031 of the Federal Acquisition Regulations (FAR), the data requirements will be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the approved CDRL (DD Form 1423) incorporated into the contract. When the provisions of FAR 52.227-7031 are not invoked, the data shall be delivered in accordance with the contract requirements.

6.4 First article. When a first article inspection is required, the item will be tested and should be a first production item or it may be a standard production item from the contractor's current inventory as specified in 4.2.1. The first article should consist of one unit. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, test, and approval of the first article.

Source: https://assist.dla.mil -- Downloaded: 202640-19T18:42Z
Check the source to verify that this is the current version before use.

6.5 Pass. Driving the roller in one direction over the material being compacted, is defined as one pass. Driving the roller over the original path a second time in the same or opposite direction is defined as two passes.

6.6 Changes from previous issue. The margins of this specification are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

* 6.7 Subject term (key word) listing.

Compaction
Double drum
Single drum
Sprinkler system

Custodians:
Navy - YD
Air Force - 99

Review Activities:
Army - ME
Air Force - 84

User Activity:
Navy - MC

Preparing Activity:
Navy - YD

(Project 3895-0330)

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T18:42Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2. 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-R-24005F	920629

3. DOCUMENT TITLE
ROLLERS, MOTORIZED, VIBRATING, TANDEM

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code)	
COMMANDING OFFICER	(1) Commercial (805) 982-5464	(2) AUTOVON 551-5464
c. ADDRESS (Include Zip Code) NCBC CESO (CODE 1564L), 621 PLEASANT VALLEY RD. PORT HUENEME, CA 93043-4300	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340	

Source: https://assist.dla.mil -- Downloaded: 202610-19T18:42Z
Check the source to verify that this is the currenversion before use.