MIL-HDBK-1028/1
15 NOVEMBER 1987
SUPERSEDING
NAVFAC DM-28.1
DECEMBER 1982

MILITARY HANDBOOK

AIRCRAFT MAINTENANCE FACILITIES

AMSC N/A

DISTRIBUTION STATEMENT A. APPROVED FOR PUBLIC RELEASE: DISTRIBUTION IS UNLIMITED

AREA FACR

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

ABSTRACT

This handbook is provided as guidance for aircraft maintenance facilities covered by Category Codes 211 and 212 for military real property. It is intended for use by experienced architects and engineers. The contents include design data for buildings and shop areas to provide aircraft maintenance, including airframes, aircraft engines, aircraft weapons systems, avionics systems, air-launched guided missiles, and other related aircraft equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

FOREWORD

This handbook has been developed from an evaluation of facilities in the shore establishment, from surveys of the availability of new materials and construction methods, and from selection of the best design practices of the Naval Facilities Engineering Command (NAVFACENGCOM), other Government agencies, and the private sector. This handbook was prepared using, to the maximum extent feasible, national professional society, association, and institute standards. Deviations from this criteria, in the planning, engineering, design, and construction of Naval shore facilities, cannot be made without prior approval of NAVFACENGCOM HQ Code 04.

Design cannot remain static any more than the functions it serves or the technologies it uses. Accordingly, recommendations for improvement are encouraged and should be furnished to Commander, Naval Facilities Engineering Command, Atlantic Division, Code 04A4, Norfolk, Virginia 23511-6287; telephone (804) 444-9970.

THIS HANDBOOK SHALL NOT BE USED AS A REFERENCED DOCUMENT FOR PROCUREMENT OF FACILITIES CONSTRUCTION. IT IS TO BE USED IN THE PURCHASE OF FACILITIES ENGINEERING STUDIES AND DESIGN (FINAL PLANS, SPECIFICATIONS, AND COST ESTIMATES). DO NOT REFERENCE IT IN MILITARY OR FEDERAL SPECIFICATIONS OR OTHER PROCUREMENT DOCUMENTS.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

MAINTENANCE FACILITIES CRITERIA MANUALS

Criteria Number	Title	PA
MIL-HDBK-1028/1	Aircraft Maintenance Facilities	LANTDIV
DM-28.2	Shipyard Maintenance Facilities	LANTDIV
DM-28.3	Maintenance Facilities for Ammunition, Explosives, and Toxins	LANTDIV
DM-28.4	General Maintenance Facilities	WESTDIV
DM-28.5	Environmental Control - Design of Clean Rooms	LANTDIV
MIL-HDBK-1028/6	Aircraft Fixed Point Utility Systems (PROPOSED)	HDQTRS
MIL-HDBK-1028/7	Electroplating Facilities (PROPOSED)	HDQTRS
MIL-HDBK-1028/8	Pest Control Facilities	HDQTRS

NOTE: Design manuals, when revised, will be converted to military handbooks and listed in the military handbook section of NAVFAC P-34

This handbook is issued to provide immediate guidance to the user. However, it may or may not conform to format requirements of MIL-HDBK-1006/3 and will be corrected on the next update.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

AIRCRAFT MAINTENANCE FACILITIES

CONTENTS

			Page
Section 1		INTRODUCTION	
	1.1	Scope	1
	1.2	Cancellation	1
	1.3	Other Design Considerations	1
	1.4	Facility Plates	1
	1.5	Definitive Drawings	1
	1.6	Planning Criteria	2
	1.7	Building Functions	2
	1.8	Organizational Communications	2
	1.9	Energy Conservation	3
	1.10	Environmental Concerns	3
	1.11	Building Protection	3
	1.12	Loading Dock Ramp Protection	3
	1.13	Fire Protection	3
	1.14	Restrictions on the Use of Uncoated Aluminum	3
	1.14.1	Seacoast	3
	1.14.2	Exterior and Interior	4
	1.14.3	Incompatible Materials	4
	1.14.4	Coated Metal	4
Section 2		MAINTENANCE HANGAR	
	2.1	Function	5
	2.2	Location	5
	2.3	Architectural and Structural Requirements	5
	2.3.1	Structure	5
	2.3.2	Roof Systems	6
	2.3.3	Wall Systems	6
	2.3.3.1	Exterior Walls	6
	2.3.3.2	Interior Partitions	7
	2.3.4	Floors	7
	2.3.5	Ceilings	8
	2.3.6	Doors and Door Controls	8
	2.3.6.1	Hangar Doors	8
	2.3.6.2	Personnel Doors	8
	2.3.6.3	Interior Personnel Doors	8
	2.3.6.4	Overload Doors	8
	2.3.6.5	Other Doors	9
	2.3.7	Soundproofing	9
	2.3.8	Surface Treatment	9
	2.3.9	Exterior Pavement	9
	2.4	Mechanical Requirements	9
	2.4.1	Heating	9
	2.4.2	Ventilation	10

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

		Page
2.4.3	Air Conditioning	10
2.4.4	Plumbing	10
2.4.5	Compressed Air	11
2.4.6	Noise and Vibration Control	11
2.5	Electrical Requirements	11
2.5.1	Hangar (OH) Space	11
2.5.1.1	Hazardous Zones	11
2.5.1.2	Power Service Points	11
2.5.2	Type I/II Spaces	11
2.5.3	Lighting	11
2.5.3.1	Interior Lighting	11
2.5.3.2	Exterior Lighting	12
2.5.4	Grounding	12
2.6	Organizational Communications	12
2.6.1	3M Communications (Maintenance and Material Management)	12
2.6.2	Intercommunications System	12
2.6.3	Public Address System	12
2.6.4	Television Surveillance System	12
2.7	Security	13
2.8	Weight-Handling Equipment	13
2.8.1	Bridge Cranes	13
2.8.1.1	Motor and Controls	13
2.8.1.2	Hook Height	13
2.8.2	Jib Cranes	13
Section 3	CORROSION CONTROL HANGAR	
3.1	Function	14
3.2	Location	14
3.3	Architectural Requirements	14
3.3.1	Structure	14
3.3.2	Walls	14
3.3.3	Roofs	15
3.3.4	Floors	15
3.3.5	Ceilings	15
3.3.6	Doors and Door Controls	15
3.3.6.1	Hangar Doors	15
3.3.6.2	Personnel Doors	15
3.3.6.3	Others Doors	15
3.3.7	Building Insulation	15
3.3.8	Surface Treatment	15
3.3.9	Exterior Pavement	15
3.4	Mechanical Requirements	16
3.4.1	Heating	16
3.4.2	Ventilation	16
3.4.3	Plumbing	17
3.4.4	Compressed Air	17
3.4.5	Noise and Vibration Control	17
3.5	Electrical Requirements	17
3.5.1	Electrical Installations	17
3.5.2	Lighting	18

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

			Page
	3.5.3	Grounding	18
	3.6	Weight-Handling Equipment	18
Section 4		AIRCRAFT WEAPONS ALIGNMENT FACILITY	
	4.1	Function	19
	4.2	Location	19
	4.3	Architectural and Structural Requirements	19
	4.3.1	Structure	19
	4.3.2	Walls	19
	4.3.3	Roofs	19
	4.3.4	Floors	19
	4.3.5	Doors	20
	4.3.6	Exterior Pavement	20
	4.3.7	Harmonization Target	20
	4.4	Mechanical Requirements	20
	4.4.1	Heating	20
	4.4.2	Ventilation	20
	4.4.3	Air Conditioning	20
	4.4.4	Noise and Vibration Control	21
	4.5	Electrical Requirements	21
	4.5.1	Power Outlets	21
	4.5.2	Lighting	21
	4.5.3	Grounding	21
Section 5		PAINT FINISHING HANGAR	
	5.1	Function	22
	5.2	Location	22
	5.3	Arrangement	22
	5.4	Architectural and Structural Requirements	22
	5.4.1	Structure	22
	5.4.2	Roofs	22
	5.4.3	Walls	22
	5.4.4	Floors	22
	5.4.5	Ceilings	22
	5.4.6	Doors and Door Controls	22
	5.4.7	Building Insulation	22
	5.4.8	Surface Treatment	23
	5.4.9	Exterior Pavement	23
	5.5	Mechanical Requirements	23
	5.5.1	Heating	23
	5.5.2	Ventilation	23
	5.5.3	Air Conditioning	23
	5.5.4	Plumbing	23
	5.5.5	Compressed Air	23
	5.5.6	Noise and Vibration Control	23
	5.6	Environmental Controls	23
Section 6		AVIATION LIFE SUPPORT SYSTEMS SHOP	
	6.1	Function	24
	6.2	Location	24

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

		Page
6.3	Architectural Requirements	24
6.3.1	General	24
6.3.2	Packing Room	25
6.3.3	Sewing and Fabrication Room	25
6.3.4	Parachute Storage	25
6.3.5	Flotation Room	25
6.3.6	Oxygen and CO_2 Room	25
6.3.7	Exterior Pavement	25
6.4	Mechanical Requirements	25
6.4.1	Heating, Ventilation, and Air Conditioning	26
6.4.2	Plumbing	26
6.4.3	Compressed Air and Vacuum	26
6.4.4	Noise and Vibration Control	26
6.5	Electrical Requirements	26
6.5.1	Power Outlets	28
6.5.2	Lighting	28
Section 7	ENGINE MAINTENANCE SHOP	
7.1	Function	29
7.2	Location	29
7.3	Architectural and Structural Requirements	29
7.3.1	High Bay	29
7.3.2	Shop Areas	29
7.3.3	Other Spaces	29
7.3.4	Exterior Pavements	30
7.4	Mechanical Requirements	30
7.4.1	Heating	30
7.4.2	Ventilation	30
7.4.3	Air Conditioning	30
7.4.4	Plumbing	30
7.4.5	Compressed Air	30
7.4.6	Noise and Vibration Control	30
7.5	Electrical Requirements	31
7.5.1	Power Outlets	31
7.5.2	Lighting	31
7.5.3	Communications	31
7.6.	Weight-Handling Equipment	31
7.6.1	Bridge Crane	31
7.6.2	Motor and Controls	32
Section 8	AIRFRAMES SHOP	
8.1	Function	33
8.2	Location	33
8.3	Architectural Requirements	33
8.3.1	Walls	33
8.3.2	Roof	33
8.3.3	Floors	33
8.3.4	Doors	33
8.3.5	Finishes	33
8.3.6	Clean Room	33

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

Page

	8.3.7	Paint Shop	33
	8.3.8	Exterior Pavement	33
	8.4	Mechanical Requirements	34
	8.4.1	Clean Room	34
	8.4.2	Heating	34
	8.4.3	Ventilation	34
	8.4.4	Air Conditioning	34
	8.4.5	Plumbing	34
	8.4.6	Compressed Air	34
	8.4.7	Nitrogen	35
	8.4.8	Noise and Vibration Control	35
	8.5	Electrical Requirements	35
	8.5.1	Power Outlets	35
	8.5.2	Lighting	35
	8.5.3	Communications	35
	8.6	Weight-Handling Equipment	36
Section 9		AVIONICS SHOP	
	9.1	Function	37
	9.2	Location	38
	9.3	Architectural Requirements	38
	9.3.1	Interior Partitions	38
	9.3.2	Floors	38
	9.3.3	Doors	38
	9.3.4	Finishes	38
	9.3.5	Exterior Pavement	38
	9.3.6	Clean Room	38
	9.3.7	Electrical Area	38
	9.3.8	CSD/Generator Room	38
	9.3.9	Battery Room	38
	9.3.10	MAD Building	38
	9.3.11	Radar Test Facility	39
	9.3.12	Avionics Building	39
	9.3.13	PME Branch and Production Control Office	40
	9.3.14	Production Control Office	40
	9.4	Mechanical Requirements	40
	9.4.1	Heating, Ventilation, and Air Conditioning	40
	9.4.2	Special Exhaust Systems	40
	9.4.3	Clean Room	40
	9.4.4	Plumbing	40
	9.4.5	Compressed Air and Nitrogen	40
	9.4.6	Noise and Vibration Control	40
	9.5	Electrical Requirements	40
	9.5.1	Electromagnetic Interference Shielding	40
	9.5.2	Power Outlets	41
	9.5.3	Lighting	41
	9.5.4	Grounding	41
	9.5.5	Communications	42
	9.6	Security	42
	9.7	Weight-Handling Equipment	42

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Page

Section 10		AIRCRAFT BORESIGHT RANGE	
	10.1	Function	43
	10.2	Location	43
	10.2.1	Type A Range	43
	10.2.2	Type B Range	43
	10.3	Architectural and Structural Requirements	43
	10.3.1	Tunnel	43
	10.3.2	Firing-in Butt	43
	10.3.3	Target System	44
	10.3.4	Wing Rooms	44
	10.3.5	Shelters	44
	10.3.6	Exterior Pavement	44
	10.4	Mechanical Requirements	44
	10.4.1	Heating and Air Conditioning	44
	10.4.2	Ventilation	44
	10.4.3	Plumbing	45
	10.5	Electrical Requirements	45
	10.5.1	Power Outlets	45
	10.5.2	Lighting	45
	10.5.3	Grounding	45
	10.5.4	Communications	46
	10.6	Safety Requirements	46
Section 11		AIR-LAUNCHED GUIDED MISSILE SHOP	
	11.1	Function	47
	11.2	Location	47
	11.3	Architectural Requirements	47
	11.4.	Mechanical Requirements	47
	11.4.1	Heating, Ventilation, and Air Conditioning	47
	11.4.2	Compressed Air	47
	11.4.3	Plumbing	48
	11.5	Electrical Requirements	48
	11.5.1	Lighting	48
	11.5.2	Grounding	48
	11.5.3	Lightning Protection	48
	11.6	Security	48
	11.7	Weight-Handling Equipment	48
Section 12		LINE SHELTER	
	12.1	Function	49
	12.2	Location	49
	12.3	Architectural Requirements	49
	12.3.1	Portable Line Shelters	49
	13.3.2	Permanent Line Shelters	49
	13.3.3	Noise Control	49
	13.3.4	Interior Finishes	49
	12.4	Mechanical Requirements	49
	12.4.1	Portable Shelter	49
	12.4.2.	Permanent Shelter	49

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

		Page
12.5	Electrical Requirements	50
12.5.1	Portable Shelter	50
12.5.2	Permanent Shelter	50
12.6	Communications	50
Section 13	FLAMMABLE STORAGE FACILITIES ON THE FLIGHT LINE	
13.1	Function	51
13.2	Location	51
13.3	Architectural Requirements	51
13.4	Mechanical Requirements	51
13.5	Electrical Requirements	51
Section 14	MARINE CORPS AIRCRAFT MAINTENANCE FACILITIES	
14.1	Function	52
14.1.1	Maintenance Responsibilities	52
14.1.2	Maintenance Facilities	52
14.2	Location	52
14.3	Design Requirements	52
14.4	Architectural and Civil Requirements	52
14.5	Security	53
14.6	Mechanical Requirements	53
14.7	Electrical Requirements	53
14.7.1	Emergency Power	53
14.7.2	400-Hertz Power	53
14.7.3	Power Outlets	53
14.7.4	Communications	53
Section 15	MARINE CORPS AIRCRAFT GROUP AVIATION SUPPLY SUPPORT CENTER	
15.1	Function	54
15.2	Location	54
15.3	Architectural Requirements	54
15.3.1	Spaces	54
15.3.1.1	Administrative	54
15.3.1.2	Security Area	54
15.3.1.3	Receiving and Issue and Supply	54
15.3.1.4	Interior Storage	54
15.3.2	Building Access	54
15.3.3	Building Protection	54
15.4	Mechanical Requirements	55
15.4.1	Heating and Ventilation	55
15.4.2	Air Conditioning	55
15.4.3	Plumbing	55
15.4.4	Noise and Vibration Control	55
15.5	Electrical Requirements	55
15.5.1	Power Outlets	55
15.5.2	Lighting	55
15.5.3	Communications	55

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

Page

APPENDIX

APPENDIX A Facility Plates 57

FIGURE

1 Parachute Packing and Storage Relative Humidity Limits 27

REFERENCES 153

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Section 1: INTRODUCTION

1.1 Scope. This handbook contains criteria for the design of Navy and Marine Corps aircraft maintenance facilities, except most Naval Air Rework Facilities (NARFs), to support the Naval Aviation Maintenance Program in accordance with Chief of Naval Operations (OPNAV) OPNAVINST 4790.2D, The Naval Aviation Maintenance Program.

1.2 Cancellation. This handbook cancels and supersedes NAVFAC DM-28.1 of December 1982.

1.3 Other Design Considerations. Aircraft maintenance officers of shore activities are to be closely consulted throughout the entire design effort of any project related to the construction, repair, or modernization of aircraft organizational and intermediate facilities (refer to Vol. 1 of OPNAVINST 4790.2D). This is to ensure that technical requirements for specific aircraft maintenance and testing procedures as outlined in Naval Air (NAVAIR) technical manuals receive proper consideration in the design of these facilities.

1.4 Facility Plates. As definitive drawings are revised, they are being restructured to be included in the handbook covering that type of building. These are included in the handbooks and are titled facility plates (refer to Appendix A). The facility plate number is the category code number, and the sheets required to present the information are numbered sequentially.

1.5 Definitive Drawings. Definitive drawings, where they exist for aircraft maintenance facilities covered by this handbook, are contained in NAVFAC P-272, Part 1, Definitive Designs for Naval Shore Facilities, and Part 4, Definitive Designs for Marine Corps Facilities, and are an integral part of the Naval Facilities Engineering Command (NAVFACENGCOM) design program. Definitive drawings are listed in numerical sequence by the Navy category code number assigned to that facility. Definitive drawings associated with this handbook shall be used as the basis for design, unless prior clearance for change is obtained from NAVFACENGCOM. The architectural treatment, materials, framing, and construction may vary. Special design features for a particular aircraft system will be provided by the system facilities requirement document of the NAVAIR Facilities Branch.

1.6 Planning Criteria. Naval Aviation is a highly dynamic, field and maintenance concepts depend increasingly on state-of-the-art computer technology. Planning factors in that NAVFAC P-80, Facility Planning Criteria for Navy and Marine Corps Shore Installations, and design criteria included within the NAVFAC criteria manuals are a guide that must be used with specific Weapons System FDRs to design a fully usable aviation facility. NAVAIR Facilities Management Division, Fleet Support Branch, works with the weapons systems developers to identify unique aviation facility requirements. NAVAIR engineering personnel are available during design and construction to provide

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

specialized expertise to NAVFAC or to arrange for weapons system manufacturers' representatives to attend design reviews if/when requested by NAVFAC/EFDs or aviation facility users.

1.7 Building Functions. Naval and Marine Corps shore aircraft maintenance complexes consist of buildings and/or Mobile Facilities (MFs). In these complexes are facilities and shops for the repair and maintenance of aircraft and all component parts. The Aircraft Intermediate Maintenance Department (AIMD) officer complex normally includes the following shops (buildings):

a) AIMD Administration,
b) Airframes Shop,
c) Engine Maintenance,
d) Avionics Shop,
e) Aviation Armament Shop (see Facility Plates in Appendix A),
f) Aviation Life Support Systems,
g) Engine Test Cells,
h) Battery Shops, and
i) Ground Support Equipment Shop.

While the construction of Mobile Facilities is not covered in this handbook, their interrelated use and connection to the buildings shall be a considered part of each design.

1.8 Organizational Communications. An intercommunicating two-way voice system, with use restricted to maintenance and material management (3M), shall be provided. The system will connect the AIMD officer, assistant officer, and production control office with each squadron maintenance control office in the aircraft maintenance hangar and the production control offices in the:

a) Airframes Shop,
b) Avionics Shop,
c) Engine Maintenance Shop,
d) Ground Support Equipment (GSE) Shop,
e) Aviation Armaments Shop, and
f) Aviation Life Support Systems Shop.

NOTE: The AIMD will be located in the station administration building, a separate maintenance administration building, or one of the shop buildings (preferably the Avionics Shop). For maintenance hangars' organizational communications, refer to para. 2.6.

1.9 Energy Conservation. Energy conservation shall be a major consideration in the design of building envelopes, mechanical systems, and electrical systems for aircraft maintenance facilities. Refer to NAVFAC DM-3.03, Heating, Ventilating, Air Conditioning, and Dehumidifying Systems, each building envelope shall be insulated to provide the minimum heat transmission ("U") factors practical to meet energy budgets.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

1.10 Environmental Concerns. The maintenance facilities shall meet all applicable pollution abatement criteria. For applicable discharge criteria NAVFAC HQ and the cognizant EFD should be consulted. Refer to NAVFAC DM-5.08, Civil Engineering - Pollution Control Systems, DM-5.09, Civil Engineering Metering, Instrumentation and Control, and Chemical Feeding, and DM-1.03, Architectural Acoustics.

It is essential that, as part of the preliminary studies, consideration be given to water conservation and source control, including the possibility of substantial alteration of the process or plant operation to reduce pollutant loading. The greater the volume of wastewater to be treated and the greater the amount of contaminant to be removed or destroyed, the higher are the capital, labor, and material costs required. As a result, it is often economical to eliminate or reduce the quantity of waste at its source prior to treatment or in place of treatment. Several possible techniques exist including process change, material recovery, segregation, and water reuse. Sometimes, with only partial purification, spent water can be reused, once or several times, in the industrial process. Water unsuitable for direct reuse may be serviceable for a different purpose, in which quality requirements are less restrictive.

Often, there are a number of alternatives that can achieve the desired result. Therefore, a major objective of the preliminary studies should be to determine what combinations of actions will be the most cost-effective and technically and operationally feasible.

1.11 Building Protection. The building structure of all aircraft maintenance facilities, including corners of interior partitions and exterior walls, doors, structural members, etc., shall be protected from damage by vehicles and moving loads by the installation of concrete-filled pipe guards, bumpers, railings, corner guards, and similar protective features.

1.12 Loading Dock Ramp Protection. Each facility requiring a loading dock ramp shall be provided side-edge protection in accordance with Section 1910.23c of Public Law 29, Code of Federal Regulations, Occupational Safety and Health Act Standards Manual.

1.13 Fire Protection. Fire protection for all aircraft maingenance facilities shall be provided in accordance with NAVFAC MIL-HDBK-1008, Fire Protection for Facilities Engineering Design and Construction, as applicable to the specific building.

1.14 Restrictions on the Use of Uncoated Aluminum

1.14.1 Seacoast. Aluminum roofing and/or siding shall not be specified for structures located within 10 miles (3.05 km) of the seacoast, due to salt deposition or incrustation from inshore winds and salt-laden atmosphere.

1.14.2 Exterior and Interior. The restrictions for the use of preformed (corrugated) aluminum roofing and/or siding are applicable also to sandwich panel and flat sheet construction of unprotected (uncoated) aluminum and to

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

ribbed aluminum extrusions. Consideration should also be given to the corrosion of aluminum surfaces on the interior of structures due to salt deposits from salt-laden air.

1.14.3 Incompatible Materials. All surfaces of incompatible metals; wet, green, or damp wood; wood treated with incompatible preservatives; masonry; and concrete shall be isolated from direct contact with the aluminum by a heavy coat of alkali-resistant paint or by other approved means.

1.14.4 Coated Metal. Coated metal roofing and siding shall be in accordance with NAVFAC Naval Facilities Guide Specification (NFGS) NFGS-07410, Preformed Metal Roofing and Siding.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Section 2: MAINTENANCE HANGAR

2.1 Function. The Maintenance Hangar shall be designed to provide weather-protected shelter for the servicing and repair of Navy and Marine Corps aircraft, emergency shelter for operable aircraft, and headquarters and office space for squadron personnel. This type of hangar shall consist of hangar (OH) space, shop and equipment (01 level) spaces, and administrative (02 level) spaces required to support the aircraft and the mission of the particular squadron or activity occupying the hangar at any particular time. The optimum Maintenance Hangar design usage shall be the support function of one or two complete squadrons dependent upon the type of aircraft involved. Squadrons housed in maintenance hangars may be either permanent or mobile, as defined in NAVFAC P-80.

2.2 Location. The siting of maintenance hangars shall be correlated to minimize distance between the hangar and parked aircraft while maximizing the efficiency of operations and visual and verbal communications. Factors that must be emphasized include building orientation to apron and taxiways, modular expansion, line shack locations, intermediate maintenance shop relationship, ground support equipment (yellow gear) location and storage, and unique climatic conditions. For the relationship of hangars to adjacent facilities, refer tO NAVFAC P-272, Part 1.

2.3 Architectural and Structural Requirements. The Maintenance Hangar shall be a modular building designed to allow flexibility and economical expansion by internal rearrangement and/or additional modules. Modules shall be designed to meet necessary flexibility and maintenance requirements in organization, strength, quantity, type of aircraft, and level of maintenance. There are two types of modular maintenance hangars, as indicated by NAVFAC P-272, Part 1: Type 1 and Type II. A Type I Maintenance Hangar is principally designed for carrier aircraft, but it is adaptable to meet flexibility requirements for rotary-wing aircraft and various types of smaller general purpose and special mission aircraft. The 01 level and 02 level spaces in this type of hangar are configured for a typical attack squadron, two carrier air early warning squadrons, and a headquarters and maintenance services squadron. A Type II Maintenance Hangar is principally designed for patrol aircraft, but it is adaptable for larger general purpose or special mission aircraft. The 01 level and 02 level spaces are designed to accommodate a typical heavy antisubmarine warfare patrol squadron. Adequate and secure storage space shall be provided throughout the Maintenance Hangar as required by the offices and shops occupying the facility. For larger special mission aircraft, hangars shall be designed for specific requirements.

2.3.1 Structure. The modular structure of the Maintenance Hangar shall be a steel frame with a rigid cantilever web truss roof. The hangar shall be designed using prefabricated components to the maximum extent practicable. Weathering steel, if considered, shall not be used where exposed to recurrent wetting by salt-water. In areas where weathering steel is acceptable, proper detailing and use of materials shall be a requirement to prevent staining of adjacent building components. The overall structural suspension system shall be designed for wind uplift conditions peculiar to the site. A bridge crane

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the currentversion before use.

shall be provided in the OH space of maintenance hangars supporting helicopters or AV-8, C-9, P-3, or C-130 aircraft. Bridge cranes shall not be used in maintenance hangars supporting other types of aircraft except in specialized instances approved by NAVFAC Headquarters or when specifically required by the Facilities Requirement Document (FRD). A storage mezzanine shall be provided in the OH space of both Type I and II maintenance hangars and designed for a live load of 100 psf (488 kg/m^2). Storage areas must comply with National Fire Protection Association (NFPA) NFPA 409, Aircraft Hangars, requirements for minimum 1-hour separation. Requirements for the bridge crane, motor, and controls are given in para. 2.8.

2.3.2 Roof Systems. The roof system, due to large surface area and proximity to operating aircraft, shall be carefully selected. Expansion joints, insulation vents, and traffic pads or walkways shall be provided where applicable. Insulation shall be provided as required in para. 1.6. On built-up roofs, the design shall preclude carrying gravel or slag aggregate from the roof surface by high winds or drainage to any area in which aircraft operate. The color of roof surfaces shall be as described in para. 2.3.8. Gutter and outrigger downspouts shall be provided at the front of the hangar. Snow guards shall be provided at the front of the hangar in areas subject to heavy snowfall. Interior access from 02 spaces to the low roof and exterior access to the high roof shall be provided through a secured access panel or hatch, to prohibit unauthorized passage. The most suitable roof systems shall be selected from the following criteria:

a) Very low slope (minimum of 1/4 in. per ft). Where roof slopes are 1/4 in. per ft (6 mm per 305 mm), decks shall be stiff enough to prevent ponding, and a built-up roof should be smooth-surfaced. Built-up roofing, insulation, and moisture protection shall conform to the applicable NAVFAC Guide Specifications listed in NAVFAC P-34, Engineering and Design Criteria for Navy Facilities. One of the following systems shall be used:

(1) Metal roof decking with insulated, built-up roof.

(2) Poured-in-place gypsum slab on formboard with insulated built-up roof.

(3) Pre-engineered insulated metal roof panels (only on roof with slope of 1 in. (25.4 mm) per ft or greater).

b) Pitched roofs. Insulated metal roof panels shall be used. Panels shall be pre-engineered or field-fabricated and filled with blanket or rigid insulation (with insulation blocks over purlins).

c) Other types of roofs based on cost and energy savings, can be considered.

2.3.3 Wall Systems. All walls and partitions shall be nonload-bearing.

2.3.3.1 Exterior Walls. Sidewalls of the OH space shall be insulated concrete masonry units (minimum 50 percent solid with joint reinforcing) or other cementitious materials, to a height of 10 ft (3.05 m) above the hangar deck. Above this height, preformed (corrugated), protected-metal panels,

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

backed with rigid or blanket insulation, shall be used, except that translucent reinforced fiberglass panels should be used to increase natural lighting. All insulated panels shall be capable of withstanding water effects of deluge discharge. The installation of translucent wall panels is contingent upon an energy analysis for areas having 3,000 heating degree-days or better. It must be shown that the quantity of lighting-related energy saved exceeds the quantity of heating-related energy lost through the uninsulated, translucent panels. Factors that should be considered other than degree-days are light transmission and the coefficient of heat transmission (U factor). In areas of seismic activity, seismic codes shall govern for this wall construction. Aluminum panels may be used only in accordance with para. 1.11. All exterior walls of the 01/02 levels of the structure shall be concrete masonry units, including walls abutting OH space, with all voids filled with insulation. Windows to the exterior of the 01/02 level spaces shall be operable thermopane units. Any framing and connecting paneling between windows shall be insulated store-front units.

2.3.3.2 Interior Partitions. The interior partitions shall be metal studs with vinyl-covered gypsum wallboard or hardboard facing over insulation (when essential to minimize noise transmission between spaces). Surface materials of interior partitions shall meet the requirements in NAVFAC MIL-HDBK-1008. All 01 and 02 level spaces, except soundproofed spaces, shall be designed to provide the Preferred Noise Criteria (PNC) levels given in Table 3-9 of NAVFAC DM-1.03. Administrative spaces requiring soundproofing shall be treated with above-ceiling barriers and shall be designed to provide a PNC of 25. Above-ceiling barriers shall be provided for spaces that require locked doors. Windows from the 02 level to the OH space shall be 1/4-in. (6 mm), fixed, tempered wire glass in steel frames and shall be provided with sound-attenuating drapes. Tempered wire glass windows shall be provided, to the extent allowed by the various codes, in swinging fire doors between shops, control rooms, and the OH area. In all 01- and 02-level administrative and shop spaces, a system shall be provided for hanging charts and schedules on all available wall surfaces. Corners of partitions in the 01 space shall be protected with corner guards.

2.3.4 Floors. Maintenance hangar floors shall meet the following criteria:

a) The primary loading areas of the hangar floors shall be designed in accordance with criteria in NAVFAC DM-21 Series, Airfield Pavement Design.

b) Hangar floors shall be sloped towards hangar doors and drains.

c) Hangar floors that are to be used for aircraft maintenance may be coated with a catalytically-cured, Chemically-resistant Urethane (CRU), reflective coating system, which shall include appropriate grit to provide slip resistance. Such coating systems are described in more detail in NAVFAC Guide Specification NFGS-09921, Reflective Floor Coatings for Aircraft Maintainance Facilities. These coatings will increase the underside illumination of aircraft fourfold, but the three-coat system with 30-mesh grit that is typically used may lose a significant portion of the grit within 1 year if not carefully used and may become objectionably slippery. Alternate systems discussed in NAVFAC NFGS-09921 should give better performance.

Source: https://assist.dla.mil -- Downloaded: 202640-26T13:56Z
Check the source to verify that this is the currentversion before use.

d) Floors of personnel and administrative spaces shall be designed for a uniform live load of 100 psf (488 kg/m^2) and provided with floor coverings as designated in NAVFAC MIL-HDBK-1001/2, Materials and Building Components. A subfloor electrical distribution system through metal ducts and built-in junction boxes through the concrete top layer shall be provided on a modular basis.

2.3.5 Ceilings. All administrative and personnel spaces shall be provided with a noncombustible, suspended acoustical ceiling. All toilet, locker, and cleaning gear room ceilings shall be water-resistant.

2.3.6 Doors and Door Controls. Doors and door controls shall meet the criteria defined in paras. 2.3.6.1 through 2.3.6.5.

2.3.6.1 Hangar Doors. Hangar doors shall be a series of insulated, horizontal sliding leaves with protected, preformed (corrugated) metal or sheet-steel siding. Each sliding door leaf shall be supported on hardened wheels rolling on recessed rails with guide rails at the top of the door. Thresholds shall be designed to minimize dirt accumulation or ice buildup at rails. Leaves of the door shall be insulated and shall be provided with waterproof weatherstripping and emergency personnel exits as required by NFPA 101, Code for Safety to Life from Fire in Buildings and Structures. The hangar doors shall be hand-crank-operated or electric motor-operated. For electric motor operation, drives may operate leaves independently or in groups of three with drives on the end leaves and a pickup mechanism for the center leaf. The use of a cable system for the pickup mechanism should not be considered due to the extra maintenance required to keep the cable system in good operating condition. Each drive unit shall have a release mechanism, and the doors shall be provided with a means of movement in the event of power failure. The minimum speed of door travel shall be 60 fpm (0.3 m/s).

Control of the doors shall be by momentary contact type pushbuttons located near the leading edge of the door and limit switches on each door leaf. Safety devices shall be installed to prevent injury to personnel and damage to equipment by moving door sections. An alarm shall sound in conjunction with safety warning beacons when doors are in motion. Sliding steel hangar doors shall be in accordance with NAVFAC NFGS-08301, Steel Sliding Hangar Doors.

2.3.6.2 Personnel Doors. Personnel doors between the hangar (OH) and shop spaces (01 level) shall be 3/4-hour, C-rated, self-closing, insulated fire doors. Hold-open devices shall not be permitted.

2.3.6.3 Interior Personnel Doors. Interior personnel doors to stairways shall be self-closing, swinging doors. Hold-open devices shall not be permitted. Refer to the appropriate specification as listed in NAVFAC P-34.

2.3.6.4 Overhead Doors. Overhead doors between the hangar (OH) and shop spaces (01 level) shall be 3/4-hour, C-rated.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

2.3.6.5 Other Doors. For other doors, provide stock industrial doors in accordance with the appropriate specifications listed in NAVFAC P-34. Provide one self-closing, insulated personnel exit door through the middle leaf of hangar door group and in each side wall of the hangar (OH space). No hold-open device shall be permitted. A vehicle access door must be provided either within or adjacent to the hangar aircraft access doors.

2.3.7 Soundproofing. The spaces requiring soundproofing, as shown on NAVFAC Drawings 1291710, 1291712, and 1291714 of NAVFAC P-272, Part 1, shall be soundproofed to reduce the noise level from the outside to a PNC of 25. Refer to NAVFAC DM-3.10, Noise and Vibration Control of Mechanical Equipment. Spaces shown in the facilities requirements document as containing equipment generating high noise levels shall be soundproofed to limit noise levels in adjacent spaces to acceptable levels.

2.3.8 Surface Treatment. The chemical properties of materials and finishes for exterior surfaces shall have the highest resistance to the effects of weather and salt-corrosive atmosphere.

Painting of all spaces shall be in accordance with the NAVFAC DM-1 Series, Architecture. The color of paint for hangar (OH) space shall be white and compatible with the reflective floor finish.

To prevent mirrorlike reflections from building surfaces to aircraft in flight, roofs and other external surfaces shall have a specular reflectance compatible with the location of the building on the airfield. If the building is so located that glare may be an operational hazard, the critical surfaces of that building shall have a light reflectance of not more than 10, measured at an angle of 85° F (29° C) in accordance with American Society for Testing and Materials (ASTM) ASTM D523-80, Standard Test Method for Specular Glass.

2.3.9 Exterior Pavement. Exterior paved areas shall include aircraft and vehicle access and nonorganizational parking. Aircraft pavement shall be in accordance with NAVFAC DM-21 Series. Vehicle access and parking shall be in accordance with NAVFAC P-272, Part 1 and P-272, Part 2, Definitive Designs for Naval Shore Facilities; NAVFAC DM-5.04, Civil Engineering - Pavements; and MIL-HDBK-1190, Facility Planning and Design Guide.

2.4 Mechanical Requirements. The Maintenance Hanger shall be designed to meet the criteria set forth in paras. 2.4.1 through 2.4.6.

2.4.1 Heating. Heating shall be provided in accordance with NAVFAC DM-3.03 and as follows:

a) Design for an infiltration rate of two air changes per hour in the OH area. This rate is dependent upon the installation of nylon brush insulation seals on the hangar sliding doors.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

b) A switch activated by opening the hangar doors shall override the space thermostat to stop the heating equipment in the OH area. Provide a minimum temperature thermostat field set at 34° F (1° C) to override the heating deactivation switch during door-open periods of subfreezing ambient temperatures. After the doors are closed, the room thermostat should assume control. Heating system recovery time shall be 30 minutes after the doors are closed.

c) A snow-melting system at the hangar door tracks shall be installed when outside design temperature is +25° F (-4° C) or lower and historical snow accumulation data supports the requirement.

d) An underfloor heating system shall be provided for the OH area when outside design temperature is below -10° F (-23° C).

e) The automatic thermostatic control shall meet the requirements of NAVFAC DM-3.03.

f) Each bay in the OH area shall be a separate heating zone.

g) Refer to NAVFAC P-272, Part 1, for design conditions.

h) Consider the installation of Naval Civil Engineering Laboratory (NCEL) Cold Jet Destratifiers based on an economic analysis.

2.4.2 Ventilation. Ventilation shall be provided in accordance with NAVFAC DM-3.03 and as follows:

a) Toxic fumes and combustible vapor that generated in work areas shall be exhausted directly to the outside.

b) If fuel systems maintenance is performed, a system for purging the fuel line and the tanks shall be provided. A fuel vapor exhaust system shall also be provided.

2.4.3 Air Conditioning. Air conditioning shall be provided in accordance with NAVFAC DM-3.03 and MIL-HDBK-1190. Automatic thermostatic control shall be provided, and equipment shall be shut down when not required for cooling.

2.4.4 Plumbing. Plumbing shall be provided in accordance with NAVFAC DM-3.01, Plumbing Systems, and shall provide:

a) an adequate storm drainage system,

b) trench drains with sufficient laterals for aeration and easy cleanout of oil or other residue,

c) an emergency shower/eyewash fixtures and floor drains, as shown in NAVFAC P-272, Part 1,

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the currentversion before use.

d) an oil/water separator for trench drains, and

e) storm drains located a minimum of 12 in. (305 mm) from the hangar access door rails.

2.4.5 Compressed Air. Compressed air shall be provided in accordance with NAVFAC DM-3.05, Compressed Air and Vacuum Systems. Compressed air shall be provided for airframe shops at 40 scfm (0.018 m^3/s) and 125 psi (862 kPa) and for hangar (OH) space, as required by NAVFAC DM-28.06, Aircraft Fixed Point Utility Systems, for hangar service points.

2.4.6 Noise and Vibration Control. All mechanical systems and equipment shall be designed to limit noise and vibration in accordance with NAVFAC DM-3.10.

2.5 Electrical Requirements. Electrical systems shall be provided in accordance with the NAVFAC Electrical Engineering Criteria Manuals and paras. 2.5.1 through 2.5.4 of this handbook.

2.5.1 Hangar (OH) Space. The Maintenance Hanger (OH) space shall be designed to meet the criteria set forth in paras. 2.5.1.1 through 2.5.1.2.

2.5.1.1 Hazardous Zones. Areas in high bay space shall be classified as hazardous or nonhazardous in accordance with the NFPA 70, National Electrical Code, and electrical installations shall meet applicable requirements. Where possible, electrical installations will not be located in hazardous zones.

2.5.1.2 Power Service Points. NAVFAC DM-28.06 identifies the various types, the capacity, and the location and installation requirements of electrical power to be provided at the power service points.

2.5.2 Type I/II Spaces. Power outlets shall be provided for shop tools and at shop bench locations. In the electronics shop, electrical power outlets shall be provided as follows:

a) Three-phase, 115/200 V, 400 Hz, 100 A capacity.
b) Three-phase, 60 Hz, 480 V, 100 A capacity.
c) 28 V direct current, 50 A capacity.

Grounded convenience outlets at 60 Hz, 120 V, 20 A capacity shall be provided throughout the Type I/II administrative, personnel, and shop spaces as required by NFPA 70.

2.5.3 Lighting. Lighting for the Maintenance Hanger shall be designed to meet the criteria set forth in paras. 2.5.3.1 through 2.5.3.2.

2.5.3.1 Interior Lighting. Interior lighting in the hangar OH space shall be an energy-efficient type, such as high-pressure sodium vapor. Other interior lighting shall be fluorescent. Lighting intensities shall be designed in accordance with MIL-HDBK-1190 and shall take into consideration the reflectance of wall and floor surfaces, especially in hangar (OH) spaces with reflective floor finish.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

2.5.3.2 Exterior Lighting. Exterior lighting shall be of the high-pressure sodium vapor type where practical and shall be in accordance with the NAVFAC DM-4 Series, Electrical Engineering.

2.5.4 Grounding. The Maintenance Hangar shall be provided with flush floor ground-receptacles, each with a 3/4-in. (19 mm) diameter ground rod, on 24-ft (7.3 m) centers across the centerline of the OH space. Resistance to ground shall be 25 ohms maximum. All ground receptacles shall be provided together with No. 4 AWG bare copper in or below the hangar floor.

2.6 Organizational Communications. The Maintenance Hangar shall be provided with internal communications as described in paras. 2.6.1 through 2.6.4 (refer to para. 1.5 for other organizational communications requirements).

2.6.1 3M Communications (Maintenance and Material Management). An intercommunications system, with use restricted to aircraft maintenance and material operations only, shall be provided. This system shall provide two-way communications from line operations shacks outside the hangar to and between all rooms in the Type I space except passages, locker and toilet rooms, and mechanical equipment room. The necessary raceway shall be provided in new building construction, with provisions in some instances for interconnection with other buildings.

2.6.2 Intercommunications System. An intercommunications system shall be provided to allow two-way communications between:

a) all rooms in the Type II space except passages, locker and toilet rooms, and storage rooms,

b) all department heads and the commanding officer and executive officers of the squadron,

c) officers' ready room and maintenance control, and the

d) administration office and maintenance administration.

2.6.3 Public Address System. A public address system shall be provided to reach interior and exterior work areas and the aircraft parking apron.

2.6.4 Television Surveillance System. A closed-circuit television surveillance system shall be provided in support of maintenance control and security. Two cameras shall be mounted on opposite ends of the hangar at the rear wall line just below truss level and shall be positioned to cover the OH space. Cameras shall be mounted on the exterior of the hangar and positioned to cover assigned apron spaces. Television monitors shall be located in the maintenance control office and the duty office.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

2.7 Security. The Maintenance Hangar shall contain secure storage vaults with walls of 8-in. (203 mm) masonry extending to the roof level. Vaults shall meet security requirements of the facility in accordance with Chapter V of OPNAVINST 5510.1G, Department of the Navy Information Security Program Regulation. In Marine Corps hangars, secure space shall be provided for organizational small arms.

2.8 Weight-Handling Equipment. The Maintenance Hangar shall contain overhead bridge cranes and jib cranes in accordance with criteria in NAVFAC DM-38.01, Weight-Handling Equipment, and paras. 2.8.1 and 2.8.2 for Types I and II (OH) spaces.

2.8.1 Bridge Cranes. Overhead bridge cranes shall have an electric motorized bridge, trolley, and hoist and shall be 6-ton (5,443 kg) capacity. Trolley and bridge shall be capable of operating at a slow speed of 15 to 20 ft/min (0.076 to 0.102 m/s) for positioning loads and at a high speed for moving loads of 60 ft/min (0.305 m/s); the hoist shall be capable of operating at a slow speed of 3 to 4 ft/min (0.015 to 0.02 m/s) and at a high speed of 12 ft/min (0.06 m/s). Refer to NAVFAC NFGS-14637, Cranes, Overhead Electric, Underrunning (Under 20,000 Pounds).

2.8.1.1 Motor and Controls. Bridge, trolley, and hoist controls shall provide for two-speed reversing of a two-speed, squirrel-cage motor. The controls shall be equipped with reduced voltage starting for the motors. Controls shall be operable from the floor.

2.8.1.2 Hook Height. The hook height for bridge cranes shall be as required to raise engines and transmissions clear of aircraft.

2.8.2 Jib Cranes. Jib cranes shall be electrically operated with a capacity of 500 pounds (226.5 kg). Jib cranes shall be capable of transferring a palletized load from the hangar deck to the mezzanine level.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Section 3: CORROSION CONTROL HANGAR

3.1 Function. The Corrosion Control Hangar shall be designed to provide space and equipment for the corrosion control processing of aircraft at the intermediate maintenance level. Functions performed in the Corrosion Control Hangar include: deicing, limited detergent washing and rinsing, paint stripping, corrosion removal, protective coating application and painting, and finish curing and drying. Refer to NAVAIR Technical Manual 01-1A-509, Aircraft Weapons Systems Cleaning and Corrosion Control, for detailed functions performed in this facility.

3.2 Location. The Corrosion Control Hangar should be located in proximity to the maintenance hangars and as close as possible to an aircraft washrack. Access between the Corrosion Control Hangar, the Maintenance Hangar, and the aircraft washrack is required. The prevailing wind should be considered in orienting the building in relation to aprons, taxiways, and parking, to allow for exhaust air dispersal over areas not affected by solvent fumes.

3.3 Architectural Requirements. Two types of corrosion control hangars are indicated in NAVFAC P-272, Part 1: Type A and B. The Type A Corrosion Control Hangar is designed for carrier aircraft and other small aircraft, and the Type B Corrosion Control Hangar is designed for land-based patrol aircraft and other large aircraft. Because both construction and operating costs increase as the volume of the hangar bay increases, corrosion control hangars for aircraft larger than those accommodated by the Type B hangar shall be individually designed around the specific dimensions of the aircraft concerned. Approval from the Naval Facilities Engineering Command shall be obtained prior to the commencement of final design of such hangars. The general architectural criteria of Section 2, covering maintenance hangars, shall apply to the Corrosion Control Hangar.

3.3.1 Structure. The hangar structure shall be steel frame with open-web, steel-joist roof. The structure for areas adjacent to the hangar area shall be load-bearing, insulated, concrete-masonry unit construction with open-web, steel-joist roof. The strip/rinse room shall be equipped with a 2-ton (1,814 kg) overhead monorail. The requirements of NFPA-33, Spray Application Using Flammable and Combustible Materials, shall be incorporated into the design.

3.3.2 Walls. Hangar walls shall meet the following criteria:

a) Exterior walls of the hangar area shall be a steel frame and girts framing system with insulated preformed (corrugated) metal siding. Exterior walls of the other areas shall be insulated concrete masonry units.

b) The hangar area shall be separated from paint mixing and storage rooms, chemical mixing room, cleaning gear and storage room, corridor, and toilet and locker areas, by 2-hour, fire-rated walls. Painting and chemical mixing and storage rooms shall also be separated by 2-hour firewalls.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

3.3.3 Roofs. Roofs shall meet the criteria defined in para. 2.3.2.

3.3.4 Floors. The hangar area floor shall be designed in accordance with criteria in NAVFAC DM-21 Series and may have a reflective floor coating. Other floors shall be designed in accordance with the NAVFAC DM-2 Series, Structural Engineering, and provided with floor coverings as specified in MIL-HDBK-1001/2.

3.3.5 Ceilings. All aircraft bays and paint storage, mixing, and spray areas shall have water-resistant gypsum ceilings. Suspended acoustical ceilings shall be provided for corridors, toilets, locker rooms, and offices. Suspended acoustical ceiling panels in shower areas shall have vinyl plastic surfaces. The strip/rinse room ceiling shall be of corrosion-resistant, perforated metal.

3.3.6 Doors and Door Controls. Doors and controls shall be as described in paras. 3.3.6.1 through 3.3.6.3.

3.3.6.1 Hangar Doors. Hangar doors shall be a specialized, insulated, hangar type with swinging leaves. These doors shall also serve as an insulated supply air plenum during test operation. Each door leaf shall be a motor-operated unit with a release mechanism, and the doors shall be provided with a means of movement in the event of a power failure. Adequate safety devices shall be installed to prevent injury to personnel and damage to equipment due to moving door sections. Thresholds shall be designed to minimize dirt accumulation and ice buildup.

3.3.6.2 Personnel Doors. Personnel doors between the hangar area and paint and chemical mixing rooms and the corridor shall be 1-1/2-hour, B-rated, self-closing fire doors. Hold-open devices shall not be permitted.

3.3.6.3 Other Doors. Other doors shall be as described in para. 2.3.6.e. One self-closing, insulated personnel exit door through each hangar door shall be provided. No hold-open devices shall be permitted. Special precautions shall be taken to seal doors between hangar areas and exterior or adjacent spaces. A vehicle access door shall be provided either within or adjacent to the hangar aircraft access doors.

3.3.7 Building Insulation. Building walls, roofs, and floors shall meet the criteria defined in para. 1.6.

3.3.8 Surface Treatment. In addition to the requirements of para. 2.3.8, the side walls, the inside of hangar doors, and the ceiling of the hangar area shall be provided with a light color, smooth surface such as white enameled metal panels.

3.3.9 Exterior Pavement. Exterior paved areas include aircraft and vehicle access and nonorganizational parking. Aircraft pavement shall be in accordance with the NAVFAC DM-21 Series. Vehicle access and parking shall be in accordance with NAVFAC P-272, Parts 1 and 2; NAVFAC DM-5.04; and MIL-HDBK-1190.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

3.4 Mechanical Requirements. The design of the Corrosion Control Hangar shall meet the mechanical requirement set forth in paras. 3.4.1 through 3.4.5.

3.4.1 Heating. Heating shall be provided in accordance with NAVFAC DM-3.03 and as follows:

a) Based on an economic analysis, consideration shall be given to providing a system for the recovery of heat from the exhaust air.

b) Following completion of paint stripping or paint application, the release rate of hazardous vapors decreases with time, with the heaviest concentration occurring during the paint stripping or application operation and the first 30 minutes after completion of the operation. As the hazardous vapor concentration decreases, the airflow rate can be decreased below that initially required for worker safety. When the vapor concentration lowers to a selected level, the use of contaminant monitors in the exhaust air to shut off selected fans should be considered to save fan power energy and heat energy.

The hangar area shall be equipped with an automatic cutoff of the heating system when the main hangar doors are open. Minimum temperature thermostat field shall be set at 34° F (1° C) to override the heating deactivation switch during door-open periods of subfreezing ambient temperatures. The recovery time for the heating system shall be 30 minutes after door closure.

c) Provide a snow-melting system at the hangar door tracks when the outside design temperature is plus 25° F (-4° C) or lower and when historical snow data supports the requirement accumulation.

d) Refer to NAVFAC P-272, Part 1, for design conditions in other hangar spaces.

e) Each bay in the OH area shall be a separate heating zone.

f) Heating shall be suitable for operation in the vapor hazard in the corrosion control and flammable storage mixing areas.

3.4.2 Ventilation. Ventilation shall be provided in accordance with NAVFAC DM-3.03 and by NFPA-33. Refer to NAVFAC P-272, Part 1, for the location of ventilation components. The ventilation system for the hangar area shall furnish 100-percent filtered outside air at a horizontal laminar flow velocity of 60 fpm (0.305 m/s) for electrostatic spraying and 100 fpm (0.51 m/s) for conventional spraying across the entire cross-section area of the stripping painting hangar bays. The ventilation system shall maintain a positive minimum static pressure of 0.10 in. (2.54 mm) water gage between the hangar area and exterior or adjacent spaces.

Filters throughout the hangar shall be made from noncombustible materials and shall meet approval of the fire control authorities. Filters having a minimum atmospheric dust spot efficiency of 30 percent on the basis

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

of the American Society for Heating, Refrigertation, and Air Conditioning (ASHRAE), ASHRAE Standard 52-76, Method for Testing Air Cleaning Devises Used in General Ventilation for Removing Particulate Matter, shall be provided at the intake to air-handling units. Grills with adjustable bar louvers shall be provided over the door supply plenum outlet to allow adjustment of air space flow in horizontal and vertical planes. The type of exhaust filter system shall be determined by an analysis of environmental control regulations at the site. The disposal cost of the replaceable dry type filters shall be compared with the sludge disposal and water treatment costs of a waterwash filter system. The compressed air system for paint spraying shall be electrically interlocked with the ventilation system, so that spray painting cannot be accomplished unless the exhaust fans are operating. Exhaust ventilation from the floor level shall be provided for the paint and chemical mixing and storage rooms at the rate of 1 cfm (0.00047 m^3/s) per ft^2 of floor area or 150 cfm (0.071 m^3/s), whichever is greater. The ventilation systems for all paint and chemical mixing rooms shall be provided in accordance with NFPA 33 and the American Conference of Governmental Industrial Hygenists' (ACGIH), Industrial Ventilation, A Manual of Recommended Practice.

3.4.3 Plumbing. Plumbing shall be provided in accordance with NAVFAC DM-3.01 and as follows:

a) Provide steam and hot and cold water.

b) Provide an emergency eyewash/safety shower and floor drains as shown in NAVFAC P-272, Part 1.

c) Provide an oil separator for drains from the hangar area and paint and chemical mixing rooms.

d) Storm-water drains should be located a minimum of 12 in. (305 mm) from the hangar access door rails.

3.4.4 Compressed Air. Low-pressure compressed air at 125 psi (862 kPa) shall be provided in accordance with NAVFAC DM-3.05.

3.4.5 Noise and Vibration Control. All mechanical systems and equipment shall be designed to limit noise and vibration in accordance with NAVFAC DM-3.10.

3.5 Electrical Requirements. Electrical systems shall be provided in accordance with the NAVFAC DM-4 Series and as defined in paras. 3.5.1 and 3.5.2.

3.5.1 Electrical Installations. All electrical installations in the following areas shall meet the requirements in NFPA-70 for the hazardous location listed:

a) Hangar area - Class I, Division 2, Group D.
b) Paint and chemical mixing rooms - Class I, Division 2, Group D.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

3.5.2 Lighting. The electrical requirements for lighting shall be as follows:

a) Interior lighting in the main hangar area shall be an energy-efficient type, such as high-pressure sodium vapor, with lighting intensities in accordance with MIL-HDBK-1190.

b) Exterior lighting shall be high-pressure sodium vapor where practical and shall be in accordance with the NAVFAC DM-4 Series.

3.5.3 Grounding. Two flush floor-ground receptacles, each with a 3/4-in. (19 mm) diameter ground rod, 10 ft (3.05 m) minimum length, shall be provided near the center of the aircraft position, with one on each side of the positioned aircraft. Resistance to ground shall be 25 ohms maximum. Bond all ground receptacles shall be bonded together with No. 4 AWG bare copper in or below the hangar floor.

3.6 Weight-Handling Equipment. The monorail hoist shall be in accordance with criteria in NAVFAC DM-38.01 and shall be of sparkproof construction with an explosion-proof motor. Controls shall be operable from the floor level and, when electric, shall meet the requirements indicated in para. 3.5.1.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

Section 4: AIRCRAFT WEAPONS ALIGNMENT FACILITY

4.1 Function. The Aircraft Weapons Alignment Facility shall be designed to contain space and equipment for the alignment of on-aircraft weapons systems. In addition to weapons systems alignment, which is the process of mechanically and electrically aligning aircraft weapons electronic systems to a common aircraft axis, this facility provides space for on-aircraft electronic maintenance of the weapons system. Refer to NAVFAC P-80 to determine the size of this facility. See facility plates in Appendix A for single-bay and multiple-bay configurations. For the mechanical alignment of guns attached to aircraft, refer to Section 10, Aircraft Boresight Range.

4.2 Location. The location selected for the aircraft weapons alignment facility must be free of vibration and electromagnetic interference that will adversely affect the weapons alignment. You must provide for the radar radiation clearance distances as shown on facility plates. With these conditions met, the location that requires the minimum amount of new aircraft access pavement should be selected.

4.3 Architectural and Structural Requirements. In addition to the following special requirements, the Aircraft Weapons Alignment Facility shall be designed using the general architectural criteria for maintenance hangars set forth in para. 2.3.

4.3.1 Structure. The facility shall be a steel frame modular structure. Each equipment room shall be provided to house the ground support equipment air conditioner and hydraulic test stand that are applicable to the aircraft being serviced. The mechanical room shall provide for the utilities called for in paras. 4.4 and 4.5.

4.3.2 Walls. Except for the rear wall of the facility, the exterior walls shall be preformed (corrugated), protected, insulated metal panels or insulated concrete masonry units. That portion of the rear wall within the radiation zone shall be completely free of metallic or conductive materials to prevent reflection of the radar beam.

The enclosing walls for mechanical and toilet rooms shall be solid masonry. The enclosing walls for equipment rooms shall have a 1-hour fire rating.

Openings shall be provided in walls of each equipment room for the passage of air conditioning ducts and hydraulic lines, if required by the aircraft slated to use the facility. All openings shall be equipped with sleeves with smooth, rounded edges and top-hinged closure doors.

4.3.3 Roofs. Roofs shall be designed as described in para. 2.3.2.

4.3.4 Floors. Floors shall be designed to withstand the wheel loads of the heaviest fighter or attack aircraft, in accordance with criteria in the NAVFAC DM-21 Series.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

The floor shall slope to trench drains along the front sliding doors at 1/16th of an inch per ft (2.0 mm per 305 mm). The workbay may have a reflective floor coating as described in para. 2.3.4.c.

4.3.5 Doors. Doors shall be provided that meet the following criteria:

a) Front workbay doors shall be as described in para. 2.3.6.a.

b) The rear wall of the facility shall contain an insulated door 10 ft (3.05 m) wide by 12 ft (3.66 m) high, without a curb or sill, to provide an exit for a tug. The door and door frame shall be constructed of materials that are nonmetallic and nonconductive.

c) Personnel doors between the workbays, equipment, and toilet rooms shall be as described in para. 2.3.6.b.

d) For other doors, provide stock industrial doors in accordance with the appropriate specifications as listed in NAVFAC P-34.

e) Provide personnel exit doors as described in para. 2.3.6.f.

f) A vehicle access door must be provided either within or adjacent to the hangar aircraft access doors.

4.3.6 Exterior Pavement. Exterior paved areas shall be provided for aircraft access in accordance with NAVFAC DM-21 and vehicle access in accordance with NAVFAC P-272, Part 2, and NAVFAC DM-5.04.

4.3.7 Harmonization Target. A remote-controlled, horizontally-movable harmonization target shall be provided to facilitate aircraft alignment.

4.4 Mechanical Requirements

4.4.1 Heating. Heating shall be provided in accordance with NAVFAC DM-3.03. The facility shall be equipped with an automatic cutoff of the heating system when the doors are open. Provide a minimum temperature thermostat field set at 34° F (1° C) to override the heating deactivation switch during door-open periods of subfreezing ambient temperatures. The recovery time for the heating system shall be 15 minutes after the doors are closed. In a multiple-bay facility, each bay shall be a separate heating zone. A snow-melting system at the sliding door tracks shall be installed when the outside design temperature is plus 25° F (-4° C) or lower and when historical snow accumulation data supports the requirement.

4.4.2 Ventilation. Ventilation shall be provided in accordance with NAVFAC DM-3.03.

4.4.3 Air Conditioning. Air conditioning shall be provided in accordance with NAVFAC DM-3.03 and MIL-HDBK-1190. Automatic thermostatic control shall be provided, and equipment shall be shut down when not required for cooling.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

4.4.4 Noise and Vibration Control. Hot and cold water shall be provided for one toilet room at each facility, in accordance with NAVFAC DM-3.01. Storm-water drains should be located a minimum of 12 in. (305 mm) from the hangar access door rails.

4.5 Electrical Requirements. Electrical systems shall meet the criteria of NAVFAC Electrical Engineering Criteria Manuals and paras. 4.5.1 through 4.5.3

4.5.1 Power Outlets. Each bay shall be provided with the following power outlets at the workbenches: single-phase, 120 V, 20 A, 60 Hz; 3-phase, 480 V, 60 Hz; 3-phase, 115/200 V, 400 Hz; and 28 Vdc. The ampacity of 3-phase and direct-current outlets shall be as required by the using agency for the specific facility.

4.5.2 Lighting. The interior lighting in the workbays shall be an energy-efficient type, such as high-pressure sodium vapor. Interior lighting in other spaces and task lighting above workbenches shall be fluorescent. Design for lighting intensities shall be in accordance with MIL-HDBK-1190 and shall take into consideration the reflectance of wall and floor surfaces, especially in workbays with reflective floor finish.

A system of flashing warning lights shall be provided to identify workbays where aircraft radar is operating.

Exterior lighting shall be of the high-pressure sodium vapor type where practical and shall be in accordance with the NAVFAC Electrical Engineering Criteria Manuals.

4.5.3 Grounding. Two flush floor-ground receptacles, each with a 3/4-in. (19 mm) diameter ground rod, 10 ft (3.05 m) minimum length, shall be provided near the center of the aircraft position, with one on each side of the positioned aircraft. Resistance to ground shall be 25 ohms maximum. All ground receptacles shall be bonded together with No. 4 AWG bare copper in or below the workbay floor.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Section 5: PAINT FINISHING HANGAR

5.1 Function. The Paint Finishing Hangar shall be designed for use only as a part of a Naval Air Rework Facility (NARF) for cleaning, painting, and curing aircraft surfaces using production line methods. In addition to the workbays, storage and administrative spaces shall be provided.

5.2 Location. The Paint Finishing Hangar shall be located with due regard to the requirement for aircraft and vehicle access. In orienting the building, consider the prevailing wind in relation to the intake and exhaust of large volumes of air for the ventilation system.

5.3 Arrangement. The workbays shall be arranged so that each has ready access to the outside and to equipment and storage spaces of the hangar. Workbays in which cleaning and stripping are done shall be isolated from workbays in which painting and curing are done. Administrative spaces such as work control offices may be accommodated in mezzanines. Mechanical equipment rooms shall be provided with outside access.

5.4 Architectural and Structural Requirements. Each hangar shall be designed for the size and configuration of the specific aircraft to be handled. Workbay dimensions, ceiling heights, and door openings are determined by the aircraft dimensions. The number of workbays is determined by the workload. In addition to the following specific requirements, the Paint Finishing Hangar shall be designed using the general architectural criteria for maintenance hangars, as set forth in para. 2.3.

5.4.1 Structure. Noncombustible construction materials shall be used in the hangar construction. Reinforced concrete slabs (with perimeter insulation) and columns with insulated masonry exterior walls are preferred refer to the NAVFAC DM-2 Series. The requirements of NFPA 33 shall be incorporated into the design of this facility.

5.4.2 Roofs. Roofs shall be designed in accordance with para. 2.3.2.

5.4.3 Walls. Workbays and spaces used for paint and chemical mixing shall be isolated with 2-hour fire-rated walls.

5.4.4 Floors. Workbay floors shall be designed in accordance with the criteria in the NAVFAC DM-21 Series. Other floors shall be designed in accordance with the NAVFAC DM-2 Series and shall be provided with floor coverings, as designated in NAVFAC DM-1.01, Basic Architectural Requirements and Design Considerations, and MIL-HDBK-1001/2.

5.4.5 Ceilings. All administrative and personnel spaces shall be provided with a noncombustible, suspended acoustical ceiling.

5.4.6 Doors and Door Controls. Doors shall be designed in accordance with para. 3.3.6.a.

5.4.7 Building Insulation. Building walls, roof, and floor shall be insulated in accordance with para. 1.6.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

5.4.8 Surface Treatment. In addition to the requirements in para. 2.3.9, the walls, the inside surfaces of doors, and the ceilings of the workbays shall be provided with a light-colored, smooth, hard surface.

5.4.9 Exterior Pavement. Exterior paved areas of the hangar include aircraft and vehicle access and nonorganizational parking. Aircraft pavement shall be in accordance with NAVFAC DM-21 Series, and vehicle access and parking shall be in accordance with NAVFAC P-272, Part 2, NAVFAC DM-5.04, and MIL-HDBK-1190.

5.5 Mechanical Requirements. The Paint Finishing Hangar shall be designed to meet the criteria set forth in paras. 5.5.1 through 5.5.6.

5.5.1 Heating. Heating shall be provided as described in para. 3.4.1.

5.5.2 Ventilation. Ventilation shall be provided in accordance with para. 3.4.2.

5.5.3 Air Conditioning. Air conditioning for administrative areas shall be provided in accordance with NAVFAC DM-3.03.

5.5.4 Plumbing. Plumbing shall be provided in accordance with para. 3.4.3. Industrial waste system, if required by facility pollution control procedures for control of paint stripping residue, shall be provided. Storm-water drains shall be located a minimum of 12 in. (305 mm) from the hangar access door rails.

5.5.5 Compressed Air. Compressed air shall be provided in accordance with para. 3.4.4.

5.5.6 Noise and Vibration Control. All mechanical systems and equipment shall be designed to limit noise and vibration in accordance with NAVFAC DM-3.10.

5.6 Environmental Controls. The type of environmental controls required will depend on the pollution abatement regulations at the site and the type and quantities of paints expected to be used. Environmental controls can be a major construction and operating cost item; therefore, an accurate determination of regulations and paints (existing and proposed) is required prior to design.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Section 6: AVIATION LIFE SUPPORT SYSTEMS SHOP

6.1 Function. The Aviation Life Support Systems Shop shall be designed to contain space and equipment for the inspection, repair, and repacking of aviators' safety and survival equipment. Safety and survival equipment includes parachutes, life-rafts, antiexposure wet suits, flotation vests, liquid oxygen systems, on-board oxygen generating systems, and ejection seats. Under current maintenance techniques, drying towers for parachutes are not normally needed and must be justified on an individual basis. The Aviation Life Support Systems Division is broken down into four separate work centers besides the Division Offices and Production Control Shop Work centers include:

a) the Parachute Shop,
b) the Aviation Safety Equipment Shop,
c) the Oxygen Regulator and Equipment Shop, and
d) the Ejection Seat Shop.

The space and facility requirements for the Ejection Seat Shop should be justified separately, as most seat work is now transitioning from organizational level maintenance to depot with no impact on I level facilities.

6.2 Location. The Aviation Life Support Systems Shop shall be located in proximity to the hangars and within or near the intermediate maintenance shop complex. This shop shall be oriented to minimize the possibility of dust, dirt, or moisture blowing into the building.

6.3 Architectural Requirements

6.3.1 General The Aviation Life Support Systems Shop shall meet the following architectural requirements:

a) It shall be a single-story structure with an interior clearance to the finished ceiling to suit the equipment maintained. Where MK-20 life rafts are supported, an interior clearance to the finished ceiling or suspended lighting of 18 ft (5.49 m) is required in the Aviation Safety Equipment Shop to turn the raft over during inflation checks. The building is to be of modular steel girder construction with insulated Concrete Masonry Unit (CMU) walls, insulated preformed (corrugated) metal walls, or a combination of the two.

b) The roof shall be of insulated metal roof panels or insulated built-up roofing assemblies, which meet the requirements of Underwriters' Laboratories (UL) UL 1572-80, Building Materials Directory, for fire-acceptable roof deck construction or Factory Mutual's Approval Guide for noncombustible deck construction.

c) Access to the shops shall be through two pairs of double doors forming a foyer. Double doors shall also be required for material and equipment passage into the workrooms. All exterior doors to workrooms shall be equipped with full contact dustproof gaskets and automatic door bottoms.

Source: https://assist.dla.mil -- Downloaded: 202640-26T13:56Z
Check the source to verify that this is the currentversion before use.

d) Windows shall not be permitted in areas where direct sunlight can reach parachute fabric. If used, windows shall be double-glazed and/or shaded, depending upon local climatic conditions.

e) Refer to facility plates of Appendix A and NAVAIR 13-1-6.2, Manual Aviation - Crew Systems Parachutes, for various layouts and other criteria for this shop.

6.3.2 Packing Room. The shop shall contain a packing room with space for 45-ft (14.6 m) parachute packing tables. Tables shall be located so that there exists a minimum of 6 ft (1.83 m) from the walls at the sides and ends and 4 ft (1.22 m) between tables. The tables shall be 36 in. (914 mm) wide by 36 in. (914 mm) high and have smooth hard tops of a color to reduce reflection and eyestrain. Where tables are sectional to permit their deployment, edge treatment shall be such that parachute fabric cannot be snagged. A suspended acoustical tile ceiling system shall be provided in the packing room for the purpose of eliminating dust and dirt accumulation in the overhead area. The floor in this area shall be steel-trowel-finished concrete or resilient tile.

6.3.3 Sewing and Fabrication Room. The shop shall contain a sewing and fabrication room with space for cutting tables and sewing machines for repair and fabrication of parachutes and other survival equipment. Space shall also be provided for storage of fabric and materials.

6.3.4 Parachute Storage. The shop shall contain facilities for repacked parachutes to be stored in smooth-surfaced individual bins 20 in. (508 mm) wide, 26 in. (660 mm) high, and 25 in. (635 mm) deep. To provide for air circulation, bins shall be open both front and back. The height shall not exceed 70 in. (1,778 mm) from floor to top of bin, and the bottom shelf shall be 18 in. (457 mm) from the floor.

6.3.5 Flotation Room. All doors between the flotation room and other parts of the shop shall be fully weatherstripped and equipped with automatic door bottoms to eliminate transfer of talcum powder to other parts of the building.

6.3.6 Oxygen and CO_2 Room. The shop shall contain a separate enclosed room for servicing and testing oxygen and CO_2 equipment and components. Double doors shall be provided to permit moving large test equipment into the area. A covered and protected area shall be provided outside of the building and adjacent to the oxygen room for storage of oxygen and nitrogen bottles. The area shall be arranged to permit storage of bottles on skids and handling of skids by forklifts. Openings shall be provided in the exterior wall for an exhaust line from test equipment and for piping from the oxygen and nitrogen storage area.

6.3.7 Exterior Pavement. The exterior paved areas shall include vehicle access and nonorganization vehicle parking. Refer to NAVFAC P-272, Parts 1 and 2, and MIL-HDBK-1190 for parking criteria.

6.4 Mechanical Requirements. The Aviation Life Support Systems Shop shall meet the mechanical requirements defined in paras. 6.4.1 through 6.4.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

6.4.1 Heating, Ventilation, and Air Conditioning. Heating, Ventilation, and Air Conditioning (HVAC) shall be provided in accordance with NAVFAC DM-3.03 and as follows:

a) Ductwork delivering supply air to the packing room shall be run above suspended acoustical ceiling or be located to prevent dirt accumulation on top of the duct over packing tables.

b) Air conditioning shall be provided to limit the relative humidity to 50 percent, plus or minus 10 percent.

c) Humidification shall be provided in parachute packing and storage areas, as required by the locality of the facility, to maintain the relative humidity within the acceptable zone shown in Figure 1.

d) The raft room shall be kept at a negative pressure relative to adjacent spaces to prevent spread of talcum. A make-up air and local exhaust system with dust collector is required to control talcum dust. The design shall be in accordance with the ACGIH, Industrial Ventilation, A Manual of Recommended Practice.

6.4.2 Plumbing. Plumbing shall be provided in accordance with NAVFAC DM-3.01 and as follows:

a) Hot and cold water and floor drains shall be provided in toilets, cleaning gear room, raft shop, and the parachute washing machine.

b) A leak test tank shall be provided in the Personal Flotation Equipment Shop.

6.4.3 Compressed Air and Vacuum. Compressed air and vacuum systems shall be provided in accordance with NAVFAC DM-3.05 and as follows:

a) Low pressure, oil-free compressed air at 30-60 psi (207-414 kPa) is required in the survival equipment room and the flotation room. The air supply shall have a minimum capacity of 50 scfm (0.024 m^3/s) and shall be adequate to inflate large liferafts in the flotation room.

b) A vacuum source shall be provided in the personal flotation room and raft shop for deflation of rafts and vests. The preferred method is portable, industrial-grade shop vacuum cleaners.

6.4.4 Noise and Vibration Control. All mechanical systems and equipment shall be designed to limit noise and vibration in accordance with NAVFAC DM-3.10.

6.5 Electrical Requirements. The Aviation Life Support Systems Shop shall meet the electrical requirements of the NAVFAC Electrical Engineering Criteria Manuals and paras. 6.5.1 through 6.5.2.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the currentversion before use.




Figure 1
Parachute Packing and Storage Relative Humidity Limits

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

6.5.1 Power Outlets. All areas shall be provided with single-phase, 120 V, 20 A, 60 Hz outlets spaced as required by NFPA 70. The sewing and fabrication room shall be provided with 3-phase, 120/208 V, 20 A, 60 Hz outlets located as required by the using agency for the specific facility. Three-phase, 120/208 V, 20 A, 60 Hz power shall be provided for test equipment in the oxygen room and for pressurizing equipment in the CO_2 transfer room.

6.5.2 Lighting. Lighting throughout the facility shall be fluorescent. Fixtures in the packing room shall be recessed when suspended ceilings are provided, run parallel to the packing tables, and located so that shadows are not cast across work surfaces. Exterior lights shall be the high-pressure, sodium vapor type where practical. Lighting intensities shall be designed in accordance with MIL-HDBK-1190.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Section 7: ENGINE MAINTENANCE SHOP

7.1 Function. The Engine Maintenance Shop (Power Plant Division) shall be designed to contain space and equipment for maintaining aircraft engines, propellers, helicopter rotors (rotor dynamics), and auxiliary fuel tanks and air-to-air refueling stores. Individual justification based on assigned aircraft or maintenance capability must be provided to authorize space for propeller, rotor dynamics, and auxiliary fuel stores maintenance (refer to NAVFAC P-80).

7.2 Location. The Engine Maintenance Shop should be in close proximity to the engine test cells and the maintenance hangars. Direct access to aprons is not required.

7.3 Architectural and Structural Requirements. For architectural and structural requirements, refer to NAVFAC P-272, Part 1, the NAVFAC DM-1 Series and the DM-2 Series and paras. 7.3.1 through 7.3.4.

7.3.1 High Bay. The main work area shall be designed for engine teardown and reassembly and equipped with an overhead bridge crane of 6-ton capacity. A second overhead crane of 6-ton (5,443 kg) capacity shall be installed if justified according to NAVFAC P-80. A clear height of 24 ft (7.3 m) shall be maintained between the floor and the hook of the bridge crane. Access from outside shall be provided through four 20-ft (6.1 m) wide, 10-ft (3.05 m) high rollup doors.

7.3.2 Shop Areas. The shop areas shall be designed to house the rotor dynamics, propeller, and auxiliary fuel store work centers, as well as engine AWP, AWM, and RFI storage, expendable supplies, and cleaning (steam and solvent) areas with the number and size of cleaning tanks determined by the type and number of aircraft being supported. Mechanical equipment and transformer rooms, as well as welding and accessory shops, shall also be located in the shop areas. Sizing of the Rotor Dynamics Shop is dominated by the length of the main rotor blades. The propeller shop requires an 18-ft (5.5 m) ceiling to accommodate propellers on stands and should have a 2-ton (1,814 kg) crane. Both the Rotor Dynamics and Propeller Shop shall be designed to eliminate drafts during blade balancing operations. The Auxiliary Fuel Stores Shop shall be designed to accommodate extending and retracting the 45-ft (13.7 m) fuel hose. A waste oil/solvent containment and storage facility shall be provided.

7.3.3 Other Spaces. Toilet facilities shall be provided with lockers and showers for men and women. The coffee mess shall be provided and equipped with a sink and utilities for dispensing machines. A cleaning-gear room shall be provided. Office spaces shall contain areas for a division officer, division personnel, training, and naval engineering technical specialist/naval aviation engineering service unit personnel. Resilient floor covering and washable wall finish shall be provided in the administrative spaces.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

7.3.4 Exterior Pavements. Exterior paved areas include vehicle access, outside storage for sealed engine containers, and nonorganizational vehicle parking (refer to NAVFAC P-272, Parts 1 and 2, and MIL-HDBK-1190 for parking area criteria).

7.4 Mechanical Requirements. The mechanical requirements for the Engine Maintenance Shop are defined in paras. 7.4.1 through 7.4.6.

7.4.1 Heating. Heating shall be provided in accordance with NAVFAC DM-3.03.

7.4.2 Ventilation. Ventilation and exhaust systems shall be designed in accordance with DM-3.03 and provide:

a) mechanical ventilation for spaces that are not air conditioned,

b) heated outside air to the cleaning and welding areas, and

c) exhaust systems in accordance with the ACGIH, Industrial Ventilation, A Manual of Recommended Practice, for the cleaning and welding areas to remove solvent and welding fumes from the building to provide a safe-work environment.

7.4.3 Air Conditioning. Air conditioning shall be provided for personnel/ administrative spaces in accordance with NAVFAC DM-3.03.

7.4.4 Plumbing. Plumbing shall be provided in accordance with NAVFAC DM-3.01 and as follows:

a) Steam shall be provided at 30 psi (207 kPa) with a capacity of 200 pounds per hour (0.025 kg/s)to the steam cleaning room. Electricity and water supplies shall be provided if portable steam generators are used in lieu of building steam system.

b) Hot and cold water shall be provided to the cleaning area, inspection area, coffee mess, cleaning gear room, and toilets.

c) An oil/water separator shall be provided for drainage systems from solvent and spray cleaning and steam cleaning areas as required for compliance with environmental regulations.

d) A waste recovery system shall be provided for film developing operations to segregate and collect silver bearing waste in accordance with NAVSUPINST 4570.23, Recovery and Utilization of Precious Metals.

7.4.5 Compressed Air. Low pressure compressed air at 125 psi (862 kPa) shall be provided in accordance with NAVFAC DM-3.05 to the main work area and all shop areas. Air outlets shall be provided, at a spacing of 24 ft (7.3 m) in the main work area.

7.4.6 Noise and Vibration Control. All mechanical systems and equipment shall be designed to limit noise and vibration in accordance with NAVFAC DM-3.10.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

7.5 Electrical Requirements. Electrical systems shall be provided in accordance with the NAVFAC DM-4 Series and as defined in paras. 7.5.1 through 7.5.3.

7.5.1 Power Outlets. Power outlets shall meet the following criteria:

a) Single-phase, 120 V, 20 A, 60 Hz outlets shall be provided in all areas.

b) Three-phase, 480 V, 60 Hz outlets shall be provided in the welding shop and inspection shops and at a spacing of 24 ft (7.3 m) in the main work area and in the propeller, rotor dynamics, and auxiliary fuel store work centers.

c) Three-phase, 115/200 V, 400 Hz outlets shall be provided in the accessory shop.

d) The ampacity of 3-phase outlets shall be as required by the using agency for the specific facility.

7.5.2 Lighting. Interior lighting shall meet the following criteria:

a) Interior lighting shall be an energy-efficient type such as high-pressure sodium vapor in the high bay area. Other interior lighting will be fluorescent.

b) Exterior lighting shall be high-pressure sodium vapor where practical.

c) Design for lighting intensities shall be in accordance with MIL-HDBK-1190.

d) Photo laboratory lighting.

7.5.3 Communications. An intercommunications system to allow two-way voice communications shall be provided between the production control office and the major shop areas. A 3M communications system outlet shall be provided in the production control office for connection to the aircraft intermediate maintenance department office located in another building (refer to para. 1.5).

7.6 Weight-Handling Equipment. The overhead bridge crane and monorail hoist shall be in accordance with criteria in DM-38.01 and the following requirements:

7.6.1 Bridge Crane. Each overhead bridge crane shall have an electric, motorized bridge, trolley, and hoist and shall be 6-ton (5,443 kg) capacity. The trolley and bridge shall be capable of operating at a slow speed of 15 to 20 ft/min. (0.076 to 0.10 m/s) for positioning loads and at a high speed for moving loads of 60 ft/min. (0.305 m/s). The hoist shall be capable of operating at a slow speed for 3 to 4 ft/min. (0.015 to 0.02 m/s) and at a high speed of 12 ft/min. (0.061 m/s), also refer to NFGS-14637.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

7.6.2 Motor and Controls. The bridge, trolley, and hoist controls shall provide for two-speed reversing of a two-speed squirrel-cage motor. The controls shall be equipped with reduced voltage starting for the motors. Controls shall be operable from the floor.

Source: https://assist.dla.mil -- Downloaded: 202640-26T13:56Z
Check the source to verify that this is the current version before use.

Section 8: AIRFRAMES SHOP

8.1 Function. The Airframes Shop shall be designed to contain space and equipment for maintaining aircraft at the intermediate maintenance level. The Airframes Division, in addition to the division offices, has 11 separate work centers organized in four branches as follows:

a. The Structures Branch consists of a: Structures Shop, Paint Shop, Welding Shop, Machine Shop, Wheel and Tire Shop, and Composites Shop.

b. The Hydraulics/Pneumatics Branch consists of a Hydraulics Shop, Brake Shop, and Strut Shop.

c. The NDI (Nondestructive Inspection) Branch consists of a: Radiography Shop, Electrical/Chemical Shop; and an Electro-Plating/Anodizing Branch. This branch is not normally required and is authorized on an individual AIMD basis. Refer to NAVFAC P-80 to determine allowance, size, and space requirements and additional special requirements for this facility.

8.2 Location. The Airframe Shop shall be located in proximity to the maintenance hangars within the intermediate maintenance shop complex. Direct unobstructed vehicle access is required.

8.3 Architectural Requirements. The Airframes Shop shall be designed to meet the requirements of paras. 8.3.1 through 8.3.8.

8.3.1 Walls. Walls shall be insulated Concrete Masonry Units (CMU), insulated preformed (corrugated) metal panels, or a combination of both.

8.3.2 Roof. The roof shall be constructed of insulated metal panels or insulated built-up roofing in accordance with para. 2.3.2.

8.3.3 Floors. Floors in the shop area shall be designed for loads as specified in the NAVFAC DM-2 Series and shall have nonslip, easily cleaned finishes.

8.3.4 Doors. Double doors into all shop areas shall be as large as practical to permit the installation of large equipment.

8.3.5 Finishes. Architectural finishes of the personnel spaces shall be in accordance with the NAVFAC DM-1 Series.

8.3.6 Clean Room. A horizontal laminar flow clean room, designed in accordance with NAVFAC DM-28.05, Environmental Control - Design of Clean Rooms, shall be provided as a part of the hydraulics and pneumatic shop area.

8.3.7 Paint Shop. The paint shop shall meet the requirements of NFPA-33.

8.3.8 Exterior Pavement. For parking and access criteria, refer to MIL-HDBK-1190 and NAVFAC P-272, Parts 1 and 2.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the currentversion before use.

8.4 Mechanical Requirements. The Airframes Shop shall be designed to meet the requirements of paras. 8.4.1 through 8.4.8.

8.4.1 Clean Room. Mechanical requirements for the prefabricated clean room shall be in accordance with criteria in NAVFAC DM-28.05.

8.4.2 Heating. Heating shall be provided in accordance with NAVFAC DM-3.03. Design for an infiltration rate of two air changes per hour in the OH space.

8.4.3 Ventilation. Ventilation shall be provided in accordance with NAVFAC DM-3.03 for spaces that are not air conditioned as follows:

a) Exhaust systems with filtered and heated makeup air shall be provided for the painting, welding, sandblasting, cleaning and plating, and fiberglass/plastics shops.

b) Ventilation for the paint shop shall meet the requirements of NFPA-33.

8.4.4 Air Conditioning. Air conditioning shall be provided in accordance with NAVFAC DM-3.03 for administrative areas, the training room, library, first-aid room, production control office, X-ray exposure room, X-ray film process room, and file room.

8.4.5 Plumbing. Plumbing shall be provided in accordance with NAVFAC DM-3.01 and as follows:

a) Hot and cold water and floor drains shall be provided in all shop areas except those for tire and wheel, machine shop, and structures shop areas.

b) Steam shall be provided in the cleaning and plating, painting, and nondestructive testing work areas. The steam supply should normally be 30 psi (207 kPa), with a capacity of 200 pounds per hour (0.025 kg/s) per cleaning station.

c) A waste recovery system shall be provided for film developing operations to segregate and collect silver bearing waste in accordance with NAVSUPINST 4570.23.

d) A safety shower/eyewash shall be provided fixtures as shown on NAVFAC P-272, Part 1.

8.4.6 Compressed Air. Low-pressure compressed air at 125 psi (862 kPa) shall be provided in all shop areas in accordance with NAVFAC DM-3.05.

Source: https://assist.dla.mil -- Downloaded: 202640-26T13:56Z
Check the source to verify that this is the current version before use.

8.4.7 Nitrogen. Gaseous nitrogen, supplied by the using agency in portable cylinders at pressures to 4,000 psi (27,579 kPa), is required in the tire and wheel work area. A nitrogen bottle rack and manifold assembly, complete with pressure regulator, pressure gages, and flexible hose, shall be provided to connect to the nitrogen cylinders.

8.4.8 Noise and Vibration Control. All mechanical systems and equipment shall be designed to limit noise and vibration in accordance with NAVFAC DM-3.10.

8.5 Electrical Requirements. Electrical systems shall be provided in accordance with the NAVFAC Electrical Engineering Criteria Manuals and as defined in paras. 8.5.1 through 8.5.3.

8.5.1 Power Outlets. Power outlets shall be provided in accordance with the following criteria:

a) Single-phase, 120 V, 20 A, 60 Hz convenience outlets shall be provided in all spaces with spacing as required by NFPA-70.

b) Three-phase, 480 V, 60 Hz outlets shall be provided in the hydraulic/pneumatic shop, structures shop, and welding shop areas.

c) Three-phase, 120/208 V, 60 Hz outlets shall be provided in the cleaning and plating shop, paint shop, and nondestructive testing area.

d) 28 Vdc outlets shall be provided in the hydraulic/pneumatic shop area.

e) The ampacity of 3-phase outlets shall be as required by the using agency for the specific facility.

8.5.2 Lighting. Lighting shall be provided in accordance with the following criteria:

a) Interior lighting shall normally be fluorescent.

b) Exterior lighting shall be of the high-pressure sodium vapor where practical.

c) The lighting intensities shall be designed in accordance with MIL-HDBK-1190.

8.5.3 Communications. A 3M communications system outlet shall be provided in the production control office for connection to the aircraft intermediate maintenance department offices located in another building (refer to para. 1.5). An intercommunications system to allow two-way voice communication shall be provided between the production control office and the major shop areas.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the currentversion before use.

8.6 Weight-Handling Equipment. The monorail hoist shall have an electrically-operated trolley and hoist with pushbutton, independent controls and shall be in accordance with criteria in NAVFAC DM-38.01.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Section 9: AVIONICS SHOP

9.1 Function. The Navy and Marine Corps Avionics Shop shall be designed to contain space and equipment for all intermediate maintenance and repair of electronic and electrical airborne equipment and systems. In addition to the Avionics Division Offices and a supply area, the Division has 10 branches as follows:

a. The Avionics Corrosion Control Branch.

b The Comm/Nav Branch consisting of a Communications Shop, Navigation Shop, Computer Shop and COMSEC/CRYPTO Repair Shop.

c. The Electrical/Instrument Branch consisting of an Electric Shop, Instrument Shop, Battery Shop - lead acid; Battery Shop - Ni-Cad; CSD/Generator Shop, Inertial Nav. Shop and, MIARS Shop.

d. The Fire Control Branch consistting of an AWG-9 Shop and AWG-10 Shop.

e. The Radar/ECM Branch consisting of a Radar Shop, ECM Shop, DECM Shop, FLIR Shop, and POD Shop.

f. The SACE/ATE Branch consists of a SACE/BACE Shop, SACE AFC Shop, SACE DIANE Shop, SACE Radar Shop, Weapons Systems Missile Component Shop, FTE/DTS Shop, VAST Shop, and VAST Calibration Shop.

g. The ASW Branch consists of a Julie/Jezebel Shop, MAD Shop, and Sonoboy Shop.

h. The PME Branch/Field Calibration Activity consists of a PME Receipt and Issue, PME Calibration Shop, and PME Repair Shop.

i. The Reconnaissance/Photo Branch.

j. Module/Micro-miniature Repair Branch consists of a: Module Test/Trouble Shooting Shop, Micro-miniature Repair Shop, and Cable/Connector Repair Shop. Few avionics facilities include all possible shops. Refer to NAVFAC P-80 to determine allowance, size, and space for this facility.

NOTE: The Battery Shop is included in the sizing of the Avionics Shops; however, they are separate facilities (Category Code 218-50) in the real property system. Due to expanded use of Mobile Maintenance Facilities (MMFs) by both Navy and Marine units, the Avionics Shop size may be adjusted. When MMFs are used, special studies must determine the reduction factor, as some MMFs are total support and others are only partial support for any specific unit.

Source: https://assist.dla.mil -- Downloaded: 202640-26T13:56Z
Check the source to verify that this is the currenversion before use.

9.2 Location. The Avionics Shop should be located in proximity to the maintenance hangars within the Intermediate Maintenance Shop complex. The Magnetic Anamaly Detection (MAD) building should be located in an electronic transmission-free area that is a minimum of 200 ft (61 m) from automotive traffic or taxiways. Direct, unobstructed vehicle access to the loading area is required.

9.3 Architectural Requirements. The Avionics Shop shall be single-story with an expandable floor plan. Use of interior partitions shall be minimized to permit maximum flexibility in space allocation and equipment modification and rearrangement.

9.3.1 Interior Partitions. All interior partitions, where possible, shall be movable.

9.3.2 Floors. Floors in the shop areas shall be designed for a live load of 300 psf (1,465 kg/m^2) and shall have an epoxy-hardened, dustproof, slip-resistant finish.

9.3.3 Doors. Doors shall be a regular industrial type except as required for security spaces.

9.3.4 Finishes. Interior finishes shall be in accordance with MIL-HDBK-1001/2.

9.3.5 Exterior Pavement. Exterior pavement shall be provided for vehicle access and nonorganizational parking. Refer to NAVFAC P-272, Parts 1 and 2, and MIL-HDBK-1190 for parking criteria.

9.3.6 Clean Room. The clean room shall be designed in accordance with NAVFAC DM-28.05.

9.3.7 Electrical Area. The electrical area requires a free-standing concrete platform, approximately 6 ft (1.83 m) square, on a special isolated foundation for maintenance of gyro systems. Refer to the latest equipment contractors specifications at the time of design.

9.3.8 CSD/Generator Room. Sound attenuation treatment shall be provided for the CSD/Generator room.

9.3.9 Battery Room. The Battery Room shall be designed in accordance with criteria in NAVFAC DM-28.04, General Maintenance Facilities.

9.3.10 MAD Building. The MAD building shall be constructed entirely of nonmagnetic materials.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

9.3.11 Radar Test Facility. For avionics facilities needing to test radar when they are transmitting, a remote radar test facility shall be provided. Requirements for this type of facility are as follows:

a) Separate areas required are a workroom, office, toilet facilities, crew lounge, utility room, and nitrogen storage and testing rooms.

b) The facility shall be located so that the radar can be beamed across an open area with no permanent structures in the field of the sweep of the radar beam.

c) A radar dome shall be provided for each radar workbench in the wall of the facility in the direction the radar is to be beamed. The radar dome shall be constructed of materials as required in Section 00800, para. 10, of NAVAIR Technical Manual, 01-1A-22, Organizational, Intermediate, and Depot Maintenance, Aircraft Radomes and Antenna Covers. The radar dome shall be designed such that with the radar dish in the dome, the sweeping dish of the radar is beyond any building component, thus eliminating the possibility of radiation being reflected back into the work area.

d) A track system shall be provided on each workbench so that the dish of the radar can be moved into the dome for tests with the radar transmitting.

e) A large window, for visual observation of the area covered by the radar beam, shall be provided adjacent to each radar dome. The window shall be of a lead-free material.

f) Window frames, workbench tracks, and any portion of the building near the radar dome shall be of a material that will not reflect radiation from the transmitting radar.

g) Where more than one workbench is used in a facility, a partition with RFI shielding shall be installed between the benches.

h) Equipment shall be provided to continuously monitor the level of radiation near operating personnel while the radar is transmitting.

i) A monorail system shall be provided to allow moving the radar units between the unloading/loading area outside of the building, storage area, nitrogen test area, and workbenches. For requirements on monorail hoist, refer to para. 9.7.

j) NAVAIR Technical Manual, 16-1-529, Volume I, Electromagnetic Radiation Hazards (Hazards to Personnel, Fuel and Other Flammable Material), contains information concerning various radio frequency sources and the hazards to personnel in the vicinity of operating radar equipment.

9.3.12 Avionics Building. The Avionics Building shall be a secured area. Outside access shall be limited. The Electonic Countermeasure (ECM) and COMSEC/CRYPTO Repair Shops require added security measures within the division building.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the currentversion before use.

9.3.13 PME Branch and Production Control Office. The PME Branch and Production Control Office should have an outside access.

9.3.14 Production Control Office. The Production Control Office should be adjacent to a Supply Support area. This supply support area may include a loading dock at the larger AIMDs.

9.4 Mechanical Requirements. The mechanical requirements of the Avionics Shop shall conform to the criteria defined in paras. 9.4.1 through 9.4.6.

9.4.1 Heating, Ventilation, and Air Conditioning. Heating, ventilation, and air conditioning, including humidity and dust control, shall be provided throughout shop spaces, in accordance with NAVFAC DM-3.03. Inside design temperature for shop spaces shall be 75° F (24° C), with a relative humidity of 50 percent for cooling and 65° F (18° C) for heating. Other spaces shall be air conditioned or ventilated and heated in accordance with NAVFAC DM-3.03.

9.4.2 Special Exhaust Systems. The CSD/Generator room requires a separate exhaust system utilizing 100 percent outside makeup air. The battery room shall be provided with an exhaust system in accordance with NAVFAC DM-28.04, Section 5, Part 6. The ultrasonic cleaning tank in the module test and repair room shall be provided with an exhaust system, with makeup air to remove toxic fumes in accordance with NAVFAC DM-3.03, para. 3.6.

9.4.3 Clean Room. Mechanical requirements for the clean room shall be in accordance with NAVFAC DM-28.05.

9.4.4 Plumbing. Plumbing shall be provided in accordance with NAVFAC DM-3.01. An ultrasonic cleaning tank is required in the module test and repair room. The battery room shall be provided with an eyewash and deluge shower with floor drain and other plumbing requirements, in accordance with NAVFAC DM-28.04, Section 5, Part 6.

9.4.5 Compressed Air and Nitrogen. Low-pressure compressed air at 125 psi (862 kPa) shall be provided in all shop areas, in accordance with NAVFAC DM-3.05. Nitrogen requirements must be determined for each area. Normal supply shall be provided from regulated bottles.

9.4.6 Noise and Vibration Control. All mechanical systems and equipment shall be designed to limit noise and vibration, in accordance with NAVFAC DM-3.10.

9.5 Electrical Requirements. Electrical systems shall be provided in accordance with the NAVFAC DM-4 Series; NAVAIR Technical Manual 01-1A-512, Design Guide For Avionics Shop Power Distribution, and paras. 9.5.1 through 9.5.5 of this handbook.

9.5.1 Electromagnetic Interference Shielding. Utility services for the ECM room may be required to be brought into the shop by way of filters with attenuation characteristics, to prevent the radiation of intelligence data into

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

the utility system. Requirements for electromagnetic interference shielding should be obtained from NAVAIR or the project sponsor. The shield room internal to the ECM room shall meet these same requirements for shielding. The shield room, including filters and compensators, is normally purchased as a prefabricated item. Alternating-current and direct-current power distribution shall be run separately to preclude interference. Electromagnetic interference-shielded fixtures are required in all spaces except the ECM room, where no fluorescent lighting is permitted and incandescent lighting must be provided. Shielded enclosures shall be in accordance with NAVFAC NFGS-13093, Radio Frequency Shielded Enclosures, Demountable Type, or NAVFAC NFGS-13094, Radio Frequency Shielded Enclosures, Welded Type. Power line filters shall be provided in accordance with NAVFAC NFGS-16650, Radio Frequency Interference Power Line Filters.

9.5.2 Power Outlets. Power outlets shall conform to the following criteria:

a) Single-phase, 120 V, 20 A, 60 Hz convenience outlets shall be provided in all spaces.

b) Three-phase, 120/208 V and 480 V, 60 Hz power outlets shall be provided in all shops.

c) Three-phase, 115/200 V, 400 Hz power outlets shall be provided in all shops. All 400 Hz power supplies shall be regulated to eliminate error in the calibration of equipment. Refer to MIL-STD-704, Aircraft Electric Power Characteristics, and DOD-STD-1399, Section 300, Interface Standard for Shipboard Systems, Electric Power, Alternating Current, for 400-Hz power requirements.

d) Twenty-eight-volt, direct-current power shall be provided in all shops. Refer to MIL-STD-704 for 28 Vdc power requirements.

9.5.3 Lighting. Lighting shall conform to the following criteria:

a) Interior lighting shall normally be fluorescent, except that only incandescent lighting shall be provided in the ECM room.

b) Exterior lighting shall be high-pressure sodium vapor where practical.

c) Design for lighting intensities shall be in accordance with MIL-HDBK-1190.

9.5.4 Grounding. Two separate grounding systems shall be provided. One system is for grounding the building structure, service entrance, and normal building equipment and one for grounding instruments and avionics equipment. The latter is required in the Communications, Navigation, and Identification (CNI); modular test and repair; electrical; fire control; and ECM spaces.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

9.5.5 Communications. A communications system outlet shall be provided in the production control office for connection to the aircraft intermediate maintenance department offices if the offices are located in another building (refer to para. 1.8). An intercommunications system shall be provided between production control, each shop, the ready-issue room, and the maintenance office.

9.6 Security. The entire building shall be designed for controlled access. The ECM room shall meet the requirements for a classification of SECRET, and the crypto repair shop and vault shall meet the requirements for a classification of TOP SECRET in accordance with OPNAVINST 5510.1G and OPNAVINST 5530.14, Physical Security and Loss Prevention.

9.7 Weight-Handling Equipment. The monorail hoist for the remote radar test facility, when required, shall be 1-ton (1,000 kg) capacity and shall have electric motorized trolley and hoist. The monorail hoist shall be operated from the floor level by pushbutton pendent controls and shall be in accordance with criteria in NAVFAC DM-38.01.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

Section 10: AIRCRAFT BORESIGHT RANGE

10.1 Function. The Aircraft Boresight Range shall be designed to provide facilities for in-place boresighting and firing-in of guns built into or attached to aircraft.

10.2 Location. Two ranges, Type A (semi-enclosed) and Type B (open), as shown in NAVFAC P-272, Part 1, have different location criteria.

10.2.1 Type A Range. The Type A range shall be located in close proximity to taxiways, but special care must be taken to ensure that no visual obstruction occurs between the tower and runways and taxiways. Due to noise generation and safety considerations, this facility shall be separated from inhabited structures and the station boundary by a minimum distance of 1,200 ft (366 m). Prevailing winds shall also be considered for orientation' and noise abatement (refer to NAVFAC DM-1 Series).

10.2.2 Type B Range. In addition to the location criteria for the Type A range, the Type B range requires a danger zone area, 1,700 yards (1,555 m) wide by 7,000 yards (6,401 m) long, as shown in NAVFAC P-272, Part 1.

10.3 Architectural and Structural Requirements. The architectural design shall be in accordance with the NAVFAC DM-1 Series, and the structural design shall be in accordance with the NAVFAC DM-2 Series. Both the Type A and Type B boresight ranges shall have a length of 2,000 in. (50.8 m) from the firing point of the aircraft to the target at the firing-in butt. There shall be no structural projections in the tunnel of the Type A range, and all lighting fixtures, fixed ladders, mechanical equipment, and target maneuvering equipment shall be recessed. The Type B range, with the addition of the danger zone, shall be similar to the Type A range, except that the tunnel portion and the exhaust system shall be deleted. This would leave only the tiedown and turnaround pad, access pavements, and the firing-in butt.

10.3.1 Tunnel. The walls and ceiling of the boresight tunnel portion shall be of 12-in. (304.8 mm)-thick reinforced concrete. The entire area of the tunnel need not have a concrete floor, but shall be center-paved to allow trucks and loaders to travel to the firing-in butt for maintenance and changing of sand. Full-height, chain-link fence gates shall be provided across the tunnel entrance. The gates shall be designed so that the tunnel entrance is completely free of obstructions when the gates are open for firing.

10.3.2 Firing-in Butt. The floor slab at the firing-in butt portion shall be reinforced concrete with a minimum thickness of 6 in. (153 mm). In the butt area, the sidewalls, ceiling, and upper half of the rear wall shall be lined with 4-in. (102 mm)-thick timber. On the Type B range, the edges of the walls and the ceiling facing the aircraft shall be faced with 12-in. (305 mm) minimum thickness timber, fastened in such a way that there is no metal facing the firing line. Four-foot (1.2 m) square openings with watertight hatch covers shall be provided in the roof over the butt area for sandfill access.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

10.3.3 Target System. The target system shall consist of a movable target easel, in which the trolley mechanism for positioning targets horizontally is recessed in the floor and the ceiling. The pulley mechanism for vertical positioning shall be recessed in the side walls. Adjacent to the target area, on each side of the tunnel, a fixed steel ladder shall be recessed in the wall for maintenance and target changing.

10.3.4 Wing Rooms. Rooms shall be provided on both sides of the firing- in butt target area of the Type A range only. The wing rooms shall serve as safe areas in which personnel may take refuge while sighting-in and firing occurs. The rooms shall also serve as a spare target storage area, a hook-up for direct communications to the firing line and the aircraft, and a control station for target light and ventilation equipment. The wing rooms shall have 8-in. (203 mm)-thick reinforced concrete or CMU walls and an 8-in. (203 mm)-thick precast or cast-in-place reinforced concrete roof. All cells of CMU walls shall be grout-filled in Seismic Zones 3 and 4. Exterior openings of wing rooms shall be provided with chain-link fence gates fitted with panic hardware locks for emergency exit.

10.3.5 Shelters. Shelters shall be designed to meet the following criteria:

a) Adjacent to the tiedown and turnaround pad near the tunnel entrance, a shelter shall be provided at the electrical service points for protection and storage of electrical gear and power service cables.

b) A standard 12- x 20-ft (3.6 x 6.1 m) line shelter shall be provided near the rear portion of the tiedown and turnaround pad for crew shelters and storage of jacks and tiedown gear (refer to Section 13 for line shelter criteria).

10.3.6 Exterior Pavement. The taxiway and turnaround pad shall be designed as an aircraft parking apron for the critical using aircraft, in accordance with NAVFAC DM-21 Series, except that tiedowns shall be provided on 10-ft (3.05 m) centers. Access pavements to the line shelter and the firing-in butt shall be as called for in NAVFAC DM-5.04.

10.4 Mechanical Requirements. The mechanical requirements for the aircraft foresight range shall conform to the criteria in paras. 10.4.1. through 10.4.3.

10.4.1 Heating and Air Conditioning. Heating and air conditioning are not required for this facility.

10.4.2 Ventilation. Ventilation shall be in accordance with NAVFAC DM-3.03. Exhaust fans shall be provided above the firing-in-butt portion of the range, to cause air to flow across the target area at the rate of 7.5 cfm (0.004 m^3/s) per square foot (0.09 m^2) of range tunnel floor area. Ventilation shall also be in accordance with Lead Exposure and Design Consideration for Indoor Firing Ranges, by Thomas L. Anania and Joseph A. Seta.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

10.4.3 Plumbing. Plumbing shall be provided in accordance with NAVFAC DM-3.01 and as follows:

a) Floor drains shall be provided at the tunnel entrance to remove wind-driven rain.

b) The floor trench containing the trolley mechanism shall be provided with drains to remove sprinkler system water.

c) A chemical toilet shall be provided in the line shelter unless a sanitary sewer is located nearby.

10.5 Electrical Requirements. Electrical systems shall be provided in accordance with the NAVFAC DM-4 Series and defined in paras. 10.5 through 10.5.4.

10.5.1 Power Outlets. Power outlets shall conform to the following:

a) Two single-phase, 120 V, 20 A, 60 Hz convenience outlets shall be provided in each wing room and electrical service points shelters.

b) Single-phase, 120 V, 20 A, 60 Hz power outlets shall be provided in the line shelter for convenience and electric heaters.

c) Three-phase, 115/200 V, 400 Hz, and 28 Vdc power outlets shall be provided in the electrical service points shelter to run the aircraft systems. Ampacity of the power outlets shall be as required by the using agency for the specific facility. Refer to MIL-STD-704 and DOD-STD-1399, Section 300, for 400 Hz power requirements and refer to MIL-STD-704 for 28 Vdc power requirements.

10.5.2 Lighting. Lighting shall conform to the following:

a) The Type A range shall be lighted to provide an intensity of 50 footcandles over the entire target face. Ceiling floodlights that light the target face shall be vertically and horizontally adjustable.

b) Lighting for the tunnel portion shall be provided at an intensity of 2 footcandles to allow safe passage in the tunnel.

c) Exterior lighting shall be in accordance with the NAVFAC DM-23 Series, Airfield Lighting and Navigational Aids. Floodlights shall be provided to light the entire tiedown and turnaround pad.

10.5.3 Grounding. Two flush-ground receptacles, each with a 3/4-in. (19 mm) diameter ground rod, shall be provided in the tiedown pad as shown in NAVFAC P-272, Part 1. The resistance to ground shall be 25 ohms maximum. Bond all ground receptacles together with No. 4 AWG bare copper in or below the tiedown pad.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

10.5.4 Communications. A two-way communications system shall be provided that consists of headsets with land wiring direct between the firing-in butt and the pilot's seat via a plug-in in the aircraft fuselage. Due toproximity of the flight line and taxiways, the headsets shall provide ear protection from medium- to high-level noise and shall consist of a noise-shielded microphone. Sound-powered phones and walkie-talkies shall not be used.

10.6 Safety Requirements. Both types of ranges shall be provided with flashing warning lights on each side of the facility, a danger flag, and a siren at the firing line to indicate firing in progress. Additionally, the Type B range and its entire danger area shall be enclosed with a chain-link fence topped with three strands of barbed wire. Gates shall be erected at the entrance and exit of all station roads cross the danger zone. A danger flag shall be furnished and erected at each gate. Warning signs showing "Danger" and "U.S. Government Property" shall be spaced at a maximum of 500 ft (152 m) along the fence line. Refer to NAVFAC DM-5.12, Fencing, Gates, and Guard Towers, for fencing criteria.

Source: https://assist.dla.mil -- Downloaded: 202640-26T13:56Z
Check the source to verify that this is the currentversion before use.

Section 11: AIR-LAUNCHED GUIDED MISSILE SHOP

11.1 Function. The Air Launched Guided Missile Shop shall be designed to provides space for the receipt of such missiles as SHRIKE, SIDEWINDER, SPARROW, WALLEYE, and PHOENIX from a Naval Weapons Station (NWS). Ready-for-issue weapons received from an NWS require only basic integrity testing at the shop. At the time of attachment to the aircraft, the "on aircraft" check and test equipment are utilized to validate the GO condition of the missile. Rejected units are repackaged and returned to the NWS for reprocessing. Repair of ejection racks is accomplished in the Aviation Armaments Shop. For missile storage requirements, refer to NAVFAC DM-32 Series, Storage.

11.2 Location. After the explosive limits for the facility have been determined, it shall be located in accordance with prescribed quantity-distance standards and the provisions of NAVSEA OP-5, Ammunition and Explosives Ashore. Site approval for explosive safety is under the cognizance of NAVFAC in accordance with NAVSUP NAVFACINST 11010.44D, Shore Facilities Planning. For ready accessibility to missile storage, the facility should be located in or near the magazine area. Direct vehicular access between the facility and the arming and de-arming pad is required.

11.3 Architectural Requirements. The Air-Launched Guided Missile Shop shall be designed as shown in the facility plates in Appendix A. The workbay and exterior loading area shall be equipped with a 3,000-pound (1,361 kg) capacity, overhead monorail system mounted 8 ft (2.4 m) above the floor. Where climatic conditions warrant, the loading area shall be covered and protected. The workbay may be finished with a CRU-reflective floor coating. The office and personnel area shall be finished in accordance with MIL-HDBK-1001/2, and shall include toilet and locker facilities for both male and female personnel. Physical security of the facility in terms of security fencing, perimeter lighting, and clear zones shall be as required by OPNAVINST 5530.14 and OPNAVINST 5510.1G.

11.4 Mechanical Requirements. The mechanical requirements for the Air-Launched Guided Missile Shop are defined in paras. 11.4.1 through 11.4.3.

11.4.1 Heating, Ventilation, and Air Conditioning. Heating, ventilation, and air conditioning, including humidity control, shall be provided throughout the shop spaces in accordance with NAVFAC DM-3.03. Inside design temperature for shop spaces shall be 78° F ± 2° (23.9° C) with a relative humidity of 50 ± 5 percent for cooling and 65° F (18.3° C) for heating. Other spaces shall be air conditioned or ventilated and heated in accordance with NAVFAC DM-3.03.

11.4.2 Compressed Air. Low-pressure compressed air shall be provided at 125 psi (862 kPa) in accordance with NAVFAC DM-3.05, with sufficient capacity to serve the monorail hoist (if an air-operated hoist is provided) and compressed air outlets for tools at the workbenches.

11.4.3 Plumbing. Plumbing shall be provided in accordance with NAVFAC DM-3.01. An eyewash and deluge shower with drain shall be provided.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

11.5 Electrical Requirements. Electrical systems shall be provided in accordance with the NAVFAC Electrical Engineering Criteria Manuals and as defined in paras. 11.5.1 through 11.5.3.

11.5.1 Lighting. Lighting shall conform to the following criteria:

a) Interior lighting shall be fluorescent.

b) Lighting intensity in the work area shall be 70 footcandles at 3 ft (0.9 m) above the floor.

c) Other lighting intensities shall be in accordance with MIL-HDBK-1190.

d) Fixed emergency work lighting shall be provided to permit completion of assembly of a missile during power outages.

e) Exterior lighting shall be of the high-pressure sodium vapor type where practical.

11.5.2 Grounding. An automatic retracting ground reel shall be provided in each work area.

11.5.3 Lightning Protection. Lightning protection shall be provided in accordance with NAVSEA OP-5 requirements.

11.6 Security. The entire building shall be designed for controlled access and shall meet the requirements of OPNAVINST 5510.1G and OPNAVINST 5530.14.

11.7 Weight-Handling Equipment. The overhead monorail hoist shall have a 3,000-pound (1,361 kg) capacity with either an air-operated (in accordance with NFGS-14335, Monorails With Air Motorpowered Hoist), or a sparkproof electric hoist and trolley motors. The hoist shall be a wire rope type. Chain hoists shall not be used, due to the possibility of the chain damaging missile components (refer to NAVFAC DM-38.01 for additional criteria).

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the currentversion before use.

Section 12: LINE SHELTER

12.1 Function. The Line Shelter is provided to support aircraft line operations and maintenance and may be used to support other functions that require a portable or permanent building. The shelter configured for line operations contains space for crew shelter and support facilities, and the shelter configured for line maintenance contains space for tiedown gear, preexpended material, and sheltered work space (refer to Appendix A). Shelters provided for other purposes shall be configured as required.

12.2 Location. Line shelters shall be located as close as possible to the working area of the personnel and/or aircraft they support.

12.3 Architectural Requirements. The architectural requirements for Line Shelters are defined in paras. 12.3.1 through 12.3.4.

12.3.1 Portable Line Shelters. The portable line shelter is a skidmounted building of non-combustible material, with outside dimensions of 12 ft (3.66 m) x 20 ft (6.1 m) and an interior floor-to-ceiling height of 8 ft (2.44 m). The shelter shall not weigh more than 18,000 pounds (8,165 kg) and shall have the capability of being lifted as a unit. Integral lift points shall be provided. Each building envelope shall be insulated as required in para. 1.6. Each portable line shelter shall be a pre-engineered panel frame metal building. Built-in bins, counters, and equipment (except lockers) shall be provided as shown in Appendix A.

12.3.2 Permanent Line Shelters. The permanent Line Shelter shall be an insulated pre-engineered metal building or of insulated concrete masonry unit construction. Each permanent shelter shall contain offices; storage; repair shop; and toilet, locker, and shower facilities for male and female personnel.

12.3.3 Noise Control. Due to their proximity to the flight line and apron, adequate acoustical insulation shall be provided in each type of shelter to meet office requirements as set forth in NAVFAC DM-1.03.

12.3.4 Interior Finishes. Interior surfaces, including walls, floors, and ceilings, shall have easily maintained and cleaned finishes as set forth in the NAVFAC DM-1 Series.

12.4 Mechanical Requirements. The mechanical requirements for Line Shelters are defined in paras. 12.4.1 and 12.4.2.

12.4.1 Portable Shelter. An electric, ceiling-mounted, variable-throw, forced-air space heater and a ventilating fan shall be provided as required in accordance with NAVFAC DM-3.03. A dry chemical toilet shall also be provided.

12.4.2 Permanent Shelter. Heating and ventilation shall be provided in accordance with NAVFAC DM-3.03. Plumbing shall be provided in accordance with NAVFAC DM-3.01.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

12.5 Electrical Requirements. The electrical requirements for Line Shelters are defined in paras. 12.5.1 and 12.5.2.

12.5.1 Portable Shelter. A weatherproof, exterior, power receptacle shall be provided for a plug-in, single-phase, 120 V, 60 Hz source from an apron service point or a portable generator. Two 20 A capacity convenience outlets shall be provided on each wall. Ceiling, surface-mounted, electrical lighting fixtures shall be provided for a minimum of 30 footcandles of light intensity at counter height.

12.5.2 Permanent Shelter. Electrical systems shall be provided in accordance with the NAVFAC DM-4 Series.

12.6 Communications. If practical, landline communications shall be provided with the organizational hangar and communications tie-in. If not practical, provide for communications by two-way radio on designated frequencies (refer to para. 1.8). Communications to the flight line apron shall be by loudspeaker.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Section 13: FLAMMABLE STORAGE FACILITIES ON THE FLIGHT LINE

13.1 Function. A flammable storage facility on the flight line shall be provided for storage of paints, oils, cleaners, solvents, and other flammable or combustible materials being used in the hangars and aircraft maintenance shops, where adequate inside fire-resistive storage has not been provided.

13.2 Location. A flammable storage facility may be located adjacent to or in the vicinity of the hangar and/or shop that it supports. Refer to NAVFAC P-272, Part 4, Definitive Designs for Marine Corps Facilities, for typical layout at a Marine Corps intermediate-level maintenance shop complex.

13.3 Architectural Requirements. A flammable storage building located less than 50 ft (15.2 m) from an adjacent building shall not have any opening in the wall facing the adjacent building. Any drainage from the flammable storage facilities shall be away from the adjacent building. The building shall be of metal panel construction. The floor and lower portion of the building walls shall be liquid-tight. Door openings shall have liquid-tight raised sills or ramps at least 4 in. (102 mm) high. Ventilation openings shall be located as low as feasible above sill height in doors and walls. Shelves 8 in. wide (203 mm) shall be provided. Refer to NAVFAC P-272, Part 4, for a 450-ft^2 (41.8 m^2) ground support equipment shop, flammable storage facility and for a 150-ft^2 (13.9 m^2) facility for a Marine Corps aircraft squadron.

13.4 Mechanical Requirements. Gravity exhaust ventilation shall be provided in accordance with the requirements set forth in NAVFAC DM-3.03.

13.5 Electrical Requirements. Electrical installations shall be in accordance with NAVFAC DM-22, Petroleum Fuel Facilities, and NFPA-70.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Section 14: MARINE CORPS AIRCRAFT MAINTENANCE FACILITIES

14.1 Function. Marine Corps aircraft maintenance facilities encompass all of the functions of aircraft maintenance facilities for the Navy. However, Marine Corps facilities differ from Navy facilities as described in paras. 14.1.1 and 14.1.2

14.1.1 Maintenance Responsibilities. A Marine Corps Air Station may be assigned only limited intermediate maintenance level responsibility for its own aircraft. All intermediate-level maintenance for Marine Corps Aircraft Squadrons is performed by a Headquarters and Maintenance Squadron (H&MS). At a Naval Station, this maintenance is performed by an aircraft intermediate maintenance department for all aircraft based at the Station. In a garrison situation, a Marine Corps Aircraft Group may be responsible for maintenance for as many as six or more squadrons.

14.1.2 Maintenance Facilities. The expeditionary nature of the Marine Corps air support mission requires that some aviation maintenance support equipment be configured for Mobile Facilities (MF) which deploy with the group. Since it is not practical or economical to remove installed equipment from MFs or to duplicate this equipment in permanent facilities, Marine Corps aircraft maintenance in the continental United States must be a combination of permanent construction and the MF. Navy aircraft maintenance facilities, however, are usually all permanent construction.

14.2 Location. Each Marine Corps intermediate level maintenance shop complex should be located in proximity to the air group hangars. Preferably, the shops should be located to the rear of the line of hangars as depicted in NAVFAC P-272, Part 4. The definitive drawing shows a hangar and shop complex for a typical Marine Corps Air Group.

14.3 Design Requirements. The design criteria contained in other sections of this handbook for maintenance hangars and intermediate level maintenance shops shall apply to the maintenance hangars and intermediate level maintenance spaces and shops supporting a Marine Corps Air Group, except as modified herein. Refer to NAVFAC P-80 for adjustments in size requirements for permanent Marine Corps facilities.

14.4 Architectural and Civil Requirements. Where facilities are to house deployable personnel units, the floor plan and exterior perimeter walls of the permanent structure shall be arranged to permit installation of one or more MFs. Provisions shall be made to connect such MFs to the permanent work-spaces with direct and level access. Standard MFs are planned to be 8 ft (2.44 m) wide, 20 ft (6.1 m) long, and 8 ft (2.44 m) high. The average distance from the floor surface of the MF bed to the bottom of jacks is 30 in. (762 m). Two MFs may be placed close together side-by-side; however, a minimum distance of 10 ft (3.05 m) must be left between pairs of MFs for MF placement, removal, and servicing. Some MF complexes require end-to-end connections between MFs arranged in combinations up to four deep. The apron around the building where the MF will be located shall be concrete pavement, in accordance with NAVFAC DM-5.04. The concrete apron shall be wide

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

enough to accommodate four MFs end-to-end. Additional aprons shall be provided as necessary for convenient parking of MFs and access around the MF complex (refer to the manufacturer's manual covering the MF that will be utilized). Access from the building to the MF shall be through watertight, weatherproof vestibules, closeable by fusible-link, actuated, rolling steel fire doors. These vestibules shall be deep enough so that the doors of the initial MF are operable and do not interfere with the fire doors. Where MFs line exterior walls of the building, a personnel door shall be provided to the exterior between every fourth MF series. Refer to NAVFAC P-272, Part 4, for definitive drawings showing shops configured for MF. Space shall be provided near the facility for parking MF trailers, and enclosures shall be provided for equipment required to service the MF.

14.5 Security. Depending upon the nature of the facility, consideration shall be given to providing security fencing and lighting of the complex's perimeter and apron area.

14.6 Mechanical Requirements. Mechanical design for the permanent portion of the facility shall be as required by other sections in this manual covering a similar type of facility not utilizing MFs (refer to Sections 5, 7, 8, 9, 10 and 15).

14.7 Electrical Requirements. Electrical design for the permanent portion of the facility shall be as required by other sections in this manual covering a similar type of facility not utilizing MF (refer to Sections 5, 7, 8, 9, 10 and 15). Additional requirements are defined in paras. 14.7. through 14.7.4.

14.7.1 Emergency Power. A power outlet shall be provided on the outside of the permanent building structure for connection of an emergency, field-type generating unit to the building power loop. The power outlet shall be of a capacity to handle the entire facility electrical power requirement and shall be connected to the power system through a manual transfer switch. The transfer switch will permit operating the generating unit during the loss of the normal power source and will permit load testing of the unit.

14.7.2 400-Hertz Power. For facilities that require 400-Hz power (refer to Sections 5, 8, and 10), a permanent source of 400-Hz power shall be provided for the facility, even though a portable unit is used for the MF complex, so that this power will be available at the permanent facility when the portable unit is deployed. Voltage regulation shall be provided when required by the work performed in some MFs.

14.7.3 Power Outlets. Power outlets shall be provided on the outside of the building at each opening for MF. The voltage and phase of the outlets shall be as required by the particular facility and the ampacity shall be sufficient to supply four MFs end-to-end. Outlets shall be adaptable to the plugs provided with the MF in accordance with MIL-C-22992, Electrical Convertors.

14.7.4 Communications. A plug-in intercommunications system between the production control office and each series of MFs shall be provided at the building perimeter.

Source: https://assist.dla.mil -- Downloaded: 202640-26T13:56Z
Check the source to verify that this is the currentversion before use.

Section 15: MARINE CORPS AIRCRAFT GROUP AVIATION SUPPLY SUPPORT CENTER

15.1 Function. A Marine Corps Aircraft Group Aviation Supply Support Center (GASSC) provides administrative, material handling, and storage spaces for Marine Corps Aircraft Group supply functions and the handling and storage of Navy and Marine Corps material and property assigned to the Group.

15.2 Location. The GASSC building and the open storage area shall be located within the intermediate level maintenance shop complex in proximity to the Marine Corps Aircraft Group Hangars. Consideration shall be given to placement of MF adjacent to the building and to unobstructed access from each maintenance shop and Base supply. The preferred location of the GASSC administrative bay is adjacent to the Marine Corps Aircraft Group Headquarters Building (refer to NAVFAC P-272, Part 4).

15.3 Architectural Requirements. The GASSC shall be a pre-engineered insulated metal building. Rooms and areas shall be provided as depicted in NAVFAC P-272, Part 4, and as defined in paras. 15.3.1 through 15.3.3.

15.3.1 Spaces. Space within the GASSC shall conform to the criteria in paras. 15.3.1.1 through 15.3.1.4.

15.3.1.1 Administrative. Administrative spaces shall be subdivided with movable partitions and shall contain provisions for convenient location of office machines.

15.3.1.2 Security Area. A security area, a pre-expended bin storage room, and a small flammable storage room shall be constructed of solid Concrete Masonry Units (CMUs) of 8-in. (203 mm) minimum thickness. Refer to NFPA-30, Flammable and Combustible Liquids Code, for construction criteria for flammable storage.

15.3.1.3 Receiving and Issue and Supply. Receiving and issue and supply screening functions shall be located in the vicinity of the building entrance and enclosed by 4-ft-high (minimum) movable partitions that offer optimum surveillance of all entrances.

15.3.1.4 Interior Storage. Interior storage areas shall be subdivided by full-height, chain-link fencing.

15.3.2 Building Access. Access to the GASSC shall be as follows:

a) Provide for permanent controlled access from the building to small parts MF. Refer to Section 14 for criteria covering Marine Corps aircraft maintenance facilities.

b) Access to the building from the loading dock and ramp shall be by rollup doors.

15.3.3 Building Protection. Interior columns and partitions shall be protected against impact by materials handling equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

15.4 Mechanical Requirements. The GASSC shall conform to the criteria defined in paras. 15.4.1 through 15.4.4.

15.4.1 Heating and Ventilation. Heating and ventilation shall be provided in the administrative, material handling, and storage spaces in accordance with NAVFAC DM-3.03.

15.4.2 Air Conditioning. Air conditioning shall be provided for the administrative spaces in accordance with NAVFAC DM-3.03.

15.4.3 Plumbing. Plumbing shall be in accordance with NAVFAC DM-3.01.

15.4.4 Noise and Vibration Control. All mechanical systems and equipment shall be designed to limit noise and vibration in accordance with NAVFAC DM-3.10.

15.5 Electrical Requirements. Electrical systems shall be provided in accordance with the NAVFAC DM-4 Series and paras. 15.5.1 through 15.5.3.

15.5.1 Power Outlets. Single-phase, 120 V, 20 A, 60 Hz convenience outlets shall be provided in all spaces.

15.5.2 Lighting. Lighting shall conform to the following:

a) Interior lighting shall normally be fluorescent.

b) Exterior lighting shall be high-pressure sodium vapor where practical.

c) Design lighting intensities shall be in accordance with MIL-HDBK-1190.

15.5.3 Communications. Internal communications shall be provided.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

APPENDIX A
FACILITY PLATES

Cat. Code	Sheet Number	Title	Supercedes DD	Page
Section 1: Introduction				
211-54	1 of 4	Aviation Armament Shop	1291741	61
211-54	2 of 4	Aviation Armament Shop	1291741	62
211-54	3 of 4	Aviation Armament Shop	1291741	63
211-54	4 of 4	Aviation Armament Shop	1291741	64
211-54	1 of 5	Aviation Armament Shop	1291742	65
211-54	2 of 5	Aviation Armament Shop	1291742	66
211-54	3 of 5	Aviation Armament Shop	1291742	67
211-54	4 of 5	Aviation Armament Shop	1291742	68
211-54	5 of 5	Aviation Armament Shop	1291742	69
211-54	1 of 1	Aviation Armament Shop - Small	N/A	70
211-54	1 of 1	Aviation Armament Shop - Medium	N/A	71
211-54	1 of 1	Aviation Armament Shop - Large	N/A	72
Section 2: Maintenance Hangar; Section 3: Corrosion Control Hangar; Section 5: Paint Finishing Hangar				
211-04	1 of 4	Pre-Engineered Maintenance Hangar	1403097	73
211-04	2 of 4	Pre-Engineered Maintenance Hangar	1403097	74
211-04	3 of 4	Pre-Engineered Maintenance Hangar	1403097	75
211-04	4 of 4	Pre-Engineered Maintenance Hangar	1403097	76
211-04	1 of 4	Pre-Engineered Maintenance Hangar	1403098	77
211-04	2 of 4	Pre-Engineered Maintenance Hangar	1403098	78
211-04	3 of 4	Pre-Engineered Maintenance Hangar	1403098	79
211-04	4 of 4	Pre-Engineered Maintenance Hangar	1403098	80
211-04	1 of 4	Pre-Engineered Maintenance Hangar	1403099	81
211-04	2 of 4	Pre-Engineered Maintenance Hangar	1403099	82
211-04	3 of 4	Pre-Engineered Maintenance Hangar	1403099	83
211-04	4 of 4	Pre-Engineered Maintenance Hangar	1403099	84

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

APPENDIX A (Continued)

Cat. Code	Sheet Number	Title	Supercedes DD	Page
Section 4: Aircraft Weapons Alignment Facility				
211-82	1 of 5	Aircraft Weapons Alignment Shelter	1291733	85
211-82	2 of 5	Aircraft Weapons Alignment Shelter	1291733	86
211-82	3 of 5	Aircraft Weapons Alignment Shelter	1291733	87
211-82	4 of 5	Aircraft Weapons Alignment Shelter	1291733	88
211-82	5 of 5	Aircraft Weapons Alignment Shelter	1291733	89
211-82	1 of 6	Aircraft Weapons Alignment Shelter	1291734	90
211-82	2 of 6	Aircraft Weapons Alignment Shelter	1291734	91
211-82	3 of 6	Aircraft Weapons Alignment Shelter	1291734	92
211-82	4 of 6	Aircraft Weapons Alignment Shelter	1291734	93
211-82	5 of 6	Aircraft Weapons Alignment Shelter	1291734	94
211-82	6 of 6	Aircraft Weapons Alignment Shelter	1291734	95

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

APPENDIX A (Continued)

Cat. Code	Sheet Number	Title	Supercedes DD	Page
Section 6: Aviation Life Support Systems Shop				
211-75	1 of 5	Aviation Life Support Systems Shop	1291735	96
211-75	2 of 5	Aviation Life Support Systems Shop	1291735	97
211-75	3 of 5	Aviation Life Support Systems Shop	1291735	98
211-75	4 of 5	Aviation Life Support Systems Shop	1291735	99
211-75	5 of 5	Aviation Life Support Systems Shop	1291735	100
211-75	1 of 4	Aviation Life Support Systems Shop	1291736	101
211-75	2 of 4	Aviation Life Support Systems Shop	1291736	102
211-75	3 of 4	Aviation Life Support Systems Shop	1291736	103
211-75	4 of 4	Aviation Life Support Systems Shop	1291736	104
211-75	1 of 1	Aviation Life Support Systems Shop	N/A	105
211-75	1 of 1	Aviation Life Support Systems Shop	N/A	106
211-75	1 of 4	Aviation Life Support Systems Shop - Large	1291737	107
211-75	2 of 4	Aviation Life Support Systems Shop - Large	1291737	108
211-75	3 of 4	Aviation Life Support Systems Shop - Large	1291737	109
211-75	4 of 4	Aviation Life Support Systems Shop - Large	1291737	110
Section 9: Avionics Shop				
211-45	1 of 4	Avionics Shop VF	1291751	111
211-45	2 of 4	Avionics Shop VF	1291751	112
211-45	3 of 4	Avionics Shop VF	1291751	113
211-45	4 of 4	Avionics Shop VF	1291751	114
211-45	1 of 5	Avionics Shop VF	1291752	115
211-45	2 of 5	Avionics Shop VF	1291752	116
211-45	3 of 5	Avionics Shop VF	1291752	117
211-45	4 of 5	Avionics Shop VF	1291752	118
211-45	5 of 5	Avionics Shop VF	1291752	119
211-45	1 of 4	Avionics Shop VW	1291753	120
211-45	2 of 4	Avionics Shop VW	1291753	121
211-45	3 of 4	Avionics Shop VW	1291753	122
211-45	4 of 4	Avionics Shop VW	1291753	123
211-45	1 of 4	Avionics Shop VA	1291754	124
211-45	2 of 4	Avionics Shop VA	1291754	125
211-45	3 of 4	Avionics Shop VA	1291754	126
211-45	4 of 4	Avionics Shop VA	1291754	127
211-45	1 of 4	Avionics Shop VP/VS/VR	1291755	128
211-45	2 of 4	Avionics Shop VP/VS/VR	1291755	129
211-45	3 of 4	Avionics Shop VP/VS/VR	1291755	130
211-45	4 of 4	Avionics Shop VP/VS/VR	1291755	131
211-45	1 of 4	Avionics Shop VA	1291756	132
211-45	2 of 4	Avionics Shop VA	1291756	133
211-45	3 of 4	Avionics Shop VA	1291756	134
211-45	4 of 4	Avionics Shop VA	1291756	135


Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the currenversion before use.

APPENDIX A (Continued)

Cat. Code	Sheet Number	Title	Super-cedes DD ___	Page
211-45	1 of 5	Avionics Shop VW	1291757	136
211-45	2 of 5	Avionics Shop VW	1291757	137
211-45	3 of 5	Avionics Shop VW	1291757	138
211-45	4 of 5	Avionics Shop VW	1291757	139
211-45	5 of 5	Avionics Shop VW	1291757	140
211-45	1 of 4	Avionics Shop VP/VS/VR	1291758	141
211-45	2 of 4	Avionics Shop VP/VS/VR	1291758	142
211-45	3 of 4	Avionics Shop VP/VS/VR	1291758	143
211-45	4 of 4	Avionics Shop VP/VS/VR	1291758	144
211-45	1 of 1	Avionics Shop	N/A	145
Section 11: Air-Launched Guided Missile Shop				
212-30	1 of 5	Air Launched Guided Missile Shop	1294512	146
212-30	2 of 5	Air Launched Guided Missile Shop	1294512	147
212-30	3 of 5	Air Launched Guided Missile Shop	1294512	148
212-30	4 of 5	Air Launched Guided Missile Shop	1294512	149
212-30	5 of 5	Air Launched Guided Missile Shop	1294512	150
Section 12: Line Shelter				
211-15	1 of 1	Portable Line Shelter	N/A	151

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291741
IN PART



FLOOR PLAN
NOT TO SCALE


TITLE	DATE	FACILITY PLAN NO.	SHEET
AVIATION ARMAMENT SHOP	SEPT 1986	211-54	1 OF 4

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1231741
IN PART




ELEVATION
NOT TO SCALE



SECTION A-A
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION ARMAMENT SHOP	SEPT 1986	211-54	2 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.



TYPICAL SITE PLAN

NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION ARMAMENT SHOP	SEP 1986	21-54	3 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES DD-1291741 IN PART

NOTES

PLUMBING REQUIREMENTS

COLD WATER G.P.M.

HOT WATER

RECOVERY RATE (100° RISE) 30 G.P.H.
STORAGE 30 GAL.

FIRE PROTECTION REQUIREMENTS NOT INCLUDED

HEATING REQUIREMENTS (MBH)

OUTSIDE DESIGN TEMPERATURE

-5° F	+5° F	+15° F	+25° F
294	252	210	168

AIR CONDITIONING REQUIREMENTS

BASED ON 91° F D.B. 76° F WB OUTSIDE DESIGN CONDITIONS

ELECTRICAL REQUIREMENTS (KW)

LIGHTS

CONNECTED LOAD	18.4
ESTIMATED DEMAND	14.2

POWER

CONNECTED LOAD	120.0
ESTIMATED DEMAND	96.0

TOTAL

CONNECTED LOAD	138.4
ESTIMATED DEMAND	110.2

AIR CONDITIONING TO BE DETERMINED


AREAS

GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM 10,000 S.F.

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION ARMAMENT SHOP	SEPT 1986	211-54	4 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-F-281(2)
[illegible]




FLOOR PLAN
NOT TO SCALE


TITLE	DATE	SHEET
AVIATION ARMAMENT SHOP	SEPT 1966	21-54

Source: https://assist.dla.mil Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291742
IN PART




SIDE ELEVATION
NOT TO SCALE




FRONT ELEVATION
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION ARMAMENT	SEPT	211-54	2 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.



SECTION A-A
NOT TO SCALE




SECTION B-B
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION ARMAMENT SHOP	SEPT 996	211-54	3 OF 5

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291742
IN PART



TYPICAL SITE PLAN

NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION ARMAMENT SHOP	SEPT 1986	211-54	4 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291742
IN PART

NOTES

PLUMBING REQUIREMENTS

COLD WATER 50 G.P.M.

HOT WATER

RECOVERY RATE (100° RISE) 30 G.P.H.
STORAGE 30 GAL.

FIRE PROTECTION REQUIREMENTS NOT INCLUDED

HEATING REQUIREMENTS (MBH)

OUTSIDE DESIGN TEMPERATURE

-5°F	+5°F	+15°F	+25°F
210	180	150	120

AIR CONDITIONING REQUIREMENTS

BASED ON 91° F D.B. 76° F WB OUTSIDE DESIGN CONDITIONS

COOLING LOAD (MBTU/HR)

SEE DM-28 FOR SPACES REQUIRING AIR CONDITIONING

ELECTRICAL REQUIREMENTS (KW)

LIGHTS

CONNECTED LOAD 16.2
ESTIMATED DEMAND 12.6

POWER

CONNECTED LOAD 18.0
ESTIMATED DEMAND 14.4

TOTAL

CONNECTED LOAD 34.2
ESTIMATED DEMAND 27.0


AIR CONDITIONING TO BE DETERMINED

AREAS

GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM 4,500 S.F.


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION ARMAMENT SHOP	SEPT 1985	211-54	5 OF 5

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.




TITLE		DATE	FACILITY PLATE NO.	SHEET
AVIATION ARMAMENT S--OP SMALL		SEPT 1986	21-54	OF 1

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.



TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION ARMAMENT SHOP - MEDIUM	SEPT 1986	211-54	1 OF 1


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.



TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION ARMAMENT SHOP - LARGE	SEPT 1966	211-54	1 OF 1

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1403097
IN PART




FLOOR PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
PRE-ENGINEERED MAINTENANCE HANGAR	SEPT 96	P1-04	1 OF 4

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1403097
IN PART



SECTION "A"-"A"
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
PRE-ENGINEERED MAINTENANCE HANGAR	SEPT 96	21-04	2 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1407097
IN PART

ARCHITECTURAL REQUIREMENTS

The drawings indicated in this facility plate are intended to provide guidance for a minimum suitable facility for aircraft maintenance.

The arrangement and functional layout indicated shall be followed unless prior clearance for change is obtained from the NAVAL FACILITIES ENGINEERING COMMAND. The architectural treatment, materials framing, and construction may vary.

Dimensions shown conform to stock dimensions and detailing of standard pre-engineered structures.

Door pockets and sliding doors may be omitted in warm climates at the option of the Command.

When location requires, structural design should incorporate sufficient anchorage and bracing for extreme wind load.

Verify horizontal and vertical dimensions of all aircraft to be accommodated. Provide a 3-ton capacity floor supported, movable crane.

Provide movable partition if required to meet special space locations within shop area.

Utilities requirements indicated are for estimating purposes only.

Provide mechanical room if required, sized to fit equipment.

FIRE PROTECTION REQUIREMENTS

Provide sealed head automatic sprinklers in office, shop areas, toilet and lockers, and C.G. spaces.

Provide foam-water sprinkler system (0.16 gpm/sq. ft.) with standard sprinklers supplied through automatic deluge valves for hangar area. Locate deluge valves in shop areas.

Provide 3 manually actuated 500 gpm oscillating foam nozzles in hangar.

Hangar water flow demand 4,000 gpm for 45 min. + 500 gpm for exterior fire hydrants.

Provide two 2,500 gal. aft storage tanks and foam equipment in area separated from hangar by 1 hour construction.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1403097
IN PART

COMMUNICATIONS REQUIREMENTS

Provide telephone jacks thoughout the structure so that if required, a voice communication system can be established between various areas within the hangar and other facilities of the activity. The following jack distribution is recommended:

Office	1	
Shop areas	4	(2 equally spaced along each partition dividing shop and hangar area)
Hangar Area	4	(2 equally spaced along each partition dividing shop and hangar area)

GROSS AREA 21,466 sq. ft.

PLUMBING REQUIREMENTS

Water

Cold 65 gpm
Does not include fire protection requirements

Hot 35 gpm Recovery rate (100 F° rise)
35 gal. Storage

HEATING REQUIREMENTS (MBH)


Outside design temperature	-5 F°	+5 F°	+15 F°	+25 F°
	1834	1572	1310	1048

ELECTRICAL REQUIREMENTS (KW)

	Lighting	Power	Total
Connected Load	65	99	164
Estimated Demand	65	79	144

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1403098
IN PART




FLOOR PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
PRE-ENGINEERED MAINTENANCE HANGAR	SEPT 1986	211-04	1 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1403098
IN PART



SECTION A
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
PRE-ENGINEERED MAINTENANCE HANGAR	SEPT 1986	21-04	2 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

ARCHITECTURAL REQUIREMENTS

The drawings indicated in this facility plate are intended to provide guidance for a minimum suitable facility for aircraft maintenance.

The arrangement and functional layout indicated shall be followed unless prior clearance for change is obtained from the NAVAL FACILITIES ENGINEERING COMMAND. The architectural treatment, materials framing, and construction may vary.

Dimensions shown conform to stock dimensions and detailing of standard pre-engineered structures.

Door pockets and sliding doors may be omitted in warm climates at the option of the Command.

When location requires, structural design should incorporate sufficient anchorage and bracing for extreme wind load.

Verify horizontal and vertical dimensions of all aircraft to be accommodated. Provide a 3-ton capacity floor supported, movable crane.

Provide movable partition if required to meet special space locations within shop area.

Utilities requirements indicated are for estimating purposes only.

Provide mechanical room if required, sized to fit equipment.

FIRE PROTECTION REQUIREMENTS

Provide sealed head automatic sprinklers in office, shop areas, toilet and lockers, and C.G. spaces.

Provide foam-water sprinkler system (0.16 gpm/sq. ft.) with standard sprinklers supplied through automatic deluge valves for hangar area. Locate deluge valves in shop areas.

Provide 3 manually actuated 500 G.P.M. oscillating foam nozzles in hangar. (Throttle for 0.10 gpm/ft. floor area)

Hangar water flow demand 2,500 gpm for 45 min. + 500 gpm for exterior fire hydrants.

Provide two 1,600 gal. aft storage tanks and foam equipment in area separated from hangar by 1 hour construction.

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1403098
IN PART

COMMUNICATIONS REQUIREMENTS

Provide telephone jacks thoughout the structure so that if required, a voice communication system can be established between various areas within the hangar and other facilities of the activity. The following jack distribution is recommended:

Office	1	
Shop areas	4	(2 equally spaced along each partition dividing shop and hangar area)
Hangar Area	4	(2 equally spaced along each partition dividing shop and hangar area)

GROSS AREA 14,700 sq. ft.

PLUMBING REQUIREMENTS

Water

Cold 65 gpm
Does not include fire protection requirements
Hot 35 gpm Recovery rate (100 F° rise)
35 gal. Storage

HEATING REQUIREMENTS (MBH)


Outside design temperature	-5 F°	+5 F°	+15 F°	+25 F°
	1,335	1,145	958	763

ELECTRICAL REQUIREMENTS (KW)

	Lighting	Power	Total
Connected Load	72	100.8	172.8
Estimated Demand	68.4	90.72	159.12

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1403099
IN PART




FLOOR PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO	SHEET
PRE-ENGINEERED MAINTENANCE HANGAR	SEPT 86	211 04	1 OF 4

Source: https://assist.dla.mil - Downloaded: 2024-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1403099
IN PART



SECTION A
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
PRE-ENGINEERED MAINTENANCE HANGAR	SEPT 1986	21-04	2 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

ARCHITECTURAL REQUIREMENTS

The drawings indicated in this facility plate are intended to provide guidance for a minimum suitable facility for aircraft maintenance.

The arrangement and functional layout indicated shall be followed unless prior clearance for change is obtained from the NAVAL FACILITIES ENGINEERING COMMAND. The architectural treatment, materials framing, and construction may vary.

Dimensions shown conform to stock dimensions and detailing of standard pre-engineered structures.

Door pockets and sliding doors may be omitted in warm climates at the option of the Command.

When location requires, structural design should incorporate sufficient anchorage and bracing for extreme wind load.

Verify horizontal and vertical dimensions of all aircraft to be accommodated. Provide a 3-ton capacity floor supported, movable crane.

Provide movable partition if required to meet special space locations within shop area.

Utilities requirements indicated are for estimating purposes only.

Provide mechanical room if required, sized to fit equipment.

FIRE PROTECTION REQUIREMENTS

Provide sealed head automatic sprinklers in office, shop areas, toilet and lockers, and C.G. spaces.

Provide foam-water sprinkler system (0.16 gpm/sq. ft.) with standard sprinklers supplied through automatic deluge valves for hangar area. Locate deluge valves in shop areas.

Provide 2 manually actuated 500 gpm oscillating foam nozzles in hangar. (Throttle for 0.10 gpm/ft. floor area)

Hangar water flow demand 15,000 gpm for 45 min. + 500 gpm for exterior fire hydrants.

Provide two 1,000 gal. aft storage tanks and foam equipment in area separated from hangar by 1 hour construction.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

COMMUNICATIONS REQUIREMENTS

Provide telephone jacks thoughout the structure so that if required, a voice communication system can be established between various areas within the hangar and other facilities of the activity. The following jack distribution is recommended:

Office	1	
Shop areas	4	(2 equally spaced along each partition dividing shop and hangar area)
Hangar Area	4	(2 equally spaced along each partition dividing shop and hangar area)

GROSS AREA 8,800 sq. ft.

PLUMBING REQUIREMENTS

Water

Cold 65 gpm
Does not include fire protection requirements
Hot 35 gpm Recovery rate (100 F° rise)
35 gal. Storage

HEATING REQUIREMENTS (MBH)


Outside design temperature	-5 F°	+5 F°	+15 F°	+25 F°
	826	708	590	472

ELECTRICAL REQUIREMENTS (KW)

	Lighting	Power	Total
Connected Load	44	62	106
Estimated Demand	41.8	55.8	97.5

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291733
IN PART




FLOOR PLAN
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AIRCRAFT WEAPONS ALIGNMENT SHELTER	SEPT 1984	211-82	1 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291733
IN PART



SIDE ELEVATION
NOT TO SCALE




FRONT ELEVATION
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIRCRAFT WEAPONS ALIGNMENT SHELTER	SEPT 1986	211-82	2 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291733
IN PART



BUILDING SECTION
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIRCRAFT WEAPONS ALIGNMENT SHELTER	SEPT 1986	211-82	3 OF 5


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291733
IN PART


ZONE A: KEEP CLEAR OF PERSONNEL, MISSILES, FUSES, ETC., BUILDINGS MOTOR VEHICLES, AIRCRAFT & OTHER RADAR REFLECTIVE OBJECTS AND DISASSEMBLED ELECTRO-EXPLOSIVE DEVICES.

ZONE B: KEEP CLEAR OF MISSILES, FUSES, ETC., BUILDINGS, MOTOR VEHICLES, AIRCRAFT & OTHER RADAR REFLECTIVE OBJECTS AND DISASSEMBLED ELECTRO-EXPLOSIVE DEVICES.

ZONE C: KEEP CLEAR OF DISASSEMBLED ELECTRO-EXPLOSIVE DEVICES.



PLOT PLAN
NOT TO SCALE



TYPICAL SITE PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIRCRAFT WEAPONS ALIGNMENT SHELTER	SEPT 1986	211-82	4 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291733
IN PART

NOTES

PLUMBING REQUIREMENTS

COLD WATER	45 GPM
HOT WATER	
RECOVERY RATE (100°RISE)	18 GPH
STORAGE	18 GAL

THE ABOVE RATES DO NOT INCLUDE REQUIREMENTS FOR FIRE PROTECTION

HEATING REQUIREMENTS (MBTU/HR)

OUTSIDE DESIGN TEMPERATURE

-5 F°	+5 F°	+15 F°	+25 F°
160	137	114	91

ELECTRICAL REQUIREMENTS (KW)

LIGHTS	
CONNECTED LOAD	18.4
ESTIMATED DEMAND	14.2
POWER	
CONNECTED LOAD	120.0
ESTIMATED DEMAND	96.0
TOTAL	
CONNECTED LOAD	138.4
ESTIMATED DEMAND	110.2


AREAS

GROSS AREA INCLUDING MECHANICAL ROOM AND EQUIPMENT ROOM	5,246 SF

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIRCRAFT WEAPONS ALIGNMENT SHELTER	SEPT 1986	211-82	5 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291754
IN PART




FOUR BAY LAYOUT

NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIRCRAFT WEAPONS ALIGNMENT SHELTER	SEPT 1986	211-82	OF 6

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291734
IN PART




THREE BAY LAYOUT
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIRCRAFT WEAPONS ALIGNMENT SHELTER	SEPT 1986	211-82	2 OF 6

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291734
IN PART




TWO BAY LAYOUT

NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIRCRAFT WEAPONS ALIGNMENT SHELTER	SEPT '86	211-82	3 OF 6

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291734
IN PART



LONGITUDINAL SECTION A-A (4 BAYS)

NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIRCRAFT WEAPONS ALIGNMENT SHELTER	SEPT 1985	21-32	4 OF 6


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291734
IN PART

ZONE A: KEEP CLEAR OF PERSONNEL, MISSILES, FUSES, ETC., BUILDINGS MOTOR VEHICLES, AIRCRAFT & OTHER RADAR REFLECTIVE OBJECTS AND DISASSEMBLED ELECTRO-EXPLOSIVE DEVICES


ZONE B: KEEP CLEAR OF MISSILES, FUSES, ETC., BUILDINGS, MOTOR VEHICLES, AIRCRAFT & OTHER RADAR REFLECTIVE OBJECTS AND DISASSEMBLED ELECTRO-EXPLOSIVE DEVICES.

ZONE C: KEEP CLEAR OF DISASSEMBLED ELECTRO-EXPLOSIVE DEVICES.



PLOT PLAN

NOT TO SCALE



TYPICAL
SITE PLANS

SCALE: NONE

TITLE	DATE (FACILITY PLATE NO.)	SHEET
AIRCRAFT WEAPONS ALIGNMENT SHELTER	SEP 1986 : 211-82	5 OF 6

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

NOTES

PLUMBING REQUIREMENTS

COLD WATER	30 GPM
HOT WATER	
RECOVERY RATE (100°RISE)	30 GPH
STORAGE	30 GAL

THE ABOVE RATES DO NOT INCLUDE REQUIREMENTS FOR FIRE PROTECTION

HEATING REQUIREMENTS (MBTU/HR)

INSIDE DESIGN TEMPERATURE 70° F
OUTSIDE DESIGN TEMPERATURE

	-5 F°	+5 F°	+15 F°	+25 F°
2 BAYS	702	605	516	426
3 BAYS	1050	906	772	631
4 BAYS	1400	1207	1057	840

ELECTRICAL REQUIREMENTS (KW)

LIGHTS	2 BAYS	3 BAYS	4 BAYS
CONNECTED LOAD	36.5	54.6	72.7
ESTIMATED DEMAND	28.4	42.4	56.5
POWER			
CONNECTED LOAD	230.0	330.0	420.0
ESTIMATED DEMAND	184.0	264.0	336.0
TOTAL			
CONNECTED LOAD	266.5	384.6	492.7
ESTIMATED DEMAND	212.4	306.4	392.5


AREAS

	2 BAYS	3 BAYS	4 BAYS
GROSS AREA INCLUDING MECHANICAL ROOM AND EQUIPMENT ROOM	10,423 SF	15,503 SF	20,583 SF

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIRCRAFT WEAPONS ALIGNMENT SHELTER	SEPT 1986	211-82	6 OF 6

Source: https://assist.dla.mil -- Downloaded: 202640-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291735
IN PART




FLOOR PLAN
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP	SEPT 1986	211-75	1 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291735
IN PART



FRONT ELEVATION
NOT TO SCALE




SIDE ELEVATION
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP	SEPT 1986	211-75	2 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291735
IN PART




SECTION A-A
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP	SEPT 1986	211-75	3 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291735
IN PART



TYPICAL SITE PLAN

NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP	SEPT 1996	21-75	4 OF 5

Source: https://assist.dla.mil -- Downloaded: 202640-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291735
IN PART

NOTES

PLUMBING REQUIREMENTS

COLD WATER	100 G.P.M.
HOT WATER	
RECOVERY RATE	
(100° RISE)	50 G.P.H.
STORAGE	70 GAL.

THE ABOVE RATES DO NOT INCLUDE REQUIREMENTS FOR FIRE PROTECTION

HEATING REQUIREMENTS (MBTU/HR)

OUTSIDE DESIGN TEMPERATURE

-5° F	+5° F	+15° F	+25° F
255	220	185	150

AIR CONDITIONING REQUIREMENTS

COOLING LOAD (MBTU/HR)	246

ELECTRICAL REQUIREMENTS (KW)

LIGHTS	
CONNECTED LOAD	15.0
ESTIMATED DEMAND	12.0
POWER	
CONNECTED LOAD	12.5
ESTIMATED DEMAND	10.0
TOTAL	
CONNECTED LOAD	27.5
ESTIMATED DEMAND	22.0
ADDITIONAL DEMAND FOR AIR CONDITIONING	20.5


AREAS

GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM	4,000 S.F.

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP	SEPT 1986	211-75	5 OF 5

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.


SUPERSEDES
DD-1291736
IN PART




TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP	SEPT 1986	21175	1 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291736
IN PART



ELEVATION
NOT TO SCALE




SECTION A-A
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP	SEPT 1986	211-75	2 OF 4

Source: https://assist.dla.mil - Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291736
IN PART



TYPICAL SITE PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP	SEPT 1986	211-75	3 OF 4

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291736
IN PART

NOTES

PLUMBING REQUIREMENTS

COLD WATER	100 G.P.M.
HOT WATER	
RECOVERY RATE (100° RISE)	70 G.P.H.
STORAGE	90 GAL.

THE ABOVE RATES DO NOT INCLUDE REQUIREMENTS FOR FIRE PROTECTION

HEATING REQUIREMENTS (MBTU/HR)

OUTSIDE DESIGN TEMPERATURE

-5° F	+5° F	+15° F	+25° F
305	261	219	178

AIR CONDITIONING REQUIREMENTS

COOLING LOAD (MBTU/HR)	336

ELECTRICAL REQUIREMENTS (KW)


LIGHTS	
CONNECTED LOAD	17.6
ESTIMATED DEMAND	14.2
POWER	
CONNECTED LOAD	14.8
ESTIMATED DEMAND	11.9
TOTAL	
CONNECTED LOAD	32.6
ESTIMATED DEMAND	26.1
ADDITIONAL DEMAND FOR AIR CONDITIONING	28.0

AREAS

GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM	7,800 S.F.


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP	SEPT 1986	211-75	4 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.



TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP	SEPT 1986	211-75	1 OF 1


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.



TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP	SEPT 1986	211-75	1 OF 1

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291737
IN PART




FLOOR PLAN
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP-LARGE	SEPT 1986	211-75	1 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291737
IN PART



ELEVATION
NOT TO SCALE




SECTION A-A
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP - LARGE	SEPT 1986	211-75	2 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291737
IN PART



TYPICAL SITE PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP - LARGE	SEPT 1986	21775	3 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291737
IN PART

NOTES

PLUMBING REQUIREMENTS

COLD WATER	30 G.P.M.
HOT WATER	
RECOVERY RATE (100° RISE)	75 G.P.H.
STORAGE	110 GAL.

THE ABOVE RATES DO NOT INCLUDE REQUIREMENTS FOR FIRE PROTECTION

HEATING REQUIREMENTS (MBTU/HR)

OUTSIDE DESIGN TEMPERATURE

-5° F	+5° F	+15° F	+25° F
589	508	427	347

AIR CONDITIONING REQUIREMENTS

COOLING LOAD (MBTU/HR)	504

ELECTRICAL REQUIREMENTS (KW)

LIGHTS	
CONNECTED LOAD	34.6
ESTIMATED DEMAND	27.7
POWER	
CONNECTED LOAD	28.9
ESTIMATED DEMAND	23.1
TOTAL	
CONNECTED LOAD	63.5
ESTIMATED DEMAND	50.8
ADDITIONAL DEMAND FOR AIR CONDITIONING	42.0

AREAS

GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM	11,200 S.F.


GENERAL NOTES:

RELOCATABLE PARTITIONS ARE DESIGNATED AS 2" PARTITIONS. ACTUAL DIMENSIONS WILL BE A FUNCTION OF DESIGN.

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIATION LIFE SUPPORT SYSTEMS SHOP - LARGE	SEPT 1986	211-75	4 OF 4

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1391-1
MAR 1




TITLE	DATE (FACILITY PLATE NO.)	SHEET
[illegible]	SEP [illegible] 20-45	[illegible]

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291751
IN PART



FRONT ELEVATION
NOT TO SCALE




SECTION A
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VF	SEPT 1986	211-45	2 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291751
IN PART



TYPICAL SITE PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP V1	1986	211-45	3 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES DD-2917S IN PART

NOTES

PLUMBING REQUIREMENTS

COLD WATER G.P.M.

HOT WATER

RECOVERY RATE (100° RISE) G.P.H.

STORAGE G.P.H

FIRE PROTECTION REQUIREMENTS NOT INCLUDED

HEATING REQUIREMENTS (MBH)

OUTSIDE DESIGN TEMPERATURE

-5°F	+5°F	+15°F	-25°F
210	180	150	120

AIR CONDITIONING REQUIREMENTS

BASED ON 91°F D.B. 76°F WB OUTSIDE DESIGN CONDITIONS

COOLING LOAD (MBTU/HR)

SEE DM-28 FOR SPACES REQUIRING AIR CONDITIONING

ELECTRICAL REQUIREMENTS (KW)

LIGHTS

CONNECTED LOAD	170.9
ESTIMATED DEMAND	160.2

POWER

CONNECTED LOAD	1228.2
ESTIMATED DEMAND	736.9

TOTAL

CONNECTED LOAD	1399.1
ESTIMATED DEMAND	897.1


AIR CONDITIONING TO BE DETERMINED

AREAS

GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM 53,400 S.F.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1391/782
IN PART




FLOOR PLAN
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VF	SEP 1986	211-45	1 OF 3

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291752
IN PART



FRONT ELEVATION
NOT TO SCALE




REAR ELEVATION
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VF	SEPT 1986	211-45	2 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291752
IN PART




SECTION A
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VF	SEPT 1990	211-45	3 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1297/52
IN PART



TYPICAL SITE PLAN
NOT TO SCALE

[illegible]	DATE SEP 1986	FACILITY PLAN NO. SHEET 21-45	[illegible]

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1391-752
IN PART

NOTES

PLUMBING REQUIREMENTS

WATER

COLD	76 G.P.M.
HOT	
RECOVERY RATE (100°RISE)	75 G.P.M.
STORAGE	75 G.P.M.

FIRE PROTECTION REQUIREMENTS NOT INCLUDED

HEATING REQUIREMENTS (MBH)

OUTSIDE DESIGN TEMPERATURE

-5°F	+5°F	+15°F	+25°F
295	253	211	169

AIR CONDITIONING REQUIREMENTS

BASED ON 91°F D.B 76°F WB OUTSIDE DESIGN CONDITIONS

COOLING LOAD (MBH)	297

HEAT REJECTED TO CONDITIONED SPACES BY ENERGIZED TEST

EQUIPMENT AND PARTS UNDER REPAIR NOT INCLUDED

ELECTRICAL REQUIREMENTS (KW)

LIGHTS	
CONNECTED LOAD	57.6
ESTIMATED DEMAND	54.0
POWER	
CONNECTED LOAD	414.0
ESTIMATED DEMAND	248.4
TOTAL	
CONNECTED LOAD	471.6
ESTIMATED DEMAND	302.4
AIR CONDITIONING	32.1

AREAS


GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM	18,000 S.F.

GENERAL NOTES:
RELOCATABLE PARTITIONS ARE DESIGNATED AS 2" PARTITIONS. ACTUAL DIMENSIONS WILL BE A FUNCTION OF DESIGN.

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VI	[illegible]	211-45	5 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291753
IN PART




FLOOR PLAN
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VW	SEPT 1986	211-45	1 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291753
IN PART



FRONT ELEVATION
NOT TO SCALE




SECTION A
NOT TO SCALE

TITLE	DATE FACILITY PLATE NO.	SHEET
AVIONICS SHOP VW	SEPT 1996 211-45	2 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291753
IN PART



TYPICAL SITE PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VW	SEPT 1986	211-45	3 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD- 291753
(NAVY)

NOTES

PLUMBING REQUIREMENTS

WATER

COLD	83 G.P.M.
HOT	
RECOVERY RATE (100°RISE)	85 G.P.H
STORAGE	85 G.P.H

FIRE PROTECTION REQUIREMENTS NOT INCLUDED

HEATING REQUIREMENTS (MBH)

OUTSIDE DESIGN TEMPERATURE

-5°F	+5°F	+15°F	+25°F
329	282	235	188

AIR CONDITIONING REQUIREMENTS

BASED ON 91°F D.B. /66°F WB OUTSIDE DESIGN CONDITIONS

COOLING LOAD (MBH)	330

HEAT REJECTED TO CONDITIONED SPACES BY ENERGIZED TEST

EQUIPMENT AND PARTS UNDER REPAIR NOT INCLUDED

ELECTRICAL REQUIREMENTS (KW)

LIGHTS	
CONNECTED LOAD	64.0
ESTIMATED DEMAND	80.0
POWER	
CONNECTED LOAD	460.0
ESTIMATED DEMAND	276.0
TOTAL	
CONNECTED LOAD	524.0
ESTIMATED DEMAND	336.0
AIR CONDITIONING	35.8

AREAS


GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM	20,000 S.F.

GENERAL NOTES:
RELOCATABLE PARTITIONS ARE DESIGNATED AS 2" PARTITIONS. ACTUAL DIMENSIONS WILL BE A FUNCTION OF DESIGN.

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VW	SEP 1986	211-45	41 OF 49

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291754
IN PART




FLOOR PLAN
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VA	SEPT 1996	211-45	1 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291754
IN PART



FRONT ELEVATION
NOT TO SCALE




SECTION A
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AV ORDS SHOP VA	SEPT 1986	211-45	2 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

MEL-HDBE-1028/1

SUPERSEDES
DD-1291754
IN PART



TYPICAL SITE PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIANO AB, ITALY	SEP 1 [illegible]	211-45	3 OF [illegible]

Source: https://assist.dla.mil - Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDED
DS-[illegible]/75.2
IN PART

NOTES:

PLUMBING REQUIREMENTS

WATER

COLD	76 G.P.M.
HOT	
RECOVERY RATE (100°RISE)	75 G.P.H.
STORAGE	75 G.P.H.

FIRE PROTECTION REQUIREMENTS NOT INCLUDED

HEATING REQUIREMENTS (MBH)

OUTSIDE DESIGN TEMPERATURE

-5°F	+5°F	+15°F	+25°F
362	31[illegible]	258	207

AIR CONDITIONING REQUIREMENTS

BASED ON 91°F D.B. 76°F WB OUTSIDE DESIGN CONDITIONS

COOLING LOAD (MBH) 363

HEAT REJECTED TO CONDITIONED SPACES BY ENERGIZED TEST

EQUIPMENT AND PARTS UNDER REPAIR NOT INCLUDED

ELECTRICAL REQUIREMENTS (KW)

LIGHTS	
CONNECTED LOAD	70.4
ESTIMATED DEMAND	66.0
POWER	
CONNECTED LOAD	506.0
ESTIMATED DEMAND	303.6
TOTAL	
CONNECTED LOAD	576.4
ESTIMATED DEMAND	369.6
AIR CONDITIONING	39.4

AREAS


GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM	22,000 S.F.

GENERAL NOTES:
RELOCATABLE PARTITIONS ARE DESIGNATED AS 2" PARTITIONS. ACTUAL DIMENSIONS WILL BE A FUNCTION OF DESIGN.

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS [illegible] DEP VA	SEPT 1984	211-15	4 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1391755
IN PART




FLOOR PLAN
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VP/VS/VR	SEPT 1986	211-45	1 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291755
IN PART



FRONT ELEVATION
NOT TO SCALE




SECTION A
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VP/VS/VR	SEPT 1986	211-45	2 OF 4


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291755
IN PART



AUXILIARY BUILDING
SCALE 3/32"=1'-0"





TYPICAL SITE PLAN
NOT TO SCALE

TITLE	DATE	ARMORY PLATE NO.	SHEET
AVIONICS SHOP VP/VS/VR	SEPT 1986	211-45	3 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291755
IN PART

NOTES

PLUMBING REQUIREMENTS

WATER

COLD	76 G.P.M.
HOT	
RECOVERY RATE (100°RISE)	75 G.P.H.
STORAGE	75 G.P.H.

FIRE PROTECTION REQUIREMENTS NOT INCLUDED

HEATING REQUIREMENTS (MBH)

OUTSIDE DESIGN TEMPERATURE

-5°F	+5°F	+15°F	+25°F
257	221	184	147

AIR CONDITIONING REQUIREMENTS

BASED ON 91°F D.B. 76°F WB OUTSIDE DESIGN CONDITIONS

COOLING LOAD (MBH)	258

HEAT REJECTED TO CONDITIONED SPACES BY ENERGIZED TEST

EQUIPMENT AND PARTS UNDER REPAIR NOT INCLUDED

ELECTRICAL REQUIREMENTS (KW)

LIGHTS	
CONNECTED LOAD	49.9
ESTIMATED DEMAND	46.8
POWER	
CONNECTED LOAD	358.8
ESTIMATED DEMAND	215.3
TOTAL	
CONNECTED LOAD	406.7
ESTIMATED DEMAND	262.1
AIR CONDITIONING	27.9

AREAS


GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM	15,600 S.F.
AUXILIARY BUILDING	400 S.F.

GENERAL NOTES:
RELOCATABLE PARTITIONS ARE DESIGNATED AS 2" PARTITIONS. ACTUAL DIMENSIONS WILL BE A FUNCTION OF DESIGN.

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VP/VS/VR	SEPT 1986	211-45	4 OF 4

Source: https://assist.dla.mil -- Downloaded: 20260-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291756
IN PART




FLOOR PLAN
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VA	SEPT 1986	211-45	1 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291756
IN PART



FRONT ELEVATION
NOT TO SCALE




SECTION A
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AV ONICS SHOP VA	SEPT 1986	21-45	2 OF 3

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291756
IN PART



TYPICAL SITE PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VA	SEPT 19[illegible]	211-45	3 OF 4

Source: https://assist.dla.mil - Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291756
IN PART

NOTES

PLUMBING REQUIREMENTS

WATER	
COLD	115 G.P.M.
HOT	
RECOVERY RATE (100°RISE)	135 G.P.H
STORAGE	135 G.P.H

FIRE PROTECTION REQUIREMENTS NOT INCLUDED

HEATING REQUIREMENTS (MBH)

OUTSIDE DESIGN TEMPERATURE

-5°F	+5°F	+15°F	+25°F
1054	903	753	602

AIR CONDITIONING REQUIREMENTS

BASED ON 91°F D.B. 76°F WB OUTSIDE DESIGN CONDITIONS

COOLING LOAD (MBH)	1056

HEAT REJECTED TO CONDITIONED SPACES BY ENERGIZED TEST

EQUIPMENT AND PARTS UNDER REPAIR NOT INCLUDED

ELECTRICAL REQUIREMENTS (KW)

LIGHTS	
CONNECTED LOAD	204.8
ESTIMATED DEMAND	192.0
POWER	
CONNECTED LOAD	1472.0
ESTIMATED DEMAND	883.2
TOTAL	
CONNECTED LOAD	1676.8
ESTIMATED DEMAND	1075.2
AIR CONDITIONING	114.4

AREAS


GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM	64,000 S.F.

GENERAL NOTES:
RELOCATABLE PARTITIONS ARE DESIGNATED AS 2" PARTITIONS. ACTUAL DIMENSIONS WILL BE A FUNCTION OF DESIGN

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VA	SEPT 1986	211-45	4 OF 4

Source: https://assist.dla.mil - Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291757
IN PART




FLOOR PLAN
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VW	SEPT 1986	211-45	1 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291757
IN PART



FRONT ELEVATION
NOT TO SCALE




REAR ELEVATION
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VW	SEPT 1986	211-45	2 OF 5

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291757
IN PART




SECTION A
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VW	SEPT 1990	211-45	3 OF 7

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291757
IN PART



TYPICAL SITE PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VW	SEPT 1986	211-45	4 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291757
IN PART

NOTES

PLUMBING REQUIREMENTS

WATER	
COLD	68 G.P.M.
HOT	
RECOVERY RATE (100°RISE)	62 G.P.H.
STORAGE	62 GAL.

*FIRE PROTECTION REQUIREMENTS NOT INCLUDED

HEATING REQUIREMENTS (MBH)

OUTSIDE DESIGN TEMPERATURE

-5°F	+5°F	+15°F	+25°F
182	156	130	104

AIR CONDITIONING REQUIREMENTS

BASED ON 91°F D.B. 76°F WB OUTSIDE DESIGN CONDITIONS

COOLING LOAD (MBH)	182

HEAT REJECTED TO CONDITIONED SPACES BY ENERGIZED TEST

EQUIPMENT AND PARTS UNDER REPAIR NOT INCLUDED

ELECTRICAL REQUIREMENTS (KW)

LIGHTS	
CONNECTED LOAD	35.2
ESTIMATED DEMAND	33.0
POWER	
CONNECTED LOAD	253.0
ESTIMATED DEMAND	151.8
TOTAL	
CONNECTED LOAD	288.2
ESTIMATED DEMAND	184.8
AIR CONDITIONING	19.7

AREAS


GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM	11,000 S.F.

GENERAL NOTES:
RELOCATABLE PARTITIONS ARE DESIGNATED AS 2" PARTITIONS. ACTUAL DIMENSIONS WILL BE A FUNCTION OF DESIGN.

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VW	SEPT 1986	211-45	5 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.


SUPERSEDES
DD-1291758
IN PART




TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VP/VS/VR	SEPT 1986	211-45	1 OF 4

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291758
IN PART



FRONT ELEVATION
NOT TO SCALE




SECTION A
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VP/VS/VR	SEPT 1986	211-45	2 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291758
IN PART



AUX. BLDG. FLOOR PLAN



TYPICAL SITE PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VP/VS/VR	SEPT 1986	211-45	3 OF 4

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1291758
IN PART

NOTES

PLUMBING REQUIREMENTS

WATER

COLD	100 G.P.M.
HOT	
RECOVERY RATE (100°RISE)	132 G.P.H.
STORAGE	132 GAL.

FIRE PROTECTION REQUIREMENTS NOT INCLUDED

HEATING REQUIREMENTS (MBH)

OUTSIDE DESIGN TEMPERATURE

-5°F	+5°F	+15°F	-25°F
550	471	393	314

AIR CONDITIONING REQUIREMENTS

BASED ON 91°F D.B. 76°F WB OUTSIDE DESIGN CONDITIONS

COOLING LOAD (MBH) 551

HEAT REJECTED TO CONDITIONED SPACES BY ENERGIZED TEST

EQUIPMENT AND PARTS UNDER REPAIR NOT INCLUDED

ELECTRICAL REQUIREMENTS (KW)

LIGHTS	
CONNECTED LOAD	103.4
ESTIMATED DEMAND	96.9
POWER	
CONNECTED LOAD	742.9
ESTIMATED DEMAND	445.7
TOTAL	
CONNECTED LOAD	846.3
ESTIMATED DEMAND	542.6
AIR CONDITIONING	59.7


AREAS

GROSS AREA INCLUDING MECHANICAL EQUIPMENT ROOM	32,300 S.F.
AIR CONDITIONING	1,080 S.F.

GENERAL NOTES:
RELOCATABLE PARTITIONS ARE DESIGNATED AS 2" PARTITIONS. ACTUAL DIMENSIONS WILL BE A FUNCTION OF DESIGN

TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP VP/VS/VR	SEPT 1986	211-45	4 OF 4


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.



TITLE	DATE	FACILITY PLATE NO.	SHEET
AVIONICS SHOP	SEPT 1986	211-45	1 OF 1

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1294512
IN PART




FLOOR PLAN
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AIR LAUNCHED GUIDED MISSILE SHOP	SEP 1986	212-30	1 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-12945-2
IN PART



FRONT ELEVATION
NOT TO SCALE




SIDE ELEVATION
NOT TO SCALE


TITLE	DATE	FACILITY PLATE NO.	SHEET
AIR LAUNCHED GUIDED MISSILE SHOP	SEPT 1986	212-30	2 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-12945:2
IN PART



SECTION A-A
NOT TO SCALE




SECTION B-B
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIR LAUNCHED GUIDED MISSILE SHOP	SEPT 1986	212-30	3 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-04-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1294512
IN PART



TYPICAL SITE PLAN
NOT TO SCALE

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIR LAUNCHED GUIDED MISSILE SHOP	SEPT 96	212-30	4 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

SUPERSEDES
DD-1294512
IN PART

NOTES

PLUMBING REQUIREMENTS

COLD WATER	50 G.P.M.
HOT WATER	
RECOVERY RATE (100° RISE)	30 G.P.H
STORAGE	40 GAL.

THE ABOVE RATES DO NOT INCLUDE REQUIREMENTS FOR FIRE PROTECTION

HEATING REQUIREMENTS (MBTU/HR)

OUTSIDE DESIGN TEMPERATURE

-5° F	+5° F	+15° F	+25° F
210	190	162	132

AIR CONDITIONING REQUIREMENTS

COOLING LOAD (MBTU/HR)	40.6

ELECTRICAL REQUIREMENTS (KW)


LIGHTS	
CONNECTED LOAD	35.1
ESTIMATED DEMAND	28.6
POWER	
CONNECTED LOAD	22.2
ESTIMATED DEMAND	19.2
TOTAL	
CONNECTED LOAD	57.3
ESTIMATED DEMAND	47.8
ADDITIONAL DEMAND FOR AIR CONDITIONING	5.9

AREA - SQ. FT. BUILDING

GROSS BUILDING AREA	7,397 S.F.

TITLE	DATE	FACILITY PLATE NO.	SHEET
AIR LAUNCHED GUIDED MISSILE SHOP	SEPT 1986	218-30	5 OF 5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.



TITLE	DATE	FACILITY PLATE NO.	SHEET
PORTABLE LINE SHELTER	SEPT 1986	211-15	1 OF 1

Source: https://assist.dla.mil -- Downloaded: 202640-26T13:56Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

REFERENCES

American Society of Heating, Refrigeration, and Air Conditioning Engineers (ASHRAE), 1791 Tullie Circle NE., Atlanta, GA 30329.

Standard 52-76	Method for Testing Air Cleaning Devices Used in General Ventilation for Removing Particulate Matter

American Society for Testing and Materials (ASTM), 1916 Race Street, Phildelphia, PA 19103.

D523-80	Standard Test Method for Specular Glass

Approval Guide, Factory Mutual Engineering Corporation, 1151 Boston-Providence Turnpike, P.O. Box 688, Norwood, MA 02062.

Department of Defense (DOD), Copies can be obtained from the Commanding Officer, Naval Publications and Forms Center, 5801 Tabor Avenue, Philadelphia, PA 19120.

DOD-STD-1399	Interface Standard for Shipboard Systems, Electric Power, Alternating Current

Department of the Navy

Chief of Naval Operations (OPNAV)

OPNAVINST 4790.2D	The Naval Aviation Maintenance Program
OPNAVINST 5510.1G	Department of the Navy Information Security Program Regulation
OPNAVINST 5530.14	Physical Security and Loss Protection

Naval Air (NAVAIR) Systems Command Technical Manuals. Available from the Department of the Navy, Naval Air Systems Command, Washington, DC 20360.

01-1A-22	Organizational, Intermediate, and Depot Maintenance, Aircraft Radomes and Antenna Covers
01-1A-509	Aircraft Weapons Systems Cleaning and Corrosion Control
01-1A-512	Design Guide for Avionics Shop Power Distribution
13-1-6.2	Manual Aviation - Crew Systems Parachutes
16-1-529 Volume 1	Electromagnetic Radiation Hazards (Hazards to Personnel, Fuel, and Other Flammable Material)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.

REFERENCES (Continued)

Naval Facilities Engineering Command (NAVFACENGCOM) Design Manuals (DM), Naval Facilities Guide Specification (NFGS), Publications (P), Military Handbooks (MIL-HDBK), Naval Facilities Instructions (NAVFACINST), Naval Sea Systems Command (NAVSEA), and Naval Supply Systems Command (NAVSUP).

DM-1 Series	Architecture
DM-1.01	Basic Architectural Requirements and Design Considerations
MIL-HDBK-1001/2	Materials and Building Components
DM-1.03	Architectural Acoustics
DM-2 Series	Structural Engineering
DM-3.01	Plumbing Systems
DM-3.03	Heating, Ventilating, Air Conditioning, and Dehumidifying Systems
DM-3.05	Compressed Air and Vacuum Systems
DM-3.10	Noise and Vibration Control of Mechanical Equipment
DM-4 Series	Electrical Engineering
DM-5.04	Civil Engineering - Pavements
DM-5.08	Civil Engineering - Pollution Control Systems
DM-5.09	Civil Engineering Metering, Instrumentation and Control, and Chemical Feeding
DM-5.12	Civil Engineering - Fencing, Gates, and Guard Towers
MIL-HDBK-1008	Fire Protection for Facilities Engineering Design and Construction
DM-21 Series	Airfield Pavement Design
DM-22	Petroleum Fuel Facilities
DM-23 Series	Airfield Lighting and Navigational Aids
DM-28.04	General Maintenance Facilities
DM-28.05	Environmental Control - Design of Clean Rooms

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

REFERENCES

American Society of Heating, Refrigeration, and Air Conditioning Engineers (ASHRAE), 1791 Tullie Circle NE., Atlanta, GA 30329.

Standard 52-76	Method for Testing Air Cleaning Devices Used in General Ventilation for Removing Particulate Matter

American Society for Testing and Materials (ASTM), 1916 Race Street, Phildelphia, PA 19103.

D523-80	Standard Test Method for Specular Glass

Approval Guide, Factory Mutual Engineering Corporation, 1151 Boston-Providence Turnpike, P.O. Box 688, Norwood, MA 02062.

Department of Defense (DOD), Copies can be obtained from the Commanding Officer, Naval Publications and Forms Center, 5801 Tabor Avenue, Philadelphia, PA 19120.

DOD-STD-1399	Interface Standard for Shipboard Systems, Electric Power, Alternating Current

Department of the Navy

Chief of Naval Operations (OPNAV)

OPNAVINST 4790.2D	The Naval Aviation Maintenance Program
OPNAVINST 5510.1G	Department of the Navy Information Security Program Regulation
OPNAVINST 5530.14	Physical Security and Loss Protection

Naval Air (NAVAIR) Systems Command Technical Manuals. Available from the Department of the Navy, Naval Air Systems Command, Washington, DC 20360.

01-1A-22	Organizational, Intermediate, and Depot Maintenance, Aircraft Radomes and Antenna Covers
01-1A-509	Aircraft Weapons Systems Cleaning and Corrosion Control
01-1A-512	Design Guide for Avionics Shop Power Distribution
13-1-6.2	Manual Aviation - Crew Systems Parachutes
16-1-529 Volume 1	Electromagnetic Radiation Hazards (Hazards to Personnel, Fuel, and Other Flammable Material)

Source: https://assist.dla.mil -- Downloaded: 202640-26T13:56Z
Check the source to verify that this is the currentversion before use.

REFERENCES (Continued)

Naval Facilities Engineering Command (NAVFACENGCOM) Design Manuals (DM), Naval Facilities Guide Specification (NFGS), Publications (P), Military Handbooks (MIL-HDBK), Naval Facilities Instructions (NAVFACINST), Naval Sea Systems Command (NAVSEA), and Naval Supply Systems Command (NAVSUP).

DM-1 Series	Architecture
DM-1.01	Basic Architectural Requirements and Design Considerations
MIL-HDBK-1001/2	Materials and Building Components
DM-1.03	Architectural Acoustics
DM-2 Series	Structural Engineering
DM-3.01	Plumbing Systems
DM-3.03	Heating, Ventilating, Air Conditioning, and Dehumidifying Systems
DM-3.05	Compressed Air and Vacuum Systems
DM-3.10	Noise and Vibration Control of Mechanical Equipment
DM-4 Series	Electrical Engineering
DM-5.04	Civil Engineering - Pavements
DM-5.08	Civil Engineering - Pollution Control Systems
DM-5.09	Civil Engineering Metering, Instrumentation and Control, and Chemical Feeding
DM-5.12	Civil Engineering - Fencing, Gates, and Guard Towers
MIL-HDBK-1008	Fire Protection for Facilities Engineering Design and Construction
DM-21 Series	Airfield Pavement Design
DM-22	Petroleum Fuel Facilities
DM-23 Series	Airfield Lighting and Navigational Aids
DM-28.04	General Maintenance Facilities
DM-28.05	Environmental Control - Design of Clean Rooms

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

REFERENCES (Continued)

MIL-HDBK-1028/6	Aircraft Fixed Point Utility Systems (PROPOSED)
DM-32 Series	Storage
DM-38.01	Weight-Handling Equipment
MIL-HDBK-1190	Facility Planning and Design Guide
P-34	Engineering and Design Criteria for Navy Facilities
P-80	Facility Planning Criteria for Navy and Marine Corps Shore Installatons.
P-272, Part 1	Definitive Designs for Naval Shore Facilities (including 1291710, 1291712 and 1291714)
P-272, Part 2	Definitive Designs for Naval Shore Facilities (Category Code 852-10)
P-272, Part 4	Definitive Designs for Marine Corps Facilities
NFGS-07410	Preformed Metal Roofing and Siding
NFGS-08301	Steel Sliding Hangar Doors
NFGS-09921	Reflective Floor Coatings for Aircraft Maintenance Facilities
NFGS-13093	Radio Frequency Shielded Enclosures, Demountable Type
NFGS-13094	Radio Frequency Shielded Enclosures, Welded Type
NFGS-14335	Monorails With Air Motorpowered Hoist
NFGS-14637	Cranes, Overhead Electric, Underrunning (Under 20,000 Pounds)
NFGS-16650	Radio Frequency Interference Power Line Filters
NAVFACINST 11010.44D	Shore Facilities Planning
NAVSEA OP-5	Ammunition and Explosive Ashore
NAVSUPINST 4570.23	Recovery and Utilization of Precious Metals

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

REFERENCES (Continued)

Industrial Ventilation, A Manual of Recommended Practice - American Conference of Governmental Industrial Hygienists (ACGIH), Committee of Industrial Ventilation, Building D-5, 6500 Glenway, Cincinnati, OH 45211.

Lead Exposure and Design Considerations for Indoor Firing Ranges, Anania, Thomas L., and Seta, Joseph A. Copies available from the National Institute for Occupational Safety and Health (NIOSH), U.S. Department of Health and Human Services, 200 Independence Ave, SW., Washington, DC 20201.

Military Standards - available from the Commanding Officer, Naval Publications and Forms Center, 5801 Tabor Ave., Phidelphia, PA 19120.

MIL-STD-704	Aircraft Electric Power Characteristics
MIL-C-22992	Electrical Convertors

National Fire Protection Association (NFPA) Inc. Batterymarch Park, Quincy, MA 02269.

NFPA 30	Flammable and Combustible Liquids Code
NFPA 33	Spray Application Using Flammable and Combustible Materials
NFPA 70	National Electric Code
NFPA 101	Code for Safety to Life from Fire in Buildings and Structures
NFPA 409	Aircraft Hangars

Occupational Safety and Health Act Standards Manuals, Public Law 29 Code of Federal Regulations Sections 1910, Occupational Safety and Health Administration. Copies can be obtained from the Superintendant of Documents, Government Printing Office, Washington, DC 20402.

Underwriters Laboratories, Inc., 333 Pfingsten Road, Northbrook, IL 60062.

1572-80	Building Materials Directory

CUSTODIAN
NAVY - YD

PREPARING ACTIVITY
NAVY - YD

PROJECT NO
FACR-0190

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

STRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in mitting comments and suggestions for improvements. All users of military standardization documents are invited to provide ns. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and iled. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the blems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an nowledgement will be mailed to you within 30 days to let you know that your comments were received and are being sidered.

TE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of cification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization waive any portion of the referenced document(s) or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

EPARTMENT OF THE NAVY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

FICIAL BUSINESS
ALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12503 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE NAVY

COMMANDER
NAVAL FACILITIES ENGINEERING COMMAND
ATLANTIC DIVISION
CODE 04A4
NORFOLK, VIRGINIA 23511-6287

Source: https://assist.dla.mil -- Downloaded: 202610-26T13:56Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-HDBK-1028/1	AIRCRAFT MAINTENANCE FACILITIES

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
	☐ USER
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ MANUFACTURER
	☐ OTHER *(Specify)*:

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T13:56Z
Check the source to verify that this is the current version before use.