MIL-T-11407L
12 March 1982
SUPERSEDING
MIL-T-0011407K(ME)
17 March 1981 and
MIL-T-11407J
27 August 1974

MILITARY SPECIFICATION

TRUCK, FIRE FIGHTING, 1000 GPM, TACTICAL TYPE, MULTIPURPOSE

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a 1000 gallon per minute (gpm) fire truck for use in combating structural, brush and aircraft crash fires at military installations.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified (see 6.2), the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

W-B-131	- Battery, Storage: Vehicular, Ignition, Lighting, and Starting.
VV-F-800	- Fuel Oil, Diesel.
QQ-C-320	- Chromium Plating-Electrodeposited.
QQ-P-35	- Passivation Treatments for Corrosion Resisting Steel.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 4210

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-P-116	- Preservation, Methods of.
MIL-P-514	- Plates, Identification, Instruction and Marking, Blank.
MIL-B-7883	- Brazing of Steels, Copper, Copper Alloys, Nickel Alloys, Aluminum and Aluminum Alloys.
MIL-A-8421	- Air Transportability Requirement, General Specification for.
MIL-E-10062	- Engines, Preparation for Shipment and Storage of.
MIL-F-24385	- Fire Extinguishing Agent, Aqueous Film Forming Foam (AFFF) Liquid Concentrate, Six Percent, for Fresh and Sea Water.
MIL-A-46153	- Antifreeze, Ethylene Glycol, Inhibited, Heavy Duty, Single Package.

STANDARDS

FEDERAL

FED-STD-H28	- Screw-Thread Standards for Federal Services.
FED-STD-595	- Colors.

MILITARY

MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-209	- Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.
MIL-STD-281	- Automobiles, Trucks, Truck-Tractors, Trailers and Trailer Dollies: Preservation and Packaging of.
MIL-STD-889	- Dissimilar Metals.
MIL-STD-1223	- Administrative Wheeled Vehicles Treatment, Painting, Rustproofing, Undercoating, Identification Marking, Data Plates and Warranty Notice Standards.

(Copies of specification and standards required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.1.2 Other Government documents and publications. The following other Government documents and publications form a part of this specification to the extent specified herein.

DEPARTMENT OF TRANSPORTATION (DOT)

Motor Carrier Safety Regulations.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A153 - Zinc Coating (Hot-Dip) on Iron and Steel Hardware.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN WELDING SOCIETY, INC. (AWS)

D1.1 - Structural Welding Code, Section 5, Qualification.

(Application for copies should be addressed to the American Welding Society, Inc., 2501 NW Seventh Street, Miami, FL 33125.)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 1901
NFPA 1931
NFPA 414

(Application for copies should be addressed to the National Fire Protection Association, 470 Atlantic Avenue, Boston, MA 02110.)

SOCIETY OF AUTOMOTIVE ENGINEERS (SAE)

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, 400 Commonwealth Drive, Warrendale, PA 15096.)

TIRE AND RIM ASSOCIATION (TRA)

Tire and Rim Association Yearbook, with Military Supplement.

(Application for copies should be addressed to the Tire and Rim Association, 3200 West Market Street, Akron, OH 44313.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 Description. The fire truck (hereinafter called "truck") shall be a front-wheel-steer, four-wheel-drive, truck cab and chassis powered by a diesel engine. The truck shall be equipped with a midship-mounted pump driven by the truck engine, a frame-mounted water tank, and such other equipment and accessories as are specified herein. This vehicle shall have a pump and roll capability. Operating parts not specifically covered herein but necessary to provide a complete and efficient truck shall be furnished. When specified (see 6.2), the truck shall be winterized as specified in 3.10. When specified (see 6.3), the Government will conduct any or all of the preproduction examination and tests, as specified (see 6.2).

3.2 First article (preproduction model). The contractor shall furnish one or more trucks as specified (see 6.2), for examination and testing within the time frame specified (see 6.2), to prove prior to starting production that his production methods and choice of design detail will produce trucks that comply with the requirements of this specification. Examination and tests shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.3).

3.3 Initial production. When specified (see 6.2), the contractor shall furnish to the Government one or more trucks (see 6.2), for inspection as specified in 4.4.

3.4 Winterized preproduction model. When winterized trucks are specified (see 3.1), in addition to nonwinterized trucks, only the winterized preproduction models shall be furnished for examination and tests.

3.5 Material. Material shall be as specified herein. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification (see 6.4 and 6.7) and shall conform to MIL-STD-889 dissimilar metals as applicable. Items normally chromium plated for fire service use shall be chromium plated in accordance with QQ-C-320.

3.6 Environmental operation requirements.

3.6.1 Temperature. The truck shall be capable of starting and performing in any temperature from plus 125°F while exposed to maximum solar radiation, to minus 25°F, or to minus 65°F without benefit of solar radiation, when winterized as specified in 3.10.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

4.5.2.12 Air transportability tests.

3.6.2 Altitude. The truck shall deliver its rated pumping capacity of 150 psi net pump pressure at any elevation from sea level to 2000 feet at the temperatures specified in 3.6.1. Pump pressure shall be calculated as established by Underwriters Laboratories. When specified (see 6.2), modification kits shall be provided and installed for utilization of trucks at specified elevations above 2000 feet.

3.7 Safety. All space which is occupied or in which work is performed during operation, service, and maintenance of the truck shall be free of hazardous protrusions, edges, cracks, or other features that may cause injury to personnel. Safety features such as steps with antiskid tread, handrails, or guards shall be provided at all points where the protection of personnel is in question. All critical switches be covered, or located so that they are protected from being operated accidentally.

3.7.1 Hazard guards. All rotating and reciprocating parts and all parts subject to high operational temperatures or to being electrically energized, that are of such nature or so located as to be hazardous to operating personnel, shall be insulated or guarded to the extent necessary to elminate the hazard.

3.8 Human factors. The characteristics of the truck shall provide for operation by personnel ranging from the small woman, through the large man, arctic-clothed, in accordance with SAE J833 and J925.

3.9 Ease of maintenance. All major assemblies, including pumps, transmission, transfer case, hose reels, foam proportioner, water and foam tanks, and similiar items, shall be arranged for individual removal and replacement without major disassembly or removal of other components or the truck body. Covers or plates which must be removed for component adjustment or maintenance shall be equipped with quick-disconnect fasteners. Drain outlets shall be located for accessiblity.

3.10 Winterization. The winterized trucks (see 3.2), shall be equipped with a heating system such that the vehicle and its fire fighting system are operable at a temperature of minus 50°F. Heaters shall be located so as to be accessible for maintenance without removing or disconnecting other components of the vehicle. Heaters shall be of fully automatic cycling type. The heating system shall maintain the following conditions when the vehicle engine is not operating and the truck is exposed to a temperature of minus 65°F:

(a) Cab heating to plus 50°F, and 50 percent windshield area defrosting.
(b) Foam tank, water tank, battery compartment, and pump compartment not less than plus 50°F. Means shall be provided for either maintaining the hose reel at the plus 50°F temperature, or for completely purging the booster hose system to preclude freezing.
(c) Engine coolant not less than 125°F. The system shall be controlled from a control panel located inside the cab. In addition, either a solenoid or a manually operated valve shall be provided to isolate the winterization coolant piping from the engine coolant system.

Ether primer for cold starting may be used.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

3.11 Performance. The truck, loaded with either all equipment specified herein and with filled water, foam, fuel, and lubricant compartments or a 1500 pound evenly distributed simulated load. A weight simulating a five man crew of 875 pounds shall be distributed in the cab and jump seat area. With this simulated weight the fire truck shall be capable of the following:

(a) From a standing start up a 10-percent grade, attain a speed of 15 miles per hour (mph) within 25 seconds of the starting point.
(b) Ascend, both in forward and reverse gears, a grade of not less than 50 percent.
(c) Accelerated on a level road from a standing start to a speed of 50 mph within 35 seconds.
(d) Attain a speed of not less than 65 mph.
(e) When tested as specified herein, there shall be no evidence of body distortion, water leakage, tire and body contact, malfunctioning of components, or irregular chassis noise, vibration or sway.
(f) Operate on a 20-percent side slope without malfunction, distortion, sliding, or tipping.
(g) From a steady speed of 15 mph the vehicle shall accelerate to a speed of 35 mph within 30 seconds without moving gear selector.
(h) Negotiate unimproved surfaces, rough terrain and soft ground.
(i) Be capable of engaging pump at speeds up to 30 mph without damage to pump or transmission components.

3.12 Truck chassis. The chassis shall be cab-ahead-of-engine type (custom cab).

3.12.1 Gross vehicle weight rating. The total gross weight of the truck when loaded as specified in 3.11, shall not exceed the published rating of the axle manufacturer and the tire manufacture.

3.12.2 Wheel base. The wheel base shall be of such length so as to mount the body and the equipment specified herein. The center of gravity shall be kept as low as possible.

3.12.2.1 Dimensions. The overall length of the truck and equipment shall not exceed 30 feet. The overall width shall not exceed 96 inches per DOT requirements. The height of the rear overhang shall not exceed 96 inches. The overall height of the transport configuration shall permit the truck to be loaded on the C-130 aircraft using the auxiliary ground loading ramps. The maximum height, including roof turret in the stored position, shall not exceed 102 inches. Restraint shall be provided to meet the requirements of MIL-A-8421. Lift and tiedown provisions shall be in accordance with MIL-STD-209 and MIL-A-8421.

3.12.2.2 Air transportability. Unless otherwise specified (see 6.2) the truck shall be transportable by highway, rail, and marine modes of transport. It shall also be designed for air transportability in accordance with MIL-A-8421 to include transport in a C-130 Air Force aircraft equipped with an A/A32H-4 dual rail cargo handling system.

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:00Z
Check the source to verify that this is the current version before use.

3.12.2.3 Transportability report. Unless otherwise specified (see 6.2), the contractor will furnish a transportability report for the truck 90 days prior to delivery of the first article truck.

3.12.3 Frame. The chassis frame shall be of heavy-duty design for fire service use and shall be provided with cross-members, exclusive of engine supports, to support the gross weight of the body and load, the power plant, the pump, the filled water tank, and all other equipment under the operating conditions specified herein, without evidence of distortion adversely affecting operation. The frame shall be reinforced for concentrated loads where necessary. No alternations shall be made to the frame which will reduce its strength.

3.12.4 Off road protection. The truck chassis shall be provided, where necessary, with skip plates, belly pans or other devices to protect the engine oil pan, pump, transmission, tailpipe, muffler, and other chassis components from damage caused by rocks, tree stumps and other objects incurred during off road travel. All protective plates shall be easily removable or shall allow for ease of maintenance.

3.12.5 Engine. A turbocharged diesel engine shall be used for powering the fire truck and shall deliver a minimum of 120 percent of the net horsepower necessary to meet the performance requirements specified herein and shall be so certified; also, calculations shall be furnished to verify this in accordance with SAE J816. Diesel engine shall deliver the required performance when using fuel conforming to VV-F-800.

3.12.5.1 Engine hourmeter. An hourmeter having a totalizing mechanism of not less than 9,999 hours shall be provided in the truck cab to register the number of hours of engine operating time.

3.12.5.2 Cooling system. A heavy duty cooling system shall be provided, that is capable of maintaining normal operating temperature during stationary pumping at 125° F and under all driving conditions specified herein.

3.12.5.2.1 Heat exchanger. An auxiliary heat exchanger shall be provided that will permit delivery of water from the fire pump for cooling the engine liquid coolant without admixture. The flow of water from the fire pump to the heat exchanger shall be controlled by a valve located at the fire pump control panel.

3.12.5.2.2 Drain cocks. Readily accessible drain cocks shall be installed at low point of the cooling and heat exchanger systems and at any other points necessary to completely drain the systems.

3.12.5.2.3 Engine fuel system. The fuel system shall include fuel filters, all necessary piping, valves, fittings, and flexible connections in the fuel line between the frame and pump, and all other necessary components to provide a complete fuel system. All components of the fuel system shall be located or shielded so as not to be subject to vapor lock. Fuel lines shall be adequately supported and shall be protected against mechanical damage. The fuel tank shall

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:00Z
Check the source to verify that this is the currentversion before use.

be made of corrosion-resistant material. The bottom of the fuel tank and its supporting member shall be not lower than the lowest adjacent parts of the chassis or body. The tank capacity shall be large enough to operate the truck for not less than 4 hours at rated output without refueling. The tank shall be equipped with an air vent, drainplug, removable screen located at the filler neck of the tank, an approved flame arrester relief fitting, and a filler opening. Construction of the filler opening shall permit filling from the spout of a military 5-gallon liquid container and shall be located so that the spills or overflow cannot run down on the engine exhaust system or batteries. The filter cap shall not protrude.

3.12.5.3 Engine lubrication. The system shall include a magnetic drainplug in the crankcase. The fill pipe shall be conveniently located and shall be large enough to permit easy filling of the oil reservoir. An oil pressure gage shall be provided on the cab dash panel and also on the pump control panel. The engine lubrication system shall include an oil filter.

3.12.5.4 Exhaust system. The truck shall be equipped with a muffler and exhasut system. The tailpipe shall be located in such a manner that entrance of exhaust gases into the cab shall be minimized under all conditions of operation. Location of the tailpipe shall prevent heating of tires, and any clogging by mud and shall be directed away from the pump control panels. The muffler shall be located not closer than 2 feet from the fuel tank, with full shielding for the tank from any part of the exhaust system within 1 foot of the tank and insulation and shielding elsewhere, where necessary. The muffler, exhaust pipe, and tailpipe shall be of high-grade corrosive-resistant materials.

3.12.5.5 Brake horsepower certification. The contractor shall certify that the engine furnished complies with the requirements of this specification.

3.12.6 Electrical equipment. The truck shall be equipped with a 12-volt electrical system. Components shall be located so as not to be adversely affected by engine heat. All electrical components shall be water resistant and designed so that their normal functioning will not be impaired by entrance of water during heavy rains, road splash, condensation, or from water spray resulting from other causes. Wiring shall be color coded or numbered for easy identification and secured (except for ignition harness) to the frame and body throughout the truck with fasteners. Means of wiring identification shall be consistant throughout the truck. Wire shall be protected by means of looms or grommets at points of potential abrasion. Wiring shall be neatly run with all excess wire removed. All components shall be designed for operation at 12-volts. The use of 6-volt equipment paired in series with resistors or tapped to the midpoint of the battery is not acceptable.

3.12.6.1 Starting system. The starting system shall be standard for the type truck furnished. The ignition system shall be furnished with a keyless switch and a pilot light. Trucks shall be provided with a safety device to prevent engine starting unless the transmission is in a neutral position.

3.12.6.2 Battery units and electrical circuits. Two 12-volt battery units shall be provided. Both battery units shall be housed and shall be mounted on

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:00Z
Check the source to verify that this is the currentversion before use.

either a draw-out-type or permanent-type tray to permit accessibility for individual cell inspection, testing, and servicing. Provision shall be made f locking the draw-out-type tray in a retracted position. Battery cables shall b arranged to prevent chafing. Batteries shall be securely held in place on carrier trays by means of removeable locking devices and shall be protected against engine and exhaust heat. Battery compartments shall be ventilated to the truck exterior and treated against acid fumes and spillage. The batteries shall be shipped charged and dry. Each battery shall be provided with a polarized receptacle for station charging and shall be located so as to automatically be disconnected when the truck moves forward. The battery circu shall be provided with a reverse current device to protect the voltage regulat from damage when the batteries are connected in reverse polarity. The receptacle shall be of the recessed male type with a spring-loaded cover, and shall be provided with a matching female plug. The batteries shall conform to W-B-131, SAE number 20T6A or 20T8A. Battery circuits and switching system sha be provided whereby:

(a) Either battery may be used:

(1) For ignition and lights alone.
(2) For starting alone.
(3) For starting, ignition and lighting.

(b) Both batteries may be used simultaneously in starting.
(c) Neither the lighting wiring nor the ignition wiring will be connect to both batteries except when both starter switches are operated.
(d) The alternator shall be connected to supply the battery which is being used for ignition and lights.
(e) Wiring shall conform to wiring diagram entitled "Suggested Application of Dual Batteries to Single Ignition Engine" in the appendix of NFPA 1901.
(f) Batteries shall be sufficient to start engine after truck and batteries have been cold soaked at minus 25°F.

3.12.6.2.1 Electrical system. The engine shall be equipped with a 12-volt alternator and regulator capable of supplying the build-in dc current requirements of the truck with a minimum rating of 125 amps. Charging rate at 1000 engine rpm shall be minimum of 70 amps. A 5000 watt minimum ac power inverter capable of continuous operation at rated output shall be provided. T inverter shall electrically attach to the vehicle alternator and shall produce constant 60 Hz ± 1 Hz power at all engine speeds. The inverter shall have voltage control of ± 5 percent no-load to full load. Pulley ratio driving the alternator shall be sized to provide a minimum of 2000 watts of ac power at 90 engine rpm. A remote control shall be installed to allow starting and stoppin of the inverter from the pump operator's position and driver's cab position. voltmeter shall be provided with both control positions. All wires shall be o sufficient gage and shall be properly supported and protected from injury. Tw fused, grounded, weather-proof, dual receptacles, with spring-loaded covers, shall be electrically wired into the 120-volt, ac output of the inverter. An outlet shall be mounted on each side of the truck adjacent to the pump compartment and two outlets shall be located for connecting the lights specifi in 3.28. The inverter shall be mounted in the cab between the two seats.

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:00Z
Check the source to verify that this is the current version before use.

3.12.6.3 Lighting system. All truck lights, reflectors, and wiring shall be standard for the truck furnished except as specified herein:

(a) Identification lamps are required.
(b) Clearance and side marker lamps shall be combined and mounted to indicate width of truck.
(c) Overload protective devices shall be of the automatic-reset, overload-circuit-breaker type. The lighting system shall be arranged so that the bedlamp circuit or circuits shall not be affected by a short circuit in any of the other circuits.
(d) Rear-mounted lights shall be located so that they shall not be obscured by equipment or personnel normally carried on the rear step.
(e) Front-turn-signal units shall be single-faced flush mounted. The self-canceling-type controller shall be mounted on the steering column, shall operate a visual indicator, and shall have a four-way flashing capability and be wired independent of the ignition system.

3.12.6.3.1 Additional lighting. The following additional lighting shall be provided:

(a) Two automotive-type sealed-beam spotlights located on each side of the windshield, with controls extended inside the cab for "on-off" control. Spotlight control handle shall not obscure the driver's vision or present a hazard to vehicle occupant's head.
(b) Two adjustable sealed-beam hose pickup lights. Lights shall be mounted to the outside of the hose bed.
(c) Two engine-compartment lights arranged to illuminate both sides of the engine. Both lights shall be controlled by one switch and indicator light installed on the dash panel of the cab.
(d) Pump control panel lights designed to illuminate the panel. Control switch shall be mounted on control panel.
(e) Two backup lights, not less than 6-inch diameter, located at rear of the body. The backup light switch shall be automatically controlled when the transmission is placed in reverse.
(f) Stoplights, taillights, turn signal lights, and backup lights shall be flush mounted.
(g) A complete wiring diagram shall be provided with each manual furnished with the truck.

3.12.6.3.2 Warning light. A warning light bar with sealed-beam lights shall be mounted on top of the truck cab. All warnings lights shall have red or blue lenses as specified (see 6.2) Two warning lights shall be mounted, one on either side at the rear of the truck outside of the hose pickup lights. Lights shall be mounted so as not to interfere with packing or laying hose. Two motorized, oscillating sign-wave pattern lights shall be recessed mounted and equally spaced on the front of the cab under the windshield. The controls for the warning lights shall be independent of all other electrical equipment and shall be broken down into three groups: front, top, and rear. All lights shall be 12-volt dc.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

3.12.6.3.3 Light switches. The headlight switch shall be the standard push-pull type. The warning light shall be the single-pole-single-throw, rocker, circuit-breaker type with indicating light for the "on" position. All switches shall be marked for their intended use.

3.12.6.4 Siren and horn. The truck shall be equipped with a Federal Sign and Signal Corporation electronic siren and PA combination model PA2100, or equal. The electronic siren shall be furnished with a microphone and all wiring applicable to two-way radio. Two tone adjustable trumpet-type air horns shall be mounted on the cab. The horns shall be controlled by a pull chain for the passenger and by the standard horn button in the center of the steering wheel for the driver. Air for the air horns shall be supplied by a line directly from the air tank. A buzzer shall be installed in the cab, and a waterproof pushbutton switch shall be mounted at the rear of the truck to provide a signaling device between the rear platforn and the driver.

3.12.7 Bumper. A heavy-duty steel Boston style bumper shall be provided on the front of the truck chassis and shall be attached directly to the chassis frame.

3.12.8 Towing hooks, rings, or eyes. Towing hooks, rings or eyes, attached to the frame with through-bolts, shall be provided to permit towing of the truck and towing of other apparatus by the truck. Two hooks at the front and two recessed rings of 3-inch inside diameter at the rear, all forged steel shall be provided. The recessed-towing-ring mounting shall include reinforcement to transfer the load directly to chassis rails.

3.12.9 Shock absorbers. Double-acting hydraulic shock absorbers shall be provided at both front and rear suspensions.

3.12.10 Springs. Front and rear springs shall sustain the distributed gvw without evidence of overload or permanent set. The springs shall be designed and suspended for the superimposed loads so as to absorb shock and limit sway. Individual wheel loadings, with the truck loaded as specified in 3.11, shall be not greater than the rated capacities of the respective springs measured at the ground.

3.12.11 Truck drive assembly. The entire propulsion train between the engine and the drive wheels shall have a torque capacity at least equal to the maximum torque developed by the engine through the intervening speed and torque ratios.

3.12.11.1 Transmission. The transmission shall be of the fully automatic type with not less than four forward and one reverse speed. The transmission shall be certified for heavy-duty fire service and designed to match the engine torque and speed to load demand. The transmission shall provide for driver selection of individual gears or range of gears required to meet performance requirements specified herein. The shift control shall be mounted on a pedestal to the right of the driver's seat and incorporate a positive indicator for each gear or range selected. The transmission shall be protected so that the operator cannot inadvertently shift into reverse. An electric operated back-up warning system conforming to SAE J944 shall be installed to automatically

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

The body shall be made of aluminum alloy having not less than

operate when the transmission is put in the reverse mode. When the transmission is used to drive the fire pump, a locking device shall be installed to insure that the transmission remains in the correct gear range and insure that power is not applied to the drive wheels when stationary pumping.

3.12.11.2 Drive axle. The drive axle shall be of the full-floating type.

3.12.11.3 Transfer case. The transfer case shall provide for either selective or continuous front axle drive. Continuous four-wheel drive shall be provided with features to compensate for differential torque and speeds between the front and rear axles. If a two-speed transfer is provided, instruments that will allow the driver to visually match transmission and transfer speeds required for ease in shifting from high to low range transfer and vice versa, shall be located at the cab instrument panel. Front and rear axle differentials shall be equipped with automatic or driver controlled locks. If automatic locks and selective front axle drive are furnished, an indicator light shall be provided on the cab instrument panel to show when front axle drive is engaged.

3.12.11.3.1 Pump drive. The pump drive and pump gear ratio shall be selected to provide the required performance in pump and roll operations. Pump drive shall allow for pump engagement for pumped roll mode up to speeds of 30 mph. Controls to place the pump in gear shall be located in the chassis cab. Provisions shall be made to protect the pump and pump drive from damage by accidently engaging the tire pump or pump drive. Mechanical means shall be provided to engage and disengage the pump under emergency conditions. Controls shall be marked and shall be accessable without getting under the truck or using tools.

3.12.12 Steering mechanism. The chassis shall be equipped with a steering mechanism located for left-hand or center drive. Provisions shall be made for rapid adjustment of lost motion in the steering mechanism. The power-assisted steering shall have sufficient capacity so that no more than 15 pounds pull is required on the steering wheel in order to turn the steering wheel from lock to lock with the engine running. Front wheels shall have a cramping angle as required by NFPA 414.

3.12.13 Brakes. Brakes shall be standard for the chassis furnished.

3.12.13.1 Service brakes. The truck shall be equipped with straight-air, quick build-up, front and rear independent, 4-wheel self-energizing-type service brakes. Service brakes shall control and hold the truck, loaded as specified in 3.11, on a 50 percent grade. Under all conditions of loading, service brakes shall stop the truck within 30 feet from a speed of 20 mph on dry hard level surfaces free from loose material. The brake mechanism shall be accessible for exterior adjustment. Brake lines shall be anchored to the chassis and protected from damage. An alcohol evaporator shall be provided to prevent system freezing. The ejector and evaporator cannister shall be easily accessible to service. An air dryer with heated automatic moisture ejector shall be provided.

3.12.13.2 Parking brake. The truck shall be provided with a parking brake. The parking brake shall be the self-energizing air-release type. The parking

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

brake shall be controlled by a control on the cab dashboard. The parking brake shall be capable of holding the loaded vehicle on a 20 percent grade. The air system when charged to not less than 100 psi shall not leak more than 50 percent in 24 hours. The system shall be of the rapid build-up type for rapid response as specified in NFPA 414.

3.12.14 Wheels and tires. Single wheels shall be provided on both the front and rear. Tires shall be 16.5-22.5, 16 ply rating with nondirectional type all-weather tread. Individual tire loading at gross vehicle weight shall not exceeed the Tire and Rim Association load ratings for 55-60 mph operation. All rims shall be interchangeable front and rear.

3.12.15 Angles of approach and departure. The angles of approach and departure shall be not less than 22 degrees. The back step shall not be higher than 25.5 inches above ground with the truck loaded as specified in 3.11.

3.13 Cab. The cab shall accommodate at least two personnel and shall have an upholstered seat and back. The driver's seat shall be four way adjustable seat. The engine compartment and driver-passenger compartment shall be separated by an insulated firewall. All wiring and tubing connected to roof mounted lights and horns shall be run behind a headliner or false roof. The cab shall be equipped with tinted glass. The windshield shall be laminated glass and the windows shall be safety plate glass. A hot water heater shall be provided. Discharge outlets shall be provided to direct heated air to the floor and to defroster louvers. The defroster system shall be able to sustain a clear windshield for the driver's line of site. Heaters shall be complete with blower, and controls shall be mounted convenient to the driver. The heater shall have sufficient capacity to maintain a minimum inside temperature of 50°F at an ambient temperature of minus 25°F. Lever controls shall be designed and located to permit easy entrance and exit to and from the driver's compartment. Floor mats or rubber boots for all levers through openings in the floor shall be furnished. Instruments and controls shall be permanmently marked to identify their function and shall be installed to facilitate removal and servicing. Chassis equipment shall be complete with all accessories and shall include, but is not limited to, the following equipment:

(a) Outside rearview mirrors, mounted on each side of the cab, each with wide angle convex mirror area and with fold back supporting arms. Stick-on convex mirrors are not acceptable. Mirrors shall be mounted so as to allow survey of both sides of the truck by the driver.
(b) Ammeter.
(c) Fuel gage.
(d) Oil pressure gage.
(e) Air pressure gage and low-pressure indicator light and buzzer.
(f) Transmission oil-temperature gage.
(g) Engine temperature gage.
(h) Hourmeter.
(i) Speedometer reading in both miles and kilometers with recording odometer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

(j) Tachometer. A tachometer shall be furnished in the dash of the truck, visible to the driver. A tachometer shall also be furnished on the pump panel. Both tachometers shall show engine speed of not less than an operating range from 0 to 4000 rpm.
(k) Dual sun visors.
(l) Interior lighting, including jump seat area.
(m) Adjustable, weather-resistant SAE J4, type I, safety seat belt, with seat belt anchors in accordance with SAE J787. Seat belts shall have a noncorrosive metal-to-metal quick-release buckle for each seated occupant. Seat belt retractors shall be provided.
(n) Jump seat areas shall be provided with a movable safety bar across the jump seat entranceway.
(o) Necessary grab handles for mounting and dismounting vehicle.

The front portion of the cab shall have an adjustable seat for the driver and seating for a passenger. The front portion of the cab shall be partitioned off from the jump seat area by a sliding glass window. The rear portion of the cab shall provide jump seats for not less than two fire-fighters and shall include seat belts. The jump seats shall face the rear of the truck. The top and sides of the cab shall extend equally to cover the jump seat area. The jump seat area shall be provided with an overhead dome light and control switch.

3.13.2 Windshield wiper and washer. Windshield wipers shall be mounted to facilitate clear vision. Wiper assemblies shall include features to permit speed control and return of the wiper blade to a retracted position out of the line of vision when not in use. The windshield cleaning system shall include a device that will spray the path of the wiper blades with a water or cleansing solution. The cleansing solution reservoir shall have a minimum capacity of 1 quart.

3.14 Fire pump. The fire pump shall be midship mounted. The pump transmission shall provide means for pump and road operation. The pump shall be of the centrifugal type. The pump shall have a certified UL minimum rating of 1000 gpm at altitudes to 2000 feet. The pump drive, gearing, and housing shall be such that at rated capacity and pressure the temperature rise in the gear oil will not exceed the maximum temperature recommended by the pump manufacturer for continuous operation in an ambient temperature of 125°F. All pump-shaft glands or mechanical seals shall be adequate for service under operating conditions specified herein. Drain cocks, accessible at the pump operator's position and arranged so that the open and closed positions are clearly indicated, shall be provided to drain the pump and all water-carrying lines. All threaded connections shall conform to FED-STD-H28.

3.14.1 Priming pump. A priming pump shall be furnished and shall be operated from the pump panel. The priming pump shall operate in accordance with NFPA 1901. The priming pump oil reservoir when used shall be located where the oil level can be easily and accurately checked and serviced.

3.14.2 Suction connections. The fire pump shall be provided with two 6-inch suction inlets, located one on each side of the truck. The inlets shall not be more than 4 feet above the ground, with a removeable and accessible brass

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

strainer provided inside each inlet. Each side suction connection shall have a long-handled, gasketed cap. The suction manifold shall also have a connection for intake from the water tank. Suction inlets shall have machined ends so as to provide a seat for suction hose gaskets and shall be threaded with 6-inch NH threads. Two additional 2-1/2-inch gated gasketed female swivel suction inlets, threaded with 2-1/2-inch NH threads and equipped with rocker lug plug and chain, shall be provided; one on the pump panel side of the truck, the other located at the right rear of the truck. Sufficient clearance shall be provided to allow the use of spanner-type wrenches. The 2-1/2-inch suction connections shall be fitted with suitably sized, balanced, corrosion-resistant, full-flow-through-type valves and shall be operated and locked by means of an individual control handle as a single-handed operation from the pump panel.

3.14.2.1 Tank fill. A 2-1/2-inch NH tank fill valve and line shall be provided at the left rear of the truck. The valve shall automatically control the flow of water to the water tank to maintain not less than 75 percent of the water tank capacity during pumping operations.

3.14.3 Discharge connections. The truck shall be provided with the following discharge connections. Each discharge shall be provided with a suitably sized, balanced, connection-resistant, full-flow-through-type valve. Each valve shall be operated and locked by means of an individual control handle as a single-handed operation from the pump panel.

(a) Two 2-1/2-inch NH outlets on each side of the truck. Each outlet shall be fitted with a 2-1/2-inch 45 or 30 degree elbow and 2-1/2 x 1-1/2 NH adaptor with 1-1/2-inch cap and chain.
(b) One 2-1/2-inch NPT connections piped to the rear of the truck for connection with the 1-1/2-inch NH leader-line hose bed. Outlet shall be equipped with an adaptor 2-1/2-inch NPT to 1-1/2-inch NH.
(c) One 1-1/2-inch discharge from the pump to the tank.
(d) Two discharges from the pump to the two 1-1/2-inch NH hose bin over the pump.
(e) One 1-1/2-inch NPT connections piped to the booster hose.

Each discharge specified in (a) above shall be provided with a drain valve of at least 3/4-inch inside diameter for draining hose lines with discharge gates closed. Drain valve controls shall be located adjacent to the discharge connection specified in (a) above. Drain lines shall be concealed behind the pump compartment panels and shall discharge at a point not above the bottom of the chassis frame. Each discharge outlet shall have machined ends so as to provide a seat for the hose gasket and shall be provided with a rocker lug fitting. The discharge valves shall assure ease of operation under all operating conditions. Clearances shall be provided to allow the use of spanner-type wrenches. The two 1-1/2-inch hose bins over the pump shall be fitted with a swivel to allow playout of the hose from either side of the truck.

3.14.4 Relief valve. One automatic relief valve shall be provided for controlling the pressure from all outlets. The location of the relief valve control shall be such that adjustment can be made by the operator when standing in normal pump operator's position, without the use of tools, and in full view

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:00Z
Check the source to verify that this is the current version before use.

of the discharge pressure gage. The relief valve shall be of such design that when set 10 psi higher than the pump working pressure, there will not be an increase in pump pressure greater than 30 psi when discharge lines are shut slowly. The relief valve shall perform satisfactorily when pumping rated capacity at any pump working pressure over 75 psi.

3.14.5 Controls. The truck shall be furnished with a top mount control panel. Provisions shall be made for quick and easy operation of the fire pump. All levers or other devices used in connection with pumping operations shall be provided with positive catches or other means to prevent them from being jarred or moved out of position. All controls for changing from road transmission to pump transmission shall be operable from the driver's position and shall be marked for road and pumping positions. Cable operated control are not allowed. All pumping controls and instruments necessary to operate the fire pump under all conditions of service shall be arranged on non-glare stainless-steel pump panel. The throttle control shall be of the screw, center-push-button-release type and shall control the entire range of engine speed smoothly. The throttle control shall hold the control lever in any designed position and shall not be affected by vibration or by pull of the accelerator spring. Controls and gages shall be as symmetrically grouped as practicable. Plates or collars shall be installed around all discharge outlets and controls on the controls panels. Each discharge control shall be systematically numbered. The assigned number shall be mechanically adhered to the pump panel near the controls.

3.14.6 Gages and instruments. All pressure and suction gages shall be of the liquid filled nonfreezing type. All gages shall have provisions for calibration. The master pressure and compound gage shall have a dial face not less than 3-1/2-inch diameter. The suction gage shall have a dial pressure range of 30 inches of Hg to a pressure of not less than 400 psi. The master discharge gage shall have a dial pressure range of 0 to 600 psi. Each fire hose discharge outlet specified in 3.14.3, except (c) and (e) shall have a separate pressure gage of not less than 2-1/2-inch diameter. Each gage shall be provided with dampening device to eliminate pressure fluctuation. The master discharge gage shall be connected to the pump manifold and the remaining gages connected to the hose line side of each of the discharge valves. Gages shall be located on the pump panel in rows. Gages shall be systematically arranged and numbered to correspond with the controls in 3.14.5. Numbers shall be affixed as specified in 3.14.5. Throttling valves and drain controls shall extend to the exterior of the pump control panel. An indicator or gage shall be provided on the pump panel and on the cab dash to show the water level in the water tank specified in 3.16. Valve bodies and connecting piping shall be concealed behind the pump control panel. Two plugged 1/4-inch NPT connections for test gages, one connected to the pressure side and one to the suction side of the pump, shall be mounted on the pump panel. Each connection shall be marked "Pressure" or "Suction". The tachometer on the pump panel shall indicate the engine speed when driving the pump. Provisions shall be made at the pump panel for checking the tachometer with a hand revolution counter without disconnecting the tachometer. All gages shall be designed to prevent the entrance of water or of fogging due to temperature change. Necessary pressure and tank fill gages shall also be located in the cab for turret operations.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

3.15 Body. The truck shall be equipped with a body which shall incorporate a pump housing, operator's panel, hose bed, equipment cabinets, running boards, rear steps, and water tank. Step plates shall be furnished, on each side of the rear of the truck, to aid personnel to move from the rear platform to the hose bed. The body shall mount the fire pump and stow the fire fighting equipment specified herein. The body, shall be reinforced at all points where personnel could conceivably walk and where hose and ladder clamps and hangers are attached. Aluminum may also be used, however contractor must certify that type of aluminum used is compatible with agents used and other body materials.

3.15.1 Cross-lay hose beds. Two cross-lay hose beds shall be located over the pump compartment area. Each bed shall have the capability of stowing not less than 150 feet of 1-1/2-inch double-jacketed polyester, rubber-lined fire hose. Hose playout shall be provided on each side of the truck with hose rollers installed in the bottom and both sides of each bed opening to prevent hose interference or snagging. The bottom of the hose beds shall be of slatted, well-seasoned hardwood or aluminum. Discharge gate controls for each hose bed shall be located at the pump control panel, and shall be suitably identified. The hose beds shall be identified as Bed No. 1 and Bed No. 2. Hose bed No. 1 shall be located towards the front of the vehicle. Discharge connections shall be located away from any hose bed partition to permit hose attachment to, or removal from, the connections without side wall interference.

3.15.2 Fire hose compartments. Compartments for stowing a minimum of 1200 feet of 2-1/2-inch polyester rubber-lined fire hose and 300 feet of 1-1/2-inch jacketed polyester, rubber-lined leader hose in the horizontal layers shall be provided. The 2-1/2-inch hose compartment located between the wheel housings shall be divided lengthwise with a steel partition to form two equal hose beds. The 1-1/2-inch hose compartment shall be located at the left side of the 2-1/2-inch hose compartment. The 1-1/2-inch hose compartments shall have a minimum width of 3-1/2-inches between partition reinforcements. The compartment shall hold a minimum of 300 feet of 1-1/2-inch hose. The compartment body and partitions shall be reinforced so as to offer no obstruction to playing out or loading of hose. The compartment floor shall be closed with sheet metal to provide protection to the hose from road dirt and tire splash. Drain holes shall be provided to preclude water retention. The floor shall be reinforced by a crossmember which shall support a slatted floor, of seasoned hardwood or aluminum. Slats shall be not less than 3-1/2-inches in width. The slats shall have a thickness of not less than 3/4-inch, shall run the full length of the compartment, and shall be spaced so as to provide ventilation for hose. The spacing shall be not less than 5/8-inch nor more than 3/4-inch. The slats shall be fastened to the crossmembers by countersunk screws or bolts. The slatted floor shall be removable. The interior of the compartment shall be free from all projecting nuts, sharp angles, or brackets. Exposed bolt or rivet heads shall of the oval type. The tank vent or overflow shall not extend into the hose bed.

3.15.3 Equipment cabinets. Equipment cabinets shall be provided on each side of the truck. The right or curb side of the truck shall have two compartments, one in front of the rear wheel well and one to the rear of the wheel well. The left or street side of the truck shall have the same compartment arrangement

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

with three additional compartments mounted over top of the bottom comp
The top compartments shall run the full length of the bottom compartme
shall have a height equal to the distance from the top of the bottom c
the top of the hose bed. The top cabinets shall be as deep as the bot
cabinet. No cabinet shall be flush with the step plates, running boar
wheel skirtings. All bottom cabinets shall be not less than 25 inches
height; cabinets depth shall be the same as the wheel housings, but no
than 20 inches. All doors shall be of box type construction and be ga
prevent the entry of water into the compartments. Cabinets shall be p
with vent openings to eliminate sweating inside compartment spaces. A
shall be provided with a recessed "D" ring-type handle and a flush bol
lock. Doors shall operate on noncorrosive piano-type hinges. Hinges
the full length of the door. All cabinets shall be illuminated, and t
lighting shall be automatically controlled through door switches to li
the doors are opened. Cabinet tops shall run continuously on each sid
truck and shall be of antiskid surface similar to the running board an
step surface. A large access door shall be provided on the curb side
panel for inspection of the pump and pump panel.

3.15.4 Handrails and hose rollers. The rear step shall be provided
vertical grabrails for mounting the step, and a handrail not more than
above the step. The handrail shall be located not more than 6 inches
the rear end of the hose bed, or 6 inches forward of the clear area of
step. A second, rubber covered, horizontal handrail shall be located
the hose bed. Hose pickup lights shall be mounted at the side of the
Both the grabrails and handrails shall be not less than 1-1/4-inch hea
tubing. All equipment attached to the body within reach of a running
shall be attached so as to serve as a personnel handrail. Vertical ha
1-1/4-inch heavy tubing shall be provided on both sides of the jump se
entranceway and cab doors. The handrails shall be not less than 18 in
long. Handrails shall be mounted on heavy-duty brackets and shall not
to turn in the brackets. Hose guide rollers shall be provided for the
hose and for both sides and bottom of the two 1-1/2-inch hose beds ove
compartment. Hose rollers shall not serve as handrails.

3.15.5 Fasteners. Fasteners used in removable panels, inspection p
compartment closures shall be of the quick-disconnect type. Sheet-meta
are not acceptable.

3.16 Water tank and piping. A water tank of not less than 600 useal
capacity shall be located to the rear of the pump, shall be mounted on
frame, and shall be removable. The tank shall not extend beyond the h
sides. Except as indicated below, the tank shall be of welded constru
The entire tank top shall be removable. The top shall be gasketed to
leakage due to surging of the water. The top retaining capscrews or fa
shall not come in contact with the water. Tank construction and outle
allow the water to be pumped out when the truck is standing on a 20 pe
grade in all planes. The outlet shall be large enough to maintain rat
capacity during turret operation for not less than 80 percent of the t
capacity. The tank shall be baffled in accordance with NFPA 1901. Th
shall be equipped with a fill opening having an area of at least 64 sq

Source: https://assist.dla.mil -- Downloaded: 202640-17T16:00Z
Check the source to verify that this is the currentversion before use.

inches to permit easy filling of the tank. The cover shall be gasketed and retained in place to prevent spillage during operation. The tank fill openings shall be provided with a removable screen to prevent entrance of foreign matter. Water shall not surge from a filled or partially filled tank due to acceleration, deceleration, or movement of the truck. The tank shall have a nonsplash combination overflow and vent pipe extended to the rear of the truck and directed inboard to the ground so that water from the overflow drain will not affect traction of rear wheels. The tank shall be made of high-strength stainless steel and shall be freed of mill scale either by a pickling threatment or sandblasting. All piping from the tank to the pump and from the pump, unless made of corrosion-resisting metal which has been passivated in accordance with QQ-P-35, shall be galvanized in accordance with ASTM A525 to a G90 coating. The pipeline between the tank and the pump shall be sized to supply both turrets at rated conditions and may incorporate a flexible reinforced noncollapsible connection(s) to take up vibration. The pipeline shall be provided with a quick-opening shutoff valve with control extended to the pump panel and a drain valve located at the lowest point with control extended to the street side of the truck. The tank-to-pump line shall include a check valve to prevent the flow of the water from the pump to the tank. The pipeline between the pump and the booster reel shall be not less than 1-1/2-inch NPT and shall incorporate a 1-1/2-inch quick-opening shutoff valve with control extended to the pump panel. Mounting of the valve shall conform to 3.14.5. A complete piping diagram shall be provided with the manuals furnished with each truck. The tank shall show no evidence of leaking after being subjected to the tests specified in 4.5.2.

3.17 Booster hose reel. A booster hose reel shall be provided with three 50 oot sections of 1-inch rubber chemical booster hose jointed with smooth full-flow-type couplings. The hose shall have a working pressure of not less than 600 psi. The reel shall have a friction brake playout to prevent overtravel and shall be an electric-rewind type. The reel shall also include provisions for handcrank rewind. The reel shall be mounted in a compartment in front of the rear platform between the truck frame. The hose reel compartment shall be provided with drains. The compartments shall be provided with a roll up type door.

3.17.1 Turret nozzles. A roof mounted turret with a non-aspirated type nozzle shall be furnished. Controls shall be remote manual type from the cab. The nozzles shall have a minimum flow of 500 gpm at 200 psi of liquid agent. A bumper turret remotely controlled from with the cab shall be mounted on the front of the cab on the vehicle centerline. Control of either turret shall be accomplished by the vehicle driver or passenger. The roof turret shall have a straight stream range not less than 150 feet, a fog foam diameter of 20/25 feet, a rotation of 120 degrees either side of front center, a depression of 15 degree to the front and elevation of 60 degrees. The bumper turret shall have a flow rate of not less than 250 gpm at 200 psi of liquid agent, an elevation of 45 degrees, depression of 15 degrees and a rotation of 80 degrees either side of center. The roof turret may be of a fold down design or rapid removable type to meet the height required in 3.12.2.1. Any change to the roof turret to meet air craft loading shall be completed by the operator in less than one hour using standard or truck tools.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

3.18 Fire fighting equipment mounting. The truck shall be provided with the necessary holders, brackets, and mounting pads, to attach the fire fighting equipment specified in 3.28. The attachments shall be of the type that remain securely in place under all running conditions and yet permit quick removal without interference with other equipment. No item of fire fighting equipment specified herein shall be stowed aboard the truck without a heavy-duty method of attachment. All attachments shall be provided with spacers for mounting away from running boards or body to allow for drainage. The two 10-feet lengths of 2-1/2-inch noncollapsible suction hose (see 3.28), shall be mounted in troughs between the water tank and the hose bed. Access to the hose shall be from the rear of the truck. The troughs shall be shaped to permit ventilation between hose and troughs over the entire length without chafing the hose. The female coupling end of each hose shall face the rear. Hose locks shall be used to hold the hose in place. Locking devices shall be adjustable to compensate for slight differences in hose sizes. All ladders shall be mounted on the right side of the truck above the cabinets and wheel-housing at a height which will not interfere with pump operation. The 12-foot roof-type ladder and the 20-foot extension ladder (see 3.28), shall be mounted together. Ladders shall be mounted by mechanical all-metal quick-release adjustable fastenings that will prevent chafing and rattling. All ladders shall conform to NFPA 1931. Ladder mounting height shall be held to the lowest practicable height above ground and in no case exceed 76 inches above ground level. Ladders and ladder mounting brackets shall not extend past the side of the bottom equipment cabinet. A 12-foot length of 6-inch NH soft suction hose shall be mounted on the right side of the truck under the discharge panel.

3.19 Mechanical foam system. The truck shall be equipped with foam-producing equipment. The foam proportioner shall be of the around-the-pump type. Foam liquid shall be inducted by venturi action into a line carrying a portion of the solution from the pump discharge. The foam liquid and water mixture shall be drawn into the pump intake and shall mix with the main water flow. A metering valve shall be provided in the foam liquid line leading into the venturi for controlling the amount of foam liquid entering the venturi. The foam liquid metering valve shall be calibrated and shall be provided with a dial and pointer to regulate the proportioning or discharge percentage of foam liquid to the total solution flow. A check valve shall be installed between the metering valve and the venturi to prevent flow of water back into the foam tank. Provisions shall be made to flush out the foam system after use. A quarter-turn ball valve shall be provided in the line from the foam tank to the metering valves. The system shall deliver 3 to 8 percent foam solution through the normal operating pressure range of the fire pump and at discharge capacities of up to 500 gpm.

3.19.1 Controls. All controls for operation of the foam system shall be located on the fire pump instrument panel and shall be accessible to the operator. An additional foam valve control shall be mounted in the cab to allow foam to the turret system. An instruction plate showing the proper setting of the metering valve and flushing operations shall be located adjacent to the foam controls.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

3.19.2 Foam tank. The foam liquid tank shall be located for easy filling. The tank shall have a capacity of not less than 65 useable gallons. The tank shall be constructed of fiberglass base plastic materials resistant to the AFFF concentrate. The tank shall be removable from the truck. Baffles shall be installed to prevent excessive surging and foaming of the liquid. A drain with discharge at a point below the bottom of the truck frame, and readily accessible from one side of the truck, shall be provided with a valve control located at the fire pump control panel. The drain valve shall be located immediately adjacent to the tank so as to minimize the amount of piping between the tank and valve. Provisions shall be made for filling from a 5-gallon container into a filler neck located in the top of the foam tank. The filler neck shall extend far enough into the tank to reduce foaming overflow while filling. The filler opening shall be large enough to allow hand cleaning of the inside of the tank. A splash-proof vent shall be provided in the foam tank and shall be piped to the under side of the truck. Removable screens shall be provided, one at the filler neck and one on the outlet of the foam tank, that will prevent entry of foreign matter into the proportioner or pump. The filler shall be provided with a gasket-type locking cover. The tank shall be fitted with an electronic type liquid level indicator or gage. The indicator or gage shall be mounted on the pump panel as specified in 3.14.6 and in the truck cab.

3.19.3 Piping. All piping and valves coming in contact with foam liquid shall be of a corrosion-resistant material for use with foam liquid conforming to MIL-F-24385. Quick-acting ball valves shall be installed between the foam liquid tank and metering valve and between the pump discharge and eductor. A ball check valve shall be installed between the eductor and metering valve, and horizontal swing check valve shall be installed in the water-tank suction line to prevent entry of foam solution into the water tank.

3.20 Communication equipment. A radio communication space approximately 1-1/2-feet long x 1-1/2-feet wide x 1 foot high for installation of communication equipment, shall be provided in the cab between the driver and passenger.

3.20.1 Communication equipment power supply. When specified (see 6.2), a 24-volt DC, 20 ampere electrical supply shall be provided and electrical service run to the communication space for operation of military radio equipment.

3.21 Rust proofing. The truck shall be rust proofed in accordance with MIL-STD-1223.

3.22 Electromagnetic interference. Unless otherwise specified (see 6.2), the electromagnetic interference emission and susceptability characteristics of the truck shall conform to SAE J551.

3.23 Lubrication. The truck shall be lubricated prior to delivery with lubricants designated for use in the 0°F to 32°F temperature range. The truck shall operate as specified herein when serviced with military oils designated for use in the temperature range specified herein. A tag shall be attached to the transmission control to indicate the temperature range, and the lubricant grade used.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

3.24 Lifting and tiedown attachments. When specified (see 6.2), lifting and tiedown attachments shall be provided on the vehicle frame in accordance with MIL-STD-209. Attachments shall be clearly identified as to their use.

3.25 Identification marking. The truck shall be identified in accordance with MIL-STD-130. The marking shall be applied to the truck on plates conforming to MIL-P-514, type I, style 1, composition C, of type I, grade A, class 1 material. Each plate shall be attached by screws, bolts, or rivets to the inside of the door on the driver's side of the cab.

3.25.1 Shipping data plates. The truck shall be equipped with shipping data plates conforming to MIL-P-514, Type III. The plates shall show the silhouette of the truck in the transport configuration. Data on the plate shall include truck overall height. Shipping cubage, shipping weight, lifting and tie-down capacity, axle loads and center of gravity.

3.26 Instruction plates. All pumping controls, valves, instruments, and truck operating controls shall be provided with instruction plates designating function and operation. Instruction plates shall conform to MIL-P-514, type III, composition C, of type 1, grade A, class 1 material, size as applicable. Each plate shall be attached by screws, bolts, or rivets in a location where the plate shall be both visible and legible.

3.27 Painting. Unless otherwise specified (see 6.2), the truck cab, chassis body and other equipment, as applicable, shall be cleaned, treated and painted gloss lime-yellow, color No. 13670 of FED-STD-595. Using not less than one coat of anti-corrosive primer and a two coat finish. When specified (see 6.2), the complete fire truck shall be painted either red, or olive drab as specified. All steps, walkways and cabinet tops shall be provided with anti-skid compound applied with the paint.

3.28 Contractor-furnished components. The following equipment shall be furnished, installed, and stowed on each truck:

(a) Two 10-foot lengths of 2-1/2-inch hard suction hose, commerical grade, NFPA approved, with 2-1/2-inch NH long-handled couplers on female ends and 2-1/2-inch NH rocker lug couplers on the male ends. The hose shall be mounted in troughs specified in 3.18.
(b) One 12-foot length of 6-inch soft suction hose, commerical grade, NFPA approved, with a 4-1/2-inch long handled swivel female gasketed coupling on one end and a 6-inch long handled swivel female gasketed coupling on the other end.
(c) One strainer with a 2-1/2-inch NH internal coupling shall be attached to a threaded mounting plate located on the street side step under the 2-1/2-inch discharge.
(d) Ladders.

    (1) One 12-foot roof-type ladder.
    (2) One 20-foot two-section extension ladder.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

(e) One reducer coupling hose, double internal, long handled, double swivel, female, gasketed couplings, the size shall be 4-1/2-inch NH to 6-inch NH.

(f) Two portable floodlights, 300 watt, with three wire ground connector. Circle-D portable light No. 150 and model P-23 holddown clamps or equal. The lights shall be mounted one on either side, near the side of the truck.

3.29 Interchangeability. All parts having the same part number shall be functionally and dimensionally interchangeable. Interchangeable parts are defined as two or more like parts possessing such functional and physical characteristics as to be equivlent in performance and durability, and capable of being exchanged one for the other without alteration of the parts themselves or of adjoining parts, except for adjustment, and without selection for fit or performance.

3.30 Workmanship.

3.30.1 Casting and forgings. All parts, components, and assemblies of the truck which include castings and forgings shall be clean of harmful extraneous material such as sand, dirt, sprues, scale, and flux. Rework shall be limited to procedures which do not reduce mechanical properties or affect function.

3.30.2 Welding. The aluminum surfaces or parts to be welded shall be free from scale, paint, grease, oxide film, and other foreign matter. Welds may be ground, filed, buffed, or chipped but shall not be hammered, and shall be free from discontinuities such as base metal cracks adjacent to or behind welds, cracks in weld metal, undercutting of base metal, lack of fuction with parent metal or between parts, lack of penetration, lack of prescribed fit, or splatter.

3.30.3 Metal fabrication. Metal used in fabrication shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the material. Corners shall be square and true. Flame-cutting, using tips suitable for the thickness of the steel, may be employed instead of shearing. All bends shall be made with controlled means to insure uniformity of size and shape. Precaution shall be taken to avoid overheating. Heated steel shall be allowed to cool slowly. External surfaces shall be free of burrs, sharp edges and corners, except when sharp edges or corners are required or where they are not detrimental to safety.

3.30.4 Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, mill scale that can be removed by chipping and wire brushing, and other foreign matter. Parent materials, weld filler metals and fabrication techniques shall be as required to enable the truck to conform to the examination and test requirements specified in Section 4. Parts to be joined by fillet welds shall be brought into as close contact as possible and in no event shall be separated by more than 3/16-inch unless appropriate bridging techniques are used. The welding process used in fabrication of the truck shall be at the option of the contractor.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

3.30.5 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall provide certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

AWS D1.1, Structural Welding Code, Section 5, Qualification.
ASME Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

Contractors who make only horizontal welds need not qualify welders for "all position welding". Subject to approval by the Government, the contractor's standard welder qualification may be substituted in lieu of the above codes provided that the contractor's procedure is equivalent to the above codes. The contractor shall be responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with AWS or ASME codes.

3.30.6 Brazing. Brazing of steels, copper alloys, and nickel alloys shall conform to MIL-B-7883.

3.30.7 Bolted connections. Boltholes shall be accurately formed and shall have burrs removed. Washers or lockwashers shall be provided where necessary. Matching thread areas securing bolts conforming to SAE J429 or capscrews shall be of sufficient strength to withstand the tensile strength of the bolt. All fasteners shall be correctly torqued and shall have full thread engagement. Bolts shall protrude not more than two full threads.

3.30.8 Riveted connections. Rivets shall fill the holes completely. The upset rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member, and shall be in accordance with SAE J492.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

Source: https://assist.dla.mil -- Downloaded: 202640-17T16:00Z
Check the source to verify that this is the current version before use.

(a) Preproduction inspection (see 4.3).
(b) Initial production inspection (see 4.4).
(c) Quality conformance inspection (see 4.6).
(d) Inspection of packaging (see 4.7).

4.3 Preproduction inspection.

4.3.1 Examination. The preproduction truck shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. The preproduction truck shall be tested as specified in 4.5.2, except the pump test shall be conducted and certified by UL before government inspection and testing. Failure of any test shall be cause for rejection.

4.4 Initial production inspection. When specified (see 6.2), one or more trucks will be selected at random by the Government from trucks being produced by production tooling and will be examined as specified in 4.5.1 and tested as specified in 4.5.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Acceptance of an initial production truck shall not exclude the remaining trucks from the quality conformance inspection and acceptance provisions specified in Section 4. In addition to any test specified as part of the initial production test, the Government reserves the right to conduct any and all other tests contained in this specification as part of the initial production test. Failure of such additional tests shall have the same effect as failure of those tests specified as initial production tests.

4.4.1 Inspection failure. Failure of an initial production truck to meet any requirement specified herein during and as a result of the examination and tests specified in 4.4 shall be cause for rejection of the initial production truck(s) and shall be cause for refusal by the Government to continue acceptance of production trucks until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on trucks previously accepted and produced under the contract. Any deficiencies found as a result of the initial production inspection will be considered prima facie evidence that all trucks accepted prior to the completion of initial production inspection are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.4.2 Tests. Each truck shall be tested as specified in 4.5.2, 4.5.2.1, 4.5.2.1.1, 4.5.2.2, and 4.5.2.3. Failure of any test shall be cause for rejection. The test in 4.5.2.1 may be performed using a water dye as a substitute for foam.

4.5 Inspection procedure. Prior to examination or tests, the truck shall be lubricated with military oils and greases for use at the ambient temperature at the inspection site.

Source: https://assist.dla.mil -- Downloaded: 202640-17T16:00Z
Check the source to verify that this is the current version before use.

4.5.1 Examination. The truck shall be examined as s preproduction and initial production inspection for the in table I.

TABLE I. Examination schedule (requi

Number	Characteristic
1	2
Major	
101.	Truck not as specified.
102.	Material not as specified.
103.	Safety not as specified.
104.	Human factors not as specified.
105.	Truck chassis not as specified.
106.	The truck manufacturer's gross vehicle weight (gvw) rating for the truck chassis not as specified.
107.	Wheel base not as specified.
108.	Length and width of the truck and equipme not as specified.
109.	Transportability not as specified
110.	The chassis frame not as specified.
111.	Engine not as specified.
112.	Engine fuel system not as specified.
113.	Lubrication of the engine not as specifie
114.	Exhaust system not as specified.
115.	Brake horsepower certification not furnis by contractor as specified.
116.	Electrical equipment not as specified.
117.	Ignition system not as specified.
118.	Battery units and electrical circuits not as specified.
119.	Lighting system not as specified.
120.	Additional lighting not as specified.
121.	Warning light not as specified.
122.	Light switches not as specified.
123.	Siren and horn not as specified.
124.	The specified type of bumper not furnishe as specified.
125.	Towing hooks, rings, or eyes not as speci
126.	Shock absorbers not as specified.
127.	Front and rear springs not as specified.
128.	Truck drive assembly not as specified.
129.	Transmission not as specified.
130.	Drive axle not as specified.
131.	Steering mechanism not as specified.
132.	Brakes not as specified.

Source: https://assist.dla.mil -- Downloaded: 202640-17T16:00Z
Check the source to verify that this is the current version before use.

TABLE I. Examination schedule (requirement).(con't)

Number	Characteristic	Requirement Paragraph
1	2	3
133.	Service brakes not as specified.	3.12.13.1
134.	Parking brake not as specified.	3.12.13.?
135.	Wheel and tire assembly not as specified.	3.12.14.
136.	Angles of approach and departure not as specified.	3.12.15
137.	Cab not as specified.	3.13
138.	Windshield wiper and washer not furnished as specified.	3.13.2
139.	Fire pump not UL rated as specified.	3.14
140.	Priming pump not furnished as specified.	3.14.1
141.	Suction connections not furnished as specified.	3.14.2
142.	Discharge connections not furnished as specified.	3.14.3
143.	Relief valve not provided as specified.	3.14.4
144.	Controls not as specified.	3.14.5
145.	Gages and instruments not as specified.	3.14.6
146.	Body of truck not as specified.	3.15
47.	Fire hose compartments not as specified.	3.15.2
148.	Equipment cabinets not as specified.	3.15.3
149.	Handrails and hose rollers not as specified.	3.15.4
150.	Fasteners not as specified.	3.15.5
151.	Water tank and piping not as specified.	3.16
152.	A booster hose reel not furnished as specified.	3.17
153.	Mounting for fire fighting equipment not provided as specified.	3.18
154.	Mechanical foam system not furnished as specified.	3.19
155.	Controls for operation of the foam system not located as specified.	3.19.1
156.	Foam tank not located as specified.	3.19.2
157.	Piping and valves coming in contact with foam liquid not of corrosive resistance material as specified.	3.19.3
158.	Communication equipment not furnished as specified.	3.20
159.	The truck not rust proofed as specified.	3.21
160.	The truck not lubricated before delivery as specified.	3.23
161.	Instruction plates not made and furnished as specified.	3.26
162.	Other specified components not furnished by contractor.	3.28

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:00Z
Check the source to verify that this is the currentversion before use.

TABLE I. Examination schedule (requirement).(con't)

Number	Characteristic	Requirement Paragraph
1	2	3
163.	Interchangeability of parts having the same part number not as specified.	3.29
164.	Casting and forgings not as specified.	3.30.1
165.	Welding not as specified.	3.30.2
166.	Metal fabrication not as specified.	3.30.3
167.	Welded surfaces not prepared for welding as specified.	3.30.4
168.	Welders not certified for welding as specified.	3.30.5
169.	Brazing not as specified.	3.30.6
170.	Bolted connections not formed and burrs removed as specified.	3.30.7
171.	Riveted connections not as specified.	3.30.8
Minor		
201.	Lifting and tiedown attachments not provided as specified.	3.24
202.	Identification marking not as specified.	3.25
203.	Painting not as specified.	3.27

4.5.2 Tests. Each truck shall be tested and certified by Underwriters Laboratories prior to any test specified in 4.3.2.

4.5.2.1 Foam system. The foam system shall be tested using foam liquid conforming to MIL-F-24385. The metering valve shall be set to deliver 3 percent of foam solution and then to deliver 6 percent of foam solution for not less than 1 minute at each setting while discharging at a rate of 250 gallons of water per minute. Failure to use at least 6 gallons of foam liquid per minute at 3 percent and 12 gallons of foam liquid at 6 percent shall constitute failure of this test.

4.5.2.1.1 Test for ambient temperature and altitude conditions. When specified (see 6.2), the contractor shall perform a pumping test of the preproduction model under actual conditions of 2000 feet altitude above sea level and at an ambient temperature of 125°F. When pumping at heights above 2000 feet altitude is required, certification is required from the contractor that the vehicle will perform as specified in 3.12.5.2. The pumping test shall consist of the tests specified in 4.5.2. Noncomformance to 3.14 shall constitute failure of this test.

4.5.2.2 Road tests. The loaded truck, including filled water tank, filled foam tank, filled fuel tank, lubricants, a 1500 pound evenly distributed simulated load, and a equivalent weight of 875 pounds for personnel shall be tested as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

(a) 100 miles over paved roads at speeds up to 65 mph.
(b) 25 miles over graded dirt roads at speeds up to 30 mph.
(c) 25 miles over cross country (off road) conditions which subject the truck to all wheel drive at speeds up to 25 mph.
(d) Service brakes shall be applied during runs (a) and (b) above.
(e) All lights, siren, horn, speedometer, hourmeter, controls, and instruments pertaining to the truck engine shall be tested.
(f) Conduct tests for the conditions specified in 3.11 (a), (b), (c), (d), (f), (h) and (i).
(g) The air-brake system shall be tested for conformance to 3.12.13.2.
(h) Operate the pump for 15 minutes during (c).
(i) A hydrostatic pump test shall be conducted in accordance with NFPA 1901 after conducting all of the road test.

Nonconformance to 3.11 and 3.12.13.2 shall constitute failure of these tests.

4.5.2.3 Electromagnetic interference. Unless otherwise specified (see 6.2), the truck shall be certified or tested as specified in SAE J551.

4.5.2.4 Winterization test. When applicable, thermocouples shall be installed inside the foam tank, water tank, pump compartment, battery compartment, truck cab, and on the engine oil pan and engine block of the winterized truck. The equipped truck, with foam and water tanks filled to capacity and arctic-type antifreeze in the radiator, shall be subjected to an ambient temperature of minus 50°F without solar radiation for 24 hours. The interization heating system shall be in operation throughout this test. emperature readings from the thermocouples shall be recorded at 30 minute intervals during the test. After completion of 12 hours of the test, two men shall sit in the cab for 1/2 hour and the windshield area defrosting shall be checked. At the completion of the 24 hour test, the truck engine shall be started, the fire pump shall be operated, and all agent system valves shall be checked for free and easy operation. Compartment thermocouple temperature readings during the test falling below plus 40°F, failure of the truck engine to start, or failure of the fire pump and valves to operate shall constitute failure of this test.

4.5.2.5 Air transportability tests.

4.5.2.5.1 Configuration testing. The truck, prepared for air transportability, shall be measured. Where necessary, items mounted above roof level (except turret) shall be removed and replaced to verify compliance with requirements specified in 3.12.2.2.

4.5.2.5.2 Loading demonstration. When specified (see 6.2), the truck shall be prepared to the extent necessary for air transport. The removed portions shall be stored in or on the truck. The truck shall be loaded aboard a C-130 aircraft equipped with an A/A32H-4 dual rail cargo handling system in according with the loading demonstration test specified in MIL-A-8421. This shall be certified by the Air Force.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

4.6 Quality conformance inspection.

4.6.1 Examination. Each truck shall be examined for defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.6.2 Tests. Each truck shall be tested as specified in 4.5.2; 4.5.2.2 (a) 50 miles, (d), (e), (f), (g), (i). The tests specified in 4.5.2.2 (f) shall only include item (c), (d), (g), (i) of 3.11. Foam test specified in 4.5.2.1 may be conducted using water dye rather than foam.

4.7 Inspection of packaging. The preservation, packing and marking of the truck and furnished equipment shall be examined to determine compliance with the quality assurance provisions of MIL-STD-281 and MIL-E-10062 as applicable for level A or for the specific requirements specified herein for level C.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or C as specified (see 6.2).

5.1.1 Level A. Each complete truck with furnished equipment shall be preserved in accordance with MIL-STD-281, level A (mobile), with the following additions and exceptions.

5.1.1.1 Engine. The engine and engine accessories shall be preserved in accordance with MIL-E-10062, type I, method I, level A. The cooling system shall be preserved by the water and antifreeze procedures except the antifreeze shall conform to MIL-A-46153.

5.1.1.2 Fire truck equipment. The fire truck equipment shall be preserved in accordance with the contractors recommendations that are adequate to prevent deterioration and damage during shipment and indeterminate storage, utilizing the preservation criteria established in MIL-P-116. Specifically the foam and water tank drain valves shall be placed in the open position.

5.1.1.3 Equipment. Equipment shall be placed and secured as provided for except exposed equipment subject to pilferage, damage or loss shall be prepared as "On vehicle equipment" in accordance with MIL-STD-281.

5.1.2 Level C. Each complete truck and all items issued with the truck shall be suitably preserved to afford protection against deterioration and damage from the contractor to the initial destination. In addition, the following specific requirements shall be accomplished. Items with critical surfaces required for fit or function shall be provided protection by use of preservative coatings, volatile corrosion inhibitors or desiccated packs. Items requiring protection from physical damage to surfaces or which are fragile by nature shall be protected by wrapping, pack compartmentization, or cartonizing of the individual item. Exposed equipment subject to easy pilferage or loss shall be placed in secured compartments, truck cab, or in wooded boxes when practical. Wooden boxes, when used, shall be secured to the truck with metal strapping and in a manner to prevent damage to the painted surface of the truck. Items such as ladders that are too large to place in compartments, truck cab or impractical to

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:00Z
Check the source to verify that this is the currentversion before use.

place in a wood box shall be secured in place using metal strapping. The cooling system shall be filled with a fresh clean solution of 50 percent antifreeze conforming to MIL-A-46153 and a tag attached indicating the temperature to which the cooling system can be subjected before damage. The crankcase and all other lubrication reservoirs shall be filled to the operating level with the grade of military lubricant designed for use in the temperature range at the shipping destination. A tag shall be attached in a conspicuous location to indicate which military lubricant has been used and its grade and temperature range. A deprocessing guide shall be furnished indicating in detail the preservation material to be removed and other servicing required prior to placing the truck in operation. Foam and water tank drain valves shall be placed in the open position.

5.2 Packing. Packing (see 6.5), each complete truck, preserved as specified in 5.1 shall not require packing.

5.3 Marking. Marking (see 6.5), shall be in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use. The truck is intended for use by garrison troops in combating structural, brush, and aircraft crash fires.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Date of issue of DoDISS applicable to this contract and exceptions thereto (see 2.1.1).
(c) When first article is required and time frame (see 3.2).
(d) When operation at 2000 feet altitude is required (see 3.6.2).
(e) Level of preservation required (see 5.1).
(f) When 24-volt dc power for radio equipment is required (see 3.20.1).
(g) When trucks are to be painted red color No. 11136 (see 3.27).
(h) When trucks are to be painted olive drab color No. 24087 (see 3.27).
(i) When light lenses are to be blue instead of red (see 3.12.6.3.2).
(j) When winterized trucks are required (see 3.10).
(k) When the Government will conduct any or all of the preproduction examination and tests (see 3.3).
(l) When the contractor is to conduct ambient and altitude tests (see 3.6.2).
(m) When lifting and tiedown attachments are required (see 3.24).
(n) When electromagnetic interference is other than specified (see 3.22).
(o) When the contractor shall demonstrate air transportability (see 4.5.2.5.2).

(p) Specify transportability modes (see 3.12.2.2).
(q) Specify when a transportability report is not required (see 3.12.2.3).

6.3 First article. When a first article is required it shall be tested as specified herein. The first article should be a first production item consisting of one complete truck unit. The contracting officer should include

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:00Z
Check the source to verify that this is the current version before use.

specific instructions in all procurement instruments, regarding arrangements for examinations, test and approval of the first article.

6.4 Recycled material. It is encouraged that recycled material be used when practical as long as it meets the requirements of the specification (see 3.5).

6.5 Marking. Levels of packing have not been included as they are not appropriate for this item. For purposes of preservation/packing level marking, the marking shall be A/A or C/A, as applicable.

6.6 Transportability report. The project manager will furnish the transportability report to and obtain transportability approval from the appropriate transportability agent as described in AR 70-44.

6.7 Materiel deterioration prevention and control (MADPAC). The contracting officer should consider for inclusion in all applicable invitations for bid, requests for proposal, and contracts the following statement:

"The technical proposal shall provide assurance that all system/item parts shall be fabricated from compatible materials, suitable finished, to provide protection from corrosion and other forms of materiel deterioration. The assurance shall be in the form of a finish plan, utilizing state-of-art technology, which clearly identifies the specific finish or treatment to be used on the various components and assemblies, to provide protection against the various forms of materiel deterioration in the applicable operating and storage environments to which they may be exposed."

Custodian:
Army - ME
Navy - MC
Air Force - 99

Review activity:
Army - CE, MT

Preparing activity:
Army - ME

Project 4210-0343

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:00Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.
NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

DOCUMENT IDENTIFIER *(Number)* AND TITLE MIL-T-11407L Truck, Fire Fighting, 1000 GPM, Tactical Type, Multipurpose

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1 OCT 76 1426 EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.

OLD

EPARTMENT OF THE ARMY

OFFICIAL BUSINESS
NALTY FOR PRIVATE USE $300

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
USA Mobility Equipment R&D Command
ATTN: DRDME-DS
Ft. Belvoir, VA 22060

OLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:00Z
Check the source to verify that this is the current version before use.