MIL-T-11407L
INT. AMENDMENT 2(ME)
30 March 1983
USED-IN-LIEU-OF
AMENDMENT 1
12 November 1982

MILITARY SPECIFICATION

TRUCK, FIRE FIGHTING, 1000 GPM, TACTICAL TYPE,

MULTIPURPOSE

This interim amendment is approved for use by the US Army Mobility Equipment Research and Development Command, Department of the Army, with Military Specification MIL-T-11407L, dated 12 March 1982.

PAGE 2

2.1.1, after SPECIFICATIONS, MILITARY, add:

"MIL-T-704	- Treatment and Painting of Materiel.
MIL-L-2104	- Lubricating Oil, Internal Combustion Engine, Tactical Service.
MIL-L-2105	- Lubricating Oil, Gear, Multi-purpose.
MIL-G-10924	- Grease, Automotive and Artillery.
MIL-G-20241	- Gasket Material, Wool Felt, Impregnated, Adhesive, Pressure-Sensitive.
MIL-G-23827	- Grease, Aircraft and Instrument, Gear and Actuator Screw.
MIL-S-40626	- Sign Kit, Vehicle Classification.
MIL-C-46168	- Coating, Aliphatic Polyurethane, Chemical Agent Resistant."

After STANDARDS, MILITARY, add:

"MIL-STD-831	- Test Reports, Preparation of.
MIL-STD-1472	- Human Engineering Design Criteria for Military Systems, Equipment and Facilities."

"HANDBOOK

MILITARY

AFSC DH 1-11	- Air Transportability."

FSC 4210

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:01Z
Check the source to verify that this is the currentversion before use.

2.1.2, add the following:

"TECOM, TOP-1-1-001, 6 July 1981, AD Nr. A103325

(Copies should be obtained from the contracting activity or as directed by the contracting officer.)"

PAGE 3

2.2, add the following:

"UNDERWRITERS LABORATORIES, INC.

Guide for Certification of Fire Department Pumpers.

(Application for copies should be addressed to Underwriters Laboratories, Inc., 333 Pfingsten Road, Northbrook, IL 60062.)"

PAGE 4

Add the following paragraphs after 3.5:

"3.5.1 Metals. Where practicable, the metals used throughout the construction of the truck, shall be of high strength-weight ratio. Unless otherwise specified herein, the parts and components of the agent system and winterization distribution systems, except the engine, which come into contact with the firefighting agents, water, foam, and foam concentrate, and coolant liquid shall be fabricated of materials which are corrosion resistant and which will meet the corrosion requirements specified herein. The cab and body shall be fabricated of aluminum. Aluminum alloy rivets shall be used in the assembly of the aluminum components of the truck wherever rivets are used.

"3.5.2 Dissimilar metals. Insofar as practicable, the use of dissimiliar metals in contact with each other shall be avoided. However, metal plating or metal spraying of dissimilar base metals to provide similar or suitable abutting surfaces will be permitted. The use of dissimilar metals separated by suitable insulating material will be permitted. Dissimilar metals are defined in MIL-STD-889.

"3.5.3 Protective treatment. When materials are used that are subject to deterioration when exposed to climatic and environmental conditions likely to occur during service usage, they shall be protected against such deterioration in a manner that will in no way prevent compliance with the performance requirements of this specification. Protective coatings that will chip, crack, or scale with age or extremes of climatic conditions shall not be used.

"3.5.4 Corrosion resistance. The materials used throughout the construction of the agent system shall be resistant to corrosive action of the extinguishing agent."

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:01Z
Check the source to verify that this is the current version before use.

3.6.1, line 2, after "exposed to" delete "maximum". Add the following at the end of the paragraph:

"Cold start aids must be integral with the fire truck and no aids may be used which rely upon external support such as an electrical power source. Hand held aerosol cans are not permitted. Ether primer for cold start may be used."

PAGE 5

3.6.2, delete last sentence and substitute:

"When altitudes above 2000 feet are specified (see 6.2), engine modification kits may be provided and installed when approved by the contracting officer."

3.8, line 3, after "in accordance with" add "MIL-STD-1472,".

3.9, line 1, after "including pumps," add "engine,".

Delete last sentence and substitute "Components and drain outlets subject to periodic servicing shall be located for accessibility and service."

3.10, line 3, delete "minus 50° F." and substitute "minus 65° F."

Line 17, delete last sentence "Ether primer for cold starting may be used."

PAGE 6

3.11, lines 1 through 5, delete and substitute "The truck fully equipped as specified herein with coolant, lubricants, fuel, water, and foam systems filled to capacity and full crew shall be capable of the following:"

3.12.1, line 3, add "The vehicle weight classification shall be marked in accordance with MIL-S-40626."

3.12.2.2, line 4, after "transport in a" add "C-141 and".

Line 5, add: "Removal and reinstallation of top mounted equipment shall be limited to removal or attachment by standard fasteners or fittings. The weight of individual parts or assemblies which must be handled or positioned during removal and reinstallation operations without mechanical assistance provided as part of the component removal shall not exceed the limits specified in MIL-STD-1472 for a one person lift."

PAGE 7

3.12.2.3, title and line 2, delete "report" and substitute "data".

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:01Z
Check the source to verify that this is the current version before use.

Add to end of paragraph:

"The data will contain all weights and dimensions based on a fully equipped vehicle as specified herein, with water tanks empty. Data should include tire footprint and dimensional drawings. Axle weight for air transport shall not exceed 13,000 pounds."

3.12.3, line 6, after "operation", add "(see 4.5.1 and 4.5.2.2)".

3.12.5, line 1, delete "turbocharged".

3.12.5.2.3, line 1, after "fuel filters" add "with automatic water ejector".

Add the following to the end of paragraph: "The fillerpipe opening shall be in accordance with SAE J1140 and shall have sufficient angle to prevent run back and spillage of fuel."

PAGE 8

After 3.12.5.5, add the following:

"3.12.5.6 Oil sampling valve. An oil sampling valve shall be provided on the engine and transmission and shall be capable of closing automatically when released. The valve shall be made of material resistant to corrosion such that it will not contaminate the sample. The valve shall be located to insure that personnel will not be exposed to danger when taking oil samples with the engine running. The location of the oil tap shall be such that samples taken shall be a true representation of oil that is flowing while the engine is running."

3.12.6, line 9, after "the truck." add: "Electrical wiring shall be constructed of SXL crosslink insulation to withstand ultra high temperature."

PAGE 9

3.12.6.2, line 17, after "SAE number" delete "20T6A".

PAGE 12

3.12.11.3.1, line 6, delete "tire pump" and substitute "fire pump".

3.12.12, line 6, after "... engine running.", add "The steering mechanism shall be designed to permit manual steering sufficient to bring the vehicle to a safe stop in event of failure of power assist."

PAGE 13

3.12.13.2, line 2, after "loaded vehicle" add "motionless for 5 minutes while pumping water from the water tank back into the tank through the tank fill line at 150 psi pump pressure."

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:01Z
Check the source to verify that this is the current version before use.

Add new sentence at end of paragraph: "Provision shall be made for release of the parking brake in an emergency if the air system is inoperative."

3.12.14, line 2, after "Tires shall be" add "minimum".

Line 4, delete "55-60 mph" and substitute "55-65 mph".

PAGE 14

3.13(n), add: "Each jump seat shall have a padded-upholstered back rest, with a quick-release type bracket to hold a 30 minute type breathing apparatus. The construction and positioning of the jump seats will be as specified in MIL-STD-1472."

Line 13, after "item (o)" add:

"(p) Transmission oil pressure gage.
(q) High beam indicator.
(r) Pump pressure gage(s).
(s) Water tank level indicator.
(t) Foam tank level indicator."

After line 20, add: "Fire pump and foam control system shall be provided as a part of the system control panel in the cab. The control shall be designed and installed in a manner that it facilitates the driver/operator to control dispensing of AFFF, water, and combination of foam and water in a preparation as specified (see 3.16 and 3.19)."

PAGE 18

3.15.3, line 5, delete: "No cabinet shall be flush ---------- or wheel skirtings." and substitute "The step-plates, running boards and wheel skirtings shall extend beyond the edge of the cabinetry to act as a rub rail. Extension shall remain with overall dimensions of the truck as specified (see 3.12.2.1)."

After 3.15.5, add the following:

"3.15.6 Component storage. The body and equipment compartments shall be capable of mounting and housing all components of the fire fignting equipment set. One equipment set may be loaned to the contractor by the Government for component mounting and compartment size determination (see 6.8)."

PAGE 21

3.20, line 2, delete: "1-1/2 feet long x 1-1/2 feet wide x 1 foot high" and substitute "2 feet long x 2 feet wide x 2 feet high".

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:01Z
Check the source to verify that this is the current version before use.

3.23, add to end of paragraph, "The truck shall operate herein when serviced with lubricants conforming to MIL-L-2104, MIL-L-2105, MIL-G-10924 or MIL-G-23827."

PAGE 22

3.27, delete in its entirety and substitute:

"3.27 Treatment and painting. Unless otherwise specified (see 6.2), the truck cab, chassis body and other equipment, as applicable, shall be cleaned, treated, and painted in accordance with MIL-T-704, gloss-lime-yellow, color No. 13670 of FED-STD-595. When specified (see 6.2), the complete fire truck shall be painted either red or olive drab, as specified. The surfaces between dissimiliar metals may be protected by using zinc chromate tape conforming to MIL-G-20241. All steps, walkways and cabinet tops shall be provided with anti-skid compound applied with the paint. When specified (see 6.2), chemical agent resistant coating (CARC) in accordance with MIL-C-46168 shall be used.

3.28(d), after (2), add: "(3) one 10-foot laterally folding attic-type ladder."

PAGE 24

Section 4, delete in its entirety and substitute the following:

"4. QUALITY ASSURANCE PROVISIONS

"4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

"4.1.1 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

"4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Initial production inspection (see 4.4).
(c) Quality conformance inspection (see 4.6).
(d) Inspection of packaging (see 4.7).
(e) Inspection comparison (see 4.8).

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:01Z
Check the source to verify that this is the current version before use.

"4.3 Preproduction inspection.

"4.3.1 Examination. The preproduction truck(s) shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

"4.3.2 Tests. The preproduction truck(s) shall be tested as specified in 4.5.2. The pumping tests shall be conducted and certified by UL prior to all other testing. Failure of any test shall be cause for rejection.

"4.4 Initial production inspection. When specified (see 6.2), one or more trucks will be selected at random by the Government from trucks being produced by production tooling and will be examined as specified in 4.5.1 and tested as specified in 4.5.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Acceptance of an initial production truck shall not exclude the remaining trucks from the quality conformance inspection and acceptance provisions specified in section 4. In addition to any test specified as part of the initial production test, the Government reserves the right to conduct any and all other tests contained in this specification as part of the initial production test. Failure of such additional tests shall have the same effect as failure of those tests specified as initial production tests.

"4.4.1 Inspection failure. Failure of an initial production truck to meet any requirement specified herein during and as a result of the examination and tests specified in 4.4 shall be cause for rejection of initial production truck(s) and shall be cause for refusal by the Government to continue acceptance of production trucks until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on trucks previously accepted and produced under the contract. Any deficiencies found as a result of the initial production inspection will be considered prima facie evidence that all trucks accepted prior to the completion of initial production inspection are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

"4.5 Inspection procedure. Prior to examination or tests, the truck shall be lubricated with military oils and greases for use at the ambient temperature at the inspection site.

"4.5.1 Examination. The truck shall be examined as specified for both preproduction and initial production inspection for the characteristics listed in table I.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:01Z
Check the source to verify that this is the current version before use.

TABLE I. Examination schedule (requirement).

Number	Characteristic	Requirement Paragraph
1	2	3
Major		
101.	Truck not as specified.	3.1
102.	Material not as specified.	3.5 thru 3.5.4
103.	Safety not as specified.	3.7, 3.7.1
104.	Human factors not as specified.	3.8
105.	Truck chassis not as specified.	3.12
106.	The truck manufacturer's gross vehicle weight (gvw) rating for the truck chassis not as specified.	3.12.1
107.	Wheel base not as specified.	3.12.2
108.	Length, height, and width of the truck and equipment not as specified.	3.12.2.1
109.	Transportability not as specified	3.12.2.2, 3.12.2.3
110.	The chassis frame not as specified.	3.12.3
111.	Engine not as specified.	3.12.5
112.	Engine fuel system not as specified.	3.12.5.2.3
113.	Lubrication of the engine not as specified.	3.12.5.3
114.	Exhaust system not as specified.	3.12.5.4
115.	Brake horsepower certification not furnished by contractor as specified.	3.12.5.5
116.	Electrical equipment not as specified.	3.12.6
117.	Starting system not as specified.	3.12.6.1
118.	Battery units and electrical circuits not as specified.	3.12.6.2
119.	Lighting system not as specified.	3.12.6.3
120.	Additional lighting not as specified.	3.12.6.3.1
121.	Warning light not as specified.	3.12.6.3.2
122.	Light switches not as specified.	3.12.6.3.3
123.	Siren and horn not as specified.	3.12.6.4
124.	The specified type of bumper not furnished as specified.	3.12.7
125.	Towing hooks, rings, or eyes not as specified.	3.12.8
126.	Shock absorbers not as specified.	3.12.9.
127.	Front and rear springs not as specified.	3.12.10
128.	Truck drive assembly not as specified.	3.12.11
129.	Transmission not as specified.	3.12.11.1
130.	Drive axle not as specified.	3.12.11.2
131.	Steering mechanism not as specified.	3.12.12

Source: https://assist.dla.mil -- Downloaded: 202640-17T16:01Z
Check the source to verify that this is the currentversion before use.

TABLE I. Examination schedule (requirement).(con't)

Number	Characteristic	Requirement Paragraph
1	2	3
132.	Brakes not as specified.	3.12.13
133.	Service brakes not as specified.	3.12.13.1
134.	Parking brake not as specified.	3.12.13.2
135.	Wheel and tire assembly not as specified.	3.12.14.
136.	Angles of approach and departure not as specified.	3.12.15
137.	Cab not as specified.	3.13
138.	Windshield wiper and washer not furnished as specified.	3.13.2
139.	Fire pump not UL rated as specified.	3.14
140.	Priming pump not furnished as specified.	3.14.1
141.	Suction connections not furnished as specified.	3.14.2
142.	Discharge connections not furnished as specified.	3.14.3
143.	Relief valve not provided as specified.	3.14.4
144.	Controls not as specified.	3.14.5
145.	Gages and instruments not as specified.	3.14.6
146.	Body of truck not as specified.	3.15
147.	Fire hose compartments not as specified.	3.15.2
148.	Equipment cabinets not as specified.	3.15.3
149.	Handrails and hose rollers not as specified.	3.15.4
150.	Fasteners not as specified.	3.15.5
151.	Water tank and piping not as specified.	3.16
152.	A booster hose reel not furnished as specified.	3.17
153.	Mounting for fire fighting equipment not provided as specified.	3.18
154.	Mechanical foam system not furnished as specified.	3.19
155.	Controls for operation of the foam system not located as specified.	3.19.1
156.	Foam tank not as specified.	3.19.2
157.	Piping and valves coming in contact with foam liquid not of corrosive resistance material as specified.	3.19.3
158.	Communication equipment not furnished as specified.	3.20
159.	The truck not rust proofed as specified.	3.21
160.	The truck not lubricated before delivery as specified.	3.23

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:01Z
Check the source to verify that this is the current version before use.

TABLE I. Examination schedule (requirement).(con't)

Number	Characteristic	Requirement Paragraph
1	2	3
161.	Instruction plates not made and furnished as specified.	3.26
162.	Other specified components not furnished by contractor.	3.28
163.	Interchangeability of parts having the same part number not as specified.	3.29
164.	Casting and forgings not as specified.	3.30.1
165.	Welding not as specified.	3.30.2
166.	Metal fabrication not as specified.	3.30.3
167.	Welded surfaces not prepared for welding as specified.	3.30.4
168.	Welders not certified for welding as specified.	3.30.5
169.	Brazing not as specified.	3.30.6
170.	Bolted connections not formed and burrs removed as specified.	3.30.7
171.	Riveted connections not as specified.	3.30.8
172.	Lifting and tiedown attachments not provided as specified.	3.24
173.	Identification marking not as specified.	3.25
174.	Painting not as specified.	3.27
175.	Cold starting aid not as specified.	3.6.1
176.	Modification kits not approved as specified.	3.6.2
177.	Ease of maintenance not as specified.	3.9
178.	Off road protection not as specified.	3.12.4
179.	Engine hourmeter not as specified.	3.12.5.1
180.	Cooling system not as specified.	3.12.5.2
181.	Heat exchanger not as specified.	3.12.5.2.1
182.	Drain cocks not as specified.	3.12.5.2.2
183.	Oil sampling valve not as specified.	3.12.5.6
184.	Transfer case not as specified.	3.12.11.3
185.	Pump drive not as specified.	3.12.11.3.1
186.	Cross-lay hose bed not as specified.	3.15.1
187.	Component storage not as specified.	3.15.6
188.	Shipping data plates not as specified.	3.25.1
189.	Turrets, pumps and nozzle not as specified.	3.17.1

"4.5.2 Test.

"4.5.2.1 Pump. Truck shall be tested and certified by Underwriters Laboratories prior to all other testing.

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:01Z
Check the source to verify that this is the currentversion before use.

"4.5.2.2 Hydrostatic. After all other tests have been satisfactorily completed, the pump and piping shall be subjected to a hydrostatic test pressure specified by UL for 10 minutes. Pump pressure relief valves, foam valves, pump-to-tank and tank to-pump valves shall be closed. All other valves shall be open with suction and discharge openings plugged or capped. Any leakage or permanent deformation shall constitute failure of this test.

"4.5.2.3 High pressure. The pump shall be operated at a discharger pressure of 500 psi for a period of 5 minutes without evidence of leakage at joints or other defects. 500 psi shall be required of two stage pumps and 350 psi shall be required of single stage pumps. The flow through the pump during this test shall be not more than 12 GPM. Failure to operate at the required pressure for 5 minutes without leakage or other defects shall constitute failure of this test.

"4.5.2.4 Run-in. The pump, assembled as a component of the truck, shall be given a run-in test of not less than 4 hours. The test shall consist of drafting water with a suction lift of not less than 10 feet through 20 feet of 6 inch suction hose and shall include at least the following:

(a) One hour rated capacity at 150 psi net pump pressure.
(b) One-half hour at 70 percent rated capacity at 200 psi net pump pressure.
(c) One-half hour at 50 percent rated capacity at 250 psi net pump pressure.

During the run-in test, there shall be no evidence of strain, vibration, unusual noises, or difficulty in shifting of the engine or pump transmission, or overheating of any part of the truck. The engine shall show no loss of power or reveal overspeed or other defects. A tendency to increase speed, pressure, and discharge under the initial throttle setting is to be expected, and only such throttle adjustments as are necessary to safeguard against excessive speed, pressure, and discharge shall be made. Nonconformance to 3.14 shall constitute failure of this test.

"4.5.2.5 Pumping. After the pump has been run-in for 4 hours, it shall be subjected to the following tests consisting of continuous pumping while drafting through 20 feet of 6-inch suction hose with a lift of not less than 10 feet. Calibrated test gages shall be used.

(a) Measure the vacuum.
(b) Operate the pump for 2 hours against 150 psi gage pressure, 30 minutes against 200 psi gage pressure and 30 minutes against 250 psi gage pressure.
(c) Operate the pump for 15 minutes against 400 psi gage pressure.
(d) Test the relief valve pressure regulator.
(e) Each discharge connection shall be tested for conformance to 3.14.3.

Nonconformance to 3.14 shall constitute failure of these tests.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:01Z
Check the source to verify that this is the current version before use.

"4.5.2.6 Foam system. When applicable, the foam system shall be tested using foam liquid conforming to MIL-F-24385. The metering valve shall be set to deliver 3 percent of foam solution and then to deliver 6 percent of foam solution for not less than 1 minute at each setting while discharging 250 gallons of water per minute. Failure to use at least 6 gallons of foam liquid per minute at 3 percent and 12 gallons of foam liquid at 6 percent shall constitute failure of this test.

"4.5.2.7 Test for ambient temperature and altitude conditions. When specified (see 6.2), the contractor shall perform a pumping test of the preproduction model under actual conditions of 2000 feet altitude above sea level and at an ambient temperature of 125° F. When pumping at heights above 2000 feet altitude is required, certification is required from the contractor that the vehicle will perform as specified in 3.12.5. The pumping test shall consist of the tests specified in 4.5.5. Noncomformance to 3.14 shall constitute failure of this test.

"4.5.2.8 Turrets. The turrets shall be tested for compliance to 3.17.1. Failure to meet flow rates, stream patterns, movement angles on leakage at connections shall constitute failure of this test. When the roof turret must be removed to meet aircraft loading, 17 shall be demonstrated at this time prior to starting this test.

"4.5.2.9 Road and pump. The truck(s), equipped as specified herein [plus the fire fighting equipment set (see 6.8), coolant, lubricants, fuel, water and foam system (water may be substituted) filled to capacity, and full crew or simulated weight], shall be tested as specified in 4.5.2.10.

"4.5.2.10 Road test course. The road test course shall be as described herein:

(a) Primary roads. Level and hilly combination of paved roads with grades up to but not exceeding 10 percent.
(b) Improved secondary roads. Combination of level and hilly, maintained and graded, dirt or gravel roads with grades up to but not exceeding 12 percent.
(c) Cross-country. Off-road hilly and level cross-country conditions which subject the vehicle to all wheel drive. Requirements and grades up to but not exceeding 20 percent.

The course may contain unimproved, unmaintained secondary roads, trails, uneven surfaces, ditches, stones and other debris. The road courses shall be as described in TECOM TOP-1-1-011, 6 July 81 AD Nr. A103325.

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:01Z
Check the source to verify that this is the current version before use.

Secondary road
1. Munson improved gravel
2. Belgian block

Cross country
1. Perryman No. 1
2. Churchville "B"

"4.5.2.11 Road. The trucks(s) shall be tested on the course specified in 4.5.2.10 with the following requirements:

(a) 1400 miles over primary roads at 7 speeds up to 55 mph.
(b) 400 miles over improved secondary roads at speeds up to 35 mph.
(c) 200 miles over cross-country in all wheel drive at speeds up to 10 mph.
(d) Service brakes shall be applied normally during all road tests.
(e) All lights, siren, horns, speedometer, hourmeter, controls and instruments pertaining to the truck engine shall be tested and observed.
(f) At 200 mile interval, plus or minus 50 miles, during (a), (b), and (c) above. The pump shall be operated as specified in 3.12.11.3.1 for a minimum of 10 cycles. The roof turret shall be used for 5 cycles and the bumper turret for 5 cycles at the pressures specified in 4.5.2.8.
(g) At 500 mile intervals (plus or minus 50 miles) for at least 4 iterations during the combined milage of (a), (b), and (c) above, conduct pump test in accordance with 4.5.2.5.
(h) Conduct test and inspection as specified in 3.11 (e) after conducting all tests in (a) thru (g) above. Additionally conduct the test specified in 4.5.2.2.

After completion of the tests specified herein, the truck shall be checked at all locations where a permanent deformation may occur to include but not be limited to: Where components are attached to body/frame, e.g.; engine, tanks, pumps, axles, shock absorbers, springs, plumbing. Flex shall be checked with strain gauges; welds shall be checked with xyglo or magnaflux as applicable. All check points shall be logged, measurements and defects noted and reported in conformance to MIL-STD-831.

"4.5.2.12 Environmental. The truck shall be tested for conformance to 3.6.1. Winterized trucks shall conform to 3.10. Failure of the truck to perform as specified in 4.5.2.5 at plus 125° F shall be cause for rejection. Failure of the truck to start and maintain condition specified in 3.10 shall be cause for rejection.

"4.5.2.13 Performance. The trucks(s) shall be tested for conformance to 3.11 (a), (b), (c), (d), (e), (f), (g), and (i), loaded as specified. Failure to perform as specified shall be cause for rejection.

"4.5.2.14 Brakes. The truck shall be tested for conformance to 3.12.13.1 and 3.12.13.2. Failure to perform as specified shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 202640-17T16:01Z
Check the source to verify that this is the currentversion before use.

"4.5.2.15 Air Transportability tests.

"4.5.2.15.1 Configuration testing. The truck, prepared for air transportability, shall be measured and weighed. Where necessary, items mounted above roof level (except turret) shall be removed and replaced to verify compliance with requirements specified in 3.12.2.2.

"4.5.2.15.2 Loading demonstration. When specified (see 6.2), the truck shall be prepared to the extent necessary for air transport. The removed portions shall be stored in or on the truck. The truck shall be loaded aboard a C-130 or a C141 aircraft equipped with an A/A32H-4 dual rail cargo handling system in accordance with the loading demonstration test specified in MIL-A-8421. This shall be certified by the Air Force for conformance to AFSC DH1-11.

"4.5.2.16 Electromagnetic interference. Unless otherwise specified (see 6.2), the truck shall be certified or tested as specified in SAE J551.

"4.6 Quality conformance inspection.

"4.6.1 Examination. Each truck shall be examined for defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

"4.6.2 Tests. Each truck shall be tested as specified in 4.5.2; 4.5.2.8 (using water dye); 4.5.2.11(a) (50 miles). The pump shall be operated as specified in 3.11(i) not less than three times. Failure of any test shall be cause for rejection.

"4.7 Inspection of packaging. The preservation, packing and marking of the truck and furnished equipment shall be examined to determine compliance with the quality assurance provisions of MIL-STD-281 and MIL-E-10062 as applicable for level A or for the specific requirements specified for level C.

"4.8 Inspection comparison. The Government may select trucks at any time during the contract production period and subject these trucks to the examination specified in 4.5.1 and the tests specified in 4.5.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government on trucks selected at random from those which have been accepted by the Government and will include the previously inspected preproduction model and initial production trucks. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.

"4.8.1 Inspection failure. Failure of an inspection comparison truck to meet any requirement specified herein during and as a result of the examination and tests specified in 4.8 shall be cause for rejection of the inspection comparison

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T16:01Z
Check the source to verify that this is the current version before use.

truck and shall be cause for refusal by the Government to continue acceptance of production trucks until evidence has been provided by the supplier that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the supplier at no cost to the Government on trucks previously accepted and produced under the contract. Any deficiencies found as a result of the inspection comparison will be considered prima facie evidence that all trucks accepted prior to the completion of the inspection comparison are similarly deficient unless evidence to the contrary is furnished by the supplier and such evidence is acceptable to the contracting officer."

PAGE 31

6.1, line 1, after "intended for use" delete "by garrison troops".

6.2(g), delete and substitute:

(g) When trucks are to be painted other than as specified (see 3.27)."

6.2(k), after "all of the" delete "preproduction" and substitute "initial production".

PAGE 32

After 6.7, add the following new paragraph:

"6.8 Government-loaned property. When required, the contracting officer should arrange to furnish the property specified in 3.15.6."

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 4210-A182

Source: https://assist.dla.mil -- Downloaded: 202610-17T16:01Z
Check the source to verify that this is the current version before use.