MIL-T-62134B(AT)
20 April 1976
SUPERSEDING
MIL-T-62134A(AT)
5 March 1971

MILITARY SPECIFICATION

TRANSMISSION, POWER SHIFT, COMMERCIAL MODIFIED

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers Power Shift Transmission P/N 4R219, as modified for use in Goer military vehicles.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

Federal

P-C-437 - Cleaning Compound, High Pressure (Steam) Cleaner.

Military

MIL-P-514 - Plates, Identification, Instruction and Marking Blank.
MIL-L-2104 - Lubricating Oil, Internal-Combustion Engine, Tactical Service.
MIL-L-10295 - Lubricating Oil, Internal-Combustion Engine, Sub-Zero.
MIL-T-62130 - Truck Tank: Fuel Servicing, 2500 Gallon, 4x4, M559.
MIL-T-62131 - Truck Wrecker: 10 Ton, 4x4, M553.
MIL-T-62132 - Truck Cargo: 8 Ton, 4x4, M520, M877.
MIL-E-62133 - Engine Diesel: 6 Cylinder, In-Line, 213 H.P. Turbo-Supercharged.

STANDARDS

Military

MIL-STD-130 - Identification Marking of U. S. Military Property.
MIL-STD-193 - Painting Procedures, Tactical Vehicles (Tracked and Wheeled).

FSC 2520

Source: https://assist.dla.mil -- Downloaded: 202610-23T01:20Z
Check the source to verify that this is the current version before use.

MIL-STD-721 - Definitions of Effectiveness Terms for Reliability.

DRAWING

11614457	- Transmission Assembly.
11681062	- Power Plant Assembly.
11635131	- Transmission and Transfer Case Assembly.
11614404	- Power Plant Installation.
11614458	- Transfer Case Assembly.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Assembly. The transmission assembly shall be in accordance with 11614457. The transmission shall interface and be compatible with engine 11681062 and as specified in MIL-E-62133. The transmission shall interface with and be functionally compatible with transfer case assembly 11614458, as an assembly of 11635131, and shall function as part of the complete power plant 11614404. The transmission shall transmit the engine power and torque as specified in MIL-E-62133, and provide the performance and durability required in this specification and the vehicle specifications MIL-T-62130, MIL-T-62131, and MIL-T-62132. The transmission shall be identified in accordance with MIL-STD-130. Spare parts, assemblies, and subassemblies requiring identification shall be identified in accordance with MIL-STD-130 when specified on drawings. Definitions contained in MIL-STD-721 shall apply.

3.1.1 Interchangeability of parts. Component assemblies and parts of the transmission shall be so constructed that they may be installed, replaced, and adjusted without requiring modification between other transmissions provided under the same part number. If some parts must be furnished in matched sets, the contractor shall provide a list giving part number, part nomenclature, and tolerance range of sets involved. This list must be approved by the Government prior to shipment of any transmission.

3.1.2 Reliability (minimum). The transmission shall have a 1000 hour Mean Time Between Failure (MTBF) when installed in either the M520, M553, M559 or M877 vehicles. Failure is defined as any malfunction which causes the transmission to cease operation, produces a safety hazard or will contribute to transmission, vehicle, or engine damage if operation is continued.

3.1.3 Durability (minimum). Transmission replacements in vehicles shall be used to measure durability and shall have probabilities of not requiring replacement as follows:

(a) M520 75% in 25,000 miles of mission operation.
(b) M553 86% in 12,500 miles of mission operation.
(c) M559 86% in 18,000 miles of mission operation.
(d) M877 75% in 25,000 miles of mission operation.

Source: https://assist.dla.mil -- Downloaded: 202640-23T01:20Z
Check the source to verify that this is the current version before use.

3.1.4 Maintainability. When maintenance procedures shown in the technical manuals are followed and the transmission is operated in the vehicles as defined in the mission statements, the demonstrated maintainability shall be as follows:

(a) Mean Operator Preventive Maintenance Time shall not exceed .25 man-hours per mission. This time shall not be included in operational preventive maintenance time.
(b) Maximum Operator Corrective Maintenance Time shall not exceed 1.00 manhours in vehicle per mission without being classified as a mission failure.
(c) The ratio of total corrective and operational preventive maintenance manhours to operating hours shall not exceed .06.
(d) The ratio of total operation preventive maintenance manhours to total operating hours shall not exceed .02.
(e) The ratio of total corrective maintenance action shall not exceed .04.
(f) Mean manhours to perform a corrective maintenance action shall not exceed 4.00.
(g) The Mean Time Between corrective maintenance actions shall not be less than 100 operating hours.

3.2 Initial production transmission assembly. The transmission selected shall be fully representative of transmissions proposed to be furnished under the contract and shall be submitted to the Government for inspection to determine conformance to the requirements of this specification.

3.3 Performance requirements.

3.3.1 Oil. The transmission shall perform as specified herein using lubricating oil in accordance with grade 10 of MIL-L-2104 from minus 10°F to plus 125°F, and MIL-L-10295 from minus 65°F to plus 10°F.

3.3.1.1 Temperature range. The transmission converter "out" oil temperature shall not exceed 275°F during each transmission evaluation sequence and production runs.

3.3.1.2 Oil level. Transmission oil level shall be maintained within the operating range on the oil level indicator. The oil level shall be between the "full" and "add oil" mark on the dipstick while operating in neutral range at between 700 rpm's and 925 rpm's input speed. The oil level shall be maintained by adding or removing oil.

3.3.1.3 Leakage. During any evaluation sequence or at completion of all evaluations, the transmission shall not shown evidence of leakage in excess of a seep as defined in 6.3.

3.3.1.4 Safety valve. Each transmission shall incorporate a safety valve to prevent torque being transmitted to the output shaft should the vehicle engine be started with transmission speed selector in a position other than neutral.

3.3.2 Functional pressure requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:20Z
Check the source to verify that this is the current version before use.

3.3.2.1 Low speed oil pressures. With transmission input speed of between 700-925 rpm, with converter "out" oil temperature stabilized between 125°F ± 10°F and the transmission supplying oil at a rate of 8.5 ± 1 gpm; the oil pressure shall be as indicated in table I.

Table I. Low speed oil pressures-psi.

Range	Speed clutch(min)	Lube	Range clutch(min)	Converter inlet
1st	160	0-20	360	0-20
2nd	160	0-20	360	0-20
3rd	160	0-20	360	-
4th	160	0-20	360	-
5th	160	0-20	360	-
6th	160	0-20	360	-
Reverse	160	0-20	360	0-20
Neutral	160	0-20	360	0-20

3.3.2.2 High speed oil pressure. With transmission input speed of 1000 rpm in 1st, 2nd or reverse and 2200 rpm and the transmission pump supplying oil at a rate of 22 ± 1 gpm and with converter "out" oil temperature stabilized at 125°F ± 10°F, the oil pressure shall be as indicated in table II.

Table II. High speed oil pressures-psi.

Range	Speed clutch	Lube	Range clutch	Converter inlet
1st	185 ± 10	47 ± 5	415 ± 15	47 ± 5
2nd	185 ± 10	47 ± 5	415 ± 15	47 ± 5
3rd	185 ± 10	47 ± 5	415 ± 15	
4th	185 ± 10	47 ± 5	415 ± 15	
5th	185 ± 10	47 ± 5	415 ± 15	
6th	185 ± 10	47 ± 5	415 ± 15	

3.3.3 Transmission friction. With converter "out" oil temperature stabilized at 125°F ± 10°F, no load on the output shaft, the transmission frictional losses shall not exceed that shown in table III.

Table III. Transmission frictional loss.

Range	Input speed ± 5 rpm	Input torque maximum	Output rpm ± 5 rpm
1st	1000 rpm	105 lb ft (pound feet)	
3rd	2200 rpm	59 lb ft	1167
6th	2200 rpm	71 lb ft	2692
Reverse	1000 rpm	105 lb ft	
Neutral	2200 rpm	47 lb ft	

3.3.4 Stall in 2nd range. With the control selector in 2nd range, the transmission pump supplying oil at a rate of 22 ± 1 gallon per minute, the output shaft stalled, and the converter out oil temperature at 190 to 220°F; the transmission shall perform as follows:

(a) Input speed, rpm - 1820 maximum (max) - 1685 minimum (min).

Source: https://assist.dla.mil -- Downloaded: 202610-23T01:20Z
Check the source to verify that this is the current version before use.

(b) Input torque, lb, ft - 635 max - 460 min.
(c) Output torque, lb, ft - 3645 min.
(d) Lubrication pressure, psi - 52 ≠ 5.
(e) Range clutch pressure, psi - 410 ≠ 20.
(f) Lube oil flow, gpm - 22 ≠ 1.

3.4 Production transmission. All transmissions procured under the production contract shall meet all the operational and performance requirements specified herein.

3.4.1 Production break-in run. Each transmission shall be given a break-in run by the contractor. After successful completion of this run, the transmission shall be ready for use in the Goer vehicles and meet all performance requirements specified herein.

3.5 Grades and slopes. The transmission shall demonstrate the performance characteristics specified herein when operated with the engine in the M520, M553 and M559 goer vehicles, (with full and add oil) oil level conditions, on lateral slopes up to 30 percent in all directions and 60% longitudinal grades. As a result of said operation, no evidence of faulty lubrication, leakage, or other malfunction shall be found.

3.6 Steam and water jet cleaning. The transmission, as installed in vehicle or a simulated mounting with protection to the input and output shafts, shall withstand cleaning with high pressure steam and cleaning compound conforming to P-C-437 and water jet, without deterioration of seals, water leakage past seals and gaskets, or other defects. Paint removal shall not be considered a deficiency. Steam and water jet cleaning as it pertains to this transmission is defined as follows: the jet is applied perpendicular to the surface to be cleaned at a minimum distance of 1 foot from the surface, and the cleaning is accomplished at a minimum rate of 1 square foot per minute. The jet pressure shall not be less than 100 psi and not more than 110 psi.

3.7 Log sheet. The contractor shall maintain a log sheet of each transmission tested as specified herein. The form of the log sheet and number of legible copies to be furnished to the Government shall be as approved by the procuring activity.

3.8 Exterior surface treatment. Pretreatment prior to painting shall be according to contractor's standard commercial practice and shall be painted in accordance with the applicable provisions of MIL-STD-193.

3.9 Name, shipping, and identification data plates. All data plates shall be in accordance with MIL-P-514.

3.10 Workmanship. The transmission assembly shall be constructed and finished thoroughly in a workmanlike manner. Particular attention shall be paid to neatness and thoroughness of marking the parts, plating, painting, machine-screw assemblage, welding and brazing, and freedom of parts from burrs and sharp edges. No condition shall exist which may create a safety hazard to operating or maintenance personnel.

Source: https://assist.dla.mil -- Downloaded: 202610-23T01:20Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Contractor's inspection or quality control system. The contractor shall provide and maintain an effective inspection or quality assurance system acceptable to the Government covering the supplies under the contract. A current, written description of the system shall be submitted to the contracting officer prior to initiation of production. The contractor shall notify the Government of any subsequent change to the submitted procedures prior to implementing the change into the system.

4.1.2 Government verification. All quality assurance operations performed by the contractor will be subject to Government verification at unscheduled intervals. Verification will consist of surveillance of the operations to determine that practices, methods, and procedures of the written inspection plan are being properly applied. Deviation from the prescribed or agreed-upon procedure, or instances of poor practices which might have an effect upon the quality of the product will be immediately called to the attention of the contractor. Failure of the contractor to promptly correct defects discovered shall be cause for suspension of acceptance until correction has been made or until conformance of product to prescribed criteria has been demonstrated.

4.1.3 Initial production test. One of the first 10 production transmissions produced under contract shall be selected by the Government and subjected to a 400-hour run. (Eight 50-hour runs as specified in Table V.) This test shall be conducted by the Government at a place designated by the Government to determine conformance to 3.2. The Contractor shall support the 400-hour run and the initial production vehicle tests by providing any components necessary for completion of such test. Delay in tests completion caused by transmission breakdown or failure of the Contractor to adequately support the transmission with parts during the tests shall not be the basis for adjustment of contract delivery schedule or contract price. In addition, the initial production test (400-hours), transmission shall be examined for all defects of Table IV and tear-down inspection (4.5.2) will be conducted following completion of the 400-hour test.

4.1.3.1 Test failure. Failure of test transmission to comply with the requirements specified or defects of a workmanship or materials nature revealed during or as a result of test shall be cause for rejection of the transmissions. Further, the Government may refuse to continue acceptance of production transmissions until evidence has been provided by the contractor that corrective action has been taken to eliminate the defect. Any defect found during or as a result of this test shall be prima facie evidence that all transmissions already accepted prior to completion of test are similarly defective unless evidence

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:20Z
Check the source to verify that this is the current version before use.

satisfactory to the Government is furnished by the contractor thay they are not similarly defective. Such defects on all transmissions shall be corrected by the contractor at no cost to the Government.

4.2 Examinations. Visual, dimensional, and primary functional examinations shall consist of examination of each transmission for the defects listed in table IV.

Table IV. Examination defects.

Categories	Defects	Gage or other method of inspection
Dimensions	Affecting interchangeability of major components, mounting in vehicle	Gage/visual
Control levers and valves	Malfunction	Functional/ visual
Marking	Improper or not legible	Visual
Appearance	Scratches, chipped, pitted or burred	Visual
Workmanship	Not following good practices improper installation adjustments of components	Functional/ visual
Paint-finish coat	Improper application or color	Visual
Exterior surface treatment	Improperly cleaned or treated for corrosion resistance	Visual
Name, shipping & identification data plates	Shall be accordance with MIL-P-514	Visual

4.2.1 Examination failure. The occurrence of any defect listed in table IV or failure to pass any specified test shall be cause of rejection of that transmission. Rejected units may be resubmitted for acceptance after objective evidence has been provided by the manufacturer that corrective action has been taken to eliminate the condition which caused rejection.

4.3 In vehicle test. To determine conformance to 3.1.2 through 3.1.4, the quantity of transmission specified in the contract shall be installed in the vehicles listed in 3.1.3 and shall be subjected to mileage specified for each vehicle type. This test shall be conducted in conjunction with the initial production test, comparison test, or any other Government test.

4.3.1 Failure. Any transmission failure during the above test due to defective workmanship or material, or non-compliance with drawings and specifications set forth herein shall be reason for refusal by the Government to accept subsequent transmission until evidence has been provided by the supplier that corrective action has been taken to eliminate the defect. Any defect found during or as a result of this test shall be prima facie evidence that all transmissions already accepted prior to completion of test are similarly defective unless evidence satisfactory to the Government is furnished by the contractor that they are not similarly defective. Such defects on all transmissions shall be corrected by the contractor at no cost to the Government.

Source: https://assist.dla.mil -- Downloaded: 202610-23T01:20Z
Check the source to verify that this is the current version before use.

4.4 Acceptance test. Following the break-in run shown in 3.4.1 and to determine conformance to 3.3, the transmission shall be installed on a test stand with provisions for connecting the input to an input power supply, linkage controls, an external hydraulic system for instrumention. The output shaft shall be free unless otherwise specified. The transmission shall than be subjected to the examinations listed in table IV and the acceptance tests listed in table VI.

4.4.1 Assembly check. To determine conformance to 3.1, each transmission shall be checked for dimensions and proper assembly.

4.4.2 Performance checks.

4.4.2.1 Oil check. To determine conformance to 3.3.1, oil being used shall be checked for meeting specifications indicated.

4.4.2.2 Temperature range and oil level check. To determine conformance to 3.3.1.1 and 3.3.1.2, the transmission shall be operated, as specified, and checked for requirements.

4.4.2.3 Leakage check. To determine conformance to 3.3.1.3, the transmission shall be visually inspected at various points during test operation and thoroughly inspected at the end of test operation for indications of oil leaks.

4.4.2.4 Safety valve check. To determine conformance to 3.3.1.4, each transmission shall be checked to assure safety valve is properly installed and tested as follows:

(a) With transmission input speed at zero rpm and no oil flow, shift gear selector into any position other than neutral.
(b) Supply hydraulic oil at the rate of 8.5 ± 1 G.P.M.
(c) Rotate input at 700-925 RPM.
(d) Speed clutch pressure gage should indicate zero psi. Shift gear selector to neutral, then back to first gear forward, speed clutch pressure gage shall indicate 160 psi min.

4.4.2.5 Low and high speed oil pressure tests. To determine conformance to 3.3.2.1 and 3.3.2.2; the transmission operating, as specified, shall be checked for meeting performance requirements.

4.4.2.6 Transmission friction test. To determine conformance to 3.3.3, the transmission operating as specified shall be checked for meeting performance requirements.

4.5 Control test. Transmissions shall be selected by the Government at the rate of one per month when production is 100 units per month or less and at the rate of two per month when production is greater than 100 units per month. Transmission shall be identified as to production period. The transmission filled with oil specified herein shall be mounted on a test stand and coupled to a motor unit at the input end and a power absorption unit at the output end. After completion of 50 hour run, transmission must meet all requirements of 3.3. Each transmission selected shall be examined for defects in table IV and subject to the tests in table V and control tests shown in table VI.

Source: https://assist.dla.mil -- Downloaded: 202610-23T01:20Z
Check the source to verify that this is the currentversion before use.

Table V. 50 hour run.

Test Cycle**	Shift Range	Hours	Input RPM*	Input Torque*
1	1	.25	1888	544
2	1	.5	2200	460
3	2	.5	1888	544
4	2	1.0	2200	460
5	3	.5	1600	500
6	3	1.0	2200	460
7	4	.5	1600	500
8	4	1.5	2200	460
9	5	1.0	1600	500
10	5	2.0	2200	460
11	6	1.0	1600	500
12	6	2.0	2200	460
13	R	.25	1888	544
14	R	.5	2200	460

*Input RPM and torque may vary ± 3%
** Repeat sequence 4 times

4.5.1 Control Test failure. Failure of the transmission to conform to the requirements specified or any major defect of workmanship or material found as a result of the test shall be cause for rejection and for refusal to accept subsequent transmissions. Defects found during or as a result of the test shall be prima facie evidence that transmissions accepted subsequent to the previous acceptable control test transmission are similarly defective unless evidence satisfactory to the contracting officer is furnished by the contractor that are not similarly defective. Defects on all transmissions shall be corrected by the contractor at no cost to the Government. In the event of a failure, another transmission from the same production period shall be subjected to a control test.

4.5.2 Tear-down inspection. Subsequent to above tests, the transmission shall be completely disassembled and the following examinations performed:

(1) Gear wear
(2) galling
(3) Bearing wear
(4) Scoring
(5) Chips & dirt

4.5.2.1 Corrections and reassembly check. Should evidence of condition requiring replacement of components, such replacements shall be made by the contractor prior to reassembly. The transmission, with replaced components, shall again be subjected to the control tests. In the event the disassembly inspection reveals no deficiencies, the transmission shall be reassembled and subjected to the acceptance tests.

4.5.2.2 Inspection and test results. The contractor shall provide inspection test results for all control tests. All data shall be obtained under stabilized operating conditions.

Source: https://assist.dla.mil -- Downloaded: 202610-23T01:20Z
Check the source to verify that this is the current version before use.

4.5.3 Stall in 2nd range. To determine conformance to 3.3.4, stall the output shaft with the range selector in 2nd position, increase the input speed within limits of 460 to 635 lb. ft. Record input speed and output torque.

4.6 Grades and slopes tests. To determine conformance to 3.5, the transmission, as installed in vehicle, shall be subjected to test requirements of applicable vehicle specification and tested at a site selected by the Government.

4.7 Steaming and jet cleaning tests. To determine conformance to 3.6, the initial production and control test transmissions shall be subjected to cleaning as specified. The seals and gaskets shall be checked for damage and leaks.

4.8 Log sheet check. To determine conformance to 3.7, a reproducible test log sheet shall be maintained incorporating data taken during evaluation of each transmission assembly.

Table VI. Test schedule.

	Requirement paragraphs	Test paragraphs	IPT	Acceptance	Control
Assembly	3.1	4.4.1		X	
Realiability (minimum)	3.1.2	4.1.3 & 4.3	X		
Durability (minimum)	3.1.3	4.1.3 & 4.3	X		
Maintainability	3.1.4	4.1.3 & 4.3	X		
Initial production transmission assembly	3.2	4.1.3 & 4.3	X		
Performance requirements	3.3	4.4.2	X	X	
Oil	3.3.1	4.4.2.1	X	X	
Temperature range	3.3.1.1	4.4.2.2	X	X	
Oil level	3.3.1.2	4.4.2.2	X	X	
Leakage	3.3.1.3	4.4.2.3	X	X	X
Safety valve	3.3.1.4	4.4.2.4	X	X	
Low speed oil pressure	3.3.2.1	4.4.2.5	X	X	
High speed oil pressure	3.3.2.2	4.4.2.5	X	X	
Transmission friction	3.3.3	4.4.2.6	X	X	
Stall in 2nd range	3.3.4	4.5.3			X
Production transmissions	3.4				
Production break-in run	3.4.1			X	
Grades & slopes	3.5	4.6	X		
Steam & water jet cleaning	3.6	4.7	X		
Inspection & test results		4.5.2.2			X
Log sheet	3.7	4.8	X	X	X

5. PREPARATION FOR DELIVERY

5.1 Packaging, packing and marking. Shall be in accordance with the technical requirements specified on the appropriate packaging data sheets (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:20Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. The transmission covered by this specification is intended for production use, as spares, or as replacements in the M520, M877, M553 and M559 Goer vehicles.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Quantity of initial production transmissions if required (see 4.1.3).
(c) Applicable packaging data sheet or sheets (see 5.1).

6.3 Definitions. The following definitions are established as a guide in determining conformance with the leakage requirements of this specification.

(a) Weep - Any non-recurring evidence of fluid beyond a seal or splitline.
(b) Seep - Any recurring evidence of fluid beyond a seal or splitline.
(c) Droplet - Any evidence of fluid beyond a seal or splitline that results in the formation of a droplet.
(d) Drip - Any evidence of fluid beyond a seal or splitline where droplets form and fall.

6.4 Definitions of test conditions.

6.4.1 Input power source. The input power supply shall be the same type as used in vehicle installation or a suitable equivalent power source.

6.4.2 Linkage controls. Separate linkage controls shall be provided for each of the following:

(a) Engine throttle.
(b) Range selector shift level.

6.4.3 Instrumentation. Instrumentation shall be provided to measure the following:

(a) Input speed - rpm.
(b) Output speed - rpm.
(c) Main oil pressure - psi.
(d) Transmission oil pressure - psi.
(e) Converter out oil temperature.
(f) Oil flow - GPM.
(g) Input torque - pound feet (lb. ft.).
(h) Output torque - pound feet (lb. ft.).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:20Z
Check the source to verify that this is the current version before use.

6.4.4 Transmissionoil level. The tests shall be conducted after establishing the design oil level by one ofthe following methods:

(a) When testing with torque converter, transmission, transfer case and sump filled with approximately forty-five (45) quarts of oil, the oil level shall be between the "full" and "add oil" mark on the dipstick while running in neutral range at 700-925 rpm input speed. Adjust the level if necessary by adding or removing oil.

(b) When testing with torque converter and transmission only, an external oil reservoir is required.

6.5 Typical vehicle life operational profile.

Model	Renewal Life Miles - Hours	Ave M.P.H	Total Missions	Mission Miles - Hrs
M520	25,000-1250	20.0	250	100 - 5
M559	18,000-1250	14.4	182	100 - 6.9
M553	12,500-1250	10.0	250	50 - 5
M877	25,000-1250	20.0	250	100 - 5

In actual troop use, this will vary due to environmental, terrains, and troop mission differences.

Custodian:
Army - AT

Preparing activity:
Army - AT
Project No. 2520-A102

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:20Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

MIL-T-62134B(AT)

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 54 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:20Z
Check the source to verify that this is the current version before use.