MILITARY SPECIFICATION

DESTRUCTOR EXPLOSIVE ASSEMBLY, XM24, FOR LANCE, XM198, PRACTICE WARHEAD, PARTS, LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the metal parts loading, assembling and packing for one type of device designated as Destructor, Explosive Assembly XM24.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-A-2550	-	Ammunition and Special Weapons, General Specification
MIL-I-45607	-	Inspection Equipment, Acquisition, Maintenance and Disposition of
MIL-R-11470	-	Radiographic Inspection: Qualification of Equipment Operators and Procedures

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109	-	Quality Assurance Terms and Definitions
MIL-STD-1168	-	Lot Numbering of Ammunition
MIL-STD-1235	-	Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

9257388	-	Destructor, Explosive Assembly: XM24

PUBLICATIONS

ARMY

ET-9257388	-	Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer).

2.2 Other publications.-The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall apply.

CODE OF FEDERAL REGULATIONS

Title 49	-	Transportation, Parts 0-190

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

(The Code of Federal Regulations is available from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402. Orders should specify, "49 CFR 0-190 (latest revision)".)

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and specifications.

3.2 Parts.-The parts shall comply with all requirements specified on Drawing (Dwg.) F-9257388, all associated drawings, and with all requirements specified in applicable specifications.

3.3 Radiographic examination of ALSC.-The ALSC shall be radiographically examined for cracks, breaks and splits.

3.4 Workmanship.-All parts and assemblies shall be fabricated, loaded and assembled in a thorough workmanlike manner. They shall be free of burrs, sharp edges, corrosion products, cracks, dirt, grease, rust, unblended radii, surface defects and other foreign matter. The cleaning method used shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agents. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required marking and stamping shall be neat and sharply defined.

3.5 Submission of results of contractor-conducted examinations and tests.-The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract. (see 6.5).

3.6 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statementat that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the cource of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2. (See 6.1) The first article sample shall consist of the following:

a. Five (5) - Destructor, Explosive Assembly: XM24 (9257388)
b. Five (5) - Cover, Destructor, Explosive (9257390)
c. Five (5) - Gasket (9257391)
d. Five (5) - Wire, Grounding (9257397)
e. Five (5) - Booster, Destructor, Explosive (9257392)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

All parts and completed assemblies submitted shall have been produced by the contractor (or furnished by a supplier) using the same production processes, procedures and equipment as will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance. A first article quantity, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspections to be performed.-Assemblies and components will be subjected by the Government to any or all the examinations or tests specified in this specification and any or all requirements of the applicable drawings.

4.2.3 Rejection.-If any assembly or component fails to comply with any of the applicable requirements, the first article quantity shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity or portion thereof. Until a first article quantity is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (See 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Gasket (See Dwg. 9257391)

Categories	Defects	Method of Inspection	Code No. (See 6.2)
Critical:	None defined		
Major:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

Minor	AQL 2.50 Percent (See 4.3.3.1)		
201.	Diameter of holes incorrect	Gage	01001
202.	Overall length incorrect	Gage	01002
203.	Width incorrect	Gage	01003
204.	Thickness incorrect	Gage	01004
205.	Location of holes incorrect	Gage	01005
206.	Burrs and material fragments on edges of holes	Visual	01006
207.	Evidence of poor workmanship (See 3.4)	Visual	01007

4.3.2.2 Aluminum linear Shaped Charge (See dwg. 9257393).-

Categories	Defects	Method of Inspection	Code No. (See 6.2)
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Height	Gage	02001
102.	Outside apex angle incorrect	Gage	02002
Minor	AQL 1.50 Percent		
201.	Total length	Gage	02003
202.	Width	Gage	02004
203.	Evidence of poor workmanship (See 3.4)	Visual	02005

4.3.2.3 Wire, Grounding (See Dwg. 9257397).

Categories	Defects	Method of Inspection	Code No.
Critical	100% Inspection		
1.	Insulation not removed from screw area	Visual	03001
2.	Solder missing or inadequate	Visual	03002
Major:	None defined		
Minor	AQL 0.65 Percent		
203.	Evidence of poor workmanship (See 3.4)	Visual	03003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

4.3.2.4 Booster, Destructor, Explosive (See Dwg 9208777).-

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Cover missing	Visual	04001
2.	Crimp and or sealant missing	Visual	04002
Major	100% Inspection		
101.	Explosive missing	Visual	04003
Major	AQL 0.40 Percent		
102.	Length	Gage	04004
103.	Diameter	Gage	04005
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.4)	Visual	04006

4.3.2.5 Cover, Destructor, Explosive (See Dwg 9257390).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	100% Inspection		
101.	Location of through holes incorrect	Gage	05001
102.	Depth of ALSC cavity	Gage	05002
Major:	AQL 1.0 Percent		
103.	Contour radii incorrect	Gage	05003
104.	Width of ALSC cavity	Gage	05004
105.	Distance from end to ALSC cavity	Gage	05005
106.	Length of ALSC cavity	Gage	05006
107.	Distance from end to first set of through holes	Gage	05007
108.	Protective finish on marked surfaces	Visual	05008
Minor:	AQL 4.0 Percent		
201.	Diameter of through holes	Gage	05009
202.	Diameter of counterbore	Gage	05010
203.	Concentricity of counterbore holes	Gage	05011

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

204.	Height at forward end	Gage	05012
205.	Height at aft end	Gage	05013
206.	Apex of ALSC cavity incorrect	Gage	05014
207.	Protective finish missing or incomplete	Visual	05015
208.	Evidence of poor workmanship (See 3.4)	Visual	05016

4.3.2.6 Destructor, Explosive Assembly: XM24 (See Dwg 9257388).-

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	ALSC groove in cover and ALSC not dry and free of foreign material, prior to assembly (See Dwg 9257389)	Visual	06001
Major	100% Inspection		
101.	Ground wire missing or insecure	Visual-Manual	06002
102.	Adhesive missing from or improperly applied to ALSC	Visual	06003
Major	AQL 0.40 Percent		
103.	Location of ALSC	Gage	06004
104.	Adhesive on mounting surface of cover	Visual	06005
Minor	AQL 1.00 Percent		
201.	Identification plates missing or unidentifiable	Visual	06006
202.	Evidence of poor workmanship (See 3.4)	Visual	06007

4.3.2.7 Destructor, Explosive Assembly: XM24 (After assembly into container and prior to assembling container covers, See Dwg 9269063).-

Categories	Defects	Method of Inspection	Code No.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

Critical: None defined

Major:	100% Inspection		
101.	Destructor booster missing	Visual	08001
102.	Gasket missing	Visual	08002
Major:	AQL 0.40 Percent		
103.	Nuts missing or loose	Visual-Manual	08003

Minor: None defined

4.3.3. Testing

4.3.3.1 Dimensional control of stamped parts.-In place of the normal sampling associated with the Classification of Defects, and with the approval of the Contracting Officer, a sample of at least ten (10) parts may be dimensionally inspected to qualify the tool used in the stamping process for use in production. In addition, a random sample of five (5) parts shall be selected from the last portion of each hour's production for dimensional inspection as a control of the tool during production.

If any defective parts are found during qualification of the tool, the tool producing the defective part shall not be used in production.

If any defective parts are found when inspection is performed for control of the tool, the tool producing the defective part shall be removed from production. Further, that portion of production since the last tool control check shall be returned to the contractor for corrective action.

All tools removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the Contracting Officer to substantiate the request.

4.3.3.2 Radiographic examination of ALSC (See 3.3 and Dwg. 9257393), Major defect, Code No. 07001.-Each ALSC shall be subjected to this test. Any ALSC that fails to comply with the specified requirement shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.1, using equipment in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

4.3.4 Inspection equipment.-Equipment Tabulation (ET) number 9257388 and Equipment Lists (EL's) referenced thereon identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction survey, and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures

4.4.1 Radiographic examination.-The Destructor, Explosive assembly shall be positioned on a fixture as specified on the equipment list. Each assembly shall be identified as to its position on the radiographic and the explosive made. Examinations of the radiographs shall be made for compliance with the applicable requirements and procedures shall be qualified in accordance with MIL-R-11470. This is a non-destructive test. Assemblies so tested may be returned to the lot if acceptable.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 Level A.-The Destructor, Explosive Assembly shall be preserved and packaged in accordance with Dwg. 9269063.

5.2 Packing

5.2.1 Level A.-the Destructor, Explosive Assembly, preserved and packaged as specified in 5.1.1, shall be packed in accordance with Dwg. 9269063.

5.3 Marking.-Marking shall be in accordance with Dwg 9269063 and Code of Federal Regulations, Title 49 Parts 171-179.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

5.4 Shipping.-When components from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167. (See 6.4).
c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor (see 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detail drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design, in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications: Mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army Designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (see 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procurement of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category A, Form 3. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor design.-All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.

design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted or approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-QA-A-S. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

6.4 Submission of test data.-In addition to the normal distribution of records, when the Destructor, Explosive Assembly is procured by the U.S. Army Munitions Command, one (1) copy of all ballistic data and ammunition data cards shall be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-QA-A-S.

6.5 Submission of results of contractor-conducted examinations and tests.-Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-QA-A-S.

Custodian:
Army-MU

Preparing Activity:
Army-MU

Project Number: 1340-A

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:40Z
Check the source to verify that this is the current version before use.