MILITARY SPECIFICATION

FUZE, INERTIAL: XM1103E4

1. SCOPE

1.1 This specification covers the quality assurance provisions for the assembling, testing, and preparation for delivery for one type of inertial fuze used for the safing, arming, and fuzing of the Pershing warhead section. This fuze is designated as Fuze, Inertial: XM1103E4.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-S-60902 - Soldering Electrical Connections for Nuclear Weapons Systems, Procedure for.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

PICATINNY ARSENAL

8858526 - Box, Packing, Ammunition, for Fuze: XM1103.
8881794 - Outline (XM1103E4).
10628481 - Mechanical Assembly.
10628503 - Leakage Test Procedure.
10628527 - XM1103 Fuze Recycling Procedure.
10628538 - Static and Dynamic Accuracy Test Specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

10628539 - Functional Test Specification.
10628540 - Dielectric and Insulation Resistance Check List.
10628541 - Dielectric and Insulation Resistance Check List
10628542 - Preflight Check List, Cover Removed.
10628543 - Wiring Check List.
10628544 - After-Cycling Check List.
10628545 - Preflight Check List.
10628570 - Test Specification for Performing Temperature, Vibration, Humidity, and Shock Portion of MIL-F-50279.
10628571 - Preflight Check List (at 160° ± 10°F.).
10628572 - After-Cycling Check List.
10628573 - Preflight Check List (at -25° ± 10°F.).
10640256 - Continuity Check List.
10640257 - Fuze Cover Assembly, Wiring Check List.
10640258 - Dielectric and Insulation Resistance Check List.

PUBLICATIONS

PICATINNY ARSENAL

ET-8881794 - Inspection Equipment Tabulation.
QAI-PA-1 - Quality Assurance Instructions for Reporting Data on Serialized Items.

Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.

3. REQUIREMENTS

3.1 Materials and components. - Materials shall conform to applicable specifications and drawings. Each component shall conform to all dimensions and tests specified on the component drawing. The contractor shall have available verifiable proof (i.e., objective evidence. See 6.2) that materials and components were fabricated, inspected, and tested under controllable conditions as set forth in the contractor's quality control or inspection procedures.

3.2 Assembly. - The inertial fuze shall comply with all requirements specified on drawings (dwg.) 8881794 and 10628481, with all requirements specified herein, and with the requirements of applicable specifications to the extent specified on the drawings and herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

3.3 First article testing. - Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2.1).

3.4 Continuity and circuit resistance. - The continuity and circuit resistance of the inertial fuze shall be as specified on the drawings referenced in 4.4.1. In addition, the circuit resistance values specified in Table I, II, III, and IV shall be recorded on punch cards (See 3.11). Testing shall be as specified in 4.4.1.

TABLE I

PREFLIGHT CHECK LIST (see dwg. 10628545)

Check No.	Limits (ohms)	Test Identification Number (see 3.11)
1	10.4 - 14.6	030001
2	4.1 - 5.9	030002
3	53.4 - 74.6	030003
4	53.4 - 74.6	030004
5	53.4 - 74.6	030005
6	53.4 - 74.6	030006
7	53.4 - 74.6	030007
8	53.4 - 74.6	030008
9	53.4 - 74.6	030009
10	53.4 - 74.6	030010
11	275 - 385	030011
12	275 - 385	030012
13	275 - 385	030013
14	275 - 385	030014
15	15 - 50	030015
17	15 - 50	030016
19	2.44- 3.06	030017
20	21.4 - 30.0	030018
21	10.0 - 14.0	030019
22	10.0 - 14.0	030020
23	10.0 - 14.0	030021
24	10.0 - 14.0	030022
25	10.0 - 14.0	030023
26	10.0 - 14.0	030024
27	10.0 - 14.0	030025
28	10.0 - 14.0	030026
29	10.0 - 14.0	030027
30	10.0 - 14.0	030028
31	10.0 - 14.0	030029
32	10.0 - 14.0	030030
33	10.0 - 14.0	030031
34	10.0 - 14.0	030032
35	10.0 - 14.0	030033
36	10.0 - 14.0	030034

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

Check No.	Limits (ohms)	Test Identification Number (see 3.11)
42	1.32 ohms max.	030035
43	92 - 130	030036
44	92 - 130	030037

TABLE II

CONTINUITY CHECK LIST (see dwg. 10640256)

Check No.	Limits (ohms)	Test Identification Number (see 3.11)
324	6.3 - 7.9	030038
325	6.3 - 7.9	030039
326	6.3 - 7.9	030040
328	6.3 - 7.9	030041
329	89 - 111	030042
330	6.3 - 7.9	030043
332	6.3 - 7.9	030044
333	6.3 - 7.9	030046
335	6.3 - 7.9	030045
337	89 - 111	030047
341	8.9k - 11.1k	030048

TABLE III

AFTER-CYCLING CHECK LIST (see dwg. 10628544)

Check No.	Limits (ohms)	Test Identification Number (see 3.11)
17	5.1 - 7.3	030049
35	5.1 - 7.3	030050

TABLE IV

PREFLIGHT CHECK LIST (COVER REMOVED) (see dwg. 10628542)

Check No.	Limits (ohms)	Test Identification Number (see 3.11)
16	21.4 - 30.0	030051

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

Check No.	Limits (ohms)	Test Identification Number (see 3.11)
18	1.33 - 1.87	030052
36	9.1 - 12.9	030053
38	1.22 ohms max.	030054
62	2.44 - 3.06	030055
77	21.4 - 30.0	030056
79	1.33 - 1.87	030057
93	9.1 - 12.9	030058
120	2.44 - 3.06	030059

3.5 Dielectric strength and insulation resistance. - The inertial fuze shall withstand the dielectric strength test without arcing, flashover, breakdown of insulation, or evidence of damage. The insulation resistance shall be not less than 10 megohms. Testing shall be as specified in 4.4.2.

3.6 Setting-line test. - The inertial fuze shall comply with the requirements of the setting-line test specified on dwg. 10628538. Testing shall be as specified in 4.4.3.

3.7 Dynamic tests and recycling procedure. - The inertial fuze shall comply with the dynamic test requirements specified on dwg. 10628570 or 10628538 as applicable. After this test, the fuze shall comply with the requirements of the recycling procedure specified on dwg. 10628527. Testing shall be as specified in 4.4.4.

3.8 Static tests and recycling procedure. - The inertial fuze shall comply with the static test requirements specified on dwg. 10628538. In addition, the values specified in Table V shall be recorded on punch cards (see 3.11). After this test, the fuze shall comply with the requirements of the recycling procedure specified in dwg. 10628527. Testing shall be as specified in 4.4.5.

TABLE V

STATIC TEST LIMITS (see dwg. 10628538)

Switch No.	Limits* (seconds)	Test Identification Number (see 3.11)
S13 A	48 - 54	090001
S13 B	48 - 54	090002
S23 A	54 - 60	090003
S23 B	54 - 60	090004
S20 A	335 - 345	090005
S20 B	335 - 345	090006

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

Switch No.	Limits*	Test Identification Number (see 3.11)
	(meters of decrement)	
S6 A	355 - 505	90007
S6 B	355 - 505	090008
S8 A	750 - 900	090009
S8 B	750 - 900	090010
S7 A	1275 - 1425	090011
S7 B	1275 - 1425	090012
S30 A	1925 - 2075	090013
S30 B	1925 - 2075	090014
	(meters/second)	
S10 A	546 - 554	090015
S10 B	546 - 554	090016

*After launch signal is received.

3.9 Functional test and recycling procedure. - The inertial fuze shall comply with the requirements of dwg. 10628539. After this test, the fuze shall comply with the requirements of the recycling procedure specified on dwg. 10628527. Testing shall be as specified in 4.4.6.

3.10 Leakage. - The leakage rate of the inertial fuze, as measured by the drop in its internal pressure, shall not exceed 0.25 in. Hg per hour. Testing shall be as specified in 4.4.8.

3.11 Serialization. - A six-letter serial code shall be assigned to each serialized production item. The cognizant inspection agency shall obtain these serial codes by means of a letter addressed to: Commanding Officer, Picatinny Arsenal, Dover, New Jersey, Attention: SMUPA-NR2. The letter of request shall include: (a) exact nomenclature of the item as specified on the applicable drawing; (b) name of the contractor, (c) contract number or procurement request order number; (d) number of serial codes required (unused codes must be returned), and (e) security classification of the number of serial codes requested only if this number reveals classified production quantities. In addition to the normal inspection records, the contractor shall provide data feedback on punch cards in conformance with Quality Assurance Instruction QAI-PA-1. The data required to be coded, and the test identification numbers, are specified in the applicable paragraphs in this section.

3.12 Soldering. - All soldering shall be in accordance with MIL-S-60902.

3.13 Workmanship. - All parts and accessories shall be constructed, assembled, and finished in a thoroughly workmanlike manner. Particular attention shall be given to neatness, marking, cleaning, and freedom of the parts from burrs and sharp edges which may affect performance or result in injury during handling. All parts shall be free of chips, dirt, grease, rust, and other foreign material. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agents.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

4.2 First article inspection.

4.2.1 Submission. - When the contract requires first article inspection, the contractor shall submit three consecutively produced inertial fuzes to the testing facility designated in the invitation for bids or request for proposal.

4.2.2 Inspection and testing to be performed. - The first article inspection samples shall be inspected for the defects specified in 4.3.2.1, using inspection methods contained therein, and for all requirements of Section 3 (also see Table VI) using the test methods specified in 4.4. The inertial fuzes shall be tested in the order specified in Table VI. If any inertial fuze fails to comply with the applicable requirements, the first article samples shall be rejected.

TABLE VI

Test	Requirement Paragraph
1. Continuity and circuit resistance	3.4
2. Dielectric strength and insulation resistance	3.5
3. Setting-line test	3.6
4. Dynamic tests and recycling procedure	3.7
5. Static tests and recycling procedure	3.8
6. Functional test and recycling procedure	3.9
7. Weight	4.4.7
8. Leakage	3.10

4.2.3 Inspection equipment. - The inspection and testing specified in 4.2.2 shall be accomplished with the use of the approved gages and test equipment specified in 4.3.4.

4.3 Product acceptance inspection.

4.3.1 Inspection lot. - A lot or batch and its formation, size, and presentation is described in MIL-STD-105, Section 5. Accordingly, a lot shall mean an inspection lot and a batch shall mean an inspection batch for the purposes of this specification. The manner in which each inspection lot or batch is to be

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

presented and identified by the contractor, shall be designated or approved by the Government representative.

4.3.2 Product inspection examination. - A sample shall be selected at random from each inspection lot in accordance with the major defect or the minor defect table as applicable (see Table VII). Any defect found in the sample, selected for the major or minor classification, shall reject the lot. Critical defects shall require 100 percent inspection of all items in the inspection lot. If any critical defect is found in an item, the item shall be removed from the lot. The sequence of inspections for the classification of defects need not be followed so long as all the defect inspections are performed.

TABLE VII

Major Defect Table		Minor Defect Table	
Lot Size	Sample Size	Lot Size	Sample Size
1 - 25	100% Inspection	1 - 25	100% Inspection
26 - 30	25	26 - 30	25
31 - 35	27	31 - 35	26
36 - 40	30	36 - 40	27
41 - 45	32	41 - 45	28
46 - 50	34	46 - 50	29
51 - 55	35	51 - 55	30
56 - 60	37	56 - 60	31
61 - 65	38	61 - 65	32
66 - 70	39	66 - 70	33
71 - 75	40	71 - 75	34
76 - 85	42	76 - 85	35
86 - 95	43	86 - 95	36
96 - 110	44	96 - 110	37
111 - 130	46	111 - 130	38
131 - 156	48	131 - 156	39

4.3.2.1 Classification of defects. - Critical, major, and minor defects are defined in MIL-STD-105.

4.3.2.1.1 Plate, Base (see dwg. 10640081).

Categories	Defects	Method of Inspection
Critical:	None defined.	
Major:		
101.	Diameter of "J" mounting hole near curved edge of plate, min. (12 holes)	Gage
102.	Location of "J" mounting hole near curved edge of plate (12 holes)	Gage

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection
103.	Location of "P" mounting hole near curved edge of plate (4 holes)	Gage
104.	Pitch diameter of "P" mounting hole near curved edge of plate, max. (4 holes)	Gage
105.	Minor diameter of "P" mounting hole near curved edge of plate, max. (4 holes)	Gage
Minor:		
201.	Thickness, min	Gage
202.	Parallelism of top and bottom surface	Gage
203.	Flatness of top and bottom surface	Gage
204.	Plate damaged or improper	Visual
205.	Marking missing, improper, or illegible	Visual
206.	Protective finish missing or improper	Visual
207.	Evidence of poor workmanship (see 3.13)	Visual

4.3.2.1.2 Adapter (see dwg. 10626195 and 10626196).

Categories	Defects	Method of Inspection
Critical:	None defined.	
Major:		
101.	Diameter of "H" and "J" holes, min. (8 holes total)	Gage
102.	Pitch diameter of "K" hole, max. (6 holes)	Gage
103.	Minor diameter of "K" hole, max. (6 holes)	Gage
104.	Location of "H," "J," and "K" holes(14 holes total)	Gage
Minor:		
201.	Counterbore of "J" hole missing or improper (2 holes)	Visual
202.	Marking missing, improper, or illegible	Visual
203.	Protective finish missing or improper	Visual
204.	Evidence of poor workmanship (see 3.13)	Visual

4.3.2.1.3 Bracket (see dwg. 10626192, 10626193, 10628563, 10628564, 10640154, 10640219, 10640274, and 10640275).

Categories	Defects	Method of Inspection
Critical:	None defined.	
Major:	None defined.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection
Minor:		
	201. Bracket configuration improper.....	.....Visual
	202. Marking missing, improper, or illegible.....	.....Visual
	203. Protective finish missing or improper.....	.....Visual
	204. Evidence of poor workmanship (see 3.13).....	.....Visual

4.3.2.1.4 Cover (see dwg. 10628525).

Categories	Defects	Method of Inspection
Critical: None defined.		
Major: None defined.		
Minor:		
	201. Welding incomplete or improper.....	.....Visual
	202. Marking missing, improper, or illegible.....	.....Visual
	203. Protective finish missing or improper.....	.....Visual
	204. Evidence of poor workmanship (see 3.13).....	.....Visual

4.3.2.1.5 Mechanical Assembly (see dwg. 10628481).

Categories	Defects	Method of Inspection
Critical: None defined		
Major:		
	101. Evidence of component missing, damaged, or loose.....	.....Visual/Manual
	102. Depth of sockets in connectors (see 6.4.2).....	.....Visual
Minor:		
	201. Improper soldering (see 3.12).....	.....Visual
	202. Insulation damaged on wires or cables.....	.....Visual
	203. Evidence of poor workmanship (see 3.13).	.....Visual

4.3.2.1.6 Outline (XM1103E4) (see dwg. 8881794).

Categories	Defects	Method of Inspection
Critical: None defined.		
Major:		
	101. Component missing, damaged, or improperly assembled.....	.....Visual/Manual
	102. Height of pins in connector (see 6.4.1).....	.....Visual
	103. Depth of sockets in connector (see 6.4.2).....	.....Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection
Minor:		
201.	Scratch on protective finish exposing base metal	Visual
202.	Marking missing, improper, or illegible	Visual
203.	Evidence of poor workmanship (see 3.13)	Visual

4.3.2.1.7 Box, Packing, Ammunition(prior to closing carton and sealing barrier bag) (see dwg. 8858526).

Categories	Defects	Method of Inspection
Critical:	None defined.	
Major:		
101.	Any packing component missing	Visual
102.	Desiccant bag missing	Visual
Minor:		
201.	Evidence of poor workmanship (see 3.13)	Visual

4.3.2.1.8 Box, Packing, Ammunition (prior to closing cover) (see dwg. 8858526).

Categories	Defects	Method of Inspection
Critical:	None defined.	
Major:		
101.	Barrier bag torn, punctured, or incompletely sealed (including evidence that air from bag was not evacuated sufficiently)	Visual/Manual
102.	Any packing component missing or damaged	Visual
Minor:		
201.	Marking on carton missing, improper, or illegible	Visual
202.	Evidence of poor workmanship (see 3.13)	Visual

4.3.2.1.9 Box, Packing, Ammunition (see dwg. 8858526).

Categories	Defects	Method of Inspection
Critical:	None defined.	
Major:		
101.	Packing box damaged	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection
Major:		
	102. Strapping missing, improperly located, or loose	Visual
Minor:		
	201. Marking missing, improper, or unidentifiable	Visual
	202. Exterior color improper or incomplete	Visual
	203. Evidence of poor workmanship (see 3.13)	Visual

4.3.3 Inspection testing. - The contractor shall perform all of the tests specified in this paragraph. The tests shall be performed in the following sequence:

	Test	Test Classification
(a)	Continuity and circuit resistance	Major
(b)	Dielectric strength and insulation resistance	Major
(c)	Setting-line test	Major
(d)	Dynamic tests and recycling procedure	Critical
(e)	Static tests and recycling procedure	Major
(f)	Functional test and recycling procedure	Major
(g)	Weight	Minor
(h)	Leakage	Minor

None of these tests is considered destructive, and samples so tested shall be returned to the lot.

4.3.3.1 Continuity and circuit resistance (see 3.4), dielectric strength and insulation resistance (see 3.5), setting-line test (see 3.6), dynamic tests and recycling procedure (see 3.7), static tests and recycling procedure (see 3.8), functional test and recycling procedure (see 3.9), weight (see dwg. 8881794), and leakage (see 3.10). - Each inertial fuze shall be subjected to these tests (see applicable paragraph in 4.4). If any fuze fails to comply with the applicable requirements, it shall be classified defective and be removed from the lot.

4.3.4 Acceptance inspection equipment.

4.3.4.1 Critical and major defects and tests. - Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions as specified on the Equipment Lists (EL). ELs are listed on Equipment Tabulation, ET-8881794. When either of the following conditions exists, the contractor shall design required equipment or specify suitable commercial equipment: (a) If any deviation from equipment or procedures, as specified on the EL, is desired (b) The code "CD" is listed in the "Part or Identifying Number" column on the EL. The contractor shall obtain approval

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

of such designs, operating instructions, and special calibration instructions prior to use on the contract (see 6.3).

4.3.4.2 Minor defects and tests. - Acceptance inspection equipment for minor defects is not specified on ELs. The acceptance inspection equipment, operating instructions, and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

4.4 Test methods and procedures. - The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used. Unless otherwise specified, the tests shall be conducted at room temperature (80° ± 20°F.).

4.4.1 Continuity and circuit resistance. - The inertial fuze shall comply with the requirements of 3.4 during these tests:

4.4.1.1 Test conducted at room temperature (80° ± 20°F.):

4.4.1.1.1 Wiring check of fuze (cover removed). - The wiring of the inertial fuze (with the cover and cable assembly removed) shall be tested in accordance with the Wiring Check List, dwg. 10628543.

4.4.1.1.2 Preflight check of fuze (cover removed). - The inertial fuze (with the cover and cable assembly removed) shall be tested to ensure that it is in the "zero" position. Testing shall be in accordance with the Preflight Check List (Cover Removed), dwg. 10628542.

4.4.1.1.3 After-cycling check of fuze (cover removed). - The inertial fuze (with the cover and cable assembly removed) shall be tested to ensure that it has functioned correctly during cycling. Testing shall be in accordance with the After-Cycling Check List, dwg. 10628544.

4.4.1.1.4 Wiring check of fuze cover (prior to bonding terminal boards). - The wiring of the inertial fuze cover and cable assembly (prior to bonding terminal boards) shall be tested in accordance with Fuze Cover Assembly Wiring Check List, dwg. 10640257.

4.4.1.1.5 Wiring check of fuze cover (after bonding terminal boards). - The wiring of the inertial fuze cover and cable assembly (after bonding terminal boards) shall be tested in accordance with Continuity Check List, dwg. 10640256.

4.4.1.1.6 Preflight check of fuze. - The inertial fuze shall be tested to ensure that it is in the "zero" position and that there is good connection between the fuze and the cover and cable assembly. Testing shall be in accordance with Preflight Check List, dwg. 10628545.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

4.4.1.2 Tests conducted at environmental temperature extremes:

4.4.1.2.1 After-Cycling check of fuze. - The inertial fuze shall be tested to ensure that it has functioned correctly during cycling at environmental test temperatures. Testing shall be in accordance with the After-Cycling Check List, dwg. 10628572.

4.4.1.2.2 Preflight check of fuze. - The inertial fuze shall be tested to ensure that it is the "zero" position and that there is good connection between the fuze and the cover and cable assembly. Testing shall be in accordance with the Preflight Check List, dwg. 10628571 or 10628573, as applicable.

4.4.2 Dielectric strength and insulation resistance. - The dielectric strength and insulation resistance of the wiring of the following assemblies shall be tested in accordance with the applicable drawings listed:

(a) Inertial fuze (cover removed) - Test in accordance with dwg. 10628541.
(b) Cover and cable assembly - Test in accordance with dwg. 10640258.
(c) Inertial fuze (with cover assembled) - Test in accordance with dwg. 10628540.

The above items shall comply with the requirements of 3.5 during this test.

4.4.3 Setting-line test. - The setting lines of the inertial fuze shall be checked by testing in accordance with the Static and Dynamic Accuracy Test Specification, dwg. 10628538, and the fuze shall comply with the requirements of this drawing during this test.

4.4.4 Dynamic tests and recycling procedure. - The inertial fuze shall be subjected to the dynamic tests in accordance with the following drawings, as applicable:

(a) Initial production testing (see 4.2.2) - Test in accordance with dwg. 10628570 (includes temperature, vibration, humidity, and shock).
(b) Inspection testing (see 4.3.3) - Test in accordance with dwg. 10628538.

The fuze shall be recycled in accordance with the procedure specified on dwg. 10628527. During these tests, the fuze shall comply with the requirements of the applicable test drawings, and during environmental tests, the fuze shall be stabilized at each temperature (see 6.5).

4.4.5 Static tests and recycling procedure. - The inertial fuze shall be subjected to the static tests in accordance with the Static and Dynamic Accuracy Test Specification, dwg. 10628538. The fuze shall comply with the requirements of 3.8 during this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

4.4.6 Functional test and recycling procedure. - The inertial fuze shall be tested to ensure that the fuze switches operate correctly and in their proper sequence. Testing shall be in accordance with the Functional Test Specification, dwg. 10628539, and the fuze shall comply with the requirements of 3.9 during this test.

4.4.7 Weight. - The inertial fuze shall be weighed on a Government-approved weighing device with an accuracy of ± 0.1 pound. The fuze shall comply with the weight requirement specified on dwg. 8881794.

4.4.8 Leakage. - The inertial fuze shall be pressure tested to ensure that it is adequately sealed. Testing shall be in accordance with the Leakage Test Procedure, dwg. 10628503, and the fuze shall comply with the requirements of this drawing during this test.

5. PREPARATION FOR DELIVERY

5.1 Preservation, packaging, and packing. - Preservation, packaging, and packing shall be in accordance with dwg. 8858526.

5.2 Marking. - Marking shall be in accordance with dwg. 8858526.

6. NOTES

6.1 Ordering data. - Procurement documents should specify the title, number, and date of this specification.

6.2 Objective evidence. - Records of the contractor's quality control and inspections which can be verified.

6.3 Acceptance inspection equipment. - The contractor shall obtain approval of equipment designs, operating instructions, and calibration instructions from Commanding Officer, Picatinny Arsenal, Dover, New Jersey 07801, Attention: SMUPA-NR4.

6.4 Inspection of connectors.

6.4.1 Height of pins. - In the event a pin does not appear to be the same relative height of adjacent pins, a gage shall be used to determine the variation from normal height. Reject any connector that has a pin that varies by more than 0.032 inch maximum from the normal pin height of the individual connector. The normal height of the individual connector pins shall be determined by calculating the average height from measurements taken of pins adjacent to the pin that appears to be defective. The forward metal edge of the connector shall be utilized as the reference surface for all measurements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

6.4.2 Depth of sockets. - In the event a socket does not appear to be the same relative depth of adjacent sockets, a gage shall be used to determine the variation from normal depth. Reject any connector that has a socket that varies by more than 0.032 inch maximum from the normal socket depth of the individual connector. The normal depth of the individual connector sockets shall be determined by calculating the average depth from measurements taken of sockets adjacent to the socket that appears to be defective. The forward metal edge of the connector shall be utilized as the reference surface for all measurements.

6.5 Temperature stabilization. - The temperature of a fuze is considered stabilized when three consecutive temperature readings, taken at 5-minutes intervals, shall not vary by more than 1°F. for each thermocouple. In addition, if two thermocouples are required, the readings of these thermocouples shall be within 2°F. of each other during this 10-minute interval.

6.6 Supersession data. - This specification includes the requirements of Purchase Description ABMA-PD-F-971 (Rev. 3) dated 11 August 1965.

Custodian:
Army-MU

Preparing Activity:
Army-MU

Project No.:
1135-A120

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

MIL-F-50279(MU) Fuze, Inertial: XM1103E4

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426 REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

OFFICIAL BUSINESS

Commanding Officer
Picatinny Arsenal
ATTN: SMUPA-NR
Dover, New Jersey 07801

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.