MILITARY SPECIFICATION

RECEIVER GROUP, SIMULATED RADIAC, OR-114( )/T

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. - This specification covers the Receiver Group, Simulated Radiac, OR-114/T. The OR-114/T consists of six Receiver, Simulated Radiac (R-1855/T), six local antennae, six remote antennae, and other miscellaneous cables and support components housed in Case, Simulated Receiver (CY-7350/T).

2. APPLICABLE DOCUMENTS

2.1 Documents. - The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of the specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

PPP-B-585	Box, Wood, Wirebound
PPP-B-601	Box, Wood, Cleated-Plywood
PPP-B-621	Box, Wood, Nailed and Lock-Corner
PPP-B-636	Box, Fiberboard
PPP-F-320	Fiberboard, Corrugated and one Solid, Sheet Stock Container Grade and Cut Shapes
PPP-T-76	Tape, Pressure-Sensitive Adhesive Paper, Water Resistant, for Carton Sealing
QQ-S-781	Steel Strapping Flat

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-P-116	Preservation, Methods of
MIL-C-3098	Crystal Unit, Quartz
MIL-P-11268	Parts, Materials and Processes Used in Electronic Communication Equipment
MIL-M-13231	Marking of Electronic Items

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection BY Attributes
MIL-STD-129	Marking for Shipment and Storage
MIL-STD-252	Wired Equipment, Classification of Visual and Mechanical Defects
MIL-STD-454	Standard General Requirements for Electronic Equipment
MIL-STD-461	Electromagnetic Interference Characteristics Requirements for Equipment
MIL-STD-462	Electromagnetic Interference Characteristics, Measurement of
MIL-STD-810	Environmental Test Methods

DRAWINGS

ELECTRONICS COMMAND

DLSM-B-748237	Receiver Group, Simulated Radiac OR-114/T
SM-A-678030	Burn-In Procedure for Receiver, Simulated Radiac R-1855( )/T

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 First Article. - When specified in the contract or purchase order, the contractor shall furnish first article units in accordance with 4.3.

3.2 Construction. - The OR-114/T equipment shall be constructed in accordance with the requirements of this specification, and of drawing DLSM-B-748237.

3.3 Parts, Materials and Processes. - In addition to any requirements of this specification covering parts, materials and processes, such items shall conform to MIL-P-11268, including the selection requirements therein.

3.4 Marking. -

3.4.1 General. - Marking shall conform to MIL-M-13231.

3.4.2 Serial Numbers. - Each equipment shall bear a serial number in accordance with the requirements of MIL-M-13231.

3.5 Interchangeability. - Like units, assemblies, subassemblies and replaceable parts shall conform to requirement 7 of MIL-STD-454. (See 4.6)

3.6 Performance Characteristics. -

3.6.1 Receiver, Simulated Radiac R-1855/T. -

3.6.1.1 Operating Frequency. - The operating frequency shall be within 138 to 144 MHz and shall be crystal controlled. Satisfactory operation shall be insured over the entire band utilizing available Military Standard (MS) crystals selected from MIL-C-3098/60. (See 4.10.1.1)

3.6.1.2 Sensitivity. - When operated with a continuous wave (CW) signal generator at the center frequency of the receiver, the receiver readings shall have the following correspondence to the signal generator power output. (See 4.10.1.2)

Signal Generator Power (dBm)	Receiver Readings (RADS)
-72	400 to 500
-89	200 to 250
-94	90 to 110
-97	45 to 55
-104	8 to 12

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

3.6.1.2.1 Minimum Indication. - When operated as in 3.6.1.2 a one RAD reading shall be obtained on the receiver for a signal generator output of between -116 dBm and -118 dBm. (See 4.10.1.2)

3.6.1.3 Weight. - The weight of the receiver without batteries shall not exceed 6 pounds. (See 4.8.1)

3.6.1.4 Battery Life. - The receiver shall be capable of operation for 12 hours at 0°F without changing batteries. The data at 0°F shall be within ± 30% of the pre-environmental data. (See 4.9)

3.6.2 Case, Simulated Receiver CY-7350/T. -

3.6.2.1 Weight. - When fully loaded with all antennae and miscellaneous components and six receivers (i.e., a complete Receiver Group OR-114/T as per DLSM-B-748237) the case shall not exceed 105 pounds. (See 4.8.2)

3.7 Environmental. - The Receiver, Simulated Radiac R-1855/T shall meet the performance requirements specified below under any combinations of these service conditions.

3.7.1 Temperature. -

3.7.1.1 Low Temperature. - The receiver shall be subjected to the low temperature extremes of 0 ± 2.5°F operating and -60 ± 2.5°F storage and shall meet the requirements of 3.6.1.2 when tested in accordance with 4.12.3.1.

3.7.1.2 High Temperature. - The receiver shall be subjected to the high temperature extremes of 125 ± 2.5°F operating and 160 ± 2.5°F storage and shall meet the requirements of 3.6.1.2 when tested in accordance with 4.12.3.2.

3.7.2 Electromagnetic Interference (EMI) Characteristics. - The receiver shall meet the requirements of MIL-STD-461, for Methods CE06, RE02 and RS03 except as modified in Table 1: (See 4.12.5)

Table 1 Deviation from MIL-STD-461. -

CE06		RE02	RS03
Narrowband: Broadband:	30 dBuV 30 dBuV/MHz	Narrowband fo: Max. Dev. 30 dBuV/M Other Freq: Max. Dev. 15 dBuV/M Broadband: All Freq: 15 dBuV/M/MHz	1 Volt/Meter .01V/M

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

NOTE: Any deviation listed for Methods CE06 and RE02 is added to the specified limit delineated in MIL-STD-461. Method RS03 is acceptable at a minimum threshold level of .01 volts per meter.

3.7.3 Altitude (Elevation). - The receiver shall meet the performance requirements of 3.6.1.2 before, during and after testing as specified in 4.12.1.

3.7.4 Vibration. - The receiver shall meet the performance requirements of 3.6.1.2 both before and after testing as specified in 4.12.4.

3.7.5 Leakage (immersion). -

3.7.5.1 Immersion, receiver. - The receiver shall show no evidence of leakage after being tested as specified in 4.12.2.1.

3.7.5.2 Immersion, case. - The case shall show no evidence of leakage after being tested as specified in 4.12.2.2.

3.7.6 Dust. - After testing as specified in 4.12.6 the receiver shall meet the performance requirements of 3.6.1.2.

3.7.7 Humidity. - During and after testing as specified in 4.12.7 the receiver shall meet the performance requirements of 3.6.1.2.

3.7.8 Salt fog. -After testing as specified in 4.12.8 the receiver shall meet the performance requirements of 3.6.1.2.

3.7.9 Fungus. - Upon completion of the test, there shall be no deterioration, corrosion or change in configuration that will prevent the maintenance or operation of the receiver. (See 4.12.9)

3.7.10 Shock, Drop. - After testing as specified in 4.12.10 the receiver shall meet the performance requirements of 3.6.1.2.

3.8 Burn-in. - Each receiver shall be capable of meeting the performance requirements specified herein after being subjected to the specified burn-in cycle of 4.11.

3.9 Workmanship. - The Receiver Group, Simulated Radiac OR-114/T shall be manufactured and assembled in accordance with requirement 9 of MIL-STD-454.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection. - Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the contractor may utilize his own facilities, facilities of a subcontractor or any commercial laboratory acceptable to the government. The government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that the supplies and services conform to prescribed requirements.

4.2 Classification of Inspections. - Inspections shall be classified as follows:

a. First article inspection. (Does not include preparation for delivery) (See 4.3)

b. Inspections covered by subsidiary documents. (See 4.4)

c. Quality conformance inspections.

(1) Quality conformance inspection of equipment before preparation for delivery. (See 4.5)

(2) Quality conformance inspection of preparation for delivery. (See 4.7)

4.3 First Article. - Unless otherwise specified in the contract or purchase order, the first article inspection shall be performed by the contractor.

4.3.1 First Article Units. - The contractor shall furnish the number of first article units in accordance with the following:

a. Four (4) each Receiver, Simulated Radiac R-1855/T.

b. One (1) each Case, Simulated Receiver CY-7350/T.

4.3.2 First Article Inspection. - The first article inspection shall consist of the inspection specified in Table II, and shall be performed in the order specified therein.

4.3.3 First Article Data. - The first article test plant and test report(s) shall be as required in the contract or purchase order.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

Table II First Article Inspection. -

Inspection	Reqt Para	Test Para	Unit 1	Unit 2	Unit 3	Unit 4
1. Inspections covered by subsidiary documents	3.3	4.4	Inspections to be performed on all units			
2. Burn-In	3.8	4.11	Inspections to be performed on all units			
3. Group A inspection	See Table III		Inspections to be performed on all units			
4. Group B inspection	See Table IV		Inspections to be performed on all units			
5. EMI	3.7.2	4.12.5	1			
6. Environmental						
Low Temperature	3.7.1.1	4.12.3.1		1		
High Temperature	3.7.1.2	4.12.3.2		2		
Altitude	3.7.3	4.12.1		3		
Vibration	3.7.4	4.12.4				4
Immersion	3.7.5	4.12.2				2
Dust	3.7.6	4.12.6			1	
Humidity	3.7.7	4.12.7			2	
Salt fog	3.7.8	4.12.8				3
Fungus	3.7.9	4.12.9			3	
Shock Drop	3.7.10	4.12.10	2			

NOTES:

1. The inspections 1 to 4, in the order shown, shall be performed on all first article units before subjecting these units to any other inspection requirements specified in the table.

2. The implementation of inspections 5 and 6 shall be expedited to satisfy contract delivery requirements.

3. The numbers in the unit columns in the table covered by 5 and 6 specify the order of inspections for the indicated unit.

4.4 Inspections covered by subsidiary documents. - The following shall be inspected under the applicable subsidiary documents as part of the inspection required by this specification, and the inspection requirement specified in the contract or purchase order.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

Item	Where required
Parts, Materials and processes-general	3.3
Marking	3.4
Workmanship	3.9

4.5 Quality conformance inspection of equipment before preparation for delivery.- The contractor shall perform the inspections specified in 4.4, 4.5.1 through 4.5.4 and 4.11. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements.

4.5.1 Group A inspection. - Each unit on contract or purchase order shall be inspected for conformance to the inspections specified in Table III. Discrete lots shall be formed from units that passed this inspection. Factors of lot composition not defined herein, or in the contract or purchase order, shall be in accordance with MIL-STD-105. Each lot shall be subject to sampling inspection, utilizing the procedures of MIL-STD-105, using the general inspection levels, and AQL's indicated in Table III.

4.5.1.1 Order of inspection within Group A. - Group A inspection shall be performed in the order listed in Table III.

Table III Group A inspection. -

Inspection	Requirement Paragraph	Test Para	AQL Major	AQL Minor
Visual & Mechanical	3.9	4.13 -	2.5%	4.0%
Electrical				
Operating Frequency	3.6.1.1	4.10.1.1	2.5%	**
Sensitivity	3.6.1.2	4.10.1.2	for the group	**

**All electrical defects are major.

4.5.2 Group B inspection. - Group B inspection shall be performed in inspection lots that have passed Group A inspection and on samples selected from units that have been subject to and met the Group A inspection. This inspection shall conform to Table IV and to the special levels of the Table I of MIL-STD-105.

4.5.2.1 Group B sampling plans. - The Group B sample plans, for the AQL's listed in Table IV, shall be as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

AQL	Inspection level
4.0 percent	S-4
6.5 percent	S-4

4.5.2.2 Order of inspection within Group B. - Group B inspection shall be performed in the order listed in Table IV.

Table IV Group B inspection. -

Inspection	Requirement Paragraph	Test Para	AQL
Interchangeability	3.5	4.6	4.0%
Weight-Receiver	3.6.1.3	4.8.1	4.0%
Electrical			
Battery life	3.6.1.4	4.9	4.0%
Weight-Case	3.6.2.1	4.8.2	4.0%
Immersion, case	3.7.5.2	4.12.2.2	4.0%

4.5.3 Group C inspection. - Group C inspection shall be performed on units that have passed Group A and Group B inspection. The inspection shall consist of the inspections specified in Table V. Samples shall be selected in accordance with 4.5.3.1.

Table V Group C inspection. -

Inspection	Requirement Paragraph	Test Paragraph
Subgroup 1		
Altitude	3.7.3	4.12.1
Dust	3.7.6	4.12.6
Subgroup 2		
Vibration	3.7.4	4.12.4
Fungus *	3.7.9	4.12.9
Subgroup 3		
Low temperature	3.7.1.1	4.12.3.1
High temperature	3.7.1.2	4.12.3.2
Leakage (immersion)	3.7.5	4.12.2
Shock (drop)	3.7.10	4.12.10

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

Table V Group C inspection. - (cont.)

Inspection	Requirement Paragraph	Test Paragraph
Subgroup 4 Humidity	3.7.7	4.12.7
Subgroup 5 Salt fog*	3.7.8	4.12.8
Subgroup 6 EMI	3.7.2	4.12.5

*The Receiver R-1855 shall be thoroughly washed, cleaned, dried and refurbished after this inspection before proceeding with subsequent inspection.

4.5.3.1 Sampling for Group C inspection. -

4.5.3.1.1 Six samples of the complete receivers shall be selected at random, one sample for each Subgroup 1 through Subgroup 6 in Table V from every (production rate basis) or fraction thereof produced. The samples shall be selected at the start of the contract from the first quality conformance inspection lot. These samples shall constitute the Group C requirement for first twenty units produced. Subgroup 6 EMI and Subgroup 2 Fungus inspections shall be performed only on first production lot.

4.5.3.2 Order of inspection within Group C. - Group C inspections shall be performed in the order specified in Table V.

4.5.3.3 Group C failures. - Actions required relative to Group C failures shall be as specified in the contract or purchase order.

4.5.3.4 Reinspection of conforming Group C sample units. - Unless otherwise specified, sample units which have been subjected to and passed Group C inspection may be accepted on the contract provided all damage is repaired and the sample units are re-subjected to and pass Group B and Group A inspection in that order.

4.6 Inspection for dimensional interchangeability. - The dimensions listed below shall be gaged or measured to determine conformance to the physical interchangeability requirement of 3.5. When a listed dimension is not within specified or design limits, it shall be considered a major defect.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

a. External and internal dimensions of cases, covers, and insertable assemblies, when such dimensions affect mating of parts.

b. Dimensions of cavities, when such dimensions affect insertion of items.

c. Location of hinges and fasteners on separable parts or assemblies which must mate, such as cases, covers, and mountings.

d. Location of connectors, locking pins, fasteners, slides, and mountings.

e. Size and form of special threads.

4.7 Quality conformance inspection of preparation for delivery. - Preparation for delivery shall be inspected in accordance with MIL-P-116 to determine conformance to the requirements of section 5.

4.8 Weight. -

4.8.1 Weight, Receiver R-1855/T. - Using a calibrated scale, the receiver shall meet the requirement of 3.6.1.3.

4.8.2 Weight, Case CY-7350/T. - Using a calibrated scale, the fully loaded case shall meet the requirements of 3.6.2.1.

4.9 Battery Life Test. - Insert batteries in the Receiver R-1855/T and conduct the test of 4.10.1.2 as pre-environmental data. Place the receiver in the test chamber and stabilize it to 0 ± 2.5°F. Perform the test of 4.10.1.2. Operate the receiver at 200 RAD's for 12 hours. At the conclusion of the 12 hour period perform the test of 4.10.1.2. (See 3.6.1.4)

4.10 Performance Characteristics. -

4.10.1 Receiver, Simulated Radiac R-1855/T. -

4.10.1.1 Operating Frequency. - Using the proper crystals for a frequency of 138 MHz, 141MHz and 144 MHz, the receiver shall meet the requirement of 3.6.1.2 for each of these frequencies. (See 3.6.1.1)

4.10.1.2 Sensitivity. - After setting the receiver meter to zero position and checking battery voltage is within the checkband of the meter, the receiver shall be tested to the requirements of 3.6.1.2. The antenna dummy load shall have an input impedance of 50 ohms.

4.11 Burn-in. - Each receiver R-1855/T submitted for acceptance shall be subjected to burn-in in accordance with drawing SM-A-678030. (See 3.8)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

4.12 Environmental. - The Receiver R-1855/T shall be tested in accordance with the following environmental conditions:

4.12.1 Altitude (Elevation) Test. - The receiver shall be tested in accordance with Method 500, Procedure 1, of MIL-STD-810. Prior to testing, the receiver shall meet full specification performance for the measurements specified in 3.6.1.2. (See 3.7.3)

4.12.2 Leakage (immersion) Test. -

4.12.2.1 Immersion, receiver. - The receiver shall be tested in accordance with Method 512, Procedure 1, of MIL-STD-810. (See 3.7.5.1)

4.12.2.2 Immersion, case. - The case shall be tested in accordance with Method 512, Procedure 1, of MIL-STD-810. (See 3.7.5.2)

4.12.3 Temperature Tests. -

4.12.3.1 Low Temperature Procedure. - The following test shall be performed on the receiver in accordance with MIL-STD-810, Method 502, Procedure 1. Perform the tests of 4.10.1.2 as pre-environmental data. Place the receiver in the temperature chamber and reduce the ambient temperature to -60 ± 2.5°F. The test will start when ambient temperature has stabilized. Hold the temperature for a period of 8 hours. At the end of 8 hours increase the ambient temperature to 0 ± 2.5°F. When the temperature of the receiver has stabilized, operate the receiver for six hours at a 200 RAD reading. At the end of this time perform the tests of 4.10.1.2. Return the receiver to room ambient temperature. Perform the test of 4.10.1.2. as post environmental data. The readings at the low temperature shall not vary from those at room temperature by more than ± 30%. (See 3.7.1.1)

4.12.3.2 High Temperature Procedure. - The following test shall be performed on the receiver in accordance with MIL-STD-810, Method 501, Procedure 1. Perform the tests of 4.10.1.2 as pre-environmental data. Place the receiver in the temperature chamber and increase the ambient temperature to 160 ± 2.5°F. The test will start when the ambient temperature has stabilized. Hold the temperature for a period of 8 hours. At the end of 8 hours reduce the ambient temperature to 125 ± 2.5°F. When the temperature of the receiver has stabilized, operate the receiver for six hours at a 200 RAD reading. At the end of this time perform the tests of 4.10.1.2. Return the receiver to room temperature. Perform the test of 4.10.1.2 as post environmental data. The readings at the high temperature shall not vary from those at room temperature by more than ± 30%. (See 3.7.1.2)

4.12.4 Vibration. - The receiver shall be vibrated in accordance with MIL-STD-810, Method 514.1, Procedure X, Curve AW and AY of Figure 514.1-7. Pre and post testing shall be performed on the receiver in accordance with 4.10.1.2. (See 3.7.4)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

4.12.5 EMI. - The receiver shall be tested in accordance with MIL-STD-462 and meet the requirements of 3.7.2.

4.12.6 Dust. - The receiver shall be tested in accordance with Method 510, Procedure 1 of MIL-STD-810. Following completion of the test, perform the tests of 4.10.1.2. (See 3.7.6)

4.12.7 Humidity (moisture-resistance) test. - The receiver shall be tested in accordance with Method 507, Procedure II of MIL-STD-810. Prior to testing, the receiver shall meet full specification performance of 3.6. During the periods shown on Figure 507-2 of MIL-STD-810 perform the test of 4.10.1.2. Following completion of the test, perform the tests of 4.10.1.2. (See 3.7.7)

4.12.8 Salt fog. - The receiver (including accessories) in its normal operating position shall be tested in accordance with Method 509, Procedure 1. Pre and post test shall be performed in accordance with 4.10.1.2. (See 3.7.8)

4.12.9 Fungus. - The receiver (including accessories) shall be tested in accordance with Method 508, Procedure 1 of MIL-STD-810. Spraying shall include parts and materials on and under the chassis, and the interior of the equipment case. The receiver shall remain in an open condition during the test. Operation is not reauired. (See 3.7.9)

4.12.10 Shock, drop. - The receiver shall be tested in accordance with MIL-STD-810, Method 516, Procedure 1, Shock parameters a and c of Figure 516-1. Pre and post test shall be performed in accordance with 4.10.1.2. (See 3.7.10)

4.13 Visual and Mechanical inspection. - Equipment shall be examined for the defects listed in MIL-STD-252.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. - Preservation and packaging shall be level A or C, as specified. (See 6.2.b)

5.1.1 Level A. -

5.1.1.1 Cleaning. - Receiver Group, Simulated Radiac, OR-114/T shall be cleaned in accordance with process C-1 of MIL-P-116.

5.1.1.2 Drying. - Receiver Group, Simulated Radiac, OR-114/T shall be dried in accordance with the applicable procedure of MIL-P-116.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

5.1.1.3 Preservation application. - None required.

5.1.1.4 Unit packaging. - Unit packaging shall be in accordance with the methods prescribed in MIL-P-116 as specified herein.

5.1.1.4.1 Technical literature. - Each technical literature shall be packaged method 1C-1.

5.1.1.4.2 Receiver Group, Simulated Radiac, OR-114/T. - Receiver Group, Simulated Radiac, OR-114/T shall be individually packaged method III as follows: Stow all units within the designated compartments of the transit case. Close cover and secure all fasteners. Cushion the transit case on all surfaces with cells or pads or both fabricated of fiberboard conforming to PPP-F-320, type CF, variety SW, class weather-resistant, grade W5c, designed to protect all projections and absorb the shock of impact in handling and transit. Place the cushioned unit within a close-fitting fiberboard box conforming to PPP-B-636, W5c. Close the box in accordance with the appendix of the box specification.

5.1.2 Level C. - Receiver Group, Simulated Radiac, OR-114/T shall be preserved and packaged in a manner that will afford adequate protection against physical and environmental damage during shipment, handling and limited intransit storage.

5.2 Packing. - Packing shall be level A, B or C as specified. Shipping containers for all levels shall be capable of stacking and supporting superimposed loads during shipment and storage without damaging the container(s) or its contents. (See 6.2.b)

5.2.1 Level A. - Receiver Group, Simulated Radiac CR-114/T, packaged as specified in 5.1, shall be individually packed within a close-fitting box conforming to PPP-B-601, overseas type; PPP-B-621, style 4, class 2; or PPP-B-585, style 2 or 3, class 3. Fiberboard boxes being placed directly in the shipping containers shall be water proofed with tape conforming to PPP-T-76, in accordance with the taping requirements of the appendix of the box specification. Place the technical literature, packaged as specified in 5.1.1.4.1, on top of the contents, directly under the lid of the box. Closure and strapping shall be in accordance with the applicable container specification or appendix thereto except that the metal strapping shall conform to QQ-S-781, type 1, finish "A".

5.2.2 Level B. - Receiver Group, Simulated Radiac OR-114/T, packaged as specified in 5.1, shall be individually packed within a close-fitting box conforming to PPP-B-601, domestic type; PPP-B-621, style 4, class 1; or PPP-B-585, style 2 or 3, class 3. Place the technical literature, packaged as specified in 5.1.1.4.1, on top of the contents, directly under the lid of the box. Closure and strapping shall be in accordance with the applicable container specification or appendix thereto.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

5.2.3 Level C. - Receiver Group, Simulated Radiac OR-114/T, packaged as specified in 5.1, shall be packed in shipping containers that comply with Federal or Military specifications, in a manner that will afford adequate protection to the package and its contents against physical and environmental deterioration and damage during limited shipment, handling and intransit storage.

5.3 Marking. - In addition to any special marking required by the contract or order, interior packages and exterior shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use. - The Receiver Group, Simulated Radiac OR-114/T used in conjunction with the Transmitter Group OT-51/T and Transmitter Group, Hot Spot OT-52/T comprises a training system which allows safe instructions and practical exercise in the survey and mapping of radiological contamination.

6.2 Ordering data. - Procurement documents should specify the following:

a. Title, number, and date of this specification and any amendment thereto.

b. Levels of preservation and packaging and packing. (See Section 5)

c. When rough handling and functional tests are required.

d. The contractor should apply for nomenclature in accordance with the applicable clause in the contract.

e. Marking and shipping of samples.

f. Place of final inspection.

g. The receiver is powered by six BA-30 batteries that meet requirements of MIL- B -18. The Government will not procure batteries with Receiver Group OR-114/T.

Custodian:
Army - EL

Preparing Activity
Army - EL

Project No. 6665-A317

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No 22-R255

INSTRUCTIONS This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost Comments and the return of this form will be appreciated Fold on lines on reverse side, staple in corner and send to preparing activity Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements

SPECIFICATION MIL-R-55403(EL) RECEIVER GROUP, SIMULATED RADIAC, OR-114()/T

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1 HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A GIVE PARAGRAPH NUMBER AND WORDING

B RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2 COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3 IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4 REMARKS *(Attach any pertinent data which may be of use in improving this specification If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED

ESC-FM 1068-68

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

FOLD

Department of the Army
Headquarters
U.S.Army Electronics Command
Fort Monmouth, New Jersey 07703

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

Commanding General
U.S.Army Electronics Command
ATTN: AMSEL-RD-TS-S
Fort Monmouth, New Jersey 07703

FOLD

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.