MILITARY SPECIFICATION

CIRCUIT BREAKERS (AUTOMATIC - ALB-1) AND SWITCH, TOGGLE (CIRCUIT BREAKER, NON-AUTOMATIC - NLB-1) AIR, INSULATED HOUSING, 125 VOLTS AND BELOW, A.C. AND D.C., (NAVAL SHIPBOARD USE)

This amendment forms a part of MIL-C-17588E(SH), dated 26 November 1985, and is approved for use by the Naval Sea Systems Command, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 7

3.5.2, Table IV under Time - seconds: Delete "0.028" and substitute "0.400".

PAGE 11

Table VI: Delete and substitute:

"TABLE VI. Sampling for quality conformance inspection.

Number of items in lot offered for inspection	Number of items in sample
8 and under	2
9 - 15	3
16 - 25	5
26 - 40	8
41 - 65	13
66 - 110	20
111 - 180	25
181 - 300	30
301 - 500	40
Over 501	50

AMSC N/A FSC 5925
DISTRIBUTION STATEMENT A Approved for public release; distribution unlimited

Source: https://assist.dla.mil -- Downloaded: 20261O-18T10:21Z
Check the source to verify that this is the currenversion before use.

PAGE 11

* 4.7.3: Delete and substitute:

"4.7.3 Quality conformance production shock testing. Five units of each ampere rating produced during a month shall be selected at random and subjected to production shock testing. If more than 2 ampere ratings are produced during a month, the total number of circuit breakers shocked may be limited to 10 units which will be divided equitably among the production lots."

PAGE 12

* 4.7.3.1: Delete and substitute:

"4.7.3.1 Test periods shall begin with the first production run circuit breaker. Circuit breakers produced during the time period (month) shall be tested during that month. The manufacturer shall conduct the shock tests on the sample circuit breakers and file the data as production shock test records. Several circuit breakers of different ampere ratings may be tested simultaneously during the same month; for example, the mounting plate may be modified to accommodate one circuit breaker of each ampere rating, and any multiple of one-to-ten circuit breakers of different ampere ratings may be tested simultaneously. The following tests shall apply:

(a) The circuit breaker shall be tested in the closed position.
(b) The circuit breaker shall be tested when mounted in its vertical and closed position and no load voltage is necessary.
(c) The circuit breaker shall be subjected to one hammer blow of a 3-foot drop from each direction--top, back, and side."

PAGE 14

4.8.4.2, line 3 and 4: Delete "The maximum current value test shall be performed followed after a cooling period of at least 15 minutes, by the minimum current value test."

NOTE: The margins of this amendment are marked with an asterisk or vertical lines to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

Preparing activity:
Navy - SH
(Project 5925-N117)

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T10:21Z
Check the source to verify that this is the current version before use.