MILITARY SPECIFICATION

AMPLIFIER, AUDIO FREQUENCY, AM-3729( )/SR

This amendment forms a part of Military Specification MIL-A-28716(EC) dated 15 October 1969.

PAGE 4

3.2.3: Delete and substitute the following:
"3.2.3 All modular assemblies shall be physically and electrically interchangeable, on modular level only, with their counterpart in the Government furnished equipment (see 3.12). The potted assemblies provided in the GFE equipment may be replaced by repairable printed circuit boards using standard parts in accordance with MIL-E-16400."

PAGE 10

3.14.17.1: Delete and substitute the following:
"3.14.17.1 Quantitative reliability requirement. The equipment shall have a mean-time-between failure (MTBF) of not less than 1,000 hours at the 90 percent lower confidence level.

PAGE 16

4.5.1: Delete and substitute the following:
"4.5.1 Reliability test. The contractor shall conduct reliability tests in accordance with the Detail Requirements of MIL-STD-781 and the requirements of the fixed time type reliability test of this specification (see 4.5.2).

4.5.2: Add the following at the end of the paragraph:
"Temperature and vibration shall be in accordance with Test Level C of MIL-STD-781. Acceptance of units on order shall be withheld pending satisfactory completion of the qualification test."

4.5.3: Delete and substitute the following:
"4.5.3 Reliability production tests. Following satisfactory completion of reliability qualification testing (see 4.5.2), five units shall be randomly selected by the Government quality assurance representative from each successive 1,000 units produced, five units every 60 days, if less than 1,000 units are produced in 60 days, shall be selected. The reliability tests to be conducted shall be as specified in 4.5.1 and 4.5.2. Final acceptance of units on order shall not be withheld pending satisfactory completion of the reliability production test, except as stated in 4.5.3.1.

Add the following new paragraph:
"4.5.3.1 Rejected equipment. In the event of rejection, acceptance of all remaining units on order shall be withheld pending a complete review and analysis of the cause for failure. No equipment shall be selected more than once for reliability testing. In the event that the cause for failure is equipment manufacturer design, corrective action shall be performed on all equipments delivered under the contract. If the failure is due to equipment manufacturer workmanship, appropriate corrective action shall be taken on all equipment remaining to be delivered on the contracts. In order to demonstrate effective corrective action, another random sample of five units shall be selected and tested as described in 4.5.1 and 4.5.2. This sample is in addition to the quantity required in 4.5.3. Acceptance of material can be resumed pending satisfactory completion of the additional testing. The contractor shall forward a complete report of the failure, cause of failure, corrective action and results of the additional test sample, to the contracting officer prior to acceptance of the remaining material on order.

4.5.5: Delete entire paragraph.

Preparing activity:
NAVY-EC
(Project 5820-N686)

FSC 5820

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:48Z
Check the source to verify that this is the current version before use.