MILITARY SPECIFICATION

WARHEAD SECTION, TRAINING M138E3

1. SCOPE

1.1 This specification covers requirements, quality assurance provisions, and the preparation for delivery criteria for one type of training warhead section entitled Warhead Section, Training M138E3, which is utilized for training on the Sergeant warhead section.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-W-13779	- Welding, Metal Arc Steels, Constructional Readily Weldable for Low Stressed Joints.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-1168	- Lot Numbering of Ammunition.
MIL-STD-1460	- Soldering of Electrical Connections and Printed Wiring Assemblies, Procedure For.

DRAWINGS

ORDNANCE CORPS

8850565	- Shipping and Storage Container M481 Sergeant Adaption Kits and Warhead Sections Packing and Marking.
8862540	- Marking.
8862543	- Probe Assembly.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

8862800 - Warhead Section, Training, M138E3.
8862890 - Warhead Section, Training, M138E3.
EL-8884214 - Equipment List.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials. The contractor shall furnish objective evidence (see 6.2) that the material complies with the specifications listed on the applicable drawing.

3.2 Assembly. The training warhead section shall comply with all requirements specified on the drawing (dwg) 8862800, with all requirements specified herein, and with the requirements of all applicable specifications to the extent specified on the drawing and herein.

3.3 First article testing. Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2).

3.4 Serialization. A six letter serial number shall be assigned to the item. Serial numbers required on these items shall be obtained by means of a letter addressed to: Commander, Picatinny Arsenal, Dover, New Jersey 07801, ATTENTION: SARPA-QA-T-M. The letter of request shall include:

a. Exact nomenclature of the item as specified on the applicable drawing.
b. Name of the contractor.
c. Contract number or procurement request order number.
d. Number of serial numbers required.

3.5 Circuit resistance and continuity. The continuity and resistance for the rotary switch, latching relay and the continuity loops shall be as specified in 3.5.1, 3.5.2 and 3.5.3 when tested as specified in 4.4.1.

3.5.1 Rotary switch circuit resistance. The resistance between terminals listed in Table I shall not exceed the values indicated when tested as specified in 4.4.1.1.

Table I

Rotary Switch Position Number	P919 Connector Pins	Maximum Resistance (ohm)
1	From 70 to 54	3K ± 0.2%
2	From 70 to 43	3K ± 0.2%
3	From 70 to 43	5K ± 0.2%
4	From 70 to 43	7K ± 0.2%
5	From 70 to 43	9K ± 0.2%
6	From 70 to 43	11K ± 0.2%

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

3.5.2 Latching relay circuit resistance. The resistance of the latch and unlatch relay positions shall be as specified below.

3.5.2.1 Latch position. The resistance between terminals 43 and 62 shall be 5K ± 0.2% when tested as specified in 4.4.1.2.

3.5.2.2 Unlatch position. The resistance between terminals 43 and 62 shall be 7K ± 0.2% when tested as specified in 4.4.1.3.

3.5.3 Continuity loop resistance. The resistance between terminals listed in Table II shall not exceed the specified in 4.4.1.4.

Table II

Connector Pins	Maximum Resistance (ohm)
From P919-71 to P910-10	0.2
From P919-72 to J2-U	0.2
From J2-S to P919-71	0.2

3.6 Insulation resistance. The insulation resistance between the pins of P919 as designated in Table III shall be 20 megohms (mego) minimum when tested at 500 ± 50 direct current volts (vdc) as specified in 4.4.2, current shall be limited to 5 milliamperes (ma). Unused terminals shall be connected together and tested as one terminal. The panel of each assembly shall be at test fixture ground.

Table III

P919 Connector Pins

From	To
56	53, 27, 40, 1, 8, 14, 21, 54, 43, 62, 70, 71, 10, 16, 23, 52, 72, U, S.
52	53, 27, 40, 1, 8, 14, 21, 31, 54, 43, 64, 62, 70, 71, 10, 16, 56, 72, U, S.
16	53, 27, 40, 1, 8, 14, 21, 31, 54, 43, 62, 63, 64, 70, 71, 10, 23, 52, 72, U, S.
10	53, 27, 40, 1, 8, 14, 21, 31, 54, 43, 62, 63, 64, 70, 16, 23, 52, 56, 72, U.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

Table III (Cont'd)

From	To
64	53, 27, 40, 1, 8, 14, 21, 54, 43, 62, 70, 71, 10, 16, 23, 52, 72, U, S.
62	53, 27, 40, 1, 8, 14, 21, 31, 54, 63, 64, 70, 71, 10, 16, 23, 52, 56, 72, U, S.
54	53, 27, 40, 1, 8, 14, 21, 31, 43, 62, 63, 64, 71, 10, 16, 23, 52, 56, 72, U, S.
21	31, 54, 43, 62, 63, 64, 70, 71, 10, 16, 23, 52, 56, 72, U, S.

3.7 Capacitor characteristics. The voltages across the terminals of the charged capacitors listed in Table IV shall be 23 dc minimum (min) 3.5 seconds min after the voltage has been removed, when tested as specified in 4.4.3.

Table IV

Terminals	Volts (Min)
From (-) 53 to (+) 27	23
From (-) 53 to (+) 40	23
From (-) 53 to (+) 1	23
From (-) 53 to (+) 8	23
From (-) 53 to (+) 14	23
From (-) 53 to (+) 21	23

3.8 Diode characteristics. The voltage drop across the diodes in the forward direction and the current in the reverse direction shall be as specified below. The measurements shall be made in accordance with 4.4.4.

Item No.	Diode	+ Voltage to Terminal	- Voltage to Terminal	Maximum Voltage or Current
1	CR2	16	52	1 Volt*
2	CR2	52	16	1 ma**

*Voltage drop across diode.
**Leakage current through diode.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

3.9 Environmental testing (see 4.4.5).

3.9.1 High temperature. The training warhead section shall withstand a temperature of 160 ± 5°F without damage and shall be capable of meeting the requirements of 3.6, 3.7, 3.8 while at this temperature. On completion of the high temperature test the warhead section shall be capable of meeting the requirements of 3.5 at ambient temperature (80 ± 20°F). Testing shall be as specified in 4.4.5.1.

3.9.2 Low temperature. The training warhead section shall withstand a temperature of -65 ± 5°F without damage and shall be capable of meeting the requirements of 3.6, 3.7, 3.8, while at this temperature. On completion of the low temperature test the warhead section shall be capable of meeting the requirements of 3.5 at ambient temperature (80 ± 20°F). Testing shall be as specified in 4.4.5.2.

3.9.3 Shock. The training warhead section, loaded in its container, shall withstand the following shock tests:

Edgewise Drop
End Impact
Rollover Impact

Upon completion of the shock tests the warhead section shall be inspected and shall show no visible evidence of damage that will impair operation. The warhead section shall meet the requirements of 3.5, 3.6, 3.7, and 3.8 after being tested as specified in 4.4.5.3.

3.9.4 Transportation vibration. The training warhead section, loaded in its container, shall be vibrated along its vertical axis as specified in Table V. Upon completion of the vibration test, the warhead section shall be inspected and shall show no visible evidence of damage that will impair operation. The warhead section shall meet the requirements of 3.5, 3.6, 3.7, and 3.8 after being tested as specified in 4.4.5.4.

Table V

Test Cycle Frequency Hertz (Hz)	Gravity (g) Load or Double Amplitude	Total Time (Minutes)
6-20-6	1g ± 0.1g	15
21-60-21	0.060 ± 0.006	10
61-300-61	10g ± 1g	25
301-500-301	10g ± 1g	25

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

3.10 Weight. The training warhead section with probe assembly attached shall weigh 1581 ± 50 pounds when weighed as specified in 4.4.6.

3.11 Center of gravity. The training warhead section with probe assembly attached shall have a center of gravity at station 100.4 measured 38.6 ± 0.5 inch forward of station 139, when tested as specified in 4.4.7.

3.12 Soldering. All soldering shall comply with the requirements specified in MIL-STD-1460.

3.13 Welding. Weldments shall be reasonable smooth and free from craters. They shall exhibit characteristics of fusion, penetration and soundness of weld deposit representative of good welding practices. All welding fluxes, scale, weld spatter, acids or basic solutions shall be completely removed prior to application of finish coats. Welding shall be in accordance with MIL-W-13779.

3.14 Workmanship.

3.14.1 Plastic and metal characteristics. All components shall be free from cracks, splits, cold flow, shrinkage, cold shuts, inclusions, porosity, or any similar characteristic.

3.14.2 Threads. Threads shall be full and undamaged for the entire minimum length or depth as required on the applicable drawing.

3.14.3 Burrs. Parts shall be free from burrs.

3.14.4 Foreign matter. Parts shall be free from chips, dirt, grease, rust, corrosion, or any embedded foreign material.

3.14.5 Cleaning. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agent.

3.14.6 Electrical. Cable assemblies and wires shall be dressed in such a manner as to prevent pinching or chafing of the wire insulation. Ends of wires shall be free from burrs, sharp edges, or points. All parts shall be free from flux, chips, dirt, grease, rust or foreign material.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.2 First article inspection.

4.2.1 Quantity to be submitted. When the contract requires first article inspection, the contractor shall submit 1 complete assembly (see dwg 8862800) for first article testing to the testing facility designated in the invitation for bids or request for proposal.

4.2.2 Inspection and testing to be performed. The first article inspection sample shall be subjected to the inspections and tests specified in Table VI. Tests shall be conducted in order specified in Table VI.

Table VI

First article inspection and tests

Inspection or Test	Dest	Non-Dest
1. Classification of characteristics (see 4.3.2.1)		X
2. Circuit resistance and continuity (see 3.5)		X
3. Insulation resistance (see 3.6)		X
4. Capacitor characteristics (see 3.7)		X
5. Diode characteristics (see 3.8)		X
6. High temperature (see 3.9.1)		X
7. Low temperature (see 3.9.2)		X
8. Shock (see 3.9.3)	X	
9. Transportation vibration (see 3.9.4)		X
10. Weight (see 3.10)		X
11. Center of gravity (see 3.11)		X

4.2.3 Inspection equipment. The inspection and testing specified in 4.2.2 shall be accomplished by using the gages and test equipment specified in 4.3.4.1.

4.2.4 Rejection. If any item fails to comply with any of the applicable requirements, the first article sample shall be rejected.

4.3 Quality conformance inspection.

4.3.1 Lot formation.

4.3.1.1 Production lot. A lot shall consist of parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance, storage, or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The criteria and procedures for the assignment of lot numbers shall be in accordance with MIL-STD-1168.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.3.1.2 Inspection lot. A lot or batch and its formation, size, and presentation is described in MIL-STD-105, Section 5. Accordingly, a lot shall mean an inspection lot and a batch shall mean an inspection batch for the purpose of this specification. The manner in which each inspection lot or batch is to be presented and identified by the contractor, shall be designated or approved by the Government representative.

4.3.2 Product inspection examination. A sample shall be selected at random from each inspection lot in accordance with the applicable major or minor characteristic table (see Table VII and Table VIII), and inspected for all characteristics in the applicable classification. Any characteristics in the sample found to be defective shall reject the inspection lot. Sequence for the inspection of characteristics in each classification need not be followed as long as all characteristic inspections are performed.

Table VII
Major Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-16	all	28-29	23	52-56	31	132-156	39
17	16	30-31	24	57-62	32	157-191	40
18	17	32-34	25	63-69	33	192-244	41
19-20	18	35-36	26	70-76	34	245-334	42
21	19	37-40	27	77-86	35	335-519	43
22-23	20	41-43	28	87-97	36	520-1120	44
24-25	21	44-47	29	98-112	37	over 1120	45
26-27	22	48-51	30	113-131	38		

Table VIII
Minor Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-9	all	14-16	12	28-33	16	77-121	20
10	9	17-18	13	34-41	17	122-273	21
11	10	19-22	14	42-54	18	over 273	22
12-13	11	23-27	15	55-76	19		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.3.2.1 Classification of characteristics (see 3.2). Critical, major and minor characteristics are defined in MIL-STD-105. Inspection shall be conducted as follows:

4.3.2.1.1 Probe assembly (see dwg 8862543).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Inability to probe to assemble with retaining block	Gage
Minor:		
	201. Vanes bent or insecurely pinned	Visual/Manual
	202. Improper or illegible marking	Visual
	203. Bare spot in protective coating except for slight scratch	Visual

4.3.2.1.2 Warhead section, training (see dwg 8862890) prior to assembly of probe.

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Mislocation of connectors	Gage
	102. Mislocation of alignment pins	Gage
	103. Inability of retaining block to accept probe	Gage
	104. Inability of warhead section to accept sling	Gage
Minor:	None defined.	

4.3.2.1.3 Warhead section, training (see dwg 8862800).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Inoperable bolt assembly	Manual
	102. Vent doors not flush or inopenable	Manual
	103. Mismatch at section #10	Visual/Manual
	104. Mismatch at station 8.125	Visual/Manual
	105. Loose component	Visual/Manual
	106. Missing component	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

107. Damaged component.....Visual
108. Soldering not in accordance with MIL-STD-1460.....Visual
109. Weldments not in accordance with MIL-W-13779.....Visual
110. Objective evidence relative to material missing or improper (see 3.1).....Visual
111. Serialization missing or improper (see 3.4).....Visual

Minor:
201. Improper, illegible or missing marking.....Visual
202. Bare spot in protective coating except for slight scratch.....Visual
203. Evidence of poor workmanship (see 3.14).....Visual

4.3.2.1.4 Packing for warhead section (see dwg 8850565) prior to inserting warhead section.

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Loose terminal component	Visual/Manual
	102. Damaged internal component	Visual
Minor:		
	201. Foreign matter in container	Visual

4.3.2.1.5 Packing for warhead section (see dwg 8850565) prior to closing container.

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Incorrect torque of bolt	Gage
	102. Insure fastening of static probe package	Visual/Manual
	103. Improper tension of strap	Visual/Manual
Minor:		
	201. Missing dust cap	Visual
	202. Loose dust cap	Visual/Manual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.3.2.1.6 Preparation for delivery (see 5).

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Preservation, packing, and packaging not in accordance with (see dwg 8850565)	Visual
102.	Marking not in accordance with (see dwg 8862540)	Visual
Minor:		
201.	Evidence of poor workmanship (see 3.14)	Visual

4.3.3 Testing. All tests shall be performed. Tests shall be performed in the order specified below:

Test	Test Classification
a. Circuit resistance and continuity	Major
b. Insulation resistance	Major
c. Capacitor characteristics	Major
d. Diode characteristics	Major
e. Weight	Major
f. Center of gravity	Major

None of these tests are considered destructive and samples so tested may be returned to the lot.

4.3.3.1 Circuit resistance and continuity, insulation resistance, capacitor characteristics, diode characteristics, weight, and center of gravity. Each training warhead section shall be tested in accordance with 4.4.1, 4.4.2, 4.4.3, 4.4.4, 4.4.6, and 4.4.7. If any item fails to comply with 3.5, 3.6, 3.7, 3.8, 3.10, and 3.11, the item shall be rejected and removed from the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.3.4 Acceptance inspection equipment.

4.3.4.1 Major characteristics and tests. Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions specified on the Equipment Lists (EL) (see EL-8884214). When either of the conditions listed below exist, the contractor shall design required equipment or specify suitable commercial equipment and obtain approval prior to use on the contract.

a. Any deviation from equipment or procedures specified on the EL is desired (see 6.3).
b. The code "CD" is listed in the "Part or Identifying Number" column on the EL (see 6.1.2).

4.3.4.2 Minor characteristics and tests. Acceptance inspection equipment for minor characteristics is not specified on ELs. The acceptance inspection equipment, operating instructions and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

4.4 Test methods. The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used.

4.4.1 Circuit resistance and continuity.

4.4.1.1 Rotary switch circuit resistance. The circuit resistance between terminals specified in 3.5.1, Table I, shall be measured with a Wheatstone Bridge or Digital Ohmmeter. The rotary switch shall be energized with +28 vdc applied to terminal 31 and return to terminal 56 and stepped from positions 1 to 6. (Positions 7 to 12 are not used).

4.4.1.2 Latching relay, latch position circuit resistance. The circuit resistance between terminals 43 to 62 shall be measured with a Wheatstone Bridge or Digital Ohmmeter. The relay circuit shall be energized with a +28 vdc across terminals +(63) and -(56).

4.4.1.3 Latching relay, unlatch position circuit resistance. The circuit resistance between terminals 43 to 62 shall be measured with a Wheatstone Bridge or Digital Ohmmeter. The relay circuit shall be energized with +28 vdc across terminals +(64) and -(56).

4.4.1.4 Continuity loop resistance. The resistance between the terminals specified in 3.5.2.3, Table II, shall be measured with a Keithly Milliohmmeter or an instrument of equivalent accuracy.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.4.2 Insulation resistance. The insulation resistance shall be measured with an insulation resistance tester at 500 ± 50 vdc. All unused terminals of the connector shall be connected together and tested as one terminal. The malfunction (K2) relay shall be in the remove position and the latching relay (K1) in the latch position and the step switch in position 1.

4.4.3 Capacitor characteristics. The terminal voltages, when read with a 20,000 ohm/volt voltmeter, shall be as specified in 3.7 when a potential of 45 ± 5 vdc is applied across the capacitor terminals listed in Table IV. The readings shall be taken 3.5 seconds minimum after the power supply has been disconnected.

4.4.4 Diode characteristics. The voltage drop across the diode in the forward direction and the current in the reverse direction shall be measured between the terminals listed in paragraph 3.8. The applied voltages, test currents and series resistance for the reverse voltage drop measurement shall be as specified below. The voltages and currents shall be applied for a period of 15 seconds maximum. For measurement of voltage drop in the forward direction and current in the reverse direction, the contacts of relay K2 shall be closed in the insert position by energizing the relay solenoid circuit with 28 vdc across terminals -(52) and +(23). The 28 vdc potential shall be removed before proceeding with the diode test.

Item No.	Diode	+ Voltage to Terminal	- Voltage to Terminal	Applied Current	Source Voltage Volts	Voltage Measurement
1	CR2	16	52	0.35-0.50 amp	28 vdc	Across Diode
2	CR2	52	16	1 ma max	400 vdc	-

4.4.5 Environmental testing (see 3.9).

4.4.5.1 High temperature. The warhead section shall be placed in a test chamber. The temperature within the chamber shall be raised to 160 ± 5°F and maintained for a minimum of 4 hours or until the temperature of the warhead section has stabilized (see 6.4) whichever is the limiting condition. During stabilized temperature and after the completion of the test, the warhead section shall meet the requirements of 3.9.1.

4.4.5.2 Low temperature. The warhead section shall be placed in a test chamber. The temperature within the chamber shall be lowered to -65 ± 5°F and maintained for a minimum of 4 hours or until stabilization (see 6.4) occurs whichever is the limiting condition. During stabilization of the warhead section, and after the completion of the test, the warhead section shall meet the requirements of 3.9.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

4.4.5.3 Shock. The warhead section loaded in its container shall be tested as specified in 4.4.5.3.1, 4.4.5.3.2 and 4.4.5.3.3. Upon completion of these tests the warhead section shall be tested as specified in 4.4.1, 4.4.2, 4.4.3, and 4.4.4.

4.4.5.3.1 Edgewise drop. The loaded container shall be supported on one end of its base on a wood sill 5 ± 0.5 inches high and placed normal to the skids. The opposite end of the container shall be raised and allowed to drop freely from a height of 12, 24 and 36 ± 0.5 inches respectively. The three drops shall be made on a concrete or similar hard surface. This test shall be applied to both ends of the container.

4.4.5.3.2 End impact. The loaded container shall be placed in a fixture which will allow free axial movement. The end of the container shall strike against a solid flat vertical abutment having a wooden face of 2 inch minimum thickness. The direction of motion shall be 90 ± 5°F with the impact surface and velocity at impact shall be 10.5 ± 1.5 feet per second. Apply the test to both ends of the container.

4.4.5.3.3 Rollover impact. The loaded container on its base on a hard level floor shall be tipped slowly sideways until it falls freely on its side. The procedure shall be repeated from the side to the top, from the top to the other side and from the other side to its base thus completing one revolution.

4.4.5.4 Transportation vibration. The warhead section shall be enclosed in its container and rigidly mounted on a suitable vibration producing apparatus. It shall be vibrated on its vertical axis at the frequencies and amplitudes shown in Table V. After the test, the warhead section shall meet the requirements specified in 3.9.4.

4.4.6 Weight. The warhead section shall be weighed on an approved weighing device and shall meet the requirements of 3.10.

4.4.7 Center of gravity. The warhead section shall be attached to an approved device to determine its center of gravity as specified in 3.11.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.1).

5.1.1 Level A. The training warhead section shall be packaged in accordance with dwg 8850565 using the specified moisture barrier.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.

5.1.2 Level C. The training warhead section shall be packaged in accordance with dwg 8850565 except that the moisture barrier may be omitted.

5.2 Packing.

5.2.1 Level A and C. The training warhead section shall be packed in accordance with dwg 8850565.

5.3 Marking. Marking shall be as specified in accordance with dwg 8862540.

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification.
b. Selection of applicable level of packaging and packing required (see 5.1 and 5.2).

6.2 Objective evidence. Records of contractor quality control and inspections which can be verified.

6.3 Acceptance inspection equipment (see 4.3.4.1). The contractor shall obtain approval from the Commander, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SARPA-QA-T.

6.4 Temperature stabilization. The temperature is considered stabilized when the greatest peaks (both highest and lowest) continually observed over 5 minutes min. do not exceed the nominal temperature plus tolerance specified.

6.5 Supersession data. This specification supersedes the requirements of Purchase Description X-PA-PD-2492 dated 27 May 1963.

Custodian:
Army - PA

Preparing activity:
Army - PA

Project No. 1115-A056

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:40Z
Check the source to verify that this is the current version before use.