MILITARY SPECIFICATION

COMPENSATOR, MAGNETIC FLUX CN-405( )/ASN

This specification is approved for use by all Departments and Agencies of the Department of Defense .

1. SCOPE

1.1 This specification covers one type of compensator designated as Compensator, Magnetic Flux CN-405( )/ASN (See 6.1 and 6.3).

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect, on date of invitation for bids, or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

PPP-B-585	Box, Wood, Wirebound
PPP-B-601	Box, Wood, Cleated Plywood
PPP-B-621	Box, Wood, Nailed & Lock-Corner
PPP-B-636	Box, Fiberboard
PPP-F-320	Fiberboard, corrugated and Solid Sheet Stock (Container Grade)
PPP-P-291	Paper, Wrapping, Cushioning
PPP-T-45	Tape, Gummed, Paper, Reinforced and Plain for Sealing and Securing
PPP-T-76	Tape, Pressure-Sensitive Adhesive Paper, (for Carton Sealing)
PPP-T-97	Tape, Pressure-Sensitive, Filament Reinforced
NN-P-71	Pallet, Materials-Handling, Wood
QQ-S-781	Strapping, Flat Steel

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-P-116	Preservation, Methods of
MIL-M-13231	Marking of Electronic Items
MIL-F-14072	Finishes for Ground Signal Equipment
MIL-B-43014	Boxes, Water-Resistant Paperboard Folding Set Up and Metal-Stayed

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	Marking for Shipment and Storage
MIL-STD-147	Palletized and Containerized Unit Loads 40 inch x 48 inch Pallets, Skids Runners or Pallet-Type Base
MIL-STD-252	Wired Equipment, classification of Visual and Mechanical Defects for
MIL-STD-454	Standard General Requirements for Electronic Equipment
MIL-STD-810	Environmental Test Methods

DRAWINGS

ELECTRONICS COMMAND

SC-DL-545359	Compensator, Magnetic Flux CN-405( )/ASN

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Description. - The Compensator, Magnetic Flux CN-405( )/ASN incorporates adjustable permanent magnets used to counteract the aircraft's magnetic field deviation effects on an induction compass transmitter (flux valve).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

3.2 First Article. - When specified in the contract or purchase order, the contractor shall furnish first article units in accordance with 4.3 and 6.2.d.

3.3 Construction. - The compensator shall be constructed in accordance with Equipment Drawing and data list:

SC-DL-545359 Compensator, Magnetic Flux CN-405( )/ASN

3.4 Finish, Protective (See 4.4). - The unit(s) shall be given protective finish in accordance with MIL-F-14072. This includes finish of hardware such as screws, etc. and necessary touch-up after mounting. The final film on Type 1 surface shall be Film B, in accordance with MIL-F-14072 and equipment drawings.

3.5 Cleaning.

3.5.1 Parts. - . Prior to the application of conformal coating on those parts affected and after fabrication, parts shall be cleaned in accordance with good commercial practice, or as specified in an applicable document. Cleaning processes shall have no deleterious effect. Post cleaning assembly processes shall minimize handling by bare hands to prevent contamination by fungus nutrients. Corrosive material shall be removed completely before the parts are mounted on chassis, panels, and other parts.

3.5.2 Units. - After assembly, units shall be cleaned thoroughly and shall be free from particles of solder, flux and other foreign material. In addition, when necessary, such cleaning shall also be performed before final assembly of the units.

3.6 Securing of Parts. -

3.6.1 General. - Brackets, lugs, inserts, bolts, and other mounting arrangements shall retain items securely when subjected to specified service conditions.

3.6.2 Securing of parts by threaded fasteners. - Nylok or other screws and nuts with plastic devices and Loctite or similar sealants shall not be subjected to temperatures in excess of 250°F (as during baking of paint). Loctite or similar sealants shall be applied in accordance with the manufacturer's instructions.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

3.7 Marking (See 4.4). -

3.7.1 General. - Marking shall conform to MIL-M-13231.

3.7.2 Visibility. - Wherever practicable, parts shall be so mounted that their identification markings will be readily visible with minimum disassembly of the unit(s).

3.7.3 Serial numbers. - The following unit(s) shall be serial numbered:

Compensator, Magnetic Flux CN-405( )/ASN

3.8 Tropicalization of Materials. - Materials shall be treated as follows:

3.8.1 Treating materials. - Treating materials containing a mercury-bearing fungicide shall not be used. The contractor shall determine that the treating material is compatible with the material or surface to be treated. Selection of treating materials shall be such that any increase in flammability of treated material will be held to the practical minimum.

3.8.2 Toxicity. - Treating materials shall cause no skin irritation or other injury to personnel handling the treated material during fabrication, transportation, operation or maintenance of the equipment, or during use of the finished items when used for the purpose intended.

3.8.3 Statement of treatment. - The contractor shall submit for approval, to the contracting officer, a statement describing in detail the materials to be treated and the treating materials and processes that he proposes to use.

3.9 Service Conditions (See 4.7). - The Compensator shall meet the service condition for Class I equipment per MIL-STD-810.

3.9.1 Temperature-Altitude (See 4.7.1). - The compensator shall meet the electrical requirement of 3.10 thru 3.10.3 before and after subjection to temperature-altitude test of Procedure 1, Method 504, Table 504-I of MIL-STD-810 for Class I equipment. After returning to room temperature, the adjusting screws on the compensator shall be operable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

3.9.2 Humidity (See 4.7.2). - The Compensator shall meet the electrical requirement of 3.10 thru 3.10.3 before, and after subjection to humidity test of Method 507, Procedure III, of MIL-STD-810.

3.9.3 Vibration (See 4.7.3). - The compensator shall meet the electrical requirement of 3.10 thru 3.10.3 before and after subjection to vibration test of Method 514.1, Curve B, Figure 514.1-2 of MIL-STD-810.

3.9.4 Salt fog (See 4.7.4). - The Compensator shall withstand exposure to salt-fog for 48 hours and shall show no evidence of corrosion as evidenced by any visible degradation that can be attributed to flaky, pitted, blistered or otherwise loosened finish. The adjusting screws shall operate after such exposure.

3.9.5 Fungus (See 4.7.5). - The compensator shall show no evidence of viable fungus after being subjected to 28 days of fungus incubation.

3.9.6 Dust (See 4.7.6). - The compensator shall withstand exposure to sand and dust particles as encountered in desert areas; the adjusting screws shall operate after such exposure.

3.10 Electrical. -

3.10.1 Neutral (Zero) setting (See 4.8.1). - The compensator set to its zero position shall not cause a shift in the heading output of the T-611( )/ASN Transmitter of more than +1.0 degree compared to the transmitter output when the compensator is removed.

3.10.2 Compensator range (See 4.8.2). - The shift in heading output of the transmitter, when the North-South or East-West adjustment is set to maximum shall be from 8 to 13 degrees.

3.10.3 Cross-axis shift (See 4.8.3). - Rotation of the North-South or East-West adjustments shall not cause a shift of the heading output of the transmitter of more than +1.5 degrees at a heading 90 degrees from the heading to which compensation is applied.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

3.11 Interchangeability (See 4.9). - Like units shall conform to Requirement 7 of MIL-STD-454 and be functionally interchangeable, without modification of the equipment. Individual items shall not be hand-picked for fit or performance. Reliance shall not be placed on any unspecified dimension, rating characteristic, etc.

3.12 Workmanship (See 4.10). - The compensator shall be manufactured and assembled in accordance with the equipment drawings (See 3.3), Requirement 9 of MIL-STD-454 and the following paragraphs herein.

Cleaning	3.5
Securing of Parts	3.6
Tropicalization of Material	3.8

3.13 Weight (See 4.11). - The weight of the compensator shall not exceed 0.5 pounds.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection. - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of Inspection. - Inspection shall be classified as follows:

a. First Article inspection (does not include preparation for delivery.) (See 4.3.2)

b. Inspection covered by subsidiary documents. (See 4.4)

c. Quality conformance inspection.

(1) Quality conformance inspection of equipment before preparation for delivery. (See 4.5)

(2) Quality conformance inspection of preparation for deli 4.12)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

4.3 First Article. - Unless otherwise specified in the contract or purchase order, the first article inspection shall be performed by the contractor.

4.3.1 First Article units. - The contractor shall furnish several First Article units of the complete CN-405( )/ASN.

4.3.2 First Article inspection. - First Article inspection shall consist of the inspection specified in subsidiary documents covering the items listed in 4.4 and the inspection specified for Group A, B and C (See Tables I, II and III respectively.) The inspection shall be performed in the following order: 4.4, Group A and Group B for all units; for Group C, one unit for temperature, humidity and vibration, one unit for dust, one unit for salt-fog and one unit for fungus.

4.4 Inspection Covered by Subsidiary Documents. - The following shall be inspected under the applicable subsidiary document as part of the inspection of equipments before preparation for delivery:

ITEM	WHERE REQUIRED
Finish	3.4
Marking	3.7

4.5 Quality Conformance Inspection of Equipment before Preparation for Delivery. - The contractor shall perform the inspection specified in 4.4 and 4.5.1 thru 4.5.4. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specified requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition, the Government at its discretion may perform all or any part of the specified inspection, to verify the contractor's compliance with specified requirements. (See 6.4). Test equipment for Government verification inspection shall be made available by the contractor.

4.5.1 Group A Inspection. - Each unit on contract or purchase order shall be inspected for conformance to the inspections specified in Table I. Discrete lots shall be formed from units that pass this inspection. Factors of lot composition not defined herein or in the contract or purchase order shall be in accordance with MIL-STD-105. Each lot shall be subject to sampling inspection, utilizing the procedures of MIL-STD-105, using the general inspection levels and AQL's indicated in Table I.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

4.5.1.1 Order of inspection within Group A. - Group A inspection shall be performed in an order satisfactory to the Government.

TABLE I - GROUP A INSPECTION

Inspection	Req. Para.	Insp. Para.	AQL Major	AQL Minor
Visual and Mechanical	3.12	4.10	6.5%	2.5%
Neutral (zero) setting	3.10.1	4.8.1)		
Compensator range	3.10.2	4.8.2)	- *1% for the group	
Cross-axis shift	3.10.3	4.8.3)		

*All electrical defects are considered major.

4.5.2 Group B inspection. - This inspection, including sampling, shall conform to Table II and to the special procedures for small-sample inspection of Standard MIL-STD-105. Group B inspection shall normally be performed on inspection lots that have passed Group A inspection and on samples selected from units that have been subjected to and met the Group A inspection. The inspection level shall be S-3.

TABLE II - GROUP B INSPECTION

Inspection	Req. Para.	Insp Para.	AQL
Interchangeability	3.11	4.9	6.5%

4.5.3 Group C inspection. - Group C inspection shall be performed on units that have passed Group A and Group B inspection. The inspection shall consist of the inspection specified in Table III. Samples shall be selected in accordance with 4.5.3.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

TABLE III - GROUP C INSPECTION

Inspection	Req. Para.	Insp. Para.
Subgroup 1		
Temperature -Altitude	3.9.1	4.7.1
Humidity	3.9.2	4.7.2
Vibration	3.9.3	4.7.3
Subgroup 2		
Weight	3.13	4.11
Dust	3.9.6	4.7.6
Salt-fog	3.9.4	4.7.4
Subgroup 3		
Fungus	3.9.5	4.7.5

4.5.3.1 Sampling for Group C inspection. -

4.5.3.1.1 Subgroup 1. - For this subgroup, two units shall be selected at random from the first production lot. For subsequent Group C inspection, two units shall be randomly selected every month.

4.5.3.1.2 Subgroup 2. - For this subgroup, two units shall be selected at random from the first production lot. For subsequent Group C inspection, two units shall be selected every two months.

4.5.3.1.3 Subgroup 3. - For this subgroup, only one unit from the first two (2) production units shall be selected for the first Group C inspections. For subsequent inspection, the next unit shall be selected when one-half of the units on order have been accepted by the Government Quality Assurance Representative.

4.5.4 Reinspection of conforming Group C sample units. - Unless otherwise specified, sample units which have been subjected to and passed Group C inspection may be accepted on contract or order provided all damage is repaired, cleaned of all foreign matter and the sample units are resubjected to and pass Group A inspection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

4.6 Standard Test Condition. - Unless otherwise specified, all tests shall be performed at ambient temperature pressure and humidity under the following conditions:

a. Supply voltage. - All tests shall be conducted with 23.5 ± 0.5 volts, single phase 400 ± 5 Hz alternating current applied to the transmitter.

b. Field strength. - All tests shall be conducted with a horizontal field strength of 0.18 + 0.02 oersted and a vertical field strength of 0.54 + 0.02 oersted. These field strengths shall be obtained with helmholtz coils or equivalent.

c. Standard signal transformer. - All tests requiring a transmitter shall be conducted with a standard signal transformer designed for this purpose. The signal transformer shall consist of a three-phase, three-wire stator surrounding a single phase two-wire rotor. The maximum input line to line impedance of the stator with the standard null meter as the rotor load shall be 133∠81° ohms ± 10 percent of the magnitude and angle, when measured at 1000 Hz with a standard laboratory instrument, such as General Radio Type 650-A impedance bridge, or equal.

The rotor when tuned to 800 Hz shall have a minimum output voltage of 635 millivolts when the line to line signal input voltage to the stator is 90 ± 10 millivolts at 800 Hz.

4.7 Service Conditions. - The service condition tests shall be conducted as specified herein. Upon completion of each service condition test, the equipments shall be subjected to and pass a visual inspection and the required electrical tests. No defects will be allowed.

4.7.1 Temperature-Altitude. - The compensator shall be subjected to the test as specified in Procedure I, Method 504, Table 504-I of MIL-STD-810, for Class I equipment. Electrical test shall be performed before and after these tests, to determine compliance with 3.9.1.

4.7.2 Humidity. - The compensator shall be subjected to the humidity test as specified in Procedure III, Method 507 of MIL-STD-810. Electrical test shall be performed before and after humidity test to determine compliance with 3.9.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

4.7.3 Vibration. - The compensator shall be subjected to vibration test as specified in Method 514.1, Curve B, Figure 514.1-2 of MIL-STD-810. Electrical test shall be performed before and after vibration to determine compliance with 3.9.3.

4.7.4 Salt-fog. - The compensator shall be exposed to salt-fog test as specified in Method 509 of MIL-STD-810, for 48 hours. The requirement of 3.9.4 shall be met. Operate the adjusting screws. Electrical Test shall not be performed.

4.7.5 Fungus. - The compensator shall be subjected to 28 days of the fungus test as specified in Method 508 of MIL-STD-810. Operational test is not required.

4.7.6 Dust. - The unit(s) shall be subjected to the dust test as specified in Method 510, Procedure I of MIL-STD-810 for compliance with 3.9.6.

4.8 Electrical. -

4.8.1 Neutral (zero) setting test. - The transmitter without compensator shall be set at the zero heading. The compensator with both North-South and East-West screws set at neutral, shall then be placed in its normal position on the transmitter. The resulting shift of the null position of the signal transformer rotor shall not exceed ± 1 degree. This test shall be repeated with transmitter set on the 90 degree heading.

4.8.2 Compensator range. - The transmitter without compensator shall be set at the zero heading. The compensator with both North-South and East-West screws set at neutral shall be placed in its normal position on the transmitter. The North-South screw shall then be turned 180 degrees. The shift in null position of the signal transformer rotor shall be between 8 and 13 degrees (plus or minus, depending on the direction of rotation of the adjustment screw).

The same screw shall then be turned an additional 360 degrees in the same direction and the resulting shift in null position of the signal transformer rotor shall be between 8 and 13 degrees. The test shall be repeated with the transmitter set on the 90 degree heading, using the East-West screw set at neutral and the North-South screw set 180 degrees both clockwise and counter-clockwise, from neutral position.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

4.8.3 Cross-Axis shift test. - The transmitter without compensator shall be set at the zero heading. The compensator shall then be placed in its normal position on the transmitter with the North-South screw set at neutral and the East-West screw first set at 180 degrees clockwise and then 180 degrees counter-clockwise from neutral. The resulting shift in null position of the signal transformer rotor shall not exceed ± 1.5 degrees in either case. The test shall be repeated with the transmitter set on the 90 degree heading, with East-West screw set at neutral and the North-South screw set 180 degrees both clockwise and counter-clockwise from neutral position.

4.9 Interchangeability. - The dimensions listed below shall be measured to determine compliance with the physical interchangeability requirements of 3.11. When a listed dimension is not within specified or design limits, it shall be considered a major defect:

a. External and internal dimension of moldings, mounting cover cases and insertable parts, when such dimension affects mating.

b. Dimension of cavities, when such dimension affects insertable items.

4.10 Visual-Mechanical. - Prior to and after assembly, the compensator shall be examined for defects in accordance with MIL-STD-252.

4.11 Weight. - The compensator shall be weighed on a suitable balance scale with an accuracy of ± 5 percent for weight to be measured, to determine compliance with 3.13.

4.12 Quality Conformance Inspection of Preparation for Delivery. - Preparation for delivery shall be inspected in accordance with MIL-P-116 to determine conformance to the packaging requirements of Section 5.

5. PREPARATION FOR DELIVERY

5.1 Preservation and Packaging. - Preservation and packaging shall be Level A or C, as specified (See 6.2).

5.1.1 Level A. -

5.1.1.1 Cleaning. - Compensator, Magnetic Flux CN-405( )/ASN, shall be cleaned in accordance with process C-1 of MIL-P-116.

5.1.1.2 Drying. - Compensator, Magnetic Flux CN-405( )/ASN, shall be dried in accordance with the applicable procedure of MIL-P-116.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

5.1.1.3 Preservation application. - None required.

5.1.1.4 Unit packaging. - Each Compensator, Magnetic Flux CN-405( )/ASN, shall be individually packaged Method III in accordance with MIL-P-116 as follows: cushion each item by wrapping in paperboard conforming to PPP-P-291, Type I and secure with tape conforming to PPP-T-45, Type III, Grade A. Place the cushioned item within a close-fitting box conforming to MIL-B-43014, Form 1, Style II. Closure shall be in accordance with the Appendix of the box specification.

5.1.1.5 Intermediate package. - A quantity of 12 each Compensator, Magnetic Flux CN-405( )/ASN, packaged as specified in 5.1.1.4 shall be placed within a close-fitting box conforming to MIL-B-43014, Form I, Style II. Closure shall be in accordance with the appendix of the box specification.

5.1.2 Level C. - Compensator, Magnetic Flux CN-405( )/ASN shall be preserved and packaged in a manner that will afford adequate protection against physical and environmental damage during shipment, handling and limited intransit storage.

5.2 Packing. - Packing shall be Level A, B or C as specified. Shipping containers for all levels shall be capable of stacking and supporting superimposed loads during shipment and storage without damaging the container(s) or its contents.

5.2.1 Level A. -

5.2.1.1 Consolidation. - A quantity of Compensator, Magnetic Flux CN-405( )/ASN, packaged as specified in 5.1, shall be packed within a close-fitting fiberboard box conforming to PPP-B-636, Type CF, class weather-resistant. Box closure shall be as specified in the appendix of the box specification. To facilitate palletization, fiberboard boxes shall be uniform in size and contain equal quantities of the packaged items to the greatest extent practicable.

5.2.1.2 Palletized load. - A quantity of containers, packed as specified in 5.2.1.1 shall be placed on a pallet, load type 1, conforming to MIL-STD-147 except that the pallet shall be softwood conforming to NN-P-71, Type IV, size 2. A fiberboard cap shall be employed over the load having two sides extending down the stacked load at least 12 inches to accommodate marking requirements. The cap shall be fabricated of fiberboard conforming to PPP-F-320, class weather-resistant, W5s or V3c. The load shall be "bonded" to the pallet by strapping.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

5.2.1.3 Less than palletized load. - When quantities per destination are less than a pallet load, the containers packed as specified in 5.2.1.1 shall be waterproofed, with tape conforming to PPP-T-76, in accordance with the taping requirements of the appendix of the box specification. A quantity of the waterproofed containers shall be packed within a close-fitting box conforming to PPP-B-601, overseas type; PPP-B-621, style 4, class 2; or PPP-B-585, style 2 or 3, class 3. When the gross weight exceeds 300 pounds, or the container length and width is 48 x 24 inches or more and the weight exceeds 100 pounds, 3 x 4 inch skids, laid flat, shall be applied in accordance with the requirements of the container specification, or if not specified in the specification, in a manner which will adequately support the item and facilitate the use of material handling equipment. Closure and strapping shall be in accordance with the applicable container specification or appendix thereto except that metal strapping shall conform to QQ-S-781, type I, class B.

5.2.2 Level B. -

5.2.2.1 Consolidation. - A quantity of Compensator, Magnetic Flux CN-405( )/ASN, packaged as specified in 5.1, shall be packed as specified in 5.2.1.1.

5.2.2.2 Palletized load. - A quantity of containers, packed as specified in 5.2.2.1, shall be palletized as specified in 5.2.1.2.

5.2.2.3 Less than palletized load. - When quantities per destination are less than a pallet load, the containers packed as specified in 5.2.2.1, shall be reinforced by pressure-sensitive filament tape conforming to PPP-T-97, type IV, as specified in the appendix of the box specification. No further packing shall be required.

5.2.3 Level C.

5.2.3.1 Consolidation. - A quantity of Compensator, Magnetic Flux, CN-405( )/ASN, packaged as specified in 5.1, shall be packed as specified in 5.2.1.1, except that the fiberboard boxes shall be class domestic.

5.2.3.2 Palletized load. - A quantity of containers, packed as specified in 5.2.3.1, shall be palletized as specified in 5.2.1.2, except that the fiberboard cap shall be class domestic.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

5.2.3.3 Less than palletized load. - When quantities per destination are less than a pallet load, the containers packed as specified in 5.2.3.1 shall be used as the shipping container. No further packing shall be required.

5.3 Marking. - In addition to any special marking required by the contract or order, interior packages and exterior shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended Use. - The Compensator, Magnetic Flux CN-405( )/ASN is intended to be used as part of the AN/ASN-43 Gyromagnetic Compass Set, to provide the means of cancelling the effect of the aircraft's permanent magnetic field on an induction compass transmitter.

6.2 Ordering data. - Procurement documents should specify the following:

a. Title, number, and date of this specification and any amendment thereto.

b. Levels of preservation and packaging and packing.

c. When rough handling and functional tests are required.

d. First Article Inspection. - Several samples of each item cited in Section 1 are required so that lengthy environmental tests can be completed on sample units while complete performance measurements can be made on other unit(s). (See 3.2)

e. Marking and shipping of samples.

f. Place of final inspection.

6.3 Nomenclature. - The parenthesis in the nomenclature will be deleted or replaced by a letter identifying the particular design. The contractor should apply for nomenclature in accordance with the applicable clause in the contract. (See 1.1)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

6.4 Verification Inspection. - Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive Quality Assurance Provisions established in the specification and contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product.

Custodian:
Army EL

Preparing Activity:
Army EL
Project No. 6605-A249

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION MIL-C-5539C(SH) COMPENSATOR, MAGNETIC FLUX CM-405( )/ASN

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

ESC-FM 1068-68

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

FOLD

Department of the Army
Headquarters
U.S.Army Electronics Command
Fort Monmouth, New Jersey 07703

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

Commanding General
U.S.Army Electronics Command
ATTN: AMSEL-[illegible]
Fort Monmouth, New Jersey 07703

FOLD

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.