INCH-POUND

MIL-C-70942 (AR)
30 **July 1990**

MILITARY SPECIFICATION

CIRCUIT CARD ASSEMBLY, POWER SUPPLY: 12922115

This specification is approved for use within the U.S. Army Armament, Munitions and Chemical Command and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification establishes the requirements for manufacture and acceptance of the power supply circuit card assembly (CCA), used in the M90 Radar Chronograph. (See 6.1) .

2* APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards and handbooks. The following specifications, standards and handbooks form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and standards (DODISS) and sUPPlement thereto, cited in the solicitation.

SPECIFICATIONS

MILITARY

MIL-F-13926 - Fire Control Materiel, Manufacture and Inspection, General Specification for
MIL-P-14232 - Parts, Equipment and Tools for Army Materiel, Packaging of
MIL-I-45607 - Inspection Equipment, Acquisition, Maintenance and Disposition of

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document, should be addressed to: Commander, U.S. Army ARDEC, ATTN: SMCAR-BAC-S, Picatinny Arsenal, New Jersey 07806-5000 by using the self-addressed Standardization Document Improvement Proposal (DD *Form* **1426)** appearing at the end of this document *or* **by** letter.

AMSC N/A FSC 1290

DISTRIBUTION STATEMENT A. Approvedforpublic release distribution isunlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-109	- Quality Assurance Terms and Definitions
MIL-STD-454	- Standard General Requirements for Electronic Equipment
MIL-STD-2164	- Environmental Stress Screening process for Electronic Equipment

(unless otherwise indicated, copies of federal and military specifications, standards and handbooks are available from: Standardization Documents Order Desk, Bldg. 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government documents, drawings and publications The following other Government documents, drawings and publications form a part of this specification to the extent specified herein. Unless otherwise specified, the issues shall be those in effect on the date of the solicitation.

DRAWINGS (See 6.4)

Us. ARMY ARMAMENT RESEARCH, DEVELOPMENT AND ENGINEERING CENTER (ARDEC)

12922105	- EMI Test Procedure
12922112	- Data Unit, Power Supply, Schematic Diagram
12922115	- Circuit Card Assembly, M90 Data Unit PS
12922225	- Environmental Test Methods

SPECIAL PACKAGING INSTRUCTIONS

P12922115	- Special Packaging Instructions for Circuit Card Assembly, M90 Data Unit PS

(Copies of drawings, publications, and other Government documents required by the contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

2.2 Order of Precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 General description. The power supply circuit card assembly (CCA) of the M90 Radar Chronograph is a DC to DC

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

converter located in the M90 data unit and provides all of the regulated and unregulated voltages for both the antenna and the data unit.

3.2 Components and assemblies. The components and assemblies shall comply with all requirements specified on Drawing 12922112, all associated drawings, and with all requirements specified in applicable specifications and standards. Where applicable, the CCA shall meet the requirements of MIL-F-13926 and MIL-STD-454 as follows :

Dimnensions and tolerances
b. Inorganic protective surface finishings
Part identification and marking
d. Workmanship
e. Soldering electrical connections

3.3 Performance requirements

3.3.1 Input Power. The CCA shall be capable to operate and withstand minimum 18 VDC to 30 VDC input voltage at 4.5 ADC maximum input current on the pins indicated in TABLE I.

3.3.2 Output Power. The CCA shall provide the following output power requirements to the pins indicated on TABLE I.

3.3.2.1 Antenna Power. Power line output for the M90 antenna unit. The voltage level is unregulated and shall be 26 VDC minimum when input power (see 3.3.1) is 18.0 VDC and 55 VDC maximum when input power is 30.0 VDC. Ripple shall be 2Vptp maximum. This output shall be protected by a fusistor.

3.3.2.2 Internal Power (+12 VDC). The CCA shall provide +12 +/- 0.6 Volts while output current is 150 mA maximum and ripple is 200 mVp-p maximum.

3.3.2.3 Internal Power (-12 VDC). The CCA shall provide -12 +/- 0.6 Volts while output current is 150 mA Maximum and ripple is 200 mVp-p maximum.

3.3.2.4 Internal Power (+5 VDC) . The CCA shall provide +5 +/- 0.25 Volts while output current is 2.0 A maximum and ripple is 100 mVp-p maximum.

3.3.2.5 Internal Power (-5 VDc). The CCA shall provide -5 +/- 0.5 **volts while output current is** 30 mA maximum and ripple is 200 mVp-p maximum.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

3.3.3 Power **line Protection. The CCA shall include protection against overvoltages that exceed the range specified in 3.3.1 and reverse voltage input power conditions.**

3.3.4 Power line monitor. The input power signal shall be provided for power monitoring (the monitoring circuit is not part of the CCA) . The input power voltage (see 3.3.1) is filtered and returned on pin 31.

Input Power	Output voltage
18.0 + .1 Volts	16.7 +/- 0.5 Volts
24.0 + .1 Volts	22.4 +/- 0.5 Volts
30.0 - .1 volts	28.5 +/- 0.5 Volts

3.3.5 Power indicator lamp. The CCA shall supply voltage to indicator lamps when power is applied to the CCA. **The input power voltage (see 3.3.1) is filtered and returned on pin 10.**

3.3.6 Relay Power. The CCA shall supply voltage to the M90 relays when power is applied to the CCA. The input power voltage (See 3.3.1) is filtered and returned on pins 12 and 13.

3.3.7 Select resistor. Output line on pin 8 of selected resistor to permit choosing an appropriate resistor when determining the +12V output voltage (See **3.3.2).**

3.3.8 Short circuit protection. The low voltage outputs: +5V, -5V, +12V and -12V shall be short circuit protected.

3.3.9 Electrical inPut/outPut interface. Electrical design of the power supply shall be in accordance with the pin assignment, as shown in TABLE I.

TABLE 1. POWER SUPPLY CIRCUIT CARD ASSEMBLY CONNECTOR CONTACTS

Connector	Pin	Signal Name
P4	1	**POWER GROUND**
P4	**2**	**+ 5V**
P4	**3**	**INPUT POWER**
P4	**4**	**POWER GROUND**
P4	**5**	**POWER GROUND**
P4	**6**	**POWER GROUND**
P4	**7**	**POWER GROUND**
P4	**8**	**SELECT RESISTOR**
P4	**9**	**POWER GROUND**
P4	**10**	**LAMP POWER**
P4	**11**	**POWER GROUND**
P4	**12**	**RELAY POWER**

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

Connector	Pin	Signal Name
P4	13	RELAY POWER
P4	14	INPUT POWER
P4	15	INPUT POWER
P4	16	INPUT POWER
P4	17	-12V
P4	18	-12V
P4	19	-12V
P4	20	+12V
P4	21	+12V
P4	22	+12V
P4	23	-5V
P4	24	-5V
P4	25	+5V
P4	26	INPUT POWER
P4	27	+ 5V
P4	28	+ 5V
P4	29	+5V
P4	30	ANTENNA POWER
P4	31	POWER LINE MONITOR
P4	32	+12V
P4	33	-5V
P4	34	+5V
P4	35	ANTENNA POWER
P4	36	ANTENNA POWER
P4	37	-12V
P4	38	POWER GROUND
P4	39	POWER GROUND
P4	40	POWER GROUND
P4	41	POWER GROUND
P4	42	POWER GROUND
P4	43	POWER GROUND
P4	44	POWER GROUND
P4	45	POWER GROUND
P4	46	POWER GROUND
P4	47	POWER GROUND
P4	48	ANTENNA POWER

3.4 Environmental requirements.

3.4.1 High temperature. The CCA shall meet the requirements of 3.2 and 3.3 when thermally stabilized at +125 degrees F. The CCA when subjected to storage temperature of +150 degrees F shall meet the requirements of 3.2 and 3.3 when returned and thermally stabilized at ambient temperature.

3.4.2 Low temperature. The CCA shall meet the requirements of 3.2 and 3.3 when thermally stabilized at -50 degrees F when returned and thermally stabilized at ambient temperature.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

3.4.3 Conformal coating. Each CCA, after completion of production stage and before ESS tests, shall be conformably coated using AR type coating, 0.003+/-0.002 inches thickness.

3.4.4 Environmental stress screening (ESS) temperature. The CCA shall meet the requirements in 3.2 and 3.3, after being subjected to 40 hours of temperature cycling between O degrees F and +125 degrees F in accordance with 5.1.2.1 of MIL-STD-2164.

3.4.5 Environmental stress screening (ESS) vibration. The CCA shall meet the requirements in 3.2 and 3.3, after being subjected to random motion in the range of 20 to 2000 Hz for 5 minutes at an axis perpendicular to the largest surfaces of the CCA . Acceleration spectral density is 6.06 g. RMS in accordance with 5.1.1 of MIL-STD-2164.

3.4.6 EMI . The CCA shall meet the requirement of Drawing 12922105 when integrated into an M90 RADAR CHRONOGRAPH supplied as Government Furnished Material.

3.5 First article inspection. When specified in the contract or purchase order, a sample shall be subjected to first article inspection in accordance with the technical provisions herein (see 4.3) .

3.6 WorkmanshiP. The workmanship requirements of MIL-F-13926 and MIL-STD-454 shall apply.

3.7 Fabrication. The CCA shall be manufactured in accordance with Drawings 12922112 and 12922115.

3.8 Materials. Materials shall be in accordance with applicable drawings and specifications.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define quality assurance terms used herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5 and all applicable drawings. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 General provisions . The component and subassembly inspection requirements of MIL-F-13926 and MIL-STD-454 forms a part of the Quality Assurance Provisions of this specifications.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Special sampling (see 4.5).

4.2.1 Inspection conditions. Unless otherwise specified, all examinations and tests shall be conducted at the following standard ambient conditions:

	Temperature	+60 degrees to +90 degrees F.
b.	Relative humidity	90% RH maximum.
c.	Pressure	28 to 32 inches of Hg.

4.3 First article inspection.

4.3.1 First article submission. The contractor shall submit a first article sample as designated by the contracting officer consisting of three CCA for inspection in accordance with 4.3.2.

4.3.2 Inspections to be Performed. First article assemblies, components and test specimens may be subjected by the Government to any or all of the examinations and tests specified in TABLE II and TABLE III herein and to any or all requirements of the applicable drawings.

4.3.3 Rejection. If any assembly, component or test specimen fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of any CCA to comply with any of the stated requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

4.4 Quality conformance inspection.

4.4.1 Inspection lot formation. The term "inspection lot" is defined as a homogeneous collection of units of product from which a representative sample is drawn or which is inspected 100 percent to determine conformance with applicable requirements. Units of product selected for inspection shall represent only the inspection lot from which they are drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, using the same materials and methods, in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions, and complies with the provisions for submission of product as specified in MIL-STD-105. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein, regardless of the type of inspection procedure which is being applied to determine conformance with requirements.

4.4.2 Examinations and tests.

4.4.2.1 Components, assemblies and subassemblies. Al 1 components, assemblies and subassemblies shall be inspected in accordance with the inspection provisions contained in this specification and Quality Assurance Provisions (QAP) listed in the Technical Data Package (TDP) . In the absence of QAPs, the applicable quality assurance provisions of MIL-F-13926 shall apply.

4.4.2.2 Final acceptance inspection. Subsequent to first article approval, examination and tests related to Section 3 herein shall be performed in accordance with the sampling plans specified in 4.4.2.3 herein. Examination and test for packaging and marking shall be in accordance with MIL-P-14232 and Section 5 herein. The tabulated classification of defects in 4.4.2.3 shall constitute the minimum inspection to be performed by the supplier after first article approval and prior to Government acceptance or rejection by item or lot.

4.4.2.3 Functional tests. The tests in TABLE II shall be performed as noted under the characteristics.

TABLE II. Functional tests
(100% Inspection)

No.	Characteristics	Requirement	Test Procedure
Critical:	None	None	N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

Major:			
	Performance	3.3	4.7.1
102	Conformal Coating	3.4.3	Visual
103	ESS Temperature	3.4.4	4.7.2.1
104	ESS Vibration	3.4.5	4.7.2.2
Minor:			
201	Workmanship	3.6	Applicable Drawing/ Visual
202	Fabrication	3.7	Applicable Drawing/ Visual
203	Materials	3.8	Applicable Drawing/ Visual

4.5 Special sampling. Three circuit card assemblies shall be selected at random as a special sample from each lot or each 150 produced, whichever comes first. The sample shall meet the requirements and tests of TABLE III.

Table 111. Environmental sampling tests

No.	Characteristics	Requirement	Test Procedure
Critical:	None	None	N/A
Major:			
	High temperature	3.4.1	4.7.3.1
302	Low temperature	3.4.2	4.7.3.2
303	EMI	3.4.6	4.7.3.3
Minor:	None	None	N/A

4.6 Inspection equipment

4.6.1 Government-furnished inspection equipment. Where the contract provides for Government-furnished test equipment supply and maintenance of test equipment shall be in accordance with the applicable requirementts of MIL-I-45607.

4.6.2 Contractor-furnished inspection equipment.

4.6.2.1 Government design. Unless otherwise specified in the contract, all inspection equipment identified by drawing number in specifications or QAPs forming a part of the contract shall be supplied by the contractor in accordance with the design specified. The contractor may, however, propose alternatives to Government designs for approval in accordance with 6.4.

4.6.2.2 Contractor design. The contractor shall design and supply inspection equipment compatible with the "Methods of

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

Inspection" specified in 4.7 of this specification and with the component inspection procedures specified in "Examination" and "Test Facilities" requirements of MIL-F-13926 whenever Government designs are not specified (see 4.6.2.1) . Since tolerance of test equipment is normally considered to be within 10 percent of the product tolerance for which it is intended, this inherent error in the test equipment design must be considered as part of the prescribed product tolerance limit. Thus , concept, construction, materials, dimensions, and tolerances used in the design of test equipment will reliably indicate acceptability of a product which does not exceed 90 percent of the prescribed tolerance limit and permit positive rejection when non-conforming. Construction shall be such as to facilitate routine calibration of test equipment. Contractor inspection equipment designs shall be submitted-for approval in accordance with 6 .4.

4.6.2.3 Inspection equipment design requirements.

4.6.2.3.1 Temperature testing. The volume of the test chamber shall conform to the test facilities requirements of MIL-F-13926. The air temperature at the control sensor shall be in accordance with the specified requirements within plus or minus 2.5 degrees F (1.4 degrees C) . The temperature-gradient across the cross-sectional area occupied by the test item shall not exceed 0.5 degrees F' per foot in any direction. The heat source of the test chamber shall be so located that radiant heat, if used, will not fall directly on the test item. Thermocouples or equivalent temperature sensors utilized to determine or control the specified chamber temperature shall be centrally located within the test chamber within the supply airstream, or in the return airstream, whichever provides the specified test condition at the item under test and shall be baffled or otherwise protected against radiation effects.

4.6.2.3.2 Fabrication, setup and calibration. Design and fabrication of test equipment shall be such that it incorporates the features of rigidity, stability, and ease of maintenance. Setup and calibration equipment necessary for certification of the testing equipment accuracy shall be furnished and will become a part of the testing equipment. Operating and calibration instruction shall be prepared and submitted to the procuring activity.

4.7 Methods of inspection. Unless otherwise specified in the contract, the following procedures shall be utilized to conduct specified tests. If the contractor chooses to use alternate test procedures, a detailed description of the set-up and procedure shall be submitted to the government procuring agency for approval prior to use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

4.7.1 Performance. The performance parameters of 3.3.1 through 3.3.10 shall be demonstrated either manually or using a contractor designed, Government-approved, automatic test fixture simulating the conditions and making the measurements of providing a visual indication of a PASS or FAIL condition. Test shall be conducted before ESS testing, and after completion of the ESS testing. The performance test shall verify that each of the following CCA functional characteristics conform to the requirements of 3.3.1 through 3.3.10 inclusive. Output Power should be verified at 18.0 to 30.0 VDC input voltage in accordance with TABLE I and 3.3.2 and:

4.7.1.1 Antenna Power output voltage. 26 VDC minimum and 55 VDC maximum while output current is 1A maximum and ripple 2 Vp-p maximum.

4.7.1.2 +12V voltage. +11.4 VDC to +12.6 VDC, with 80 +/- 4 ohm resistive load and ripple of 200 mVp-p maximum.

4.7.1.3 -12V voltage. -12.6 VDC to -11.4 VDC, with 80 +/- 4 ohm resistive load and ripple of 200 mVp-p maximum.

4.7.1.4 +5 voltage. 4.75 to 5.25 VDC, with 2.5 +/- 0.1 ohm resistive load and ripple of 100 mVp-p maximum.

4.7.1.5 -5V voltage. -5.5 VDc to -4.5 VDC, with 167 +/- 8 ohm resistive load and ripple of 200 mVp-p maximum.

4.7.1.6 Reverse Voltage Protection. Reverse voltage protection on power input lines shall be verified by applying a reverse voltage supply to the CCA, and verify that the input current is less than 0.01 Ampere.

4.7.1.7 Power. Line Monitor, Lamp Power and Relay Power shall be tested for short circuit between pins 12, 13, 31, 10 of P4. Output voltages shall be verified on pins 12, 31 of P4 as follows:

Input Power	Output voltaae
18.0 + .1 Volts	16.7 +/- 0.5 Volts
24.0 + .1 Volts	22.4 +/- 0.5 Volts
30.0 - .1 volts	28.5 +/- 0.5 Volts

4.7.1.8 Short circuit Protection. Short circuit protection shall be tested by shorting each of the outputs (+5V, -5V, +12V and -12V only) for at least 30 seconds and then verify that the supply has recovered, by measuring the output voltage according to 4.7.1.1.

4.7.2 Environmental stress screening.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

4.7.2.1 ESS temperature. Testing equipment utilized in this test shall conform to the requirements of 4.6.2.3.1. The circuit card shall be placed in the chamber and subjected to a 40-hour run-in period which includes vibration and operation at temperature extremes. The temperature shall be gradually raised at a rate not to exceed 2 degrees F per minute until thermally stabilized at +125 degrees F for 4 hours duration. Then the temperature of the chamber shall be decreased to O degrees F at the same rate for another 4 hours. Subsequent to the above temperature extremes (+125 degrees F and O degrees F), the CCA shall not have been damaged or adversely affected and shall meet the requirements in 3.2 and 3.3 of this specification for the entire 40-hour run-in period.

4.7.2.2 ESS vibration. The CCA in an operating mode shall be exposed to 5 minute burst of random vibration. Failures occurring during this five minute test shall be accrued (if possible) and corrected at the conclusion of the 5 minute period in accordance with the requirements of 3.2 and 3.3. The random vibration spectrum shall be:

20 - 80 Hz at 3 dB/octave rise
80 - 350 Hz at 0.04 g sq/Hz
350-2000 Hz at 3 dB/octave rolloff

The motion shall be applied perpendicular to the largest surfaces of the CCA.

4.7.3 Environmental sampling tests

4.7.3.1 High temperature. This test shall be conducted in accordance with Drawing 12922225. Subsequent to the exposure, the CCA shall not be damaged or adversely affected and shall meet the requirements of 3.4.1.

4.7.3.2 Low temperature. This test shall be conducted in accordance with Drawing 12922225. Subsequent to the exposure, the CCA shall not be damaged or adversely affected and shall meet the requirements of 3.4.2.

4.7.3.3 EMI. The test shall be conducted in accordance with Drawing 12922105 when the CCA is integrated into an M90 RADAR CHRONOGRAPH (NSN: 1290-01-073-0764).

5. PACKAGING

5.1 Packaging, Packing, and marking. Packaging, packing and marking shall be in accordance with MIL-P-14232 and Special Packaging Instruction P12922115. The level of protection shall be specified in the procurement document.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful but is not mandatory.)

6.1 Intended use. The circuit card assembly is intended for use in the M90 Radar Chronograph.

6.2 Acquisition requirements. Procurement data should specify the following :

Title, number and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1).
Applicable stock number.
d. First Article Sample requirements (see 3.5) .
e. Level of preservation and packing (see 5.1) .
f. Serialization requirements, if applicable.
g. Certificate of conformance for each lot or shipment of product.

6.3 Consideration of data retirements. The following data requirements should be considered when this specification is applied on a contract. The applicable Data Item Descriptions (DID's) should be reviewed in conjunction with the specific acquisition to ensure that only essential data are requested/provided and that the DID's are tailored to reflect the requirement of the specific acquisition. To ensure correct contractual application of the data requirements, a Contract Data Requirements List (DD Form 1423) must be prepared to obtain the data, except where DOD FAR Supplement 27.475-1 exempts the requirement for a DOD Form 1423.

Reference Paragraph	DID Title	DID No.	Suggested Tailoring
4.6	Quality Engineering Acceptance Inspection Equipment Description Documentation	DI-R-1714	None

6.4 Drawings. Drawings listed in Section 2 of this specification under the heading U.S Army Armament Research, Development and Engineering Center (ARDEC), may also include drawings prepared by, and identified as, U.S. Army Armament, Research and Development Command (ARRADCOM), Frankford Arsenal, Rock Island Arsenal or Picatinny Arsenal drawings. Technical data originally prepared by these activities is now under cognizance of ARDEC.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

6.5 Submission of contractor inspection equipment designs for approval. Submit two copies of designs as required: Commander, U.S. Army AMCCOM, ATTN: AMSMC-QAF-I(D), Picatinny Arsenal, NJ 07806-5000. This address will be specified on the Contract Data Requirements List, DD Form 1423 in the contract. Unless otherwise specified, data item DI-R-1714 or as stated in the contract will apply.

6.6 Definitions.

6.6.1 Contractor. Unless otherwise" specified, the word Contractor used throughout this specification shall mean any supplier or producer of items or material to the Government. This shall include commercial contractors, sub-contractors, Government Owned-Contractor Operated (GOCO), and Government Owned-Government Operated (GOGO) plants.

6.6.2 Technical data Package. A technical description of an item adequate for use in procurement. The description defines the required design configuration and assures adequacy of item performance. It consists of all applicable lists, specifications, standards, models, performance requirements, quality assurance provisions and packaging data.

6.7 Government furnished property. The contracting officer should arrange to furnish the property listed in 3.4.6.

6.8 Subject term (key word) listing.

M90 Radar Chronograph (M90)
Circuit Card Assembly (CCA)

Custodian:
Army -AR

Preparing activity:
ARMY-AR

(Project 1290-A454)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-C-70942 (AR)	30 July 1990

3. DOCUMENT TITLE

CIRCUIT CARD ASSEMBLY, POWER SUPPLY: 12922115

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial	(2) AUTOVON
US Army ARDEC Standardization & Specification Office	(201) 724-6674	880-6674
c. ADDRESS (Include Zip Code) ATTN: SMCAR-BAC-S Picatinny Arsenal, NJ 07806-5000	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340	

Source: https://assist.dla.mil - Downloaded: 2026-10-23T04:15Z
Check the source to verify that this is the current version before use.