MIL-S-27396B(USAF)
11 August 1972
SUPERSEDING
MIL-S-27396A(USAF)
6 April 1966

MILITARY SPECIFICATION

STAIRCASE, AIRCRAFT BOARDING, TRUCK-MOUNTED

1. SCOPE

1.1 This specification covers a truck-mounted, aircraft boarding staircase, designated A/S32S-3.

2. APPLICABLE DOCUMENTS

* 2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of the specification to the extent specified herein.

SPECIFICATIONS

Military

MIL-P-514	Plates, Identification, Instruction And Marking, Blank
MIL-W-5044	Walkway Compound, Nonslip, And Walkway Matting, Nonslip
MIL-W-5050	Walkway, Coating And Matting, Nonslip, Aircraft, Application Of
MIL-P-5315	Packing, Preformed, Hydrocarbon Fuel Resistant
MIL-H-5606	Hydraulic Fluid, Petroleum Base; Aircraft, Missile, And Ordnance
MIL-T-45338	Trucks: Commercial, 4,800 to 10,000 Pounds GVW, 4 X 2

STANDARDS

Military

MIL-STD-100	Engineering Drawing Practices
MIL-STD-130	Identification Marking Of US Military Property
MIL-STD-143	Standards And Specifications, Order Of Precedence For The Selection Of
MIL-STD-162	Materials Handling Equipment: Preparation For Shipment, Storage, Cyclic Maintenance, Routine Testing And Processing
MIL-STD-808	Finishes, Protective, And Codes, For Finishing Schemes For Ground And Ground Support Equipment

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T11:40Z
Check the source to verify that this is the current version before use.

MIL-STD-826	Electromagnetic Interference Test Requirements And Test Methods
MIL-STD-831	Test Reports, Preparation Of
MIL-STD-889	Dissimilar Metals

Air Force-Navy Aeronautical

AN6227	Packing, "O" Ring Hydraulic

DRAWINGS

Air Force

49B6412	Ring - Packing, Back-Up
49B6413	Ring - Packing, Back-Up

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Preproduction. This specification makes provisions for preproduction testing.

3.2 Components. The staircase shall consist of the following major components:

Item or System Name	See Requirement
Chassis	3.7
Frame	3.8
Height adjustment system	3.9
Lighting system	3.10

3.3 Selection of specifications and standards. Specifications and standards for necessary commodities and services not specified herein shall be selected in accordance with MIL-STD-143.

3.4 Materials.

3.4.1 Metals. Metals shall be of the corrosion-resistant type or treated to resist corrosion due to fuels, salt spray, or atmospheric conditions likely to be met in storage or normal service.

* 3.4.1.1 Dissimilar metals. Unless protected against electrolytic corrosion, dissimilar metals shall not be used in intimate contact with each other. Dissimilar metals are defined in MIL-STD-889.

3.5 Design and construction. The staircase shall be so designed and constructed that no parts will work loose in service. It shall be built to withstand the strains, jars, vibrations, and other conditions incident to shipping, storage, and service.

3.5.1 Reliability. The staircase shall have a reliability of not less than 0.978 at 0.9 confidence level.

Source: https://assist.dla.mil -- Downloaded: 202610-20T11:40Z
Check the source to verify that this is the current version before use.

3.5.2 Maintainability. The staircase shall be designed and constructed as specified herein and to provide the following:

a. Minimum number of parts consistent with reliability and performance specified herein.

b. Minimum amount of training and time necessary for assembly, disassembly, location of trouble sources, and maintenance including servicing. Where practical, parts and components shall be located or positioned for rapid and simple inspection and recognition of excessive wear or potential failure.

c. Permit adjustments, servicing, replacement of parts and components, and other maintenance with minimum disturbance to other equipment parts or components. Parts and components shall be located for ample and rapid access unless performance or reliability will be appreciably degraded by the accessible location. In performing maintenance, if engineering reasoning or data determines that physical or visual interference between items cannot be avoided, the item predicted to require the most maintenance shall be located for best accessibility.

d. Permit maintenance with general-purpose tools and equipment normally available commercially. Use of special-purpose tools and equipment shall be subject to approval by the procuring activity.

e. Minimum number of tools required for maintenance by design practices such as reducing the variety of bolt head sizes to the practicable minimum.

f. Foolproofness - Where improper installation of an item could cause malfunctioning of that item or the system in which it is installed, an unsymmetrical mounting means shall be provided where practical. This mounting shall be so designed that the item can be installed only in its proper operating position. If any unsymmetrical mounting means is not practical, the item shall be so mounted that its proper operating position can be readily and visibly determined by service maintenance personnel.

* 3.5.3 Access to passenger entrance. The staircase shall be designed to provide a safe and easy means of access to the passenger entrance of the aircraft. The top platform shall be adjustable to all heights above ground level within the range of 100 to 160 inches.

3.5.4 Ramp aircraft mating. The adjustment provisions shall be so designed that the top platform and its sliding side panels will mate with aircraft loading doors at any height within the required operating range without forming a step or gap of more than 2 inches between the doorsill of the aircraft and the top platform. The platform side panels shall not strike the side of the aircraft serviced by this staircase nor form a gap at the top of the panel between the side panel and aircraft of more than 3 inches when adjusted for the aircraft being serviced.

* 3.5.4.1 Top platform side panel rollers. If rollers are utilized on the top platform side panels, the roller grooves shall be configured to conform to the shape of the track on which they operate and the grooves shall be of sufficient depth to prevent the rollers from coming off the track. Rollers shall be fabricated from solid material (aluminum or cadmium plated steel); cast rollers are not permitted.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T11:40Z
Check the source to verify that this is the current version before use.

3.5.5 Wiring. The electrical wiring system shall be of a standard commercial, outdoor, weatherproof construction including wire, junction boxes, switches, fixtures, and receptacles. The wire shall be of adequate rating for the power load imposed and shall be securely mounted throughout the staircase.

3.5.6 Lifting eyes. The staircase shall be provided with four lifting eyes (two forward and two rearward) to enable the stairway to be lifted from the truck by a cradle sling with the cables vertical. The inside diameter of each lifting eye shall be not less than 2 inches. Each lifting eye shall support a vertical load of 2,500 pounds.

3.5.7 Drainage provisions. The staircase shall include provisions for the continuous drainage of water from the steps, platform, structural members, and other components.

3.5.8 Ground clearance. The staircase shall have a minimum ground clearance of 9 inches.

* 3.5.9 Air transportability. The completely assembled staircase shall be transportable in a type C-124 and C-133 aircraft.

* 3.5.9.1 Shipping weight and center-of-gravity location. The shipping weight of the completely assembled staircase in the air transportable condition shall be marked in a conspicuous location. The center-of-gravity along each axis influencing the method of loading and tiedown shall be marked on the staircase.

* 3.6 Performance. The staircase shall withstand the following conditions without detrimental effect to subsequent operation:

a. Operation in ambient temperatures ranging from +125° Fahrenheit (F) to -35°F. When operating temperatures are below -20°F, power plant heaters as specified in MIL-T-45338 shall be provided (see 6.2).

b. Intermittent wind velocities up to 60 miles per hour (mph) and unsupported by aircraft contact from any direction when fully extended with 500 pounds on the top platform. Under these conditions, the horizontal movement of the top platform shall not exceed 1-5/8 inches in either direction.

3.6.1 Concentrated load. Each step and the top platform of the staircase shall withstand a concentrated load of 500 pounds on any square foot.

3.6.2 Static load. The fully extended staircase shall withstand a combined static load of 250 pounds per step and 1,000 pounds on the platform. Total deflection at the staircase platform shall be less than 1 inch from the unloaded to fully loaded condition. The fully extended staircase, unsupported by aircraft contact, shall withstand a combined static load of 250 pounds per step and 1,000 pounds on the platform.

3.7 Chassis. The truck chassis shall conform to MIL-T-45338, class D, type IV, (see 6.2). Modifications to the truck to satisfy requirements herein shall be accomplished by the staircase manufacturer. The following options of MIL-T-45338 shall apply.

3.7.1 Cooling system. A heavy-duty cooling system shall be provided for 125°F operation.

Source: https://assist.dla.mil -- Downloaded: 2026l0-20T11:40Z
Check the source to verify that this is the currentversion before use.

3.7.2 Generator or alternator. A heavy-duty, low-cut-in, 40 ampere (amp) (minimum) generator or alternator shall be provided.

3.7.3 Transmission. The truck shall be provided with an automatic transmission. The transmission shall provide for driver selection of individual gears or selection of ranges of gears required for efficient operation throughout the speeds specified under the mobility requirements. (Full power shift features shall be provided.) The shift control shall incorporate a positive indicator for each gear or range selected. The vehicle shall be so protected that the operator cannot start the engine with the transmission in gear or inadvertently shift from forward to reverse gear. The transmission shall have a torque capacity adequate to transmit maximum net engine torque throughout all reductions. A foot-actuated clutch member shall not be used. The transmission assembly shall be of a commercial design and capacity that has been produced and supplied as a part of a commercial vehicle.

3.7.4 Tire tread. Tires shall use either military nondirectional cross-country or nondirectional mud and snow tread.

3.7.5 Items not required. The following items shall not be provided:

a. Positive traction differential

b. Power brakes

c. Telescoping roof

d. Spare wheel assembly

e. Tire carrier

f. Jack and wheel nut wrench.

3.7.6 Roof window. A glareproof, waterproof installation of safety glass window shall be provided in the cab roof to facilitate positioning of the staircase at the aircraft. The window shall be of sufficient size to permit the driver of the vehicle to view, from his normal driving position, the entire underside of the mating area of the aircraft.

3.8 Frame. The staircase frame shall be constructed of structural members of sufficient strength to rigidly support personnel traversing the stairs. The frame shall be reinforced to prevent sidesway and to withstand the step and platform loads specified in 3.6.1 and 3.6.2.

3.8.1 Steps and top platform. Each step shall be a minimum of 36 inches wide with a 12 ±1/2 inch tread. The vertical rise between adjacent steps shall be within the range of 7-1/2 to 8-1/2 inches. The step treads shall not deviate more than 1-1/2 degrees from the horizontal regardless of platform elevation. Step risers shall connect the front of each step with the rear of the next lower step at each platform height within the operating range. Step and step riser design shall insure that usable tread will be a minimum of 9 inches. The top step shall be made in the form of a platform. The width of the platform shall substantially conform to the width of the steps and the length shall be 60 ±2 inches. For other than loading operations, the bottom step shall be so designed that it can be easily positioned to provide the ground clearance specified in 3.5.8.

Source: https://assist.dla.mil -- Downloaded: 20260-20T11:40Z
Check the source to verify that this is the current version before use.

3.8.2 Nonslip step coating. The steps and top platform shall be coated with type II nonslip material conforming to MIL-W-5044, applied in accordance with MIL-W-5050.

3.8.3 Handrails. Handrails shall be provided on each side of the staircase and shall extend from the base of the stairs to the aircraft end of the top platform. The handrails shall maintain a constant height of 36 ±1 inch above the steps and top platform of all platform heights within the operating range of the staircase. This dimension shall be measured along a vertical line from the handrail to the nose of each step. Both sides of the handrails on the platform shall be hinged, mounted on a rail, or easily collapsed to permit opening and closing of the aircraft entrance doors with the staircase in place.

3.8.4 Siding. Solid, durable, metal siding shall be provided and shall extend upward a minimum of three-fourths the distance from the steps to the handrails, and full height for platform panels.

3.8.5 Bumper. A round, tubular, rubber bumper shall be securely fastened to the front of the platform to protect the aircraft from possible damage when staircase is firmly drawn against the aircraft. The outside dimension of the bumper shall be a minimum of 7 inches, the inside dimension a minimum of 5 inches.

* 3.9 Height adjustment system. A hydraulic height adjustment mechanism shall be provided to elevate and lower the staircase through its entire operating range. The system shall be suitable for operation in temperatures ranging from -35° to +125°F. The system shall be designed to operate the unloaded staircase from the lowest to the highest position in a maximum of 2 minutes throughout the temperature range. A relief valve, preset to be released at 125 percent of the normal operating pressure, shall be provided. All hydraulic fittings and lines (rubber or metal) shall be of a high-pressure type. The system shall show no leaks or breakage when the staircase is subjected to the loads specified in 3.6.1 and 3.6.2. When so loaded, the platform shall not settle more than 1/2 inch in height in a 4-hour period. Operating controls shall be provided inside the cab of the truck to permit raising and lowering. Positive removal stops shall be provided to prevent over extension of the upper ramp assembly.

3.9.1 Actuating pump. Power used for height adjustment shall be furnished by a hydraulic pump directly driven by the truck engine.

* 3.9.2 Hydraulic reservoir. The storage tank shall be of welded steel construction and shall have a capacity of not less than 110 percent of the fluid required for the hydraulic system operation. The tank shall be equipped with a filler neck at the top, fluid level indicator, a drain plug at the bottom, and an air vent in the filler cap. The storage tank breather and filler cap shall provide protection against contamination of hydraulic fluid by direct impingement or seepage. An oil strainer shall be installed in the hydraulic suction line. Means shall be incorporated in the tank to prevent oil from splashing out when the staircase is moved. The hydraulic system and tank shall be filled with hydraulic fluid conforming to MIL-H-5606. A filter system shall be installed in the pump pressure line. The filter shall be so located as to provide easy access for element replacement. Degree of filtration shall be from 10 to 40 microns.

Source: https://assist.dla.mil -- Downloaded: 2026l0-20T11:40Z
Check the source to verify that this is the currentversion before use.

3.9.3 Hydraulic cylinders. Where practicable, the cylinder components shall conform to AN standards. The piston shall be fitted with O-type rubber packings conforming to MIL-P-5315 and AN6227, and protected with backup rings conforming to Drawing 49B6412 or 49B6413. A seal shall be installed to prevent the entrance of moisture into the cylinders. The piston rods shall be provided with an electrodeposited hard chromium finish.

3.9.4 Lift lock. The staircase shall be provided with a device(s) to automatically lock the staircase in any position attained by the lifting mechanism. The lock shall be positive. A release control button shall be provided inside the cab of the truck to disengage the lift lock. If the lock is not automatically unlocked by actuation of the raising and lowering control, it shall be capable of withstanding full load as imposed through hydraulic system up to relief valve pressures (see 3.9).

3.9.5 Supports. Hydraulic outriggers, spring lockouts, or other devices may be used in obtaining the rigidity; however, the use of such devices shall not change the platform height after initial positioning to the aircraft. If outriggers are used, they shall be spring retractable under all specified temperature extremes within 30 seconds without the use of a power hydraulic system.

3.10 Lighting system. The staircase shall be equipped with the following lights to provide adequate illumination for night operation. Each set of lights shall be controlled by separate commercial toggle switches.

3.10.1 Step light. The staircase shall be equipped with sufficient lights to insure that the platform and every step will be clearly visible at night to personnel ascending the stairway. The lights shall be recessed flush with the staircase, weatherproofed, and shall provide a minimum illumination of 5 foot-candles over the entire step and platform area. The step light switch shall be located inside the cab of the truck.

3.10.2 Spotlight. A high-quality, adjustable, waterproof, commercial spotlight shall be so mounted on the cab to illuminate the underside of the platform, bumper, aircraft door, and adjacent area to facilitate positioning the staircase at the aircraft. The lamp shall be a 12-volt, 100-watt, 300-hour life, screw terminal lamp (American Standards Association No. 4595, or equal). The spotlight switch shall be mounted on the instrument panel and shall be readily accessible to the driver.

3.11 Electromagnetic interference. The electrical components shall be so designed that when assembled, employing optimum suppression techniques, the unit will meet the requirements of MIL-STD-826, method 7001.

3.12 Part numbering of interchangeable parts. All parts having the same manufacturer's part number shall be functionally and dimensionally interchangeable. The item identification and part number requirements of MIL-STD-100 shall govern the manufacturer's part numbers and changes thereto.

3.13 Finishes and protective coatings. Cleaning, painting, plating, anodic films and chemical treatments shall be in accordance with MIL-STD-808. The color shall be yellow film designation DG.

Source: https://assist.dla.mil -- Downloaded: 202640-20T11:40Z
Check the source to verify that this is the currentversion before use.

3.14 Markings.

3.14.1 The words LIFT HERE shall be stenciled in close proximity to each lifting eye of the staircase.

3.14.2 Instruction plate. A metal instruction plate conforming to MIL-P-514 shall be installed in a conspicuous location on the dash panel in the cab. The plate shall contain the following information:

CAUTION

THIS STAIRCASE IS EQUIPPED WITH RADIO INTERFERENCE SUPPRESSION DEVICES. CARE SHOULD BE EXERCISED DURING MAINTENANCE TO RETAIN AND REINSTALL THESE DEVICES PRIOR TO REUSE OF STAIRCASE.

3.14.3 Data plates. The manufacturer's standard nameplates and data plates will be acceptable but shall be permanently attached to the staircase. The contract number, date of delivery, and inspector's stamps shall be shown on the data plate.

3.15 Identification of product. Equipment, assemblies, and parts shall be marked for identification in accordance with MIL-STD-130.

3.16 Workmanship. The staircase, including all parts and accessories, shall be fabricated and finished in a workmanlike manner. Particular attention shall be given to freedom from blemishes, defects, burrs, and sharp edges; accuracy of dimensions, radii of fillets, and marking of parts and assemblies; thoroughness of soldering, welding, brazing, painting, wiring, and riveting; alignment of parts and tightness of assembly screws and bolts; et cetera.

3.16.1 Dimensions and tolerances. Dimensions and tolerances not specified shall be as close as is consistent with the best commercial practice. Where dimensions and tolerances may affect the interchangeability, operation, or performance of the staircase, they shall be held or limited accordingly.

3.16.2 Riveting. Riveting operations shall be performed to insure tightness and satisfactory heading of rivets.

3.16.3 Cleaning. The staircase shall be thoroughly cleaned and loose, spattered, or excess solder, metal chips, and other foreign material removed during and after final assembly.

4. QUALITY ASSURANCE PROVISIONS

* 4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 20260-20T11:40Z
Check the source to verify that this is the current version before use.

* 4.2 Classification of tests. The inspection and testing of the staircase shall be classified as follows:

a.	Preproduction testing	See 4.3
b.	Quality conformance inspection	See 4.4

4.3 Preproduction testing (see 6.2).

4.3.1 Test sample. One staircase shall be subjected to the tests specified in 4.3.3.

4.3.2 Test report. After completion of the preproduction tests, a test report shall be prepared in accordance with MIL-STD-831 and three complete copies of the report furnished to the procuring activity.

4.3.3 Preproduction tests. The preproduction tests shall consist of all the tests specified under 4.5.

4.4 Quality conformance inspection. The acceptance tests shall consist of the individual tests.

4.4.1 Individual tests. The individual tests shall consist of the following:

a.	Examination of product	See 4.5.1
b.	Functional tests	See 4.5.2

4.5 Test methods.

4.5.1 Examination of product. The staircase shall be inspected to determine compliance with the requirements specified herein. Particular attention shall be given to dimensions, workmanship, materials, finishes and marking.

* 4.5.1.1 Air transportability. A dimensional check shall be conducted to determine compliance with 3.5.9. Proof that the staircase will enter each aircraft shall be furnished.

4.5.2 Functional tests. The staircase shall be operated through the range specified in 3.5.3 to determine that the general functioning of the staircase is satisfactory. All controls, components, and accessories shall be checked for proper operation. Malfunctioning, excessive rough operation, excessive vibration, or irregular movement shall be cause for rejection. The staircase shall be operated to determine compliance with 3.8.1, 3.8.3, 3.9.4 and 3.9.5.

4.5.3 Static load. With the stairway fully extended, a concentrated static load of 500 pounds having a maximum bearing surface of 1 square foot shall be applied individually to each step and the platform. The center of the load shall be applied individually at 9 inches from both sides and at the center of each step, and at 9-inch centers on the platform. There shall be no evidence of failure nor permanent deformation to the steps or frame.

Source: https://assist.dla.mil -- Downloaded: 20260-20T11:40Z
Check the source to verify that this is the current version before use.

* 4.5.4 Stability. With all parts of the staircase assembled, a 500-pound load on platform not having contact with the aircraft, and the stairway extended to its maximum rated height, an intermittent wind of 60 mph or the equivalent force shall be applied alternately to both entire sides of the staircase at a right angle to the longitudinal axis. The staircase shall remain upright in a stable position and the horizontal movement of the top platform shall not exceed 1-5/8 inches in any direction. If equivalent force method is used, air resistance shall be computed by the formula: Air Resistance (Force) equals coefficient of drag, times air velocity squared in feet per second, times air density in slugs per cubic foot, times area in square feet, times one-half. A minimum of two independent and simultaneous forces will be applied as computed by this formula. One force shall be applied at the centroid of the truck chassis and lower (fixed) portion of the staircase, and one force shall be applied at the centroid of the telescoping portion of the staircase. Coefficients of drag shall be 0.98 for fixed portion and 1.17 for telescoping portion.

* 4.5.4.1 Stair assembly test. With the staircase extended to its maximum rated height, stabilizers down, and a load of 500 pounds on the platform not having contact with the aircraft, a horizontal force (tension or compression) of 500 pounds shall be applied to the centroid of the stair assembly (exclusive of the truck chassis). This force shall be applied and released 500 times. Permanent deformation or failure (cracks, et cetera) of any component shall be cause for rejection of the staircase, with particular emphasis being directed at the area where the stair assembly attaches to the truck (or channel).

* 4.5.5 Height adjustment mechanism. With no load, the staircase shall be operated through its entire height and adjustment range 100 times. During the 1st, 50th, and 100th lift cycles, the time required to raise the stairway from 100 to 160 inches shall be measured. Failure to complete each lift operation within 2 minutes shall be cause for rejection. At the completion of this test, the stairway shall be fully extended, the engine shutoff, and a load of 1,000 pounds placed on the top platform and 250 pounds on each step. The deflection of the platform from the unloaded to fully loaded condition shall not exceed 1 inch. The staircase shall be permitted to remain under this load for 4 hours without the locking device in use. The settling rate of the platform under this test load shall not exceed 1/2 inch in 4 hours. Malfunction of any height adjustment mechanism shall be cause for rejection.

4.5.6 Environmental tests. The staircase shall be subjected to the following environmental tests.

4.5.6.1 Low temperature. The staircase shall be placed within a low-temperature chamber and the chamber cooled to and maintained at a temperature of -20°F for 72 hours. At the conclusion of this exposure and while at this temperature, the truck engine shall start within 15 minutes. After starting the engine and while still at this temperature, the staircase shall be raised from the lower position through the specified lift range of 100 to 152 inches within 2 minutes then lowered in less than 2 minutes. The time to raise and lower the staircase shall be recorded. The outriggers, if provided, shall be lowered and retracted within 30 seconds. With the staircase in the fully raised position, the static load test specified in 4.5.3 shall be conducted. At the conclusion of the static load test, the loaded staircase shall be fully lowered in less than 2 minutes. All controls, components, and accessories shall be checked for proper operation. Malfunctioning, excessive rough operation, failure to complete the lift or lowering operation within 2 minutes, or irregular movement shall be cause for rejection. The test shall be repeated

Source: https://assist.dla.mil - Downloaded: 20260-20111:402
Check the source to verify that this is the current version before use.

except the chamber shall be maintained at a temperature of -35°F during which the power plant heaters shall be turned on 15 minutes prior to starting the engine.

4.5.6.2 High temperature. The staircase shall be placed within a high-temperature chamber and the internal temperature of the chamber raised to 125°F with an internal relative humidity of not more than 5 percent for 50 hours. While still at this temperature, the engine shall be started. After starting the engine and while still at this temperature, the staircase shall be raised from the lower position through the specified lift range of 100 to 152 inches within 2 minutes. The time to raise and lower the staircase shall be recorded. The outriggers, if provided, shall be lowered and retracted within 30 seconds. With the staircase in the fully raised position, the static load test specified in 4.5.3 shall be conducted. At the conclusion of the static load test, the loaded staircase shall be fully lowered in less than 2 minutes. All controls, components, and accessories shall be checked for proper operation. Malfunctioning, excessive rough operation, failure to complete the lift or lowering operation within 2 minutes, irregular movement, failure of any of the components, engine overheating, or leaks that impair operation shall be cause for rejection.

4.5.7 Lifting eye pull test. Each lifting eye shall be subjected to a 2,500-pound pull in a vertical direction. Permanent deformation shall be cause for rejection.

4.5.8 Road test. The staircase shall be driven a distance of 100 miles on a smooth, hard surface. After this test, compliance with MIL-T-45338 shall be verified and vibration damage noted.

4.5.9 Electromagnetic interference. The staircase assembly shall be tested for radiated interference in accordance with MIL-STD-826, method 7001.

4.5.10 Reliability demonstration and tests. Satisfactory completion of all tests specified herein demonstrates compliance with the quantitative reliability requirements of this specification.

4.5.11 Maintainability evaluation. The staircase shall be inspected and evaluated from the standpoint of ease of maintenance, servicing, and operation. Particular attention shall be given maintenance, servicing, and operation. Particular attention shall be given maintenance with a minimum number of common tools, servicing, and operation by personnel wearing heavy gloves and provisions made to prevent accumulation of dirt, snow, ice, et cetera, that may hinder servicing and operation.

4.6 Inspection of preparation for delivery. Preservation, packaging, packing, and marking shall be inspected to verify conformance to the requirements of Section 5 herein.

5. PREPARATION FOR DELIVERY

5.1 Preservation, packaging, packing, and marking. The staircase shall be preserved and packaged level A or C, packed level A, B, or C, and marked in accordance with MIL-STD-162 (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 20260-20T11:40Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. The A/S32S-3 staircase is intended for loading and unloading passengers from military personnel aircraft.

* 6.2 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification.

b. Location and conditions for preproduction testing (see 4.3).

c. If power plant heaters are required (see 3.6).

d. Selection of applicable levels of preservation, packaging, and packing required (see 5.1).

e. Ordering data for MIL-T-45338.

* 6.3 The margins of this specification are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodian:
Air Force - 82

Preparing Activity:
Air Force - 82

Project No. 1730-F199

Source: https://assist.dla.mil -- Downloaded: 20261O-20T11:40Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

ORGANIZATION

CITY AND STATE | CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)* | DATE

DD FORM 1 JAN 68 1426 REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T11:40Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID

DEPARTMENT OF THE AIR FORCE

OFFICIAL BUSINESS

SAN ANTONIO AIR MATERIEL AREA
SERVICE ENGINEERING DIVISION (MMEOP)
KELLY AFB TX 78241

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T11:40Z
Check the source to verify that this is the current version before use.