MILITARY SPECIFICATION

POWER SUPPLY SUBASSEMBLY: 10525745

This amendment forms a part of Military Specification MIL-P-60178(MU), dated 18 February 1965.

Paragraph 3.4.3.2: Delete and substitute new paragraph 3.4.3.2:

"3.4.3.2 AC capacitance.- The capacitors shall exhibit the ac capacitance values specified in Table II."

Table II: Delete "Low Nominal High" and substitute the following:

Line 12, fifth column: Delete "0.152" and substitute "0.052".

* Paragraph 3.4.6.2.1: Change "4.0 ua maximum" to "25.6 ua maximum".

* Following paragraph 3.4.6.2.1 add new paragraph.

"3.4.6.2.2 DC leakage current (operating humidity).- The maximum leakage current of each diode shall be 170 ua."

* Table IV, under Requirement column, following 3.4.6.2.1 add "3.4.6.2.2".

* Table VI, last column: Change "4.0" to "25.6".

Following paragraph 4.1.1: Add paragraphs 4.1.2, 4.1.2.1 and 4.1.2.2.

"4.1.2 First article (initial production) approval.- The requirement for first article approval and the responsibility (Government or contractor) for first article testing shall be as specified in the contract. The sample for first article approval tests shall consist of three (3) power supplies manufactured in the same manner using the same materials, equipment, processes, and procedures as used in regular production. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as used in regular production.

4.1.2.1 Government testing.- When the Government is responsible for conducting first article approval tests, the contractor, prior to submitting the sample to the Government, shall inspect the sample to insure that it

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:14Z
Check the source to verify that this is the current version before use.

conforms to all the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials.

4.1.2.2 Contractor testing.- When the contractor is responsible for conducting first article approval tests, the sample shall be inspected by the contractor for all the requirements of the contract. The sample and a record of this inspection, including certificates of conformance for materials, shall be submitted to the Government for approval. The Government reserves the right to witness the contractor's inspection."

Paragraph 4.2.3: Add the following sentence: "No lots shall be accepted until control samples have been satisfactorily tested."

Change first sentence of paragraph 4.3.2 as follows:

"Environmental.- Power supply units shall be selected at random by a Government representative as control samples from each three (3) months production or portion thereof as follows:

3 units per first 100 produced
5 units per 200
7 units per 300
9 units per 400
10 units per 500
12 units per 700
15 units per 1000
and 2 units for each 100 items produced in excess of 1000."

Paragraph 4.5.1.3.2: Delete in its entirety and substitute:

"4.5.1.3.2 Operating.- This test shall be conducted in accordance with the humidity test defined in Procedure III of MIL-F-13926, except that the humidity shall be maintained at 92 to 97 percent for the 24 hour period, and the test shall cease at the end of that period (Method 106 of MIL-STD-202 shall be excluded). Throughout the test period, the board shall be capable of performing the tests of 4.5.2.6. In order to demonstrate this capability, the tests of 4.5.2.6 shall be performed a minimum of once each 6 hours of the 24 hour period. The final test shall be conducted during the final portion of the 24 hour period. Between tests the boards shall be electrically de-energized.

Paragraph 4.5.1.4: Delete in its entirety and substitute:

"4.5.1.4 Salt spray.- This test shall be conducted in accordance with the salt spray test defined in Method 101, Condition B of MIL-STD-202 using a 5 percent salt solution. At the end of the exposure period, salt deposits shall be removed from the board by a gentle wash, not to

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:14Z
Check the source to verify that this is the current version before use.

exceed 30 minutes, in running water not warmer than 100°F, using a soft hair brush or plastic bristle brush. The board shall then be air dried in a controlled environment at 72°F ± 5°F and a relative humidity of 30 to 50 percent for a period of 24 hours. The board shall be inspected visually for any physical damge, then tested in accordance with 4.5.2.1 to 4.5.2.4."

Paragraph 4.5.2.1.2.1: Delete "(-20Vdc)" and substitute "(-2.0 Vdc)".

Paragraph 4.5.2.1.2.3: Delete "Collector to base" and substitute "Emitter to base." Delete "switch 52" and substitute "switch S3".

* Paragraph 4.5.2.3.2: Delete last sentence and substitute:

"The voltages shall be applied at the specified frequencies between the terminals as shown in Figure 4 for compliance with 3.4.3.2"

Table VIII, line 8, second column: Delete "61B" and substitute "61A".

Lines 10, 11 and 12: Delete under

Vdc	Vac	Voltage Frequency
"10 ± 0.5	1.02	120 ± 5
10 ± 0.5	1.02	120 ± 5
10 ± 0.5	1.02	120 ± 5

and substitute

0	10 ± .2	1000 ± 100
0	10 ± .2	1000 ± 100
0	10 ± .2	1000 ± 100"

* Paragraph 4.5.2.6.2: After last sentence add: "During the operating humidity test (4.5.1.3.2), the maximum leakage of each diode shall be within the limits specified in 3.4.6.2.2."

Table IX, line 3, third column: Delete "0.01" and substitute "0.10".

*The outside margin has been marked to indicate where additions to the previous amendment have been made. This has been done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in this notation. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content as written irrespective of the marginal notation and relationship to the last previous amendment.

Custodian:

Army - MU

Preparing activity:

Army - MU

Project No. 1220-A235

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:14Z
Check the source to verify that this is the current version before use.