MILITARY SPECIFICATION

PROJECTILE, 165MM, TP M624, METAL PARTS

This amendment forms a part of Military Specification MIL-P-50398, dated 18 May 1979

PAGE 1

Paragraph 2.1, delete "MIL-I-6868 Inspection Process, Magnetic Particle."

PAGE 3

Paragraph 3.5.1, delete and substitute the following.

"3.5.1 Raw material. The billets, bars, tube or plate material from which projectile components are formed shall be free from cracks, splits, cold shuts, inclusions, pipe, porosity, folds, bursts, seams, laminations and other metal defects".

PAGE 4

Paragraph 3.6.d, delete in its entirety.

Paragraph 3.8.2, add to end of sentence: "(see 6.7)".

PAGE 8

Paragraph 4.4.2.1.3, delete and substitute the following:

"4.4.2.1.3 Inspection of raw material prior to forming. Each slug, tube or disc obtained from bar, tube or plate stock shall be visually examined for surface indications of the types of metal defects described in 3.5.1 which are visible to the unaided eye on all exterior surfaces. Visual standards may be selected to aid in the determination of a slug's, tube's, or disc's acceptability".

PAGE 11

Paragraph 4.4.2.3, add the following note to the note block:

"A. See 4.4.3.1 for sample size."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:23Z
Check the source to verify that this is the current version before use.

PAGE 17

Paragraph 4.4.2.7, title, delete "Carton, Packing, Prior to Sealing" and substitute "Carton, Packed, Prior to Sealing (Base Plug)".

PAGE 18

Paragraph 4.4.2.8, Title, delete "Cartons, Packed, After Sealing" and substitute "Carton, Packed, After Sealing (Bore Plug)".

PAGE 19

Paragraph 4.4.2.9, Title, delete "Pallet" and substitute Pallet (Projectile Body)".

PAGE 20

Paragraph 4.4.3.1, delete and substitute the following:

"4.4.3.1 Tensile strength of projectile body. Two projectile bodies from the first batch of a stress-relieved lot shall be subjected to this test. Following satisfactory compliance of the initial sample with the requirements of dwg. 10551955, two projectile bodies from every five stress relieved batches, or fraction thereof, of a stress-relieved lot shall be subjected to this test. Failure of any projectile body tensile specimen to meet the applicable requirements shall reject the lot of stress-relieved bodies which the specimen represents and shall require the establishment of a new stress-relieved lot."

Paragraph 4.4.3.2, delete and substitute the following:

"4.4.3.2 Tensile strength of base plug. Two base plugs from the first batch of a stress-relieved lot of base plugs shall be subjected to this test. Following satisfactory compliance of the initial sample with the requirements of dwg. 10535957, two base plugs from every five stress-relieved batches, or fraction thereof, of a stress-relieved lot shall be subjected to this test. Failure of any base plug tensile specimen to meet the applicable requirements shall reject the lot of stress-relieved base plugs which the specimen represents and shall require the establishment of a new stress-relieved lot",

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:23Z
Check the source to verify that this is the current version before use.

Paragraph 4.4.3.3, delete the second sentence and substitute the following:

"Failure to comply with the applicable specification and drawing requirements shall be cause for the rejection of the material represented by the failing samples."

PAGE 21

Paragraph 4.5.1.1, delete and substitute the following:

"4.5.1.1 Tensile test of projectile body. From the samples provided in accordance with 4.4.3.1, two tensile test specimens conforming to the largest obtainable standard specimen for tubular products, as prescribed by ASTM E8, shall be taken from opposite sides of the body in the minimum wall thickness area rear of the nose ogive".

Paragraph 4.5.2, add the following sentence:

"The contractor shall prepare a written standard operating procedure, to include the inspection of projectile bodies and calibration procedures, which shall be submitted for the review and approval of the Contracting Officer prior to the submission of the first article sample (see 6.2)".

PAGE 22

Paragraph 4.5.2.1, delete the last sentence in its entirety. Delete (see 4.5.3.1) from first sentence.

Paragraph 4.5.3, add the following sentence:

"The contractor shall prepare a written standard operating procedure to include the inspection of projectile bodies and calibration procedures, which shall be submitted for the review and approval of the Contracting Officer prior to the submission of the first article sample (see 6.2)".

Paragraph 4.5.3.1, delete this paragraph in its entirety.

PAGE 23

Paragraph 4.5.5.4, add the following sentence:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:23Z
Check the source to verify that this is the current version before use.

"The proving ground shall prepare a written assembly procedure for the assembly of projectile metal parts ballistic samples and submit the procedure for review to the Contracting Officer prior to the assembly of the first article ballistic test samples (see 6.4)".

PAGE 26

Add the following paragraph:

"6.7 Burr. A burr that is loose, injurious to personnel, interferes with the assembly of other components, or interferes with inspection gaging is not permissible."

Custodian:
Army-AR

Preparing Activity:
Army-AR

Project Number: 1315-A350

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:23Z
Check the source to verify that this is the current version before use.