MILITARY SPECIFICATION

Fuze, MT, XM711 Assembly

This amendment forms a part of Military Specification Mil-F-60589B(MU) dated 5 October 1970.

Paragraph 3.3.3 delete in its entirety.

Paragraph 4.2.5 under "Test" delete Forty Foot Drop in its entirety.

Paragraph 4.3.2.22 add MAJOR characteristic 105.
"105. Perpendicularity of lever wings with Datum A & B Gage"

Paragraph 4.3.2.34 add
"g. Laminated Plate #1 and #2 Assembly D10542816
(1) Damaged or bent lever
(check immediately, prior to assembly of plates)"

Paragraph 4.3.3.11.5 change "sub-assembly" to "assembly" and "F10542817" to "D10542813".

Paragraph 4.3.3.16 under "Test" delete Forty Foot Drop in its entirety.

Paragraph 4.4.11.5 change "F10542817" to "D10542813"

Paragraph 4.4.16.3 delete in its entirety.
Add paragraphs 6.11, 6.11.1, 6.11.2, 6.11.3, 6.11.4 and 6.11.5.
6.11 Statement of Safety Requirements

6.11.1 Safety Limitations and Precautions Relating to Production Equipment and Facilities:

Assembly of detonators and relay into fuze should be performed under protective hoods with static electricity controls. Protective hood should be used when performing the jolt and transportation vibration test.

FSC 1390

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:47Z
Check the source to verify that this is the current version before use.

6.11.2 Hazards Presented by Materials:

Possible injury (burns or dismemberment) to limbs and body from flash of detonators and relay.

6.11.3 Known Hazards or Hazardous Areas:

All areas in which detonators are used in assembly operations or stored.

6.11.4 Specific Instructions Relative to Manufacture, Handling, Storage and Shipment of Material: The number of persons exposed to explosive operations and the quantities of explosive materials should at all times be the minimum consistent with safety and the efficiency of operation. Signs setting forth personnel and explosive limits also should be posted. Prior to starting operations including any of the hazardous materials or items described herein, a standard operating procedure should be developed and approved by the contractor outlining the specific requirements to safely perform the particular operation. All personnel concerned should be cognizant of SOP contents. Applicable portions of the approved procedure should be conspicuously posted convenient to all stations involved in the operation for guidance of all personnel.

6.11.5 Explosive Hazard Classification of Materials:

Assembled fuzes - Class 1, Detonators in Storage - Class 7.

Custodian

Army - MU

Preparing activity

Army - MU(FA)

Project no. 1390 -A212

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:47Z
Check the source to verify that this is the current version before use.