MIL-F-60890(MU)
AMENDMENT 2
8 NOVEMBER 1972
SUPERSEDING
AMENDMENT 1
29 July 1971

MILITARY SPECIFICATION

FUZE, MECHANICAL TIME, M591, ASSEMBLY

This amendment forms a part of Military Specification MIL-F-60890(MU) dated 6 April 1971.

* Paragraph 4.2 change "200" to "180".

* Paragraph 4.2.1 change "Two-hundred (200)" to"One-hundred and eighty (180)".

* Paragraph 4.2.2.1 change "(9)" to "(8)".

* Paragraph 4.3.3.2 Delete "Arbor Escapement D8594416".

Add paragraphs 6.9, 6.9.1, 6.9.2, 6.9.3, 6.9.4 and 6.9.5.

"6.9 Statement of Safety Requirements

6.9.1 Safety Limitations and Precautions Relating to Production Equipment and Facilities:

Assembly of explosive elements into fuzes shall be performed under protective hoods with static electricity controls. Protective barrier should be used when performing the MIL-Standard tests.

6.9.2 Hazards Presented by Materials:

Possible injury (burns or dismemberment) to limbs and body from flash or detonation of explosive elements.

6.9.3 Known Hazards or Hazardous Areas:

All areas in which explosive elements are used in assembly operations or stored.

FSC 1390

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:03Z
Check the source to verify that this is the current version before use.

6.9.4 Specific Instructions Relative to Manufacture, Handling, Storage and Shipment of Material: The number of persons exposed to explosive operations and the quantities of explosive materials should at all times be the minimum consistent with safety and the efficiency of operation. Signs setting forth personnel and explosive limits also should be posted. Prior to starting operations including any of the hazardous materials or items described herein, a standard operating procedure should be developed and approved by the contractor outlining the specific requirements to safely perform the particular operation. All personnel concerned should be cognizant of SOP contents. Applicable portions of the approved procedure should be conspicuously posted convenient to all stations involved in the operation for guidance of all personnel.

6.9.5 Explosive Hazard Classification of Materials:

Assembled fuzes - Class I, Detonators in Storage - Class 7.

* The margins of this amendment are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodian:

Army - MU

Preparing Activity:

Army - MU(FA)

Project No. 1390-A111

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T01:03Z
Check the source to verify that this is the current version before use.