MILITARY SPECIFICATION

CASES, FIELD, OFFICE MACHINE (PLYWOOD)

This specification is mandatory for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope.- This specification covers one type of office machine case (plywood) for field use (see 6.1).

1.2 Classification.- Cases shall be of the following sizes as specified (see 6.2). Dimensions of cases are inside dimensions.

Size	Length (Inches)	Width (Inches)	Depth (Inches)
A	18-1/2	13-1/4	17
B	22-1/2	13-1/4	17
C	26-1/2	13-1/4	17
D	34-1/2	13-1/4	17

* 2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

FF-R-556 - Rivets, Solid, Small; Rivets, Split, Small; Rivets, Tubular, Small; and Caps, Rivets; General Purpose.
QQ-B-613 - Brass, Leaded and Non-Leaded; Flat Products (Plate, Bar, Sheet, and Strip).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

QQ-S-698 - Steel, Sheet and Strip, Low-Carbon.
QQ-S-781 - Steel Strapping, Flat.
TT-C-490 - Cleaning Methods and Pretreatment of Ferrous Surfaces for Organic Coatings.
TT-E-529 - Enamel, Alkyd, Semi-Gloss.
TT-I-558 - Ink, Marking Stencil, Opaque, for Nonporous Surfaces (Metals, Glass, etc.).
TT-P-636 - Primer Coating, Synthetic, Wood and Ferrous Metal.
UU-P-121 - Paper, Bond and Writing, White and Colored.
MMM-A-181 - Adhesive, Room Temperature and Intermediate-Temperature Setting Resin (Phenol, Resorcinol, and Melamine Base).
PPP-F-320 - Fiberboard, Corrugated and Solid Sheet-Stock, Container Grade and Cut Shapes.

MILITARY

MIL-F-495 - Finish, Chemical, Black, for Copper Alloys.
MIL-C-496 - Clips, End, Strap.
MIL-W-530 - Webbing and Tape, Textile, Cotton, General Purpose, Natural or in Colors.
MIL-B-543 - Buckles, Tongueless and Web Strap.
MIL-R-3065 - Rubber, Fabricated Parts.
MIL-C-3133 - Cellular Elastomeric Material, Fabricated Parts.
MIL-A-5092 - Adhesive, Rubber Base, General Purpose.
MIL-F-10336 - Fiber Sheet, Vulcanized.

STANDARDS

FEDERAL

Fed. Std. No. 101 - Preservation, Packaging, and Packing Materials, Test Procedures.
Fed. Std. No. 595 - Colors.

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129 - Marking for Shipment and Storage.
MIL-STD-130 - Identification Marking of U.S. Military Property.
MIL-STD-147 - Palletized and Containerized Unit Loads.
MIL-STD-417 - Rubber Compositions, Vulcanized, General Purpose, Solid (Symbols and Tests).
MIL-STD-670 - Classification of System and Tests for Cellular Elastomeric Materials.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

DRAWINGS

ARMY NATICK LABORATORIES

5-13-73 - Cases, Field, Office Machine (Plywood): Assembly and Details.
5-13-74 - Cases, Field, Office Machine (Plywood): Details and Sections.
5-13-1746 - Cases, Field, Office Machine (Plywood): Packing for Level A Shipment.
5-13-1782 - Cases, Field, Office Machine (Plywood): Instruction Label.

(Miniature copies of Drawings 5-13-73, 5-13-74, 5-13-1746, and 5-13-1782, identified as figures 1 through 4 respectively, are attached for information purposes only.)

(Copies of specifications, standards, and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

* 2.2 Other publications.- The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

UNITED STATES DEPARTMENT OF COMMERCE

Commercial Standard CS 35-61 - Hardwood Plywood.

Product Standard PS 1-66 - Softwood Plywood, Construction and Industrial.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, D.C. 20402.)

3. REQUIREMENTS

* 3.1 First article.- Unless otherwise specified (see 6.2), before production is commenced, a sample field case shall be submitted or made available to the contracting officer or his authorized representative for approval in accordance with 4.2. Approval of the preproduction sample authorizes the commencement of production, but does not relieve the supplier of responsibility for compliance with all applicable provisions of this specification. The preproduction sample shall be manufactured in the same facilities to be used for the manufacture of the production items.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

* 3.2 Materials.- The materials shall conform to the referenced specifications and requirements specified hereinafter.

* 3.2.1 Plywood.- Plywood used for the body and lid panels shall be 3/8-inch, 3-ply. Plywood used for the slide shall be 1/2-inch, 5-ply. The plywood shall conform to either one of the following:

(a) Hardwood. Hardwood plywood shall conform to Commercial Standard CS 35-61, type I, fully waterproof bond, grade 2 face and back, regular sanded. Body and face veneers shall be high, medium or low density, with the exception that Ash or Oak shall not be used for the face or back veneers.

(b) Softwood. Softwood plywood shall conform to group 1, exterior type, grade B-B of Product Standard PS 1-66.

3.2.2 Fiber, vulcanized.- The vulcanized fiber shall conform to MIL-F-10336. Fiber thicknesses shall be as shown on Drawing 5-13-73.

* 3.2.3 Steel, carbon, sheet and strip.- Sheet and strip steel shall conform to commercial quality, in accordance with QQ-S-698.

3.2.4 Rubber.- The rubber for the lid gasket and shock absorber shall conform to either one of the following:

(a) Type, class, grade and suffix letter RS-315A of MIL-R-3065 and MIL-STD-417.

(b) Type, style and grade R015 of MIL-C-3133 and MIL-STD-670.

* 3.2.5 Webbing, cotton, 5/8-inch wide.- The 5/8-inch cotton webbing shall conform to type III, class 4, olive drab No. 7 of MIL-W-530.

* 3.2.6 Paper.- The paper for the instruction label shall conform to UU-P-121. The color shall be white, having a basis weight of 24 pounds (17 x 22 - 500).

3.2.7 Adhesive.-

3.2.7.1 Rubber (synthetic and reclaimed base).- Rubber adhesive shall conform to type I of MIL-A-5092.

* 3.2.7.2 High-temperature setting resin.- High-temperature setting resin adhesive shall conform to the requirements of type III of MMM-A-181, except that the shear strength by compression loading requirement and the curing cycle requirement shall not apply.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

* 3.2.7.3 Room-temperature and intermediate-temperature setting resin.- Room-temperature and intermediate-temperature setting resin adhesive shall conform to any grade of types I or II of MMM-A-181.

3.2.8 Enamel.- Enamel shall conform to class A of TT-E-529. The color shall be olive drab No. X24087 of Fed. Std. No. 595.

3.2.9 Primer.- Primer shall conform to TT-P-636.

* 3.2.10 Ink, marking.- Marking ink shall conform to the requirements of TT-I-558. The color shall be black.

3.2.11 Hardware.- All hardware components shall be commercial type, fabricated from steel specified in 3.2.3, and shall be of similar design to those shown on Drawings 5-13-73 and 5-13-74. Hasp, drawbolt, and hinges shall have a minimum metal thickness of 0.0478 inch and other hardware shall have a minimum metal thickness of 0.0359 inch.

3.2.12 Rivets.-

* 3.2.12.1 Steel, solid, tubular or split.- The solid, tubular or split steel rivets shall conform to the following types of rivets, as applicable: Type X, grade E; type XI, class 1, grade E; type XII, class 1, grade E of FF-R-556. The quantity and size of rivets shall be as normally used by the industry in producing similar or like design and size cases. The length of split rivets shall be sufficient to provide a minimum of 1/8-inch clinch. The length of the tubular or solid rivets shall be sufficient to provide a minimum of 1/16-inch for peening or curling the diameter to size.

3.2.12.2 Brass, tubular.- Tubular brass rivets shall conform to type XII, class 2, grade F of FF-R-556. The number, size and length of the tubular brass rivets shall be as recommended by the rivet industry.

3.2.13 Washers.-

3.2.13.1 Steel.- The steel washers shall be fabricated of cold rolled, half-hard, No. 2 temper steel strip, 0.055 inch to 0.071 inch thick, conforming to QQ-S-698. The number and size washers shall be as normally recommended by industry. The washers shall be zinc coated.

* 3.2.13.2 Brass, washers and caps.- The brass washers and caps shall be fabricated of brass strip, copper alloy No. 260, half-hard temper conforming to QQ-B-613. The thickness, number and size washers and caps shall be as normally recommended by industry.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

3.2.14 Box nails.- Steel, box nails shall be commercial, smooth, box nails, cement coated, not smaller than 3d (1-1/8 inch long by 0.0625 inch diameter).

3.3 Construction.- The construction of the field case shall conform to the requirements specified herein and as shown on Drawings 5-13-73 and 5-13-74. All body and lid edge joints shall be glued and nailed with the number of nails shown on Drawing 5-13-73.

* 3.3.1 Fiber covering.- The vulcanized fiber specified in 3.2.2 shall be bonded with adhesive specified in 3.2.7.2 or 3.2.7.3 to both surfaces of the plywood for the case body and lid. Each plywood surface shall be covered fully with a single sheet of fiber. The plywood-fiber bond shall be clean, smooth surfaced and free from waves or irregularities. The adhesive bond of fiber to plywood shall show no delamination when tested as specified in 4.4.1. The adhesive bond shall show not less than 90 percent minimum average and 80 percent minimum fiber failure when tested as specified in 4.4.2. The fiber covered plywood panels shall be fabricated by either one of the following processes:

(a) Unit process. The vulcanized fiber and wood veneers shall be glued with the same adhesive, assembled, pressed and cured in one operation.

(b) Two-step process. The vulcanized fiber shall be bonded to the plywood specified in 3.2.1 with adhesive specified in 3.2.7.2 or 3.2.7.3. Application of adhesive to joint surface, assembly periods, pressing time and pressure curing temperature shall be in accordance with adhesive manufacturer's recommendations.

3.3.2 Fiber bindings.- The vulcanized hard fiber strip used for edge bindings "A" shall be formed to set tightly to the body and lid edges when riveted or tacked in position.

* 3.3.3 Metal bindings.- The metal bindings for the slide shall be formed with 90° angle, square corner blends. The guide shall be of one piece construction, properly notched to provide miter joints at corners and permit proper alignment. Tongue and groove bindings shall be formed and assembled in one unit or from four pieces with tight mitered joints. All joints shall be smoothly finished. Care shall be exercised in fitting the tongue and groove binding on the body and lid of the case so as to insure proper fit without forcing.

3.3.4 Gluing.- All joints of the case, in addition to being nailed as shown on Drawing 5-13-73, shall be glued with adhesive specified in 3.2.7.2 or 3.2.7.3. Application of adhesives to the case joints shall be done in a uniform manner with adequate quantities as recommended by the adhesive manufacturer. Assembly, clamping or pressing time and pressure shall be in accordance with the adhesive manufacturer's instructions.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

3.3.5 Driving of nails, cut trunk tacks and rivets.- All solid and tubular rivets shall be driven with heads flush against hardware or washers and the ends shall be securely headed. Holes for solid and tubular rivets shall be drilled or punched not more than 0.015 inch over the rivet diameter. All split rivets, trunk tacks and box nails shall be thoroughly driven with heads flush against hardware or fiber. Rivets and tacks shall be clinched to provide a projection free interior.

3.3.6 Surfacing and fitting of slide.- Top and bottom surfaces of the slide, the front edge and hand hole shall be sanded smoothly. The slide shall be fitted with allowance for finish so that it will operate freely in the guide without binding and without unnecessary play.

3.3.7 Buckle, securing strap.- The securing strap buckle shall conform to type II, class 1 of MIL-B-543. The buckle shall be securely attached to webbing straps by firmly setting the tubular rivets and caps in the webbing.

* 3.3.8 Clip, end, ball type, 5/8-inch.- The 5/8-inch end clip shall conform to type I of MIL-C-496. The clip shall be firmly attached to the end of the securing strap webbing after the webbing has been inserted the full depth of the clips prior to flattening. The webbing shall lay flat at the point where it enters the clips.

3.4 Finish.-

3.4.1 Surface preparation.- Prior to assembly, all steel hardware, including tacks, rivets, washers and metal bindings and guides, shall be thoroughly cleaned and prepared for painting in accordance with type I or II of TT-C-490. Rivets, washers and caps made of brass shall be finished in accordance with MIL-F-495.

* 3.4.1.1 Metal parts.- All metal parts, exclusive of tacks, rivets, caps, and washers, after treatment specified in 3.4.1 and before assembly, shall be given a coat of primer specified in 3.2.9.

3.4.2 Priming, lid, body and slide.- The assembled (nailed and glued) lid, body and slide shall be given a coat of primer specified in 3.2.9, before attaching straps, guides, hardware, tongue and lid groove binding, fiber bindings and fillers. Forced drying is permitted, provided a surface temperature of 140 F. is not exceeded and relative humidity of the surrounding air is maintained at 30 to 50 percent. The coating shall level out to a dry uniform film thickness without objectionable orange peel, runs, wrinkles, drops, streaks, or areas of no film, and shall be free from grit or coarse particles. All parts shall be thoroughly dry prior to assembly of hardware. The slide shall be lightly sanded after priming to remove raised grain particles.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

3.4.2.1 Fiber bindings, fiber quarter circles and fiber fillers.- All surfaces of the fiber bindings, quarter circles and fillers shall be primed with primer specified in 3.2.9, prior to assembly to body and lid assemblies.

3.4.3 Enameling, body and lid assemblies, and the slide.- Prior to assembly of the securing straps and molded rubber gasket in lid groove binding, but after the assembly of the fiber and metal bindings and hardware, the body and lid assemblies, inside and out, shall be given a coat of enamel specified in 3.2.8. The enamel shall level out to produce a smooth and uniform film without objectionable orange peel, runs, wrinkles, drops, streaks or areas of no film and shall be free of grit or coarse particles. All surfaces of the lid, slide and body shall be thoroughly dry before stacking or packing.

3.5 Marking, identification.- Identification marking shall be in accordance with MIL-STD-130. The letters "U.S.", manufacturer's name or trademark, item name, and year of manufacture shall be of the size characters, and located as shown on Drawing 5-13-73. Ink for marking shall be as specified in 3.2.10.

3.6 Instruction label.- The instruction label shall be printed on paper specified in 3.2.6 and cemented to the underside of the slide as shown on Drawing 5-13-74.

4. QUALITY ASSURANCE PROVISIONS

* 4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

* 4.2 First article inspection.- When a preproduction sample is required, it shall be examined for defects in table III and dimensions specified.

* 4.3 Inspection.- Sampling for inspection shall be performed in accordance with MIL-STD-105, except where otherwise indicated hereinafter.

* 4.3.1 Component and material inspection.- In accordance with 4.1 above, components and materials shall be inspected and tested in accordance with all the requirements of referenced specifications, drawings, and standards unless otherwise excluded, amended, modified or qualified in this specification or applicable purchase document.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

* 4.3.2 In-process inspection.- Examination shall be made during the manufacturing process for the requirements specified in table I to establish that no deviation is made from indicated requirements. Whenever nonconformance is noted, correction shall be made to the affected items and process.

TABLE I.- In-process inspection

Requirement, operation, or assembly	Requirement paragraph
Fiber binding forming and application	3.3.2
Metal binding forming and application	3.3.3
Glue application	3.3.4
Driving of nails, cut trunk tacks and rivets, and hole size for rivets	3.3.5
Surfacing and fitting of the slide	3.3.6
Cleaning and pretreatment of hardware and metal parts	3.4.1
Priming	3.4.1.1 & 3.4.2 & 3.4.2.1

4.3.3 Intermediate testing.-

4.3.3.1 Vulcanized adhesion test.- The test specified in 4.4.1 shall be performed on five (5) samples of 4-inch square, fiber covered plywood to determine compliance with 3.3.1. Each sample shall be from a different piece of fiber covered plywood. The inspection lot shall be all the fiber covered plywood offered for inspection at one time. Any sample failing to meet the specified requirements shall be cause for rejection of the lot.

4.3.3.2 Finished hardware and metal parts testing.- Testing of the completely finished hardware and metal parts shall be performed in accordance with table II for the characteristics shown therein. The inspection level shall be S-1 with an AQL of 6.5, expressed in terms of defects per hundred units.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

TABLE II.- Finished hardware and metal parts testing

Characteristic	Requirement paragraph	Test Method	Number determinations per sample unit	Results reported as
Black chemical finish:				
Color and gloss	3.4.1	MIL-F-495	1	Pass or fail
Resistance to hot soap solution	3.4.1	MIL-F-495	1	Pass or fail
Resistance to accelerated weathering	3.4.1	MIL-F-495	1	Pass or fail

4.3.4 Inspection of the end item.- The lot shall consist of all complete cases offered for inspection at one time. The sample unit for this inspection shall be one completely fabricated case.

4.3.4.1 Visual examination.- Examination of the case shall be in accordance with the classification of defects specified in table III. The inspection level shall be II with an acceptable quality level (AQL) of 4.0 for major defects, and 10.0 for total defects, expressed in terms of defects per hundred units.

TABLE III.- Classification of defects

Examine	Defect	Classification Major	Classification Minor
Finish	Color of finish not as specified.		X
	Finish is not smooth or uniform e.g., has runs, streaks, orange peel, wrinkles, drops.		X
	Area of no film.		X
	Wet or tacky finish.	X	
	Not free of grit or coarse particles.	X	
Construction and workmanship	Not constructed as specified.		X
	Component missing.	X	
	Any component not securely joined or attached as specified.	X	
	Lid does not align evenly with body when in closed position.	X	
	Rivets not securely set.		X

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

TABLE III.- Classification of defects (cont'd)

Examine	Defect	Classification Major	Classification Minor
Fiber covering	Not one piece only on any one wood panel.		X
	Bond not clean, smooth surfaced or free from waves or irregularities.		X
Fiber bindings	Not formed or assembled as specified.		X
Metal bindings	Not formed or constructed as specified.		X
Nails, cut trunk, tacks and rivets	Not driven or headed as specified.		X
	Rivet holes not constructed as specified.		X
	Split rivets, trunk tacks and box nails not driven as specified.		X
	Rivets and tacks not clinched as specified.		X
Slide	Not constructed as specified.		X
	Not sanded as specified.		X
	Not fitted as specified.	X	
Securing strap buckle and clip	Not as specified.		X
	Buckle and clip not attached to strap as specified.		X
Identification	Missing, illegible; incorrect; wrong location or not as specified.		X
Instruction label	Not printed on paper or located as specified.		X

* 4.3.4.2 Dimensional examination.- Inspection shall be made of cases for compliance with dimensions specified. Any dimension not within specified requirements shall constitute a defect. The inspection level shall be S-2 with and AQL of 4.0, expressed in terms of defects per hundred units.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

4.3.5 Examination of preparation for delivery.- An examination shall be made to determine that case strapping, strap protector or tray cap and marking as required by section 5 of this specification are complied with. Defects shall be scored as specified in table IV. The sample unit shall be one field case fully prepared for delivery. The lot shall be the number of cases offered for inspection at one time. The inspection level shall be S-2 with an AQL of 4.0, expressed in terms of defects per hundred units.

TABLE IV.- Examination of preparation for delivery

Examine	Defect
Markings (exterior and interior)	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application.
Materials	Component missing or damaged.
Workmanship	Inadequate application of components such as loose strapping or inadequate construction of fiberboard strap protector and fiberboard tray cap. Improper insertion of slide in guide. Webbing straps improperly coiled or folded and secured.
Preservation	Inadequate application of talc to rubber gasket.

4.4 Test.-

* 4.4.1 Adhesion of vulcanized fiber to plywood.- Samples of the fiber covered plywood, nonprimed and nonenameled, each 4 inches square, shall be immersed in boiling water for 3 hours. The sample shall be cooled in cold water (70 F. plus or minus 5 F.) for a period of 10 minutes and immediately examined while wet for delamination or weakness of bond at the glue line.

* 4.4.2 Glue shear stress test.- The sample shall be tested for adhesive strength of the glue bond in accordance with Method 265 of Federal Test Method Standard No. 101, except that the specimens shall be cut from the laminated board submitted for inspection.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.- Preservation and packaging shall be level A.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

5.1.1 Level A.- The molded rubber gasket of each case shall be uniformly covered with talc to prevent adhesion during storage. The slide shall be inserted in the guide and the webbing straps coiled or folded compactly and secured in place. The lid of each case shall then be securely closed with four drawbolts.

5.2 Packing.- Packing shall be level A.

5.2.1 Level A.- Each case, preserved and packaged as specified in 5.1.1, shall be protected by a solid fiberboard cap tray as shown on Drawing 5-13-1746. The cap tray shall be fabricated from fiberboard conforming to type SF, class domestic, grade 200 of PPP-F-320. The flat steel strapping shall conform to type I, class B of QQ-S-781.

* 5.2.2 Palletization.- Unless otherwise specified (see 6.2), cases packed as specified in 5.2.1 shall be palletized in accordance with load type I of MIL-STD-147. Each prepared load shall be bonded with primary and secondary straps in accordance with bonding means K and L. Pallet patterns shall be in accordance with the appendix of MIL-STD-147. Interlocking of loads shall be effected by reversing the pattern of each course. If the container is of a size which does not conform to any of the pallet patterns specified in MIL-STD-147, the pallet pattern used shall be approved by the contracting officer.

* 5.3 Marking.- The cap tray on each case shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use.- The cases covered by this specification are intended for transportation and storage of standard office machines in the field. The cases will remain with the machine throughout their service life and may be reused if the machines are expended.

* 6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number and date of this specification.
(b) Size of cases required (see 1.2).
(c) First article.- When preproduction sample is not required (see 3.1).
(d) When palletization is not required (see 5.2.2).

* 6.3 The margins of this specification are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and suppliers are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodians:

Army - GL
Air Force - 84

Review activities:

Air Force - 84, 85

User activity:


Army - SM

Preparing activity:

Army - GL

Project No. 7490-0026

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.



Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.






FIGURE 2

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.



Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.



THIS FIGURE IS A MINIATURE COPY OF ARMY NATICK LABORATORIES DRAWING NUMBER 5-13-1782 REVISION NUMBER 1, DATED 10 FEB 64. THIS COPY IS FOR INFORMATION ONLY; THE DRAWING REFERENCED IN PARAGRAPH 2.1 GOVERNS.

UNLESS OTHERWISE STATED; FABRICATING TOLERANCES ARE: DECIMALS ± ; WHOLE NUMBERS AND FRACTIONS ± ; DEGREES ±

FIGURE 4 CASES, FIELD, OFFICE MACHINE, (PLYWOOD); INSTRUCTION LABEL

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

CASES, FIELD, OFFICE MACHINE (PLYWOOD) - MIL-C-10101F

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
U. S. Army Natick Laboratories
Natick, Massachusetts 01760

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

OFFICIAL BUSINESS

Commanding General
U. S. Army Natick Laboratories
ATTN: AMXRES-EQS
Natick, Massachusetts 01760

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:32Z
Check the source to verify that this is the current version before use.