MILITARY SPECIFICATION

CONTAINER, SHIPPING AND STORAGE, M468 FOR BOMB DISPENSER METAL PARTS

1. SCOPE

1.1 This specification covers the metal parts for one type of container designated as Shipping and Storage Container, Bomb Dispenser.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons, General Specification for
MIL-D-1000 - Drawings, Engineering and Associated Lists
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of

STANDARDS

FEDERAL

FED-STD-151 - Metals; Test Methods

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions

FSC: 8140

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1169 - Packaging, Packing and Marking for Shipments of Inert Ammunition Components
MIL-STD-1261 - Welding Procedures for Constructional Steels
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U. S. ARMY MUNITIONS COMMAND

8846908 - Shipping and Storage Container, Bomb Dispenser: M468

PUBLICATIONS

U. S. ARMY MUNITIONS COMMAND

ET 8846908 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.

2.2 Other publications.-The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall apply.

CODE OF FEDERAL REGULATIONS

Title 49 - Transportation, Parts 171-179

(The Code of Federal Regulations is available from the Superintendent of Documents, U. S. Government Printing Office, Washington, D. C. 20402. Orders should specify 49 CFR 171-179 (latest revision).)

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and specifications.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

3.2 Parts.-The parts shall comply with all requirements specified on Drawing (Dwg.) 8846908, all associated drawings, and with all requirements specified in applicable specifications.

3.3 Welding.-Welds shall be uniform, smooth and free from irregularities caused by repairs, tacks or cold starts. Craters on filled welds shall not require filling as long as the minimum weld size is maintained. Craters on butt welds shall not exceed thirty (30) percent of the material thickness in depth when measured from the surface of the part. All welding fluzes, scale, excessive weld spatter, acids or basic solution shall be removed prior to application of finish.

3.3.1 Workmanship samples.-Workmanship samples shall be prepared to establish the minimum acceptable quality for each type of joint. These samples shall be acceptable to the contractor and the Government inspector.

3.4 Weld imperfections.-

3.4.1 Cracks.-There shall be no visible cracks as determined by more than three (3) power magnification but not greater than five (5) power magnification.

3.4.2 Porosity undercut and burn through shall not exceed the limitations established by the workmanship samples (See 3.3.1).

3.4.3 Repair.-A repair welding procedure shall be established that will produce a sound weld, having a uniform, workmanlike appearance.

3.5 Assembly and disassembly.-The container shall accept the dispenser, without evidence of excessive effort in assembly or disassembly, or closing and securing the cover when tested as specified in 4.4.1.

3.6 Performance characteristics.-The container shall comply with the requirements specified herein, when properly loaded with a dispenser, without evidence of loose parts, or broken or permanently-set structural members which render the container unusable. Minor dents or creases in non-structural members, bent rings or eyes, and cracking of the wooden runners shall not be considered. The dispenser shall be operable after completion of the below listed tests.

3.6.1.1 Edgewise drop.-The loaded container shall comply with the requirements of 3.6, when tested as specified in 4.2.2.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

3.6.1.2 Cornerwise drop.-The loaded container shall comply with the requirements of 3.6, when tested as specified in 4.2.2.3.

3.6.1.3 End impact.-The loaded container shall comply with the requirements of 3.6, when tested as specified in 4.2.2.4.

3.6.1.4 Roll over.-The loaded container shall comply with the requirement of 3.6, when tested as specified in 4.2.2.5.

3.6.1.5 Vibration.-The loaded container shall withstand vibration applied in the vertical axis, as specified in Table I, without evidence of loose components or breakage of the container structure when tested as specified in 4.2.2.1.

TABLE I

Frequency (Cycles per second)	Maximum Acceleration	Test Duration
20 ± 1	1.3G (.06DA)	30 minute

3.6.1.6 Fork lifting.-The loaded container shall withstand fork lifting without evidence of punctures or broken or bent frame structures when tested as specified in 4.2.2.6.

3.6.1.7 Stacking.-The container shall withstand a stacking load of 7200 ± 100 pounds without evidence of permanent set or breakage in any structural members when tested as specified in 4.2.2.7.

3.6.1.8 Hoisting.-The loaded container shall withstand lifting, free of support, by means of the lifting rings or eyes, without evidence of deformation or breaks when tested as specified in 4.2.2.8.

3.7 Workmanship.-All parts and assemblies shall be fabricated, loaded and assembled in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, grease, rust and other foreign matter. The cleaning method used shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agents. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required marking and stamping shall be neat and sharply defined.

3.8 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2. (See 6.1) The first article sample shall consist of one (1) container which has been produced by the contractor using the same production processes, procedures and equipment which will be used in fulfilling the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

All parts and completed assemblies submitted shall have been produced by the contractor (or furnished by a supplier), using the same production processes, procedures and equipment as will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance. A first article quantity, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspection to be performed.-The container will be subjected by the Government to any or all of the examinations or those specified in 4.3.2 and 4.3.3 of this specification any any or all requirements of the applicable drawings. In addition, any or all of the following examinations and tests will be performed. These tests are considered destructive, containers so tested may not be returned to the lot.

4.2.2.1 Vibration.-The loaded container shall be subjected to this test first in order of sequence. It shall withstand the vibrations specified in Table 1. The container shall be assembled to a suitable fixture with cover closed and latches fastened in a normal manner. Adequate safety precautions shall be observed to preclude endangering personnel and equipment.

4.2.2.2 Edgewise drop.-The container, with load assembled, shall be supported at one end of its base on a sill approximately five (5) inches in height and placed at right angles to the skids. The other end of the container shall be raised and allowed to fall freely from an eighteen inch height to a concrete or similarly hard surface. This test shall be applied to both ends of the container.

4.2.2.3 Cornerwise drop.-The container with load assembled, shall be supported at one corner of its base on a block approximately five (5) inches in height and with a block approximately twelve (12) inches high placed under the other corner of the same end of the container. The opposite end of the container shall be raised and allowed to fall freely from a eighteen inch height, measured from the lower of the two (2) corners, to a concrete or similarly hard surface. This test shall be applied to one corner of each end of the container.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

4.2.2.4 End impact.-The container with load assembled shall be suspended as a pendulum at the end of four (4) cables, one (1) through each hoisting provision. The container shall be permitted to swing, with a velocity of 10 ± 1.5 feet per second, into a hard, flat, vertical surface. The impact shall be applied to both ends of the container, parallel to the longitudinal axis. Observation shall be made for evidence of external damage. Damage to wooden skids shall be disregarded.

4.2.2.5 Roll over.-The loaded container, erect on its skids on a hard level floor, shall be tipped slowly sideways until it falls freely by its own weight to the floor. This process shall be repeated for one (1) revolution with falls from side to top, top to opposite side, and from that side to base.

4.2.2.6 Fork lifting.-The container shall be lifted clear of another container (or equipment) when stacked, lowered to the floor by a fork-lift truck having forks forty (40) inches minimum in length. The truck shall be cleared of the container, reassume lifting position and restack. This procedure shall be followed in lifting once from each side. The container shall be examined for punctures or broken or bent frame structures.

4.2.2.7 Stacking.-The required load shall be placed on top of the container in such a manner as to simulate stacking of five (5) additional loaded containers thereon. The containers shall be examined for permanent set and breakage of structural members.

4.2.2.8 Hoisting.-The loaded container shall be lifted free of any support by means of the lower lifting eyes or rings.

4.2.3 Rejection.-If any container fails to comply with any of the applicable requirements, the initial production sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new initial production sample or portion thereof. Until an initial production sample is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification or drawing not affecting safety, performance, interchangeability, or storage as determined by the Government, shall not be deemed to alter the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects, using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraphs of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Upper assembly (See Dwg. 8846937).-

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Length of side pads	Gage	01001
102.	Position of side pads	Gage	01002
103.	Side pads loose	Manual	01003
104.	Presence of adhesive on cargo resting surface of cushioning material	Visual	01004
105.	Any cushioning pad missing	Visual	01005

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	01006

4.3.2.2 Lower assembly (See Dwg. 8846936).-

Categories	Defects	Method Inspection	Defect Code
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Length of side pads	Gage	02001
102.	Position of side pads	Gage	02002
103.	Side pad loose	Manual	02003
104.	Presence of adhesive on cargo or cover resting surface of cushioning material	Visual	02004
105.	Any cushioning pad missing	Visual	02005
106.	Disk missing, damaged or out of position	Visual	02006
107.	Plain solid plywood disk missing	Visual	02007
108.	Pipes missing from end assembly	Visual	02008
109.	Hole missing from rear plywood disk	Visual	02009
110.	Marking misleading or unidentifiable	Visual	02010
111.	Drain holes missing	Visual	02011
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	02012

4.3.2.3 Shipping and Storage Container (See Dwg. 8846908).-

Categories	Defects	Method of Inspection	Defect Code
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Total length	Gage	03001
102.	Height	Gage	03002
103.	Inspection cover assembly missing	Visual	03003
104.	Stiffener plate missing	Visual	03004
105.	Latch assembly missing or damaged	Visual	03005
106.	Metal identification plate missing	Visual	03006
107.	Any component missing or damaged	Visual	03007

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

Minor:		AQL 1.50 percent	
201.	Holes for car seal missing.....	Visual	03008
202.	Improper weld (see 3.3).....	Visual	03009
203.	Marking misleading or unidentifiable.....	Visual	03010
204.	Evidence of poor workmanship (see 3.7)....	Visual	03011

4.3.3 Production Testing.-

4.3.3.1. Assembly and disassembly, (See 3.5) Major Defect, Defect Code 04001.-Each container shall be subjected to this test. If any container fails to comply with the applicable requirement, it shall be classified defective and removed from the lot.

4.3.4 Inspection equipment.-Equipment Tabulation (ET) number 8846908 and Equipment Lists (EL's) referenced thereon identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contracto shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activites for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures.-

4.4.1 Assembly and disassembly.-The latch assembly shall be released and the upper assembly removed utilizing the hand holes. The dispenser shall be loaded, and the container components reassembled. There shall be no excess effort required to assemble the dispenser, or to reassemble and latch the container components.

5. PREPARATION FOR DELIVERY

5.1 Marking.-Marking shall be in accordance with Dwg. 8846909.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor (see 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA-1010) the numbers of drawings of Federal Stock numbers of existing equipment designs, or codes as indicated in Paragraph 6.3.2. Design action required of the contractor is described in Paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army design falls into two basic classifications: Mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army Designs, the contractor shall comply with, and use these designs accordingly. The contractor

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (See 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary view, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category A, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit three (3) copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor design.-All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND13. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed to the Contracting Officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally, within one month after receipt.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.

6.4 Submission of results of contractor-conducted examinations and tests.-Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND13.

Custodian:
Army-MU

Preparing Activity:
Army-MU

Project Number: 8140

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:25Z
Check the source to verify that this is the current version before use.