MIL-T-40019C(ME)
28 April 1978
SUPERSEDING
MIL-T-40019B(ME)
26 December 1968

MILITARY SPECIFICATION

TANK, SHIPPING AND STORAGE, DRY ICE

This specification is approved for use by the Mobility Equipment Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers a skid-mounted tank having a nominal capacity of 1 ton for the storage and transport of dry ice (carbon-dioxide) blocks.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

NN-P-71	- Pallets, Material Handling Wood Stringer Construction, 2-Way and 4-Way (Partial).
QQ-A-200/8	- Aluminum Alloy Bar, Rod, Shapes, Tube and Wire, Extruded, and Structural, Shapes, 6061.
QQ-C-320	- Chromium Plating (Electrodeposited).
QQ-S-781	- Strapping, Steel, and Seals.

FSC 3655

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

QQ-Z-325	- Zinc Coating, Electrodeposited, Requirements for.
TT-E-485	- Enamel, Semigloss, Rust-Inhibiting.
TT-W-572	- Wood-Preservative; Water-Repellent.

MILITARY

MIL-P-514	- Plates, Identification, Instruction and Marking, Blank.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-R-14328	- Rubber, Synthetic, Medium Soft, General Purpose Gasket Material (For Extreme Climatic Conditions).
MIL-E-52798	- Enamel, Alkyd, Camouflage.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-209	- Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.
MIL-STD-889	- Dissimilar Metals.
MIL-STD-1595	- Aerospace Welder Performance Qualification (Supplement to ASME Boiler and Pressure Vessel Code, Section IX 1974).

(Copies of specifications and standards required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall apply.

NATIONAL BUREAU OF STANDARDS

Handbook H28 - Screw-Thread Standards for Federal Services.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Boiler and Pressure Vessel Code, Welding Qualifications, Section IX. Rules for Construction of Unfired Pressure Vessels.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM G-21-70 - Determining Resistance of Synthetic Polymerric Material to Fungi.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN WELDING SOCIETY, INC.

AWS D1.1 Structural Welding Code, Section 5, Qualification.

(Application for copies should be addressed to the American Welding Society, Inc., 2501 N.W. 7th Street, Miami, FL 33125.)

3. REQUIREMENTS

3.1 Description. The tank shall be a vented, insulated, rectangular, skid-mounted container with a capacity of not less than 1 ton nor more than 1-1/2 tons of dry ice (carbon dioxide). The overall height of the tank including the skids shall not exceed 48 inches. The internal height of the tank shall not exceed 36 inches. The internal width shall not exceed 36 inches and the length shall be in multiples of 12 inches. The weight of the finished, empty tank shall be not more than 700 pounds. The tank shall support a uniformly distributed compression load of 3700 pounds in a like tank directly over the skids and shall withstand the impact and dropping tests specified herein. The tank shall be furnished with a lid and seal that will vent flash off gases and prevent water entry. A framework of the same material as the skids shall support the bottom and the upright sections and the lid of the tank. Tanks shall be stackable two levels high.

3.2 First article (preproduction model). The contractor shall furnish one or more tanks as specified (see 6.2), for examination and tests within the time frame specified (see 6.2), to prove prior to starting production that his production methods and choice of design detail will produce tanks that comply with the requirements of this specification (see 6.3). Examination and tests shall be as specified in Section 4; and, unless

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

otherwise specified herein, all examination and tests shall be conducted by the contractor subject to surveillance and approval by the Government (see 6.3). When specified (see 6.2), the Government will conduct any or all of the preproduction examination and tests, as specified (see 6.2).

3.2.1 Initial production. When specified (see 6.2), the contractor shall furnish to the Government one or more tanks for inspection as specified in 4.4.

3.3 Material. Material shall be as specified herein. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification (see 6.5).

3.3.1 Metallic parts. Unless otherwise specified herein, all metallic parts shall be made of corrosion-resistant material or shall be zinc coated or chromium plated. Corrosion-resistant material shall be either stainless steel (18 percent chromium - 8 percent nickel), copper, brass, bronze, copper-nickel alloys or aluminum alloys. Zinc castings shall not be used. Zinc coating shall be in accordance with QQ-Z-325, Type I, Class 2. Chromium plating shall be in accordance with QQ-C-320, Class 2.

3.3.2 Sheet metal and metal stampings. Sheet metal and metal stampings that are less than 1/8-inch thick shall be corrosion-resistant material.

3.4 Tank construction.

3.4.1 Ventilation. The tank shall be provided with a vent or vents to permit the continuous escape of carbon-dioxide gas generated from the thawing of the dry ice. The vents shall be so constructed as to prevent the entry of water when tested as specified in 4.5.2.5. Mechanical venting devices which require differential pressure for operation shall not be used.

3.4.2 Openings. The tank opening shall be of the top and front loading type and shall provide access to the full length and depth of the tank. A front access door shall be provided in the front wall of the tank. The front access opening shall be provided with latching devices to assure strength and water tightness when tested as specified in 4.5.2.4 and 4.5.2.5. The lid shall be fitted with a continuous hinge at the back of the tank and with a latch keeper at each front corner. A keeper chain or cable shall be provided at each end to support the lid while in the open position. The chain anchor supports shall be reinforced to prevent damage to the tank or lid. The gasket insulating seal material of sheet cellular rubber conforming to MIL-R-14328 shall be provided at all contact surfaces between the tank and lid (except where the tank is vented through the gasket). A chain or cable shall be provided at each rear corner of the

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

tank to be attached at the upper end of the lid to prevent its accidentally closing while the tank is being filled or unloaded. Provision shall be made for stowing these chains or cables out of the way during handling.

3.4.3 Side walls. The tank walls shall be constructed on the inside and outside walls of sheet aluminum or molded fiberglass of sufficient strength to support the weight specified in 3.1.

3.4.4 Reinforced bottom. The exterior bottom of the tank shall be reinforced with hardwood boards conforming to the deckboards specified in NN-P-71, Grade A. The boards shall be of a size to support the entire bottom of the tank and shall be water and fungus resistant in accordance with TT-W-572, composition optional. A drain plug accessible from one end shall be provided in the bottom of the tank for draining collected liquid.

3.4.5 Skids. The tank shall be cradled in a frame work and mounted on two I-beam skids. Fabrication shall be aluminum alloy conforming to QQ-A-200/8, Temper T6. The I-beam shall extend the full length of the tank and shall have the bottom flange turned up at an angle of 45 degrees at each end to facilitate skidding. The I-beam web shall be drilled at each end for attaching a screw pin, anchor shackle (standard type), 5/8-inch, 3/4-inch pin, for pulling or lifting. Four shackles shall be furnished (one at each corner). Two slots, uniformly spaced, shall be provided in each skid to accomodate fork lift tines for handling. Steel plates not less than 5/32 inch in thickness shall be provided on the underside of the tank over the fork path to prevent damage from the fork lift tines during handling. The slots through the skids shall be not less than 18 inches apart and not more than 22 inches apart and shall service tines 8 inches in width and 3 inches in thickness. The skids shall be fastened to the tank frame work and the reinforced bottom, flush with the tank sides.

3.4.6 Insulation. The insulation may be a rigid nonpermeable, fungus-resistant and moisture-proofed multicellular mass of small nonconnecting cells, or a pour-in-place urethane foam insulation. The fungus resistance shall be tested in accordance with 4.5.2.6.1. The insulation shall limit loss by sublimation to an average of 60 pounds of dry ice per 24 hours at an ambient temperature of plus 70° F, plus or minus 2° F, when tested as specified in 4.5.2.6.

3.4.7 Lid seal. The tank shall withstand rain for 1 hour when tested in accordance with 4.5.2.5.

3.4.8 Hinges and fastening devices. Hinges and fasteners shall be provided with locknuts, lockwashers, or castellated nuts and cotter pins.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

Threads shall conform to Handbook H28. Metal cable guides shall be provided at each tap corner of the tank for stabilizing while being lifted on suspended cables.

3.5 Lifting attachments. Permanently affixed attachments that enable the tank to be lifted in its normal travel position shall be provided and shall conform to MIL-STD-209. Lifting attachments may also be used as tiedown attachments when such attachments conform to the requirements specified in 3.6.

3.6 Tiedown attachments. Permanently affixed attachments that permit fastening the tank to the floor or deck of a transportation medium shall be provided. The tiedown attachments shall conform to MIL-STD-209. Attachments shall be rounded and beveled to prevent cutting of the tiedown material.

3.7 Identification marking. The tank shall be identified in accordance with MIL-STD-130. The marking shall be applied to the tank on plates conforming to MIL-P-514, Type I, Style 3, Composition C, of Type I, Grade A, Class 1 material. Plates shall be attached by screws, bolts, or rivets in a conspicuous protected location. The tanks shall be marked as follows: NOT TO BE USED FOR STORING FOODS.

3.8 Shipping data plate. Shipping data plate conforming to MIL-P-514, Type III, Composition C, of Type I, Grade A, Class 1 material and in addition shall show the silhouette of the tank in transport position indicating the center of gravity and the location and capacity of the lifting and tiedown attachments. The plates shall be attached by screws, bolts, or rivets in a conspicuous protected location.

3.9 Treatment and painting. The portions of the tank normally painted shall be cleaned, treated, and painted in accordance with MIL-T-704, Type A. The finish color for the tank shall be: Forest green in accordance with MIL-E-52798.

3.10 Contact surfaces of dissimilar metals. Where dissimilar metals are used they should be separated by a layer of vinyl zinc chromate tape or both faces should be given two coats of primer conforming to TT-E-485. Definition of dissimilar metals shall be in accordance with MIL-STD-889, Type II.

3.11 Technical publications. Such technical publications as are specified shall be furnished.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

3.12 Workmanship.

3.12.1 Metal fabrication. Metals used in the fabrication of the tank shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the metal. Shearing and chipping shall be done neatly and accurately. Corners shall be square and true. Flame cutting of ferrous metals may be employed instead of shearing or sawing. Burned surfaces of flame-cut material shall be ground or machined sufficiently to remove ash and cooling checks. Aluminum alloys up to 1/2 inch in thickness may be cut by shearing; above 1/2 inch in thickness, alloys shall be cut by common or high-speed saws. All bends of a major character shall be made with metal dies or fixtures in order to insure uniformity of size and shape. Precautions shall be taken to avoid overheating, and heated metal shall be allowed to cool slowly.

3.12.2 Bolted connections. Boltholes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided where necessary and all bolts, nuts, and screws be tight. Self-tapping sheet metal screws shall not be used.

3.12.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall completely fill the holes. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member.

3.12.3.1 Aluminum bolt and rivet holes. Bolt and rivet holes in aluminum alloys shall be made by any one of the following methods:

(a) Holes may be subpunched or subdrilled undersize and reamed to finish size upon assembly.
(b) Holes may be drilled to size at assembly.
(c) Holes may be drilled to size prior to assembly with accurately mated steel drilling jigs. The jigs shall be equipped with hardened steel bushings to insure the correct alinement and location of the holes. All burrs and rough edges shall be removed from the holes prior to final assembly.

3.12.4 Welders and welding.

3.12.4.1 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes or in MIL-STD-1595 for

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

the type of welding operation to be performed, and that such qualification is effective as defined by the particular code:

AWS D1.1, Structural Welding Code, Section 5, Qualification.
ASME Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.
Rules for Construction of Unfired Pressure Vessels.

3.12.4.2 Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, and other foreign matter. Under proof and service loading, welds shall develop strength and transmit stress to the parts connected without failure.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Initial production inspection (see 4.4).
(c) Quality conformance inspection (see 4.5).
(d) Inspection of packaging (see 4.6).

4.3 Preproduction inspection.

4.3.1 Examination. The preproduction tank shall be examined for the defects marked "X" in Column 1 of Table I. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. The preproduction tank shall be tested as specified in 4.5.2.1 through 4.5.2.7. Failure of any test shall be cause for rejection.

4.4 Initial production inspection. When specified (see 3.2.1), one or more initial production tanks will be selected at random by the Government from tanks being produced by production tooling and will be examined as specified in 4.5.1 and subjected to the tests specified in 4.5.2.2 through 4.5.2.7 to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Acceptance of an initial production tank shall not exclude the remaining tanks.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

4.4.1 Inspection failure. Failure of initial production tanks to meet any requirement specified herein during and as a result of the examination and tests specified in 4.4 shall be cause for rejection of the initial production tanks and shall be cause for refusal by the Government to continue acceptance of production tanks until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on tanks previously accepted and produced under the contract. Any deficiencies found as a result of the initial production testing will be considered prima facie evidence that all tanks accepted prior to the completion of initial production testing are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.5 Quality conformance inspection.

4.5.1 Examination. Each tank shall be examined for the defects marked "X" in Column 2 of Table I. Presence of one or more defects shall be cause for rejection.

4.5.2 Tests. Sampling shall be in accordance with MIL-STD-105, Inspection Level S-1. Samples selected shall be tested in accordance with 4.5.2.4 and 4.5.2.6. When performing these tests the drop test shall be accomplished before the insulation test. AQL shall be 2.5 percent defective.

4.5.2.1 Test conditions. Unless otherwise specified in a test all tests shall be performed without shelter and at the climatic conditions existing at the place of test. Tests shall be conducted in the sequence in which they appear.

Table I. Examination Schedule

Preproduction 1	Individual 2	Defect 3	Paragraph(s) 4
X	X	101. Dimensions and weight not as specified.	3.1
X	-	102. Capacity not as specified.	3.1
X	X	103. Vents not as specified.	3.4.1
X	-	104. Insulation not as specified.	3.4.5
X	-	105. Opening not as specified.	3.4.2
X	-	106. Reinforced bottom not as specified.	3.4.4
X	-	107. Skids not as specified.	3.4.5

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

Table I. Examination Schedule (Cont'd)

1	2	3	4
X	X	108. Material not as specified.	3.3
X	X	109. Fasteners not as specified.	3.4.8
X	X	110. Components not as specified.	Section 3
X	X	111. Identification marking not as specified.	3.7 and 3.8
X	X	112. Treatment and painting not as specified.	3.9
X	-	113. Material at joints subject to galvanic action.	3.10
X	X	114. Welding not as specified.	3.12.4.2
X	X	115. Workmanship not as specified.	3.12
X	-	116. Units will not stack.	3.1
X	-	117. Each tank not prepared for shipment as a loose item as specified (see 6.4).	5.1

4.5.2.2 Compression test. A uniformly distributed load of 3,700 pounds shall be placed on the lid of the tank, directly over the skids for 30 minutes. Any indication of deformation of or damage to structural members or permanent deformation of nonstructural members shall constitute failure of this test.

4.5.2.3 Impact test. The tank shall be loaded with 1 ton of material of the same density as dry ice. The tank shall be suspended, on slings, at a height permitting free swing then swung to cause one end to strike a concrete barrier at a speed of 6 miles per hour. This speed can be attained by moving the suspended tank along the arc of free swing until its center of gravity is 18 inches above the lowest point of the arc. This test shall be repeated for the opposite end of the tank. Any indication of damage to the tank covering or its structural members shall constitute failure of this test.

4.5.2.4 Drop test. The tank shall be loaded with 1 ton of material of the same density as dry ice. One end of the tank shall be placed on a ledge 6 inches above a concrete floor. The other end shall be raised to a height of 36 inches and allowed to fall free to the floor level. This test shall be repeated for testing the opposite end. Any deformations to the structural members or the tank skin or lid shall constitute failure of this test.

4.5.2.5 Waterproofing test. The tank shall be subjected to a simulated rainstorm by spraying fresh water at a minimum rate of 3 inches per hour for a period of 1 hour. The spray shall be directed simultaneously at the lid and at all four sides at an angle of 45 degrees from the vertical. The

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

apparatus for producing the spray shall emit the water in the form of droplets rather than as a fine mist. Any water leakage through the tank shall constitute failure of this test.

4.5.2.6 Insulation test. The tank shall be loaded with 1 ton of dry ice in the form of 10-inch cubes, then placed in a closed room with temperature controlled and maintained at 70° F plus or minus 2° F for a period of 7 days. At the end of each 24-hour period, the containers shall be weighed. The average weight loss for a 24-hour period shall be computed. An average loss of more than that specified in 3.4.6 shall constitute failure of this test.

4.5.2.6.1 Fungus test. The fungus resistance shall be tested in accordance with ASTM G-21-70.

4.5.2.7 Tiedown and lifting attachments. The static load as specified in 3.5 for lifting attachments and in 3.6 for tiedown attachments shall be applied to each attachment when it is mounted on its structural member. Weld failure or permanent deformation of the attachment or the structural member shall constitute failure of this test.

4.6 Inspection of packaging.

4.6.1 Quality conformance inspection of pack.

4.6.1.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.1.3 Examination. Samples selected in accordance with 4.6.1.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

116. Strapping not Finish B as specified.
117. Strapping not applied as specified.
118. Marking missing, illegible, incorrect, or incomplete.

5. PACKAGING

5.1 Packing (see 6.4). Each tank shall be prepared for shipment as a loose item. The tank lid shall be secured with two straps conforming to QQ-S-781, Class 1, Type I or IV, Size 3/4-inch by 0.015, Finish B. The straps shall be applied lengthwise completely encircling the tank and shall be placed approximately 12 inches in from each side.

5.2 Marking. The tanks shall be marked in accordance with MIL-STD-129 (see 6.4).

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. The tanks are intended for use in the storage and transport of dry ice (solid carbon-dioxide or extruded pellets) in military field service. The tanks are not intended for food storage.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Time frame required for submission of preproduction model and number of preproduction tanks required (see 3.2).
(c) When the Government will conduct any or all of the preproduction model examination and tests. When the Government will conduct some but not all of the preproduction examination and tests, the contracting officer should specify which examination and tests will be conducted by the Government and which examination and tests shall be conducted by the contractor (see 3.2).
(d) When initial production testing is required and number of initial production tanks required when applicable (see 3.2).

6.3 Preproduction model. Any changes or deviations of production tanks from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the contractor of his obligation to furnish tanks conforming to this specification (see 3.2).

6.4 Degrees of preservation and packing have not been included as the nature of the item is such that the minimum protection specified is acceptable for any level. For purposes of preservation/packing level marking, the marking shall be A/A.

6.5 Recycled material. It is encouraged that recycled material be used when practical as long as it meets the requirements of the specification (see 3.3).

Custodian:
Army - ME

Preparing activity:
Army - ME

Review activities:
Army - MD
DLA - GS

Project 3655-A049

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314



OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

Commander
US Army Mobility Equipment Research and
Development Command
ATTN: DRDME-DS
Ft. Belvoir, VA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/ vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE
MIL-T-40019C(ME) Tank, Shipping & Storage, Dry Ice

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T19:01Z
Check the source to verify that this is the current version before use.