MILITARY SPECIFICATION

CONTROLS, RADIO SET C-8057(*)/ARC AND C-7549(*)/ARC

This specification has been approved by the Naval Air Systems Command, Department of the Navy.

1. SCOPE

1.1 Scope - The equipment covered by this specification shall provide remote control of the Juliet-28 equipment. The only difference between the controls is that C-8057/ARC uses 28 vdc lamp power while the C-7549/ARC uses 5 vdc lamp power.

1.2 Associated Equipment - This equipment shall operate with the associated equipment listed in 6.7.

2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the date of invitation for bids form a part of this specification to the extent specified herein.

SPECIFICATIONS

Military

MIL-W-5088	Wiring; Aircraft, Installation of
MIL-E-5400	Electronic Equipment Aircraft, General Specification for
MIL-T-5422	Testing, Environmental, Aircraft Electronic Equipment
MIL-I-6181	Interference Control Requirements, Aircraft Equipment

FSC 5841

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

MIL-C-6781	Control Panel: Aircraft Equipment, Rack or Console Mounted
MIL-E-17555	Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of
MIL-T-18303	Test Procedures; Preproduction and Inspection, for Aircraft Electronic Equipment, Format for
MIL-P-7788	Plate, Plastic, Lighting
MIL-N-18307	Nomenclature and Nameplates for Aeronautical Electronic and Associated Equipment

Naval Air Systems Command

AR-5	Microelectronic Devices Used in Avionics Equipment, Procedures for Selection and Approval of

STANDARDS

Military

MIL-STD-704	Electric Power, Aircraft Characteristics and Utilization of
MIL-STD-781	Reliability Tests, Exponential Distribution

2.1.1 Availability of Documents -

(1) When requesting specifications, standards, drawings and publications, refer to both title and number. Copies of this specification and applicable specifications required

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:35Z
Check the source to verify that this is the current version before use.

by contractors in connection with specific procurement functions may be obtained upon application to the Commanding Officer, Naval Supply Depot, Code 105, 5801 Tabor Avenue, Philadelphia, Pennsylvania 19120.

3. REQUIREMENTS

3.1 Preproduction - This specification makes provision for preproduction testing.

3.2 Parts and Materials - In the selection of parts and materials, fulfillment of major design objectives shall be the prime consideration. In so doing the following shall govern:

(1) Microelectronic items shall conform to requirements specified herein.

(2) Other parts and materials requirements shall conform to Specification MIL-E-5400.

(3) Nonrepairable subassemblies, as outlined in Specification MIL-E-5400, shall be used when practicable. The general size of the subassembly and the amount of circuitry to be included therein shall be approved by the procuring activity. Nonrepairable subassemblies must be reliable. (See 6.5)

(4) When previously produced models of this equipment did not use nonrepairable subassemblies, the design shall not be changed to employ nonrepairable assemblies without the approval of the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

3.2.1 Nonstandard Parts and Materials Approval - Approval for the use of nonstandard parts and materials (including electron tubes, transistors and diodes) other than microelectronic devices shall be obtained as outlined in Specification MIL-E-5400. Microelectronic devices shall be approved as outlined in AR-5.

3.2.2 Microelectronic Modular Assemblies - When used, Microelectronic Modular Assemblies shall meet the requirements of Specification AR-5.

3.2.3 Microelectronic Interchangeability - The interchangeability provisions of AR-5 shall govern Microelectronic interchangeability.

3.3 Design and Construction - The equipment shall conform with all the applicable requirements of Specification MIL-E-5400 for design, construction and workmanship, except as otherwise specified herein.

3.3.1 Total Weight - The total weight of the equipment, excluding cables, shall be a minimum consistent with good design and shall not exceed 15 ounces.

3.3.2 Reliability -

3.3.2.1 Operating Life - The equipment shall have a total operating life of 20,000 hours with reasonable servicing and replacement of parts. Parts requiring scheduled replacement shall be specified by the contractor.

3.3.2.2 Reliability in Mean Time Between Failure (MTBF) - The equipment shall have 10,000 hours of mean (operating) time between failures as demonstrated by using the analytical method specified in MIL-STD-756.

3.3.3 Cabling and Connections -

3.3.3.1 Cables and Connectors - The equipment shall provide for the use of cables and connectors in accordance with Specification MIL-E-5400.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:35Z
Check the source to verify that this is the current version before use.

3.3.3.2 Interconnection Cabling - The equipment shall be capable of satisfactory operation using external wiring in accordance with the applicable requirements of Specification MIL-W-5088. The external wiring shall be unshielded, except that a minimum number of the individual wires may be shielded when demonstrated as necessary to meet interference control requirements and provided the assembly of the cable to its plugs may be easily accomplished. External cables and that portion of the connectors attached to the cables shall not be supplied as part of the equipment.

3.3.4 Control Panels - The control panel shall conform to the applicable requirements of Specification MIL-C-6781. The configuration of the control panel must be approved by the procuring activity prior to preproduction testing.

3.3.5 Interchangeability - The equipment shall meet the interchangeability requirements of Specification MIL-E-5400.

3.3.6 Interference Control - The generation of radio interference by the equipment and the vulnerability of the equipment to radio interference shall be controlled within the limits of Specification MIL-I-6181.

3.3.7 Maintenance Provisions and Field Testing - Provisions for maintenance shall be as specified in Specification MIL-E-5400. Specific test points and test facilities shall be provided to the greatest extent practicable for ease of field testing and maintenance.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

3.3.8 Nomenclature and Nameplates - Nomenclature assignment and nameplate approval for equipment identification shall be in accordance with Specification MIL-N-18307.

3.3.9 Standard Conditions - The following conditions shall be used to establish normal performance characteristics under standard condtions and for making laboratory bench tests.

Temperature	Room ambient (25°C ±5°C)
Altitude	Normal ground
Vibration	None
Humidity	Room ambient up to 90% relative humidity
Input power voltage	27.5 +0.5 vdc

3.3.10 Service Conditions - The equipment shall operate satisfactorily under any of the environmental conditions or reasonable combination of these conditions as specified in Specification MIL-E-5400 for Class 2 equipment, except as modified herein:

3.3.10.1 Vibration - The equipment shall operate satisfactorily when subjected to the requirements of Curves I and II of Specification MIL-E-5400.

3.3.11 Warm-up Time - The time required for the equipment to warm-up prior to operation shall not exceed 10 seconds.

3.3.12 Primary Input Power Requirements - The equipment shall meet all applicable requirements of MIL-STD-704 and shall give specified performance from the following power sources with characteristics as defined in MIL-STD-704 having limits as specified therein. The power required shall not exceed the specified amounts.

(1) DC Power 28 V, Category "B", 0.1 Amp, power for C-8057/ARC

(2) DC Power 5 V, 0.25 Amp, Lamp Power for C-7549/ARC

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

3.3.12.1 Degraded Performance - Degraded performance will be permitted for voltage transients not exceeding 0.5 second during normal electric system operation. Operation shall return to normal with no resulting damage to the equipment.

3.4 Performance - Unless otherwise specified, values set forth to establish the requirements for satisfactory performance apply to performance under both standard and extreme service conditions. When reduced performance under the extreme conditions is acceptable, tolerances or values setting forth acceptable variations for the performance under the standard conditions will be specified.

3.4.1 Operation - The C-8057/ARC or the C-7549/ARC shall be used to control the Juliet-28. Switching shall be provided to control Juliet-28 input power, the P/C mode selection, the Juliet-28 time delay selection and the Juliet-28 zeroize function.

The POWER-ON/RELAY Control has three positions: OFF, ON and RELAY. In the OFF position, input power is removed from the Juliet-28. In the ON position, input power is routed to the Juliet-28. In the RELAY position, input power is routed to the Juliet-28 and a ground is provided at the connector for use in operating the Juliet time delay function.

The P/C mode selector is used to select either "P" mode or "C" mode for the Juliet-28. The zeroize switch routes primary power to the Juliet-28 in the zeroize position and zero volts in the non-zeroize position.

3.5 Detail Requirements -

3.5.1 Control C-8057/ARC or C-7549/ARC - The Controls shall meet the applicable requirements of MIL-C-6781 for Type I control panel.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

3.5.1.1 Function - The C-8057/ARC or C-7549/ARC Control is the remote control for the Juliet-28 equipment and shall provide remote switching to control the Juliet-28 input power, the P/C mode selection, the time delay selection and the Juliet-28 zeroize function.

3.5.1.2 Form Factor - The controls shall not exceed the follwoing dimensions: 5-3/4" in width, 1-1/2" in height, and 4-1/2" in depth, including the connector and switches

3.5.1.3 Weight - The weight of the controls shall not exceed 15 ounces.

3.5.1.4 Controls - The units shall have the following three switches located on the front panel.

(1) The P/C switch shall be a 2 position toggle switch to provide +27.5 vdc to the Juliet-28 equipment in the "P" position and chassis ground in the "C" position. The switch shall automatically lock in either position to prevent accidental operation.

(2) The zeroize switch shall be a 2 position switch to provide +27.5 vdc to the Juliet-28 equipment in the zeroize position and shall be an open circuit in the nenzeroize position. The switch shall be protected while in the nonzeroize position to prevent accidental operation and shall have a spring return to the nonzeroize position.

(3) The ON/OFF/RELAY switch shall be a 3 position rotary swtich to provide +27.5 vdc to the Juliet-28 equipment in the ON and RELAY positions and zero volts in the OFF position. In addition, this switch shall provide a ground in the RELAY position which shall be open in the OFF position and the ON position.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

3.5.1.5 Electrical Connections - Connections to external circuits shall be provided as follows:

Referenced Designation	Receptacle Type	Function
J1	MS3112E-12-10P	Outlet to Juliet-28

3.5.1.6 Illumination - Panel illumination shall be provided in accordance with MIL-P-7788. C-8057/ARC uses 28 vdc lamps and C-7549/ARC uses 5 vdc lamps.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Classification of Tests - Items covered by this specification shall be subjected to the following tests to determine compliance with all applicable requirements.

(1) Preproduction (First Article) Tests

(2) Initial Production Tests

(3) Acceptance Tests

(4) Life Tests

4.2 Preproduction (First Article) Tests - Preproduction tests shall be made on an equipment representative of the production equipments to be supplied under the contract. Preproduction tests shall be accomplished under the approved

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

test procedure of 4.6. The Government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the services of a commercial testing laborabory acceptable to the Government.

4.2.1 Preproduction (First Article) Test Data - The contractor shall submit all data collected in conducting these tests to the procuring activity for review and approval. On first production contracts this data shall include a list of all electrical and electronic parts giving their specified voltage, current and temperature rating and the applied circuit voltage, current and ambient and surface temperatures. The ambient and surface temperature shall be obtained under the extreme high temperature operating condition.

4.2.2 Scope of Tests - Preproduction tests shall include all tests deemed necessary by the procuring activity to determine that the equipment meets all the requirements of this specification and the contract. Preproduction tests shall include environmental tests in accordance with the procedures of Specification MIL-T-5422 and interference tests in accordance with Specification MIL-I-6181.

4.2.3 Preproduction (First Article) Approval - Approval of the preproduction sample shall be by the procuring activity upon satisfactory completion of all tests. No production equipments shall be delivered prior to the approval of the preproduction sample. Prefabrication of production equipment prior to the approval of the preproduction sample is at the contractor's own risk. The approved preproduction sample shall be retained by the contractor for his use in the fab-

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

rication and testing of equipment to be submitted for acceptance. The preproduction sample shall not be considered as one of the equipments under the contract.

4.2.4 Production Equipments - Equipments supplied under the contract shall in all respects, including design, construction, workmanship, performance and quality, be equivalent to the approved preproduction sample. Each equipment shall be capable of successfully passing the same tests as imposed on the preproduction sample. Evidence of non-compliance with the above shall constitute cause for rejection and for equipment already accepted by the Government, it shall be the obligation of the contractor to make necessary corrections as approved by the procuring activity.

4.3 Initial Production Tests - One of the first ten production equipments shall be selected and sent at the contractor's expense to a designated Government laboratory for tests. This equipment shall be selected by the procuring activity after the equipment has successfully passed all individual tests. The preproduction sample shall not be selected for this test.

4.3.1 Scope of Tests - This equipment may be subjected to any and all tests the procuring activity deems necessary to assure that the production equipment is equivalent to the previously approved preproduction sample in design, construction, workmanship, performance, and quality and that it meets all applicable requirements.

4.3.2 Accessory Material - In addition to the complete equipment submitted for Initial Production Tests the contractor shall also submit such accessory material and data necessary to test the equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

4.3.3 Initial Production Sample Approval - Approval of the Initial Production Sample shall be by the procuring activity upon satisfactory completion of all tests. Any design, material or performance defect made evident during this test shall be corrected by the contractor to the satisfaction of the procuring activity. Failure of the Initial Production Sample to pass any of the tests shall be cause for deliveries of equipment under the contract to cease until proper corrective action is approved and accomplished. Corrective action shall also be accomplished on equipment previously accepted when requested by the procuring activity.

4.3.4 Reconditioning of Initial Production Test Sample - On completion of the initial production test the equipment shall be reworked by the contractor by replacing all wear or damaged items. After reworking, the contractor shall resubmit the equipment for acceptance.

4.4 Acceptance Tests - The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the Government inspector. Contractors not having testing facilities satisfactory to the procuring activity shall engage the service of a commercial testing laboratory acceptable to the procuring activity. The contractor shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the contractor or laboratory, as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following:

(1) Individual Tests

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

(2) Sampling Tests

(3) Reliability Assurance Tests

(4) Special Tests

4.4.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability. As a minimum, each equipment accepted shall have passed the following tests:

(1) Examination of Product

(2) Operational Test

4.4.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

4.4.1.2 Operation Test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

4.4.1.3 Manufacturing Run in Test - Due to the simplicity of the equipment, no manufacturing run in test shall be required.

4.4.2 Sampling Tests - Equipments selected for sampling tests shall first have passed the individual tests. Equipments shall be selected for sampling tests by the Government inspector in accordance with the following: (Sampling tests shall be conducted only when Reliability Assurance Tests of 4.4.3 are deleted by contractual action.)

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:35Z
Check the source to verify that this is the currentversion before use.

Quantity of Equipments Offered for Acceptance	Quantity to be Selected for Sampling Test
First 10	0**
Next 50	1
Next 75	1
Next 100	1
	1 for each additional 200 or fraction thereof

**NOTE: If by contract action the Initial Production Test (4.3) is deleted a Sample Test shall be conducted on one equipment from the first 10 produced.

4.4.2.1 Scope of Tests - As a minimum, each equipment selected for sampling tests shall be subjected to the following tests:

(1) Complete operational test at ambient room conditions, making all necessary measurements to assure that all applicable specification requirements have been met.

(2) Operational test at certain environmental conditions. The conditions may vary for each equipment tested and should be based on results of the preproduction, initial production, individual and special tests.

4.4.3 Reliability Assurance Tests - When required by Contract, this equipment shall be tested in accordance to the reliability assurance test requirements of MIL-STD-781. The numbers of equipments, test MTBF, test level,

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

and accept-reject criteria shall be as specified by the contract.

4.4.4 Special Tests - Special tests shall be conducted on a quantity of equipments for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the sampling or reliability assurance tests.

4.4.4.1 Special Test Schedule - Selection of equipments for special tests shall be made as follows:

(1) On an early equipment after an engineering or material change.

(2) Whenever failure reports or other information indicate that additional tests are required. (This will be determined by the procuring activity.)

4.4.4.2 Scope of Tests - Special tests shall consist of such tests as approved by the procuring activity. Test procedures previously approved for the preproduction tests shall be used where applicable. When not applicable, the contractor shall prepare a test procedure and submit it to the procuring activity for approval prior to conducting the tests.

4.4.5 Equipment Failure - Should a failure occur during either the sampling, reliability assurance or special tests, the following action shall be taken:

(1) Determine the cause of failure.

(2) Determine if the failure is an isolated case or design defect.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:35Z
Check the source to verify that this is the currenversion before use.

(3) Submit to the procuring activity for approval, proposed corrective action intended to reduce the possibility of the same failure(s) occurring in future tests.

(4) Where practical, include a test in the individual test to check all equipment for this requirement until reasonable assurance is obtained that the defect has been satisfactorily corrected.

4.5 Life Test - The contractor shall furnish all samples and shall be responsible for accomplishing the life tests. The test shall be of 300 hours duration and shall be conducted on equipments that have passed the individual test. The life test shall be performed under the conditions specified in 4.5.1. The life test sample shall be selected by the Government inspector in accordance with the following. (Equipments which have successfully passed the Initial Production Test, Sampling Tests, Reliability Tests, or Special Tests may be selected for life tests.) When reliability tests are conducted, the life test shall be omitted if, during the reliability tests, a quantity of equipments equal to, or more than, that listed below receive at least 300 hours each of test time.

Quantity of Equipments Offered for Acceptance	Quantity to be Selected for Life Test
First 25	1
Next 175	1
Next 300	1
	1 for each additional 500 or fraction thereof

4.5.1 Test Conditions - The life test shall be conducted under the following simulated service conditions:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

Temperature	Normal room
Altitude	Normal ground (0-5000 ft.)
Humidity	Room ambient
D.C. Voltage	27.5±2.0 volts

4.5.2 Test Periods - The test may be run continuously or intermittently. Any period of operation shall be of sufficient duration to permit the equipment temperature to stabilize. Periodically, the equipment shall be turned on and off several times and put through its various phases of operation.

4.5.3 Performance Check - At approximately 8 hour intervals during the test, a limited performance check shall be made. The performance check proposed by the contractor shall be subject to approval by the procuring activity.

4.5.4 Test Data - The contractor shall keep a daily record of the performance of the equipment, making particular note of any deficiencies or failures. In event of part failures, the defective part shall be replaced and the operation resumed for the balance of the test period. A record shall be kept of all failures throughout the test, including all tube failures. This record will indicate the following:

(1) Part type number

(2) The circuit reference symbol number

(3) The part function

(4) Name of the manufacturer

(5) Nature of the failure

(6) The number of hours which the part operated prior to failure.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

4.5.4.1 Failure Report - In the event of a failure, the Government inspector shall be notified immediately. A report shall be submitted to the procuring activity upon completion of the test. In this report, the contractor shall propose suitable and adequate design or material corrections for all failures which occurred. The procuring activity will review such proposals and determine whether they are acceptable.

4.6 Test Procedures - The procedures used for conduction pre-production tests, acceptance tests and life tests shall be prepared by the contractor and submitted to the procuring activity for review and approval. The right is reserved by the procuring activity or the Government inspector to modify the tests or require any additional tests deemed necessary to determine compliance with the requirements of this specification or contract. Specification MIL-T-18303 shall be used as a guide for preparation of test procedures. When approved test procedures are available from previous contracts, such procedures will be provided and may be used when their use is approved by the procuring activity. However, the right is reserved by the procuring activity to require modification of such procedures, including additional tests, when deemed necessary.

4.7 Reconditioning of Tested Equipment - Equipment which has been subjected to initial production acceptance and life tests shall be reconditioned by the contractor by replacing all wear or damaged items. After reworking the contractor shall resubmit the equipment for acceptance.

4.8 Presubmission Testing - No item, part or complete equipment, shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

4.9 Rejection and Retest - Equipment which has been rejected may be reworked or have parts replaced to correct the defects and resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejection and the action taken to correct the defects found in the original shall be furnished the Government inspector.

5. PREPARATION FOR DELIVERY

5.1 General - All major units and parts of the equipment shall be preserved, packaged, packed and marked for the level of shipment specified in the contract or order in accordance with Specifications MIL-E-17555 and MIL-STD-794. In the event the equipment is not covered in Specification MIL-E-17555, the method of preservation for Level A shall be determined in accordance with the selection chart in Appendix D of MIL-STD-794.

6. NOTES

6.1 Intended Use - The control unit is intended for use with the Juliet-28 equipment or with a Romeo-8 equipment when used in conjunction with the SA-1489/ARC audio switching unit in certain installations.

6.2 Ordering Data - Purchasers should exercise any desired options offered herein, and procurment documents should specify the following:

(1) Title, number, and date of this specification

(2) Selection of applicable levels of packaging and packing (See 5.1)

6.3 Precedence of Documents - When the requirements of the contract, this specification, or applicable subsidiary specifications are in conflict, the following precedence shall apply:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

(1) Contract - The contract shall have precedence over any specification.

(2) This Specification - This specification shall have precedence over all applicable subsidiary specifications. Any deviation from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

(3) Referenced Specifications - Any referenced specification shall have precedence over all applicable subsidiary specifications referenced therein. All referenced specifications shall apply to the extent specified.

6.4 Performance Objectives - Minimum size and weight, simplicity of operation, ease of maintenance, and an improvement in the performance and reliability of the specific functions beyond the requirements of this specification are objectives which shall be considered in the production of this equipment. Where it appears a substantial reduction in size and weight or improvement in simplicity of design, performance, ease of maintenance or reliability will result from the use of materials, parts and processes other than those specified in Specification MIL-E-5400, it is desired their use be investigated. When investigation shows advantages can be realized, a request for approval shall be submitted to the procuring activity for consideration. Each request shall be accompanied by complete supporting information.

6.5 Non-Repairable Subassemblies - As a general rule, non-repairable subassemblies should be encapsulated or hermetically-sealed. The number of connections internal to the subassembly should be held to a minimum.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

Detail parts tolerances and ratings should be so selected that the life of the subassembly is greater than that of a similar repairable one. With few exceptions (such as high voltage power supplies), the non-repairable subassembly should evidence a Mean-Time-To-Failure greater than 5000 hours, and for many applications this figure must be nearer 50,000 hours.

6.6 Type Designations - The parentheses (*) when used in the equipment type designation, will be deleted or replaced by either a number or letter furnished by the procuring activity upon application by the contractor for assignment of nomenclature in accordance with 3.3.8. The complete type number shall be used on nameplates, shipping records and instruction books, as applicable.

6.7 Associated Equipment - The equipment shall operate with the following associated equipment.

Juliet-28 Equipment

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity *(as indicated on reverse hereof)*.

SPECIFICATION
MIL-C-81470(AS) CONTROLS, RADIO SET C-8057(*)/ARC and C-7549(*)/ARC

ORGANIZATION *(Of submitter)*	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1 APR 63 1426

C-8279

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:35Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY

Naval Air Systems Command
Washington, D.C. 20360

POSTAGE AND FEES PAID
NAVY DEPARTMENT

OFFICIAL BUSINESS

NAVAL AIR SYSTEMS COMMAND (AIR-52021)
DEPARTMENT OF THE NAVY
WASHINGTON, D. C. 20360

FOLD

GPO 303-224/Z 786

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:35Z
Check the source to verify that this is the current version before use.