MILITARY SPECIFICATION

DISPLAY GROUP TACTICAL DATA AN/ASA-66

This specification has been approved by the Naval Air Systems Command, Department of the Navy

1 SCOPE

1.1 Scope - The equipment covered by this specification shall be capable of displaying computer generated tactical and navigational data, together with necessary cueing information to the pilot.

*1.2 Classification - The equipment covered by this specification shall consist of the following items

Type Designation	Applicable Paragraph
Display Tactical Data ID-886/ASA-66	3.5.1
Control Tactical Data Display C-7444/ASA-66	3.5.2

1.3 Associated Equipment - This equipment shall operate with the associated equipment listed in 6.8

2. APPLICABLE DOCUMENTS

*2.1 General - The following documents form a part of this specification to the extent specified herein. Listed are the issues of the documents in effect for the previous procurement. However in lieu of the issue listed the contractor shall use the latest issue in effect of these documents where feasible If the use of the latest issue will affect design performance, or interchangeability of any replaceable part, then the issue of the document listed below shall be used

SPECIFICATIONS

Military

MIL-W-5088C 26 May 1965	Wiring Aircraft Installation of
MIL-E-5400H 1 June 1965	Electronic Equipment Aircraft General Specification for
MIL-T-5422F 13 April 1959 And Amend 2 15 Nov 1961	Testing Environmental, Aircraft Electronic Equipment
MIL-C-6781B 13 Sept 1960	Control Panel, Aircraft Equipment, Rack or Console Mounted

FSC 6605

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

Military (cont)

MIL-P-7788C 1 Sept 1964	Panels, Information, Integrally Illuminated
MIL-M-7793C 14 Aug 1961 And Amend 1 24 May 1962	Meter, Time Totalizing
MIL-E-17555F 5 March 1965	Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of
MIL-T-18303B 1 Sept 1966	Test Procedures Preproduction and Acceptance for Aircraft Electronic Equipment, Format for
MIL-N-18307C 1 Oct 1958 And Amend 4 19 Sept 1966	Nomenclature and Nameplates for Aeronautical Electronic and Associated Equipment
MIL-K-25049B 25 July 1960	Knobs Control Equipment, Aircraft
MIL-C-26500B 21 Sept 1961	Connectors, General Purpose, Electrical, Miniature Circular, Environmental Resisting, Established Reliability

Naval Air Systems Command

AR-5 1 Oct 1966	Microelectronic Devices Used in Avionics Equipment, Procedures for Selection and Approval of
#AR-34 26 March 1969	Failure Classification for Reliability Testing, General Requirements for
EI-490	Avionic Installation Instructions for Tactical Data Display Group AN/ASA-66
WR-101 28 Feb 1966	Weapon Requirement for Advanced ASW Electronic Systems Part I - Electromagnetic Control Requirements for Advanced ASW Avionics Systems

STANDARDS

MIL-STD-415B 8 Feb 1961	Test Points and Test Facilities for Electronic Systems and Associated Equipment, Design Standard for
MIL-STD-470 21 March 1966	Maintainability Program Requirements (for Systems and Equipment)
MIL-STD-471 15 Feb 1966	Maintainability Demonstration
MIL-STD-704 6 Oct 1959	Electric Power, Aircraft Characteristics and Utilization of
MIL-STD-704A 9 Aug 1966	Electric Power, Aircraft, Characteristics and Utilization of
MIL-STD-781A 10 Dec 1965	Reliability Tests, Exponential Distribution
MIL-STD-785 30 June 1965	Requirements for Reliability Program
MIL-STD-794 10 March 1965	Parts and Equipment Procedures for Packaging and Packing of
MS17322C 22 July 1964	Meter, Time Totalizing, 115 Volt, 400 Cycle
MS24264H 20 July 1965	Connectors, Receptacle, Electrical-Flange mount, miniature

#This document was not in effect for the previous procurement

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

*2.1.1 Availability of Documents - When requesting specifications, standards, drawings, and publications refer to both title and number. Copies of this specification and applicable specifications required by contractors in connection with specific procurement functions may be obtained upon application to the Commanding Officer, Publications and Forms Center, Code 105, 5801 Tabor Avenue, Philadelphia, Pennsylvania 19120.

3. REQUIREMENTS

3.1 Preproduction - This specification makes provision for preproduction testing.

*3.2 Parts and Materials - In the selection of parts and materials, fulfillment of major design objectives shall be the prime consideration. In so doing, the following shall govern.

(1) Microelectronic technology shall be considered and microelectronic items shall conform to the requirements specified herein and AR-5.

(2) Other parts and materials requirements shall conform to Specification MIL-E-5400.

(3) Nonrepairable subassemblies as outlined in Specification MIL-E-5400, shall be used when practicable. The general size of the subassembly and the amount of circuitry to be included therein shall be approved by the procuring activity. Nonrepairable subassemblies must be reliable. (See 6.5.)

(4) When previously produced models of this equipment did not use nonrepairable subassemblies, the design shall not be changed to employ nonrepairable subassemblies without the approval of the procuring activity.

*3.2.1 Nonstandard Parts and Materials Approval - Approval for the use of nonstandard parts and materials (including electron tubes, transistors and diodes) other than microelectronic devices shall be obtained as outlined in Specification MIL-E-5400 Microelectronic devices shall be approved in general accordance with AR-5

3.2.2 Microelectronic Modular Assemblies - When used Microelectronic Modular Assemblies shall meet the requirements of AR-5.

*3.2.3 Module - A Maintenance Module is defined as the least complex segment of the contract end article(s) which is capable of being removed and replaced at organizational level maintenance using tools support equipment and procedures approved for the end article(s). Further, it is the segment to which the Contractor will provide fault detection level maintenance requirements.

*3.3 Design and Construction - The equipment shall conform with all the applicable requirements of Specification MIL-E-5400, for design, construction and workmanship, except as otherwise specified herein. When necessary to meet performance characteristics any component mounted by its leads may have lead lengths less than 1/8" to its terminals, more than three components may be connected to the same terminal and a component may be positioned over leads of another component.

*3.3.1 Total Weight - The total weight of the equipment, excluding cables and mounting, shall be a minimum consistent with good design and shall not exceed 45 pounds.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:34Z
Check the source to verify that this is the currentversion before use.

3.3.2 Reliability

*3.3.2.1 Operational Stability - The equipment shall operate with satisfactory performance, continuously or intermittently for a period of at least 300 hours without the necessity for readjustment of any controls which are inaccessible to the operator during normal use.

*3.3.2.2 Operating Life - The equipment shall have total operating life of 40 000 hours with reasonable servicing and replacement of parts. Parts requiring scheduled replacement and replacement intervals shall be specified by the contractor.

*3 3.2.3 Reliability in Mean-Time-Between-Failures (MTBF) - The specified mean (operating) time between failures for the Display Group shall be 2,000 hours, when tested and accepted in accordance with paragraph 4.4.3.

*3.3.2.4 Time Totalizing Meter - The Tactical Data Display shall contain a time totalizing meter type MS17322-2 in accordance with Specification MIL-M-7793

3.3.3 Cabling and Connections

*3.3.3 1 Cables and Connectors - The equipment shall provide for the use of cables and connectors in accordance with Specification MIL-W-5088. Connectors shall conform to MIL-C-26500 The use of Triax connectors is authorized.

3.3.3.2 Interconnection Cabling - The equipment shall be capable of satisfactory operation using external wiring in accordance with the applicable requirements of WR-101, Part I The external wiring shall be unshielded, except that a minimum number of individual wires may be shielded when demonstrated as necessary to meet interference control requirements and provided the assembly of the cable to its plugs may be easily accomplished External cables and that portion of the connectors attached to the cables shall not be supplied as part of the equipment.

3.3 4 Control Panels - All rack or console mounted control panels shall conform to the applicable requirements of Specification MIL-C-6781. The configuration of all panels must be approved by the procuring activity prior to preproduction testing

*3 3.5 Interchangeability - The equipment shall meet the interchangeability requirements of Specification MIL-E-5400.

*3.3.6 Interference Control - The equipment shall conform with all of the requirements of WR-101, Part I.

*3 3.7 Provisions for Maintainability - The contractor shall establish and conduct a maintainability program in accordance with MIL-STD-470 and MIL-STD-471 All maintenance actions shall be capable of being performed by a technician with a comprehensive ability level as follows

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

(a) Civilian eduation - High schóol graduate or equivalent.

(b) Technical training- Navy school, Class A Technician appropriate to the maintenance task.

(c) Experience - Two (2) years of technician experience in addition to technical training.

*3.3.7.1 Compatibility with VAST - VAST compatibility is not intended.

*3.3.7.2 Operational Maintainability Requirements - The time required to perform unscheduled maintenance actions shall be composed of

(1) Recognition of a fault.
(2) Isolation of the fault to a maintenance module.
(3) Maintenance module replacement.
(4) Adjustment or Alignment (when required).
(5) Check out of the repair.
(6) Retest for system readiness.

Mean Repair Action Time is the summation of all maintenance downtimes during a given period divided by the number of maintenance tasks performed during the same period. For Organizational maintenance this number shall not exceed thirty (30) minutes The maximum time required to accomplish any single maintenance action at Organizational level will not exceed sixty (60) minutes.

*3.3.7.3 Readiness Measurement Requirements - Suitable features shall be incorporated in the equipment to provide the operator while airborne and while on the ground, with GO-NO-GO indication of equipment readiness These features may be in conjunction with, but not necessarily as part of the fault isolation features.

*3.3.7.4 Packaging Requirements - The equipment shall be packaged in modular form so that, to the maximum extent practical all subassemblies shall be of the plug-in type and should be easily removable. If a special tool is required for removal, it shall be provided and attached to the equipment.

*3.3.7.5 Module Commonality - The number of different modules will be kept to an absolute minimum. This standardization is mandatory to ease the testing and spares requirements at all levels of maintenance.

*3.3.7.6 Maintenance Module Accessibility - Maintenance module arrangement will be such that access to each module does not require the removal of adjacent modules or parts other than access panels.

*3.3.7.7 Keying - Modules and connectors, except those required for shielded leads, shall be keyed to prevent the insertion of a connector or module into an improper location within or on the equipment.

*3.3.7.8 Part Replacement - Part replacement on the analog modules shall be possible by skilled technicians working in a designated service area such as an intermediate maintenance activity. Use of potting compounds excessive

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

moisture/fungus proofing compounds or any other substance to mechanically support piece parts is forbidden. Use of potting compounds for moisture/fungus proofing purposes is allowed, provided

(1) A 30-mil thickness is not exceeded.

(2) Reference designators and/or part identifications remain clearly legible.

(3) Compliance with paragraph 3.2.1 1.9 of MIL-E-5400 is maintained.

(4) Part replacement is not impeded.

*3 3 7.9 Non-repairable Assemblies - All designs for non-repairable assemblies shall be submitted to the Procuring Activity for approval, prior to release for fabrication.

*3.3 7.10 Adjustments - Procuring activity approval is required for design and use of all periodic adjustment alignment, or calibration functions except for those specified herein Adjustments required at the organizational level shall be identified and accessible without a requirement to remove or relocate the module any other module or part.

*3.3 7.11 Access Panels - Access panels shall be retained by quick-disconnect fasteners i e., hand-operated slide Dzus type etc.

*3.3.7.12 Service Access - Devices requiring removal periodically for inspection and/or servicing shall be retained by quick-disconnect fasteners, i e., hand-operated, Dzus type, etc.

*3.3.7.13 Mounting Devices - Connectors receptacles circuit breakers or any other electronic parts, shall not be a part of any mounting device associated with the equipment

*3.3 7.14 Handles - A handle or handles shall be provided if required to afford one man optimum handling. Handle location shall be appropriate for ease of handling installation and removal, and consistent with viewing of CRT display.

*3.3.7.15 Protective Devices - Circuit breakers shall be used Circuit breaker reset mechanisms shall be accessible from the exterior of the equipment and shall be of the fault indicating type.

*3.3.7 16 Fault Isolation

*3.3.7.16.1 Fault Isolation - In conjunction with but not necessarily as part of the Performance/Readiness testing features there shall be features incorporated which will permit fault isolation to the maintenance module level. These features shall include the necessary switching arrangement to test the equipment with the CPT that will clearly indicate whether or not the function selected is at least equal to minimum performance standards Means shall be provided to use general or standard test equipment i.e oscilloscope, VTVM etc.

*3.3 7 16 2 Diagnostic Ability - If feasible, the equipment shall be logically and electrically designed to facilitate the location of malfunctioning modules through diagnostic programming in conjunction with the aircraft computer and/or other installed electronic equipment Test points shall be made available at the front of the equipment to assist diagnosis of malfunctions.

*3.3.7.16.3 Interface Specification - The contractor shall be responsible for preparation and delivery of the diagnostic interface specification

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

*3.3.7.17 Test Points

*3.3.7.17.1 Test Point Requirement - All test points shall be in accordance with MIL-STD-415 and shall accommodate standard Navy approved test equipment; i.e., multimeter or oscilloscope probes. In the event test points cannot accommodate standard probes, use of adapters will be permitted. These adapters are to be provided with and secured to the set.

*3.3.7.17.2 Power Supply Test Points - Accessible external individual test points shall be provided on the equipment to measure the output voltages. The test points shall be identified as to the voltage normally present.

*3.3.7.17.3 Chassis Test Points - Test points and built-in test facilities shall be included in the design of the equipment. Test points shall be chosen to provide a straightforward logical, step-by-step trouble shooting sequence, as well as provide a single end-to-end performance check.

*3.3.7.18 Special Support Equipment - There shall be no special support equipment for the Display Group except as authorized by the procuring activity.

3.3.8 Nomenclature and Nameplates - Nomenclature assignment and nameplate approval for equipment identification shall be in accordance with Specification MIL-N-18307.

*3.3.9 Standard Conditions - The following conditions shall be used to establish normal performance characteristics under standard conditions and for making laboratory bench tests.

Temperature	Room Ambient (25°C ±5°C)
Altitude	Normal ground
Vibration	None
Humidity	Room ambient up to 90% relative humidity
Input power voltage	115 ±1.0 V AC Single phase, 400 ±20 Hz and 27.5 ±0.5 V DC

*3.3.10 Service Conditions - The equipment shall operate satisfactorily under any of the environmental service conditions or reasonable combination of these conditions as specified in Specification MIL-E-5400 for Class 1A equipment, except as modified herein.

*3.3.10.1 Vibration. The equipment shall operate satisfactorily when subjected to the vibration requirements of Curve I and II of Specification MIL-E-5400, or ±2 g whichever is less

3.3.10.2 Temperature - The equipment shall perform satisfactorily when operated within the temperature range of -25°C to +55°C Degraded performance may occur when operating within the temperature range of -54°C to -25°C.

3.3.11 Warm-up Time - The time required for the equipment to warm up prior to operation shall be kept to a minimum and shall not exceed 5 minutes under standard conditions, and 5 minutes at -25°C Turn-on capability shall be maintained down to a temperature of -54°C with no damage to the equipment.

3.3.12 Input Electrical Power

*3.3.12.1 Operating Power - The equipment shall meet all applicable requirements of MIL-STD-704 and shall give specified performance. The power required shall not exceed the specified amounts from the following power sources.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

(1) AC Power (Single phase), 115 volts, 400 Hz, Category B, 350 VA.

(2) DC Power, 28 volts, Category B, 20 Amperes

The equipment shall operate within the bounds of the transient AC limits 2 and 3 of figure 3 of MIL-STD-704A, except that the upper operating limit shall be 130 volts and the lower operating limit shall be 100 volts The equipment shall operate within the transient frequency limits 2 and 3 of figure 5 of MIL-STD-704A and shall operate within the transient DC limits 2 and 3 of figure 9 of MIL-STD-704A except that the lower operating limit shall be +25 volts.

*3 3.12 2 Lighting Power - Input power for lighting shall require not more than 0.3 amp at 0 to 28 V DC

*3.3.12.3 Standby Power - The equipment shall provide for a standby position whereby rated voltage shall be applied to all tube filaments Except for the associated filament circuits, voltages shall not be applied to other parts of the equipment The standby power shall not exceed 3 VA. When the standby provision is not supplied the equipment shall provide for warm-up for the CRT filament.

*3 3 12 4 Degraded Performance - Degraded performance will be permitted for voltage transients not exceeding 0 5 second during normal electric system operation Operation shall return to normal with no resulting damage to the equipment. Degraded operation may occur when the input power exceeds the limits of paragraph 3.3 12 1 but remains within limits 1 and 4 of figures 3, 5 and 9 of MIL-STD-704A However, no damage shall be suffered by the equipment and normal operation shall automatically resume upon return of the input power voltage to levels within the operating limits as defined above.

*3.3.13 Cooling - The Tactical Data Display shall operate in a temperature environment of +55°C maximum Air circulating fans required for operation at this temperature are mounted internal to the Tactical Data Display and designed to accommodate the free delivery of air Cooling of the Tactical Data Display Control shall be accomplished by natural cooling based on conduction radiation and free convection which uses the ambient as the thermal sink

*3 4 Performance - Unless otherwise specified values set forth to establish the requirements for satisfactory performance apply to performance under both standard and extreme service and input power conditions When reduced performance under the extreme conditions is acceptable tolerances or values setting forth acceptable variations from the performance under the standard conditions will be specified.

*3 4.1 Operation - The Display Group shall be capable of displaying computer-generated data consisting of alpha-numeric dot-formatted characters, special symbols, straight lines, and circles in conjunction with the Data Analysis Logic Unit MX-8034/AYA-8

*3.4.2 Accuracy - The bear shall be positioned within ±2% of the useful display screen diameter

*3 4.3 Frequency Characteristics - The display CRT shall provide a flicker-free display at 40 frames/sec The sine wave frequency for generating lines and circles shall be 12 kHz

*3.4.4 Video Presentations - In conjunction with the Data Analysis Logic Unit the Display Group will

(1 Display a point and one or two characters at a defined position.

(2) Display an open ended sequence of characters (type message), starting at a defined coordinate position (two characters per word).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

(3) Display straight lines centered about defined coordinate positions.

(4) Display circles centered about defined coordinate positions.

(5) Flash a single character or group of characters The nominal height for all characters shall be 0.125 inch.

(6) Inhibit any of the previous presentations from appearing on the display

*3.4.5 Sensitivity - A deflection signal from ±6 V to ±8 V shall deflect the beam ±3.8" (one radius). Video signals between +2.0 V to +2.5 V shall provide for maximum video intensity The unblank signal shall be +5 ±1 volts. The Display Group shall interface directly with the Data Analysis Logic Unit.

3.5 Detail Requirements

*3.5.1 Display Tactical Data IP-886/ASA-66 - The Tactical Data Display shall meet the following requirements

*3.5.1.1 Function - The Tactical Data Display shall provide a means of electronically displaying tactical situations to the pilot. It shall receive its input signals from the Data Analysis Logic Unit MX-8034/AYA-8 and transform these into a visual presentation. All input signals shall originate from the logic unit.

*3.5.1.1.1 Input Signal Characteristics

(1) Deflection Signal - The rise time of the input deflection step voltages for the generation of the character raster shall be less than 0.8 microsecond Input signals from ±6 to ±8 volts are required for a beam deflection of ±3.8" (one radius).

(2) Video Signal - The input video signal shall be delayed a minimum of 1.3 microseconds to a maximum of 1.45 microseconds after the start of the deflection voltage for the presentation of any data. The rise time of the video signal shall be 1 nanosecond maximum. The video input level shall be between +2.0 to +2.5 volts maximum with 0 V for the black reference levels When characters are being generated, the minimum video shall be +1 volt

(3) Unblank Signal - The rise time of the unblank signal shall be 1.0 nanosecond maximum. The unblank signal is +5 ±1 volts (unblank) and 0 V (blank).

(4) Radial Compensation Signal - A step voltage pulse of 17.5 milliseconds duration and +5 ±1 volts shall be supplied as this signal. The rise time of the radial compensation signal shall be 1.5 microseconds maximum.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:34Z
Check the source to verify that this is the current version before use.

3.5.1.2 Form Factor The maximum dimensions of IP-886/ASA-66 shall not exceed 12.27 inches in width, 12.21 inches in height and 12.07 inches in depth.

*3 5.1.3 Weight - The weight of the Tactical Data Display shall be less than 44 pounds

*3 5.1 4 Contents - The Tactical Data Display shall consist of the following major subassemblies

Deflection Amplifiers

Amplifier Unblank and Radial Compensation

Video Amplifier

Phosphor Protection Circuit

Low Voltage Power Supplies

High Voltage Power Supply

Built-In Test Equipment

Chassis with CRT

(1) Deflection Amplifiers - The amplifiers shall be identical for both horizontal and vertical deflection The input circuits of the deflection amplifiers shall process the deflection signals for rejection of common mode signal provide grounding isolation between the Display Group and the transmitting sources, and must be capable of tolerating a voltage difference of up to ±4 volts DC between the triax conductor with its inner shield and the airframe (outer shield)

The termination for the input signal shall be resistive between 90-95 ohms and have a maximum of 100 pf capacitance

The time of response and settling to 1 0% of a useful diameter of the CRT for the deflection amplifier and equalization circuit combination shall not exceed 18 microseconds in the random write mode and shall not exceed 15 microseconds in the raster scan mode

The small signal bandwidth for character generation shall be a minimum of 900 kHz Linearity correction circuitry shall be incorporated into the amplifier to provide a linear relationship between the input voltage and the CRT beam deflection distance

The linearity correction circuitry shall allow the beam to be positioned within ±2% of the useful CRT diameter.

Adjustments shall be provided to shift the phase difference to zero between the deflection amplifiers Peaking control gain equalization BITE signal phase shift deflection gain bias and centering adjustments shall be provided

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:34Z
Check the source to verify that this is the current version before use.

(2) Amplifier, Unblank and Radial Compensation - The unblank amplifier and radial compensation circuit shall accept positive-going video, unblank and radial compensation signals. Rejection of common mode voltage shall be provided for by means of differential inputs capable of tolerating voltage differences of up to ±4 V DC between the triax conductor with its inner shield and the airframe (outer shield). The input signal termination shall be between 90-95 ohms resistive, and no more than 100 pf capacitance. Grounding isolation between the transmitting source and the Display Unit shall be provided.

For future utilization, the radial compensation circuit shall allow the video output of the video amplifier to increase as the spiral raster increases in diameter. The ramp voltage generated by this circuit shall be adjustable and provide for a constant display intensity as the writing rate increases. The circuit shall provide a ramp having a peak voltage up to +8 V at the end of the compensation period and shall return to 0 volts in less than 6 ±1.5 milliseconds

When connected to the video amplifier, the unblank amplifier shall have a nominal gain of 1, and be direct coupled with provision for remote adjustment of this gain, for the video signal. For the unblank signal, the unblank amplifier shall be direct coupled and have a nominal gain of 0.5 The response time of the unblank amplifier to a step voltage at the video and unblank inputs shall be 6 nanoseconds maximum measured at their respective outputs.

The outputs of the unblank amplifier and radial compensation circuit shall be the inputs to the video amplifier. The unblank amplifier shall provide for the unblank of the CRT when an unblank signal is received.

(3) Video Amplifier - The video amplifier shall be DC coupled and shall receive positive-going video, unblank, and radial compensation signals from the Unblank Amplifier and Radial Compensation Circuit It shall combine these inputs into a single output. The amplifier output shall have at least a 45 V dynamic range An adjustment shall be provided to set the quiescent output level over a range of at least 10 volts

The video amplifier shall have a sufficient bandwidth so that when driver by a step input voltage via the video input of the Unblank Amplifier the video channel shall exhibit an equivalent bandwidth of 35 MHz for an output swing of at least 20 volts with the amplifier loaded by the CRT and associated wiring Under these conditions the rise time of the output of the video amplifier shall be 10 nanoseconds maximum, when driven by a step voltage via the Unblank Amplifier unblank input, the response of the video amplifier output

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:34Z
Check the source to verify that this is the current version before use.

shall not exceed 40 nanoseconds. The amplitudes of the step inputs shall be according to paragraph 3.5.1.1.1.

When radial compensation is used, the video amplifier shall provide a compensation ramp voltage of up to 4.5 volts peak at the output of the video amplifier.

(4) Phosphor Protection Circuit - The phosphor protection circuit shall prevent burning of the CRT phosphor under normal operations and predictable failure conditions

(5) Low Voltage Power Supplies - The low voltage power supplies shall be incorporated into the display to provide the DC power necessary for proper display operation. The regulation of these supplies shall be ±2% over the voltage range of 3.3.12.

(6) High Voltage Power Supply - The high voltage power supply shall be incorporated into the display to provide the necessary high voltage potentials The regulation of the accelerating supply shall be ±2% over the voltage range of 3 3.12

(7) Built-In Test Equipment (BITE) - The BITE circuitry shall consist of a module for the generation of deflection test signal and a module for video and unblank test signals. The BITE circuitry shall also provide the voltages and switching that will enable the maintenance modules to be checked for satisfactory operation. When in self test, all external signal inputs to the Tactical Data Display shall be ignored.

(8) Chassis with CRT - The chassis of the Tactical Data Display shall contain the CRT alignment assembly, EMI filter, equalization transformers, component boards circuit breaker, controls and other miscellaneous components

The CRT shall have a maximum diameter of 9 0 inches, maximum length of 9.5 inches and a minimum useful screen diameter of 7 6 inches. It shall employ low voltage electrostatic focusing and magnetic deflection. The screen shall use P-31 aluminized phosphor and have a line width of 0 012 ±0.004 inches measured by shrinking raster method resulting from 50 microamperes anode current Electrical characteristics shall have the following maximum ratings

Grid No. 1 - Neg. bias value, 140 V max.
- Pos. bias value, 0 V max.
- Pos. peak value, 0 V max.

Grid No. 2 - 700 V max.

Grid No. 3 - (Internal connection)

Grid No. 4 - (Focus), 1000 V max.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

Anode Voltage - 12,000 V max.

Heater Voltage - 6.3 V

Heater Current - 0.300 amp

A high efficiency, anti-reflection (HEA) coating shall be applied to the outside surface of the neutral density (55 percent transmissibility) filter bonded to the CRT.

A variable density polarized filter shall be provided on each equipment. The transmissibility of the filter assembly shall be adjustable approximately between 5 and 20 percent A high efficiency, anti-reflection (HEA) coating shall be applied to variable red filter.

*3.5.1.5 Controls - The Tactical Data Display shall contain controls on the unit front panel. The lighting of the plastic panel shall conform to MIL-P-7788 Class 1-R Type I with a lamp voltage of 0 to 28 volts The following operator controls shall be mounted so as to be accessible in the fully installed position.

(1) A Display Group POWER switch shall be provided on the front panel of the Tactical Data Display. This switch will have circuit breakers for both AC and DC power as an integral part of its function, and is an operational control It shall have a trip coil for the protection of the deflection amplifiers.

(2) A MODE switch shall be provided on the front panel of the Tactical Data Display for the selection of either the normal or BITE modes and is an operational control.

*3.5 1.6 Electrical Connections - Connections to external circuits shall be provided as follows

Reference Designation	Receptacle Type	Function
1J1	MS24264R22B12P	Power inlet
1J2	MS24264R12B12S	Outlet to Tactical Data Display Control
1J3	Dage - 4679-1 or approved equivalent	Video input
1J4	Dage - 4679-1 or approved equivalent	Horizontal input
1J5	Dage - 4679-1 or approved equivalent	Vertical input
1J6	Dage - 4679-1 or approved equivalent	Radial compensation input
1J7	Dage - 4679-1 or approved equivalent	Unblanking input

*3.5.1.7 Mounting - The Tactical Data Display shall be hard mounted.

*3.5 2 Control, Tactical Data Display C-7444/ASA-66 - The control shall meet the applicable requirements of Specification MIL-C-6781 for Type I Control Panel. The lighting on the plastic panel shall conform to MIL-P-7788 Class 1-R Type I with a lamp voltage of 0 to 28 volts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

*3.5.2.1 Function - The Tactical Data Display Control shall control the brightness and video level of the display.

*3.5.2.2 Form Factor-The maximum dimensions of C-7444/ASA-66 shall exceed 5.75 inches in width, 1.5 inches in height and 2.63 inches in depth.All connectors shall be mounted at the rear. Knobs shall conform to MIL-K-25049.

*3 5.2.3 Weight - The weight of the Tactical Data Display Control shall not exceed 1 pound

*3 5 2.4 Contents - The Tactical Data Display Control shall contain the following components

(1) Potentiometer for video control

(2) Potentiometer for brightness control

(3) Regulator for video control voltage

*3.5.2 5 Controls - The Tactical Data Display Control shall contain operator controls as listed below

(1) Brightness - The BRT control shall be used to vary the brightness of the Tactical Data Display CRT presentation

(2) Video - The VID control shall be used to vary the amplitude of the video in the Tactical Data Display.

*3.5.2.6 Control Signals - The control signals shall be as follows

*3 5.2 6.1 Input for Control Voltages - Reference voltages shall be provided from the Tactical Data Display for controlling the video intensity and brightness level of the CRT presentation.

*3 5 2 6 2 Reference Control Voltages

(1) Video Signal - A video control voltage shall be provided for controlling the video intensity of the display CRT presentation This level shall be adjusted by the VID control

(2) Brightness - A brightness voltage shall be provided for controlling the brightness of the display CRT presentation. The level shall be adjusted by the BRT control.

*3 5.2 7 Electrical Connections - Connections to external circuits shall be provided as follows

Reference Designation	Receptacle Type	Function
2J1	MS24264R12B12P	Interconnection with Tactical Data Display

*3 5 2 8 Mounting - The Tactical Data Display Control shall be mounted on a standard control panel mounting rail assembly with 5.365 ±0 005 inch mounting centers in accordance with MIL-C-6781

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:34Z
Check the source to verify that this is the current version before use.

3.5.2.9 Grounding - All electronics contained in the Tactical Data Display Control Unit shall be isolated from airframe ground.

4. QUALITY ASSURANCE PROVISIONS

*4.1 Responsibility for Inspection - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection and test requirements as specified herein Except as otherwise specified the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements

*4.1 1 Classification of Tests - Items covered by the specification shall be subjected to the following tests to determine compliance with all applicable requirements.

(1) Preproduction (First Article) Tests

(2) Initial Production Tests

(3) Acceptance Tests

(4) Life Tests

4.2 Preproduction (First Article) Tests - Preproduction tests shall be conducted by the contractor on an equipment representative of the production equipments to be supplied under the contract. Preproduction tests shall be accomplished under the approved test procedure of 4.6 The Government inspector and the procuring activity shall be advised when tests are to be conducted so that a government representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the services of a commercial testing laboratory acceptable to the Government.

*4 2.1 Preproduction (First Article) Test Data - The contractor shall submit all data collected in conducting these tests to the procuring activity for review

*4.2.2 Scope of Tests - Preproduction tests shall include all tests deemed necessary by the procuring activity to determine that the equipment meets all the requirements of this specification, other applicable specifications and the contract. Preproduction tests shall include environmental tests in accordance with the procedures of Specification MIL-T-5422, and interference tests in accordance with WR-101, Part I.

*4.2 3 Preproduction (First Article) Approval - Approval of the preproduction sample shall be by the procuring activity upon satisfactory completion of all tests No production equipments shall be delivered prior to the approval of the preproduction sample Prefabrication of production equipment prior to the approval of the preproduction sample is at the contractor's own risk The approved preproduction sample shall be retained by the contractor for his use in the fabrication and testing of equipment to be submitted for acceptance. The preproduction sample shall not be considered as one of the equipments under the contract.

*4.2.4 Production Equipments - Equipments supplied under the contract shall in all respects including design construction, workmanship, performance and quality be equivalent to the approved preproduction sample. Each equipment shall be capable of successfully passing the same tests as imposed on the pre-production sample Evidence of non-compliance with the above shall constitute cause for rejection and for equipment already accepted by the Government, it shall be the obligation of the contractor to make necessary corrections as approved by the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:34Z
Check the source to verify that this is the current version before use.

*4.3 Initial Production Tests - One of the first ten production equipments shall be selected and sent at the contractor's expense to a designated Government laboratory for tests. This equipment shall be selected by the procuring activity after the equipment has successfully passed all individual tests. No other tests shall be conducted on the equipment prior to starting the Initial Production Tests. The preproduction sample shall not be selected for this test.

4.3.1 Scope of Tests - This equipment may be subjected to any and all tests the procuring activity deems necessary to assure that the production equipment is equivalent to the previously approved preproduction sample in design construction workmanship performance and quality and that it meets all applicable requirements.

4.3.2 Accessory Material - In addition to the complete equipment submitted for Initial Production Tests, the contractor shall also submit such accessory material and data necessary to test the equipment.

4.3.3 Initial Production Sample Approval - Approval of the Initial Production Sample shall be by the procuring activity upon satisfactory completion of all tests. Any design, material or performance defect made evident during this test shall be corrected by the contractor to the satisfaction of the procuring activity. Failure of the Initial Production Sample to pass any of the tests shall be cause for deliveries of equipment under the contract to cease until proper corrective action is approved and accomplished. Corrective action shall also be accomplished on equipment previously accepted when requested by the procuring activity.

4.3.4 Reconditioning of Initial Production Test Sample - On completion of the Initial Production Test, the equipment shall be reworked by the contractor by replacing all wear or damage items. After reworking, the contractor shall resubmit the equipment for acceptance.

*4.4 Acceptance Tests - The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the Government inspector. Contractors not having testing facilities satisfactory to the procuring activity shall engage the service of a commercial testing laboratory acceptable to the procuring activity. The contractor shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the contractor or laboratory as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following:

(1) Individual Tests
(2) Sampling Tests
(3) Reliability Assurance Tests
(4) Special Tests

*4.4.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability. As a minimum, each equipment accepted shall have passed the following tests:

(1) Examination of Product
(2) Operational Test
(3) Manufacturing Run-In Test

*4.4.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

4 4.1.2 Operational Test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

*4 4.1.3 Manufacturing Run-In Test - Each equipment shall be operated under the conditions specified herein for a period of ten (10) hours without failure A failure shall be defined as anything which causes malfunctioning of the equipment Only those adjustments will be permitted which can be made by using such controls and adjustments that are accessible to the operator during the normal use of the equipment This test shall be deleted if the reliability test includes a test on each equipment which consumes at least 10 hours of operation.

Temperature	Ambient room
Humidity	Ambient room
Vibration	Any selected frequency within the range of 20 to 30 Hz (excluding resonant points) and a minimum amplitude of ±2 g's

The equipment shall be vibrated (without vibration isolators) for a period of 10 minutes prior to the beginning of the 10 hour period of operation. Where feasible the equipment shall be operated during this vibration period for the purpose of detecting flaws and imperfect workmanship. Operation within the specified limits of satisfactory performance is not necessarily required during the vibration period. The direction of vibration should be vertical to the normal mounting plane for 5 minutes and lateral to the plane for 5 minutes. Where it is not feasible to vibrate the equipment in two directions, the vertical direction shall be used. During the 10 hour period of operation following the 10 minute vibration period the equipment shall be mechanically cycled periodically through its various phases of operation Should a failure occur, it should be repaired and the test started over except that the 10 minute vibration period need not be repeated when it is certain the failure was not a result of the vibration. Should repetitive failures occur, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures The 10 hour period specified above may be composed of two 5 hour periods to conform with standard working hours. This test is not required if a Reliability Assurance Test is selected which includes a test on each equipment which consumes at least 10 hours of operation.

*4 4.2 Sampling Tests - Equipments selected for sampling tests shall first have passed the individual tests. Equipments shall be selected for sampling tests by the Government inspector in accordance with the following

Quantity of Equipments Offered for Acceptance	Quantity to be Selected for Sampling Test
First 10	0 (See Note)
Next 50	1
Next 75	1
Next 100	1
	1 for each additional 200 or fraction thereof

NOTE If by contract action the Initial Production Test is deleted a Sample Test shall also be conducted on one equipment from the first 10 produced.

Sampling Tests are not required when Reliability Assurance Tests are conducted.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

*4.4.2.1 Scope of Tests - As a minimum, each equipment selected for sampling tests shall be subjected to the following tests

(1) Complete operational test at ambient room conditions, making all necessary measurements to assure that all applicable specification requirements have been met.

(2) Operational test at certain environmental conditions The conditions may vary for each equipment tested and should be based on results of the preproduction initial production individual and special tests

(3) Manufacturing run-in test specified in paragraph 4 4.1.3 except that the test duration shall be 120 hours with no restriction on the number of failures. However each failure shall be analyzed as to cause and remedial action necessary to reduce the possibility of its recurrence in future equipment.

*4 4.3 Reliability Assurance Tests - Reliability Assurance Tests shall be conducted using MIL-STD-781 Tests as required by both the Qualification Phase and the Production Acceptance (Sampling) Phase shall be conducted. Failure classification shall be in accordance with AR-34.

4.4 3.1 Qualification Phase - Prior to the acceptance of equipments under the contract or order a minimum of three (3) equipments shall be tested as outlined in MIL-STD-781 under the section entitled "Qualification Phase of Production Reliability Tests." The maximum number of equipments to be used shall be those listed in Table 5 of MIL-STD-781 For the Qualification Phase, Test Level E shall be used except that the lower temperature limit will be -25°C. The Accept-Reject Criteria for Test Plan IV shall be used.

*4 4.3.2 Reliability Production Acceptance (Sampling) Phase Tests - Samples of the production equipment shall be tested as outlined in MIL-STD-781 (as modified herein) under the section entitled "Sampling Phase of Production Reliability Tests " For the Sampling Phase (or All-Equipment Test) Test Level E shall be used except that the lower temperature limit will be -25°C.

*4 4.3.2 1 All Equipment Test - Each equipment produced shall be tested for 50 hours Prior to the 50 hour test on each equipment a burn-in period may be used at the option of the contractor If the burn-in period is to be used the details thereof must be included in the approved test procedures. To determine whether the MTBF is being met at any time during the contract the operating test hours and the failures thereon (not counting burn-in failures or burn-in operating time, shall be totaled and the results compared with the reject line of Test Plan II of MIL-STD-781 (Extend the line as necessary to accommodate the data.) These totals shall accumulate so that any one time the experience from the beginning of the contract is included At the conclusion of each month the test results shall be sent to the procuring activity and to the Naval Air Systems Command Attn Avionics Division. At any time that the current totals of test hours and test failures plotted on Test Plan II curves show a reject situation, the procuring activity shall be notified The procuring activity reserves the right to stop the acceptance of equipment at any time that a reject situation exists pending a review of the contractor's efforts to improve the equipment, the equipment parts the equipment workmanship etc , so that the entire compilation will show other than a reject decision.

*4.4.3.3 Test Details - The test details such as length of the test cycle, the length of the heat portion of the cycle, the performance characteristics to be measured, special failure criteria, preventive maintenance to be allowed

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

during the test, etc., shall be part of the test procedures to be submitted and approved by the procuring activity prior to the beginning of the Qualification Test Phase of the Reliability Assurance Tests.

*4.4.4 Special Tests - Special tests shall be conducted for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the sampling or reliability assurance tests.

4.4.4.1 Special Test Schedule - Selection of equipments for special tests shall be made as follows

(1) On an early equipment after an engineering or material change

(2) Whenever failure reports or other information indicate that additional tests are required. (This will be determined by the procuring activity.)

4.4.4.2 Scope of Tests - Special tests shall consist of such tests as approved by the procuring activity. Test procedures previously approved for the preproduction tests shall be used where applicable. When not applicable, the contractor shall prepare a test procedure and submit it to the procuring activity for approval prior to conducting the tests

4.4.5 Equipment Failure - Should a failure occur during either the sampling, reliability assurance or special tests, the following action shall be taken

(1) Determine the cause of failure.

(2) Determine if the failure is an isolated case or design defect.

(3) Submit to the procuring activity for approval, proposed corrective action intended to reduce the possibility of the same failure(s) occurring in future tests.

(4) Where practical, include a test in the individual test to check all equipment for this requirement until reasonable assurance is obtained that the defect has been satisfactorily corrected.

*4.5 Life Test - The contractor shall furnish all samples and shall be responsible for accomplishing the life tests The test shall be of 300 hours duration and shall be conducted on equipments that have passed the individual test The life test shall be performed under the conditions specified in 4.5.1 The life test sample shall be selected by the Government inspector in accordance with the following (Equipments which have successfully passed the Initial Production Test Sampling Tests, Reliability Tests or Special Tests may be selected for life tests.) When reliability tests are conducted the life test shall be omitted if during the reliability tests a quantity of equipments equal to or more than that listed below receive at least 300 hours each of test time.

Quantity of Equipments Offered for Acceptance	Quantity to be Selected for Life Test
First 25	1
Next 175	1
Next 300	1
	1 for each additional 500 or fraction thereof

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

*4.5.1 Test Conditions - The life test shall be conducted under the following simulated service conditions:

Temperature	Normal room
Altitude	Normal ground (0-5000 ft)
Humidity	Room ambient
A.C Voltage	115 ±5 volts (at lowest applicable frequency)
D C Voltage	27.5 ±2.0 volts

*4 5.2 Test Periods - The test may be run continuously or intermittently Any period of operation shall be of sufficient duration to permit the equipment temperature to stabilize. Periodically, the equipment shall be turned on and off several times and put through its various phases of operation.

*4.5.3 Performance Check - At approximately 8 hour intervals during the test a limited performance check shall be made. The performance check proposed by the contractor shall be subject to approval by the procuring activity

*4 5.4 Test Data - The contractor shall keep a daily record of the performance of the equipment, making particular note of any deficiencies or failures In the event of part failures the defective part shall be replaced and the operation resumed for the balance of the test period A record shall be kept of all failures throughout the test This record shall indicate the following

(1) Part type number
(2) The circuit reference symbol number
(3) The part function
(4) Name of the manufacturer
(5) Nature of the failure
(6) The number of hours which the part operated prior to failure

*4 5.4 1 Failure Report - In the event of a failure the Government inspector shall be notified immediately A report shall be submitted to the procuring activity upon completion of test In this report the contractor shall propose suitable and adequate design or material corrections for all failures which occurred. The procuring activity will review such proposals and determine whether they are acceptable.

*4 6 Test Procedures - The procedures used for conducting preproduction tests, acceptance tests and life tests shall be prepared by the contractor and submitted to the procuring activity for review and approval The right is reserved by the procuring activity or the Government inspector to modify the tests or require any additional tests deemed necessary to determine compliance with the requirements of this specification or the contract Specification MIL-T-18303 shall be used as a guide for preparation of test procedures. When approved test procedures are available from previous contracts such procedures will be provided and may be used when their use is approved by the procuring activity However the right is reserved by the procuring activity to require modification of such procedures including additional tests, when deemed necessary.

*4.7 Reconditioning of Tested Equipment - Equipment which has been subjected to initial production acceptance and life tests shall be reconditioned by the contractor by replacing all wear or damaged items After reworking the contractor shall resubmit the equipment for acceptance

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

4.8 Presubmission Testing - No item, part or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.9 Rejection and Retest - Equipment which has been rejected may be reworked or have parts replaced to correct the defects and resubmitted for acceptance. Before resubmitting full particulars concerning previous rejection and the action taken to correct the defects found in the original shall be furnished the Government inspector

5. PREPARATION FOR DELIVERY

*5 1 General - All major units and parts of the equipment shall be preserved, packaged, packed and marked for the level of shipment specified in the contract or order in accordance with Specification MIL-E-17555 and MIL-STD-794 In the event the equipment is not covered in Specification MIL-E-17555, the method of preservation for Level A shall be determined in accordance with the selection chart in Appendix D of MIL-STD-794.

6. NOTES

*6.1 Intended Use - The equipment covered by this specification shall be capable of displaying computer-generated tactical and navigational data together with necessary cueing information to the pilot. This shall be accomplished by means of direct communication with the Data Analysis Logic Unit.

*6.2 Ordering Data - Purchasers should exercise any desired options offered herein and procurement documents should specify the following

(1) Title, number, and date of this specification

(2) Selection of applicable levels of packaging and packing (See 5.1)

*6.3 Precedence of Documents - When the requirements of the contract, this specification, or applicable subsidiary specifications are in conflict, the following precedence shall apply

(1) Contract - The contract shall have precedence over any specification.

(2) This Specification - This specification shall have precedence over all applicable subsidiary specifications. Any deviation from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

(3) Referenced Specifications - Any referenced specification shall have precedence over all applicable subsidiary specifications referenced therein. All referenced specifications shall apply to the extent specified.

*6 4 Performance Objectives - Minimum size and weight simplicity of operation, ease of maintenance, and an improvement in the performance and reliability of the specific functions beyond the requirements of this specification are objectives which shall be considered in the production of this equipment. Where it appears a substantial reduction in size and weight or improvement in

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:34Z
Check the source to verify that this is the currentversion before use.

simplicity of design, performance, ease of maintenance or reliability will result from the use of materials, parts and processes other than those specified in Specification MIL-E-5400, it is desired their use be investigated. When investigation shows advantages can be realized, a request for approval shall be submitted to the procuring activity for consideration. Each request shall be accompanied by complete supporting information.

*6.5 Non-Repairable Subassemblies - As a general rule, non-repairable subassemblies should be encapsulated or hermatically sealed The number of connections internal to the subassembly should be held to a minimum Detail parts tolerances and ratings should be so selected that the life of the subassembly is greater than that of a similar repairable one With few exceptions (such as high voltage power supplies), the non-repairable subassembly should evidence a Mean-Time-To-Failure greater than 5000 hours, and for many applications this figure must be nearer 50,000 hours.

*6.6 Type Designation - The parenthesis ( ) when used in the equipment type designation will be deleted or replaced by either a number or letter furnished by the procuring activity upon application by the contractor for assignment of nomenclature in accordance with 3.3.6. The complete type number shall be used on nameplates shipping records and instruction books, as applicable.

6.7 Revisions - In specification revisions and superseding amendments an asterisk "" preceding a paragraph number denotes paragraphs in which changes have been made from the previous issue. This has been done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content as written, irrespective of the asterisk notations and relationship to the last previous issue

*6.8 Associated Equipment - The equipment shall operate with the following associated equipment

Data Analysis Logic Unit MX-8034/AYA-8 or any other providing inputs to the Tactical Data Display Group consistent with the requirements of paragraph 3.4.

Project Number 6605-N192

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:34Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity *(as indicated on reverse hereof)*.

SPECIFICATION

MIL-D-81358B(AS) DISPLAY GROUP, TACTICAL DATA AN/ASA-66

ORGANIZATION *(Of submitter)*	CITY AND STATE

CONTRACT NO	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1 HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A GIVE PARAGRAPH NUMBER AND WORDING.

B RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

2 COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3 IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4 REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1 APR 63 1426

C-8378

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:34Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY
Naval Air Systems Command
Washington, D.C. 20360

POSTAGE AND FEES PAID
NAVY DEPARTMENT

OFFICIAL BUSINESS

NAVAL AIR SYSTEMS COMMAND (AIR-52021)
DEPARTMENT OF THE NAVY
WASHINGTON, D. C. 20360

FOLD

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:34Z
Check the source to verify that this is the current version before use.