INCH POUND

MIL-W-80042C
23 February 1988
SUPERSEDING
MIL-W-80042B
7 February 1977

MILITARY SPECIFICATION

WELDING CONTROL STATIONS FOR MULTI-OPERATOR SYSTEM

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers welding control stations used as components in a direct current, constant voltage (80 volt open circuit), multiple-operator welding systems for shielded metal arc welding (SMAW). When furnished with the necessary optional equipment (see 3.7), the welding control station will also be capable of performing gas metal arc welding (GMAW), direct current (DC), gas and tungsten arc welding, (GTAW),stud welding, and arc air gouging processes. The welding machine power supply used with these control stations are Covered by MIL-W-80040

1.2 Classification. The control stations shall be of the following types and sizes. The type and size to be furnished shall be as specified (see 6.2.1).

Type I - Single operator control station.

Size 200 - 195 amperes capacity per operator station.
Size 250 - 245 amperes capacity per operator station.
Size 300 - 295 amperes capacity per operator station.
Size 400 - 395 amperes capacity per operator station.

Type II - Dual operator welding control station.

Size 200 - 195 amperes capacity per operator station.
Size 250 - 245 amperes capacity per operator station.
Size 350 - 345 amperes capacity per operator station.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Defense Industrial Plant Equipment Center, ATTN: DIPEC-SSG, Memphis, TN 38114 -5051, by using the self-addressed Standardization Document improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 3438

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specification and standards. The following specification and standards form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation.

SPECIFICATION

MILITARY

MIL-W-45562 - Welding and Soldering Equipment, Supplies and Accessories, Packaging of.

STANDARDS

FEDERAL

FED-STD-H28 - Screw Thread Standards for Federal Service.

FED-STD-376 - Preferred Metric Units for General Use by the Federal Government.

2.1.2 Other Government documents. The following other Government document forms a part of this specification to the extent specified herein. Unless otherwise specified, the issue shall be that in effect on the date of the solicitation.

U. S. DEPARTMENT OF LABOR

29 CFR, CHAPTER XVII, PART 1910 - Occupational Safety and Health Standards.

(Application for copies should be addressed to the Superintendent of documents, U.S. Government Printing Office, Washington,DC 20402-0001.)

(Copies of specifications, standards, and other Government documents required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted shall be those listed in the issue of the DODISS specified in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS shall be the issue of the nongovernment document which is current on the date of the solicitation.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3951 - Standard Practice for Commercial Packaging.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

ATSM B 76 - Method of Accelerated Life Test of Nickel-Chromium and Nickel-Chromium-Iron Alloys for Electrical Heating

ATSM B 168 - Specification for Nickel-Chromium-Alloy Plate, Sheet, and Strip.

ATSM B 344 - Specification for Drawn or Rolled Nickel-Chromium and Nickel-Chromium-Iron Alloys for Electrical Heating Elements.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race St., Philadelphia, PA 19103-1187.)

AMERICAN WELDING SOCIETY (AWS)

WELDING HANDBOOK

(Application for copies should be addressed to the American Welding Society, Inc., 2501 NW 7th St., Miami, FL 33125-3136).

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 - National Electrical Code.

(Application for copies should be addressed to the National Fire Protection Association, Batterymarch Park, Quincy, MA 02269-9101.)

(Nongovernment standards and other publications are normally available from the organizations which prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 First article. When specified in the contract or purchase order (see 6.2.1), a sample shall be subjected to first article inspection (see 4.4 and 6.3).

3.2 Design. The welding control station shall be new (not a prototype) and one of the manufacturers' current production models capable of operating from a direct current, constant voltage welding power supply. The welding control station shall be of the single or dual operator type, Type I, single operator type stations, shall have one resistor assembly with one set of controls. The type II, dual operator type stations, shall have two individual resistor elements with separate controls that will allow two operators to weld at the same time. The control station shall be designed for outdoor all weather conditions and to withstand the rough treatment encountered around

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

construction work. The control station shall be enclosed and protected against sea coast environments. The control station shall be equipped with handles *or* other suitable means to permit manual carrying of the unit. The control station shall include all components, parts, and features necessary to meet the performance requirements specified herein. All parts subject to wear, breakage, or distortion shall be accessible for adjustment, replacement, and repair.

3.2.1 Dimensional system. Unless otherwise specified, either the U.S. Customary System of Units (US) or the International System of Units (SI) Shall be used in the design and construction of the control station. When only one dimensional system is acceptable, the particular system required shall be as specified (see 6.2.1). In this specification, all dimensions, measurements, sizes, and capacities are given in US units. These dimensions may be converted to SI units through the use of the conversion factors and methods specified in FED-STD-376.

3.2.2 Reclaimed materials. The control station may contain reclaimed materials provided such materials will not jeopardize the intended use, performance, and design life of the control station. The reclaimed materials shall have been reprocessed, remanufactured, or recycled in a manner which will restore them to the same chemical composition and physical properties as the materials originally selected for use on the control station.

3.2.3 Energy efficiency. The control station and its components that directly consume energy in normal operation shall be designed and constructed for the highest degree of energy efficiency as governed by the latest developments available within the industry.

3.2.4 Controls. All operating controls shall be located conveniently to the operator at his normal work station.

3.2.5 Safety and health requirements. Covers, guards, or other safety devices shall be provided for all parts of the control station that present safety hazards. The safety devices shall not interfere with the operation of the control station. The safety devices shall prevent unintentional contact with the guarded part, and shall be removable to facilitate inspection, maintenance, and repair of the parts. All parts, components, mechanisms, and assemblies furnished on the control station, whether or not specifically required herein, shall comply with all of the requirements of OSHA 29 CFR, Chapter XVII, Part 1910 that are applicable to the control station itself. The control station shall be equipped with all point-of-operation guarding normally furnished as standard on the manufacturer’s commercial control station supplied to the commercial market. Additional safety and health requirements shall be as specified (see 6.2.1).

3.2.6 Environmental protection. The control station shall be so designed and constructed that, under the operating, service, transportation, and storage conditions described herein, the control station shall not emit materials hazardous to the ecological system as prohibited by Federal, state, or local statutes in effect at the point of installation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

3.2.7 Interchangeability. All parts shall be manufactured to definite dimensions and tolerances that will permit installation of replacement parts without modification of the part or control station.

3.3 Construction. The control station shall be constructed of parts which are new, without defects, and free of repairs. The structure shall withstand all forces encountered during operation of the control station to its maximum rating and capacity without permanent distortion.

3.3.1 Welding, brazing, or soldering. Welding, brazing, or soldering shall be employed only where specified In the original design. None of these processes shall be employed as a repair measure for any defective part.

3.3.2 Fastening devices. All fasteners shall be installed in a manner to prevent change of tightness. Fastening devices subject to removal or adjustment shall not be permanently installed.

3.3.3 Surfaces. All surfaces shall be clean and free of harmful or extraneous materials. All edges shall be either rounded or beveled unless sharpness is required to perform a necessary function. Except as otherwise specified herein, the condition and finish of all surfaces shall be in accordance with the manufacturer's commercial practice.

3.3.4 Painting. Unless otherwise specified (see 6.2.1), the control station shall be painted in accordance with the manufacturer's standard commercial practice and color.

3.3.5 Threads. All threaded, parts either US or SI, used on the control station and its related attachments and accessories shall conform to FED-STD-H28 and the applicable "Detailed Standard" section referenced therin.

3.4 Components. The control station shall consist of not less than a frame and enclosure, resistor elements, electrical connections, controls, and protection devices.

3.4.1 Frame and enclosure. The welding control station shall have an enclosure complete with a front, rear, top, and side panels connected to an all welded steel frame forming a rigid unit. A baffle plate shall be installed between the resistor elements and the control panel to protect the switches from the heat of the resistor elements. The welding control station shall be convection cooled with ventilation and cooling adequate to prevent temperatures In excess of design requirement.

3.4.2 Resistor elements. The individual control unit shall contain resistor elements of nickel-chromium material in accordance with the requirements of either ASTM B168 or ASTM B344. Each element shall be wound on or supported by electrical insulating material in such a manner as to provide mechanical support to prevent elements from shorting to the frame or to each other. Ample spacing shall be provided for expansion and contraction in both horizontal and vertical planes. All resistor elements shall be designed for a 50 volt, direct current drop at their respective current ratings and up to 1400 degrees Fahrenheit operating temperatures.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

3.4,3 Electrical connections. All resistor elements shall be attached to the input bus bar forming a low resistance common connection. The free end of each resistor element shall be silver-brazed, welded, or bolted to a flexible, high-temperature pigtail wire having adequate provisions to protect the pigtail wire from shorting to the frame or other wires. The connection of the pigtail wire lead to the switches shall be by means of a crimp type lug and screw-in or bolted switch connection with provisions so that neither the wire nor the insulation can come into direct contact with the metal frame during all operations and movements of the equipment. The output terminal shall be a quick-connect type terminal firmly fastened to the output bus bar, and accessible through an insulated opening in the front panel to prevent accidental grounding when making or breaking the output connection. Each unit shall be equipped at its power input end with an appropriately rated short circuit protective device. The device shall be located in an accessible area that is protected from thermal and mechanical damage. All electrical connections for the control station and the mounting rack if required, shall conform to the requirements of NFPA 70 where applicable, and not in conflict with the requirements of this specification.

3.4.4 Amperage control. The output amperage of the control station shall be controlled by rotary, double plunger, or toggle switch of the multiple position action type. Unless otherwise specified, the welding amperage output shall be controlled in increments of not more than five amperes per step from five amperes to full rating of the control station. When specified (see 6.2.1), the amperage output shall be in increments of not more than 2-1/2 amperes per step throughout the range of the control station. The controls shall be located so as to be readily accessible to the operator. All adjustment knobs, switches and amperage steps shall be clearly marked. The dual operator control station shall have separate controls for each operator. A switch or other suitable means shall be provided to change the dual operator control station to a parallel single operator control station when increased amperage output is required. Ampere rating of all switches shall be at least 10 percent higher than the rating of the resistor elements to which they are connected. When switches contain thermal overload devices, the devices shall be sized to protect the elements from overload. All switch controls shall be designed for manipulation by a gloved or mitten hand. Each switch shall be installed with means of preventing accumulation of foreign matter on its current carrying members. The controllable output from all switches shall terminate on a common bus bar so that the welding current from all switches may be used simultaneously. Material for the bus bar shall be hard drawn copper.

3.4.4.1 Remote amperage control. When specified (see 6.2.1), a remote control unit shall be furnished and the control unit shall have not less than 50 feet of multi-conductor control cable. The front of the welding control station shall have a multi-pin receptacle to accommodate a matching plug on the end of the remote control cab e. Amperage controls in the remote control unit shall be capable of adjusting the amperage in increments as required in 3.4.4.

3.4.5 Mounting rack. When required, a mounting rack for two, four, or six welding control stations shall be furnished as specified (see 6.2.1). The mounting rack shall have an a ll welded steel frame. The mounting rack shall be designed for use in outdoor weather conditions and constructed-to allow the

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

rack to be lifted by a crane or hoist and handled by a forklift truck. The frame shall consist basically of shelves or ledges to accommodate individual control stations. The lowest shelf or ledge shall be positioned so that the bottom of the lowest control station shall have a minimum of six inches clearance from the floor, Steel cross members capable of supporting an assembled rack including control stations, shall be welded to the bottom of the frame for protection to the lower individual control station from such hazards as transport by a forklift truck. Six unit control station racks shall be provided with not less than three cross members. The rack shall have a roof securely attached to the frame. The roof shall be fabricated from sheet steel having a thickness of not less than 18 gauge. The roof of the rack shall be one complete sheet designed to assist the convection cooling but shall not be louvered or perforated. The welding power input connector to the rack shall be a size 500 MCM quick-connect type connector or a bolted lug type. The connector shall be securely mounted to a common, insulated, main power input bus bar network. The bus bar shall be rigidly mounted to a low moisture absorbent, high temperature insulator which is securely mounted to the frame. The bus bar shall have connections for each individual control station.

3.4.6 Dimensions and weight. The dimensions and weight of the welding control stations and the mounting racks shall not exceed the values specified in tables I and II. All type and size control stations shall be interchangeable on the mounting racks.

TABLE I. Welding control stations.

Type	Size	Height (inches)	Width (inches)	Depth (inches)	Weight pounds)
I	200 thru 400	17	18	31	110
II	200 thru 400	17	18	31	120

TABLE II. Mounting racks.

Number stations	Size	Height (inches)	Width (inches)	Depth (inches)	Weight (pounds)
2	200 thru 400	54	25	39	200
4	200 thru 400	54	45	39	250
6	200 thru 400	60	66	39	350

3.5 Performance. The welding control station, when connected to a multiple operator, constant voltage welding power source, shall be capable of furnishing an individual operator with welding current within the limits of the individual control station. Accurate control of the welding current shall be provided to enable the operator to produce, shielded metal arc welds (SMAW) specified herein without excessive spatter and other irregularities not conducive to good welding. The operator shall not have difficulty in starting or maintaining an arc.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

3.5.1 Additional performance requirements. Performance features required in addition to, or in lieu of, the requirements herein shall be as specified and fully described (see 6.2.1).

3.6 Standard equipment. Unless otherwise specified, all equipment normally furnished with the manufacturer's standard commercial control station shall be furnished. When specified (see 6.2.1), required additional equipment shall be furnished and fully described.

3.7 Optional equipment. When required, all necessary optional equipment to provide capability for additional welding processes such as gas metal-arc welding (GMAW), DC-gas tungsten arc welding (GTAW), stud welding and arc air gouging shall be furnished as specified (see 6.2.1).

3.8 Welding accessories. When required, welding accessories such as welding cables, control cables, cable connectors, and other accessories shall be furnished. The quantity, type, length, and design shall be as specified (see 6.2.1).

3.9 Repair parts. Repair parts shall be furnished as specified (see 6.2.1).

3.10 Marking on plates and charts, and decals. All words on plates, charts, and decals shall be in the English language. Characters shall be engraved, etched, embossed, or stamped in boldface on a contrasting background. When these methods are not practical, the instructions shall be applied directly onto the item by environmentally protected decalcomania transfer , a metal wrap-around tag, stenciling, silk screening, or by any other method suitable for the use intended. Marking shall be as permanent as the normal life expectancy of the item to which they are applied and shall be capable of withstanding the environmental test and cleaning procedures specified for the item.

3.10.1 Nameplate. A corrosion resistant nameplate shall be securely attached to the control station. The nameplate shall contain the information listed below. If the control station is a special model, the model designation shall include the model of the basic standard control station and a suffix identified in the manufacturer's permanent records. The captions listed may be shortened or abbreviated, provided the entry for each caption is clear as to its identity.

Nomenclature
Manufacturer's name
Manufacturer's model designation
Manufacturer's serial number
Power output characteristics
Contract Number or Order Number
National Stock Number or Plant Equipment Code
Date of manufacture

3.11 Technical data. When technical data is required it shall be furnished in accordance with the requirements of the contract. All technical data furnished shall be written in the English language.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

3.12 Workmanship. Workmanship of the control station and accessories shall meet all requirements specified herein and shall be of a quality equal to that of the manufacturer's commercial equipment of the type specified herein.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspections. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.2 Classification of inspections. The inapection requirements specified herein are classified as follows:

a. First article inspection (see 4.4).

b. Quality conformance inspection (see 4.5).

4.3 Inspection conditions. Unless otherwise Specified herein. all inspections, tests, and examinations shall be performed in the manufacturer's designated indoor test area under the ambient temperature, the relative humidity, and the air pressure existing inside the building at the time the inspections, tests, and examinations are performed.

4.4 First article inspection. When first article inspection is required, it shall be applied to the first article submitted in accordance with 3.1. Unless otherwise specified (see 6.2.1), first article inspection shall consist of the examination in 4.6 and all tests in 4.7.1, 4.7.2, 4.7.3, and when applicable 4.7.4 and 4.7.5. Failure of the item to pass the first article examination and all applicable tests shall be cause for rejection.

4.5 Quality conformance inspection. A quality conformance inspection shall be applied to each item prior to being offered for acceptance under the contract. Unless otherwise specified (see 6.2.1), the quality conformance inspection shall consist of the examination in 4.6, the test in 4.7.1, and the inspection in 4.8. Failure of the item to pass the examination, the test, and the inspection shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

4.6 Examination. The control station shall be visually examined to determine compliance with all requirements of this specification.

4.7 Tests.

4.7.1 Operational test. The welding control station shall be connected to a multiple operator, constant voltage power supply, and prepared for welding in accordance with the manufacturers instruction. When a mounting rack is furnished, the welding control stations shall be installed in the rack for testing. The control station shall be loaded by resistance banks at its minimum and maximum welding range applicable to the size control station being tested, or by performing the actual welding test specified in 4.7.2. The welding currents, voltage, and control setting shall be recorded to verify that the output of the control station conforms to the control settings.

4.7.2 Welding performance test. The welding performance test shall be performed on each control station. The operator shall make a total of two six-inch fillet welds on mild steel plate using two different size electrodes conforming to E-6011 of Amercian Welding Society (AWS) Welding Handbook at minimum and maximum welding range applicable to size of control station being tested. Table III may be used to select appropriate size of electrode, amperage, and voltage. The operator shall not have difficulty in starting or maintaining an arc. The completed welds shall be examined for conformance to the performance requirements specified herein. The welding currents, voltage, and control settings shall be recorded to verify that the control station conforms to the control settings.

TABLE III Electrode selection.

Size	(Electrode diameter, inches)	Amperage	Voltage
	3/32	30-90	17-21
	1/8	80-120	18-22
	5/32	120-190	18-22
	3/16	140-240	20-24
	7/32	170-325	20-24
	1/4	250-400	20-24

4.7.3 Life tests - resistor elements. The supplier shall furnish test data or certification confirming that the nickel-chromium material used in the resistor elements is of the type that meets the 100-hour life test at 2050 degrees Fahrenheit in accordance with ASTM B76.

4.7.4 Tests for optional welding equipment. When optional welding equipment is specified, the type material to be welded and welding performance test required shall be as specified (see 6.2.1). The welding control station manufacturer shall submit weld schedule and test procedures to the procuring activity for approval.

4.7.5 Rough handling tests. When specified (see 6.2.1), a rough handling test shall be performed prior to performing the test in 4.7.1. With a chain or cable attached to the control station's lifting eyes or lugs and adjusted in length to permit a "free-fall" of not less than six inches and not more

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

than ten inches before the control station is suspended thereby. The control station shall survive three such falls without measurable damage. Additionally, the control station shall be dropped a distance of six inches to a rigid hard surface. Dropping shall be arranged so that the initial impact is successively made on each of three of the lower edges. No measurable damage, other than minor denting shall be encountered. All electrical and mechanical connections shall be inspected to verify tightness when the rough handling test is completed.

4.8 Packaging inspection. Packaging of each item shall be inspected to determine compliance with the requirements of section 5.

5. PACKAGING

5.1 Preservation, packing, and marking. Unless otherwise specified, preservation, packing, and marking shall be in accordance with ASTM D 3951. When specified (see 6.2.1), level A or level B preservation, level A or level B packing, and marking shall be accomplished in accordance with MIL-W-45562.

6. NOTES

6.1 Intended use. The welding control stations covered by this specification are intended for use in contractor's plants, military and Government repair facilities for use with multiple operator welding systems utilizing welding current supplied by a constant voltage power source.

6.2 Ordering data.

6.2.1 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.

b. Type, size, and quantity required (see 1.2).

c. First article, if required (see 3.1).

d. If the control station design and construction is required in a specific dimensional system (US or SI), state required system (see 3.2.1).

e. Additional safety and health requirements, if required (see 3.2.5).

f. Painting, if different (see 3.3.4).

g. Amperage control, if different (see 3.4.4).

h. Remote amperage control, if required (see 3.4.4.1).

i. If mounting rack is required, specify the number of control stations to be held (see 3.4.5).

j. Additional performance features, if required (see 3.5.1),

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

k. Standard equipment, if different (see 3.6).

l. Specify and fully discribe optional equipment, if required (see 3.7).

m. Specify and fully describe accessories, if required (see 3.8).

n. Specify applicable repair parts, if required (see 3.9).

o. First article inspection, if different (see 4.4).

p. Quality conformance inspection, if different (see 4.5).

q. Welding test for optional equipment, if required (see 4.7.4).

r. Rough handling test, if required (see 4.7.5).

s. If preservation, packing, and marking in accordance with MIL-W-45562 is required, specify level of preservation and packing required (see 5.1).

6.2.2 Contract data requirements, Required technical data such as operator's manuals, parts lists, wiring diagrams, and acceptance test reports should be specified on a DD Form 1423, Contract Data Requirements List, incorporated into the contract.

6.3 First article. When first article inspection is required, the item to be tested should be the first item offered for acceptance under the contract. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, test, and approval of the first article.

6.4 Cross-reference of classification changes. The control station classification changes from the previous issue of this specification are as follows:

MIL-W-80042A	MIL-W-80042B	MIL-W-80042C
Type I -One operator station	Type I-Single operator	Type I-Single operator
Type II -Two operator station	Type II-Dual operator	Type II-Dual operator
Type III-Four operator station	Deleted	
Type IV -Six operator station	Deleted	
Sizes 200	Size 200	Size 200
Sizes 250	Size 250	Size 250
Size 300	Size 300	Size 300
Size 400	Size 400	Size 400
Style A-standard five ampere	Deleted	
Style B-stepless control	Deleted	
Style C-remote control	Deleted	

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

6.5 Subject term (key word) listing.

Arc welding
Control stations
Gas metal arc welding
Metal arc welding
Multi-operator
Tungsten arc welding
Welding

6.6 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodians:
Army - AL
Navy - SH
Air Force - 99

Preparing activity:
DLA - IP

(Project 3438-0058)

Review activities:
Navy - CG
Air Force - 86

User activity:
Navy - YD

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEFENSE LOGISTICS AGENCY
Commander
Defense Industrial Plant Equipment Center
ATTN: DIPEC-SSG
Memphis, TN 38114-5051

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO 4966 WASHINGTON D C

POSTAGE WILL BE PAID BY THE DEFENSE LOGISTICS AGENCY

Commander
Defense Industrial Plant Equipment Center
ATTN: DIPEC-SSG
Memphis, TN 38114-5051

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-W-80042C	Welding Control Stations for Multi-Operator System

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
	☐ USER
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ MANUFACTURER
	☐ OTHER *(Specify)*. _____

5 PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording

c. Reason/Rationale for Recommendation

6 REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23104:33Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T04:33Z
Check the source to verify that this is the current version before use.