MIL-S-9926A(USAF)
15 Mar 82

SUPERSEDING
MIL-S-9926 (USAF)
15 September 1961

MILITARY SPECIFICATION

SIGN, FOLLOW ME, TRUCK MOUNTING

This specification is approved for use by the AFLC Cataloging and Standardization Office, Department of the Air Force, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers one type of Follow-Me Sign for mounting on Pick-Up Trucks or Jeeps.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on the date of invitation for bids, form a part of this specification to the extent specified herein:

STANDARDS

Military

MIL-STD-130	Identification Marking of U.S. Military Property

DRAWINGS

Air Force

59D24432	Assembly, Follow-Me Sign
59D24433	Door, Follow-Me Sign
59D24434	Housing Follow-Me Sign
59D24435	Components, Door and Housing, Follow-Me Sign
59D24438	Mounting and Mounting Items, Follow-Me Sign (Use Pick-Up truck-mounting instructions.)

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to HQ AFLC/LODSAC, Federal Center, Battle Creek, MI 49016 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:12Z
Check the source to verify that this is the current version before use.

2.2 Other Publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids shall apply.

OFFICIAL CLASSIFICATION COMMITTEE
Uniform Freight Classification Rules

(Application for copies of the above publication should be addressed to the Official Classification Committee, 1 Park Avenue at 33rd Street, New York 16, New York.)

AMERICAN TRUCKING ASSOCIATION
National Motor Freight Classification Rules

(Application for copies of the above publication should be addressed to the American Trucking Association, 1424 16th Street, N.W., Washington DC.)

3. REQUIREMENTS

3.1 Preproduction model. The preproduction model is defined as a production model of the product which the manufacturer shall produce in the fulfillment of the contract. As soon as practicable after award of the contract or order and prior to submission of any complete units for final acceptance, the contractor shall furnish a complete Follow-Me Kit Assembly to determine conformance to the requirements contained herein. Examination and tests shall be as specified herein. Approval of the preproduction model by the activity concerned shall not relieve the contractor of his obligation to supply equipment as specified herein. Any changes or deviations of the production units from the preproduction model shall be subject to the approval of the contracting officer.

3.2 Materials. Materials shall be in accordance with the applicable drawings and recycled and recovered raw material should be used to the maximum extent possible in lieu of virgin raw material as long as these materials do not jeopardize the intended use and fully comply with all contract requirements. Materials used shall be free from defects which would adversely affect the performance or maintainability of individual components or the overall assembly. Materials not specified herein shall be of the same quality used for the intended purpose in commercial practice. None of the above shall be interpreted to mean that the use of used or rebuilt products will be allowed.

3.3 Design. The Follow-Me Sign shall conform to all drawings in 2.1 and specifications listed thereon.

3.4 Construction. The Sign shall be constructed to withstand the stresses and strains normally encountered in service and shipping.

3.5 Performance.

3.5.1 Vibration resistance. Equipment shall operate without malfunction and shall subsequently evidence no permanently deformed, cracked, or broken parts if subjected to vibrations normally expected of this type item.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:12Z
Check the source to verify that this is the current version before use.

3.5.2 Road Performance. When properly mounted on a vehicle, the equipment shall be capable of satisfactory operation over improved and unimproved roads.

3.6 Identification marking. Equipment shall be identified in accordance with Standard MIL-STD-130.

3.7 Workmanship. All workmanship shall be in accordance with good commercial practices with attention to elimination of all burrs, sharp edges, kinks, loose solder or flux and loose wire ends.

4. QUALITY ASSURANCE PROVISIONS

4.1 The supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examination and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspection. Inspection shall be classified as follows:

a. Preproduction inspection.

b. Acceptance inspection.

4.3 Preproduction inspection. The preproduction inspection and test shall be conducted in accordance with 4.3.1 through 4.3.3.4

4.3.1 Determine that all material and parts are in accordance with specifications referenced on the drawings.

4.3.2 A detailed visual and dimensional inspection of the completed item including the following:

4.3.2.1 Make measurements as necessary to verify conformance with dimensional requirements of drawings.

4.3.2.2 Perform detailed inspection to assure proper assembly of all component parts and quality workmanship.

4.3.2.3 Inspect finish and marking.

4.3.2.4 Inspect all wiring and cable connections to assure firm electrical and mechanical connections, and to detect any visible short circuits, open circuits, etc.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:12Z
Check the source to verify that this is the current version before use.

4.3.2.5 Inspect dress and routing of wiring inside sign. Any binding or possibility of chafing of insulation must be eliminated.

4.3.2.6 Inspect cable and connectors for proper assembly.

4.3.3 Perform tests as follows:

4.3.3.1 Check all wiring for grounds using an ohmmeter known to be accurate in the 20 megohm range. The resistance between any conductor to ground shall be at least 20 megohms.

4.3.3.2 Connect the sign to a suitable 12-volt power source.

4.3.3.3 Operate sign to determine if all lights are operating properly.

4.3.3.4 The equipment shall be properly attached to a vehicle and the vehicle driven over an improved road at 50 miles per hour for a minimum distance of 5 miles. Upon completion of this road test, all controls, components, and accessories shall be checked for proper operation. The equipment shall be properly attached to a vehicle and the vehicle driven over an unimproved road at a minimum of 15 miles per hour for a minimum distance of 5 miles. Upon completion of this road test, all controls, components, and accessories shall be checked for proper operations.

4.4 Acceptance inspection. Acceptance inspection of each unit shall include all examinations necessary to insure compliance with the requirements of the drawings and specifications listed herein, and shall include tests contained in 4.3.3.2 and 4.3.3.3.

5. PREPARATION FOR DELIVERY

5.1 Sign processing. Sign shall be processed for shipment from manufacturer's plant to initial receiving activity in accordance with manufacturer's standard commercial practice.

6. NOTES

6.1 Intended use. The Follow-Me Sign is designed for use on either a Jeep or Pick-Up Truck and its specific purpose is to furnish electrical directional signals to taxiing aircraft on runways. It is the intent that the directional signals shall be controlled by an electric powered switch box which is operable by the driver of the vehicle.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification.

b. Selection of applicable levels of preservation, packaging, and packing (see Section 5).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:12Z
Check the source to verify that this is the current version before use.

6.3 Improved road. An improved road is a road of level concrete, mamadam, steel landing mat, or smooth, hard-packed dirt.

6.4 Unimproved road. An unimproved road is a level or rolling, gravel or loose dirt roadway which exhibits minor flexing under load.

6.5 Switch box assembly. The truck mounting, follow-me sign specified herein shall be designed to mate with a follow-me sign switch box assembly specified on Air Force drawings 60C24436 and 60C24437 and WR-ALC/IRA Purchase Description 2540-085 dated 24 September 80.

Custodian:
Air Force – 99

Preparing Activity:
Air Force – 99

Project No. 2540-F296

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T13:12Z
Check the source to verify that this is the current version before use.