MILITARY SPECIFICATION

RELAY, ARMATURE, TYPE MA-1

This amendment forms a part of Military Specification MIL-R-7611 (USAF) dated 18 November 1952.

Page 2, paragraph 3.3, lines 2 and 3: Delete "92.5 ± 2.5V" and substitute "82.5 ± 2.5V".

Page 2, paragraph 3.3.1, line 3: Delete "400 ± 10 cps" and substitute "400 cps".

Page 4, paragraph 3.4.4.3, line 2: Delete "92.5 ± 2.5V" and substitute "82.5 ± 2.5V".

Page 6, paragraph 4.1.1: Delete and substitute:

"4.1.1 PREPRODUCTION TESTING"

Page 7, paragraphs 4.3 through 4.3.2: Delete and substitute:

"4.3 PREPRODUCTION TESTING

"4.3.1 PREPRODUCTION TEST SAMPLES.- The preproduction test samples shall consist of three relays representative of the production equipment. They shall be tested at a laboratory designated by the procuring activity, or when so stated in the contract, at the contractor's plant under the supervision of the procuring activity."

Page 7, paragraph 4.3.3, line 1: Delete "qualification" and substitute "preproduction".

Page 7, paragraph 4.3.3.1.1: Delete.

Page 8, paragraph 4.3.3.1.3, second sentence: Delete and substitute "At the completion of this period, the contacts shall close when the applied voltage is reduced to 80V."

Page 8, paragraph 4.3.3.3, lines 5 and 8: Delete "92.5 ± 2.5V" and substitute "82.5 ± 2.5V".

Page 8, paragraph 4.3.3.4, third sentence: Delete and substitute "The relay shall be mounted in the position most likely to cause malfunctioning, and shall be

FSC 5945

Source: https://assist.dla.mil -- Downloaded: 20260-17T08:39Z
Check the source to verify that this is the current version before use.

-1269. and shall

4.5 Marking. Relays shall be marked in accordance with method I of MIL-STD

accelerated for a minimum of one minute without causing the contacts to open when 80V is applied to the coil. The test shall be repeated without causing the contacts to close when 105V is applied to the coil."

Page 9, paragraph 4.3.3.7, line 3: Delete "90V" and substitute "80V". Line 8, delete "qualification" and substitute "preproduction".

Page 10: Add:

"4.4.2.3 OPENING VOLTAGE.- The relay shall be subjected to test to determine that the contacts open when an alternating current potential of 105V 400 cps ac is applied to the holding coil terminals and to determine that the contacts close when this voltage is reduced to 80V."

Page 11, paragraph 4.4.3.4: line 2, delete "qualification" and substitute "preproduction".

Page 11, paragraph 4.4.3.4, lines 3 and 5: Delete.

Page 11, paragraph 6.1, line 4: Delete "(below 90V ac)".

Page 12, paragraph 6.2: Delete and substitute:

"6.2 ORDERING DATA.- Procurement documents should specify the following:

"6.2.1 PREPRODUCTION TESTS.- Three relays will be required as preproduction samples to be subjected to the preproduction tests to determine compliance with the requirements of this specification. The point of inspection for these tests will be specified."

OWB/BEM/je
WCIE

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T08:39Z
Check the source to verify that this is the current version before use.