MILITARY SPECIFICATION

BOMB DISPENSER, CNU-80/E25

SHIPPING & STORAGE CONTAINER FOR

This specification is approved for use within the Department of the Air Force, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This Specification covers the metal parts for one type of container designated as Shipping and Storage Container, Bomb Dispenser: CNU-80/E25.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified, the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550	-	Ammunition, General Specification for
MIL-I-45607	-	Inspection Equipment Acquisition, Maintenance and Disposition of

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Ogden-ALC/MMEDO, Hill AFB, Utah 84056, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 1325

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-109	-	Quality Assurance Terms and Definitions
MIL-STD-129	-	Marking for Shipment and Storage
MIL-STD-1168	-	Ammunition Lot Numbering
MIL-STD-1235	-	Single and Multi-Level Continuous Sampling Procedures and Table for Inspection by Attributes
MIL-STD-1595	-	Qualification of Aircraft, Missile and Aerospace Fusion Welders

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein.

DRAWINGS

AIR FORCE

8889492	-	Container, Shipping and Storage, Dispenser-Bomb CNU-80/E25
DL 8889492	-	Data List

(Copies of specifications, standards, handbooks, drawings, and publications required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer).

2.1.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 First article. When specified, a sample shall be subjected to first article inspection (see 4.3 and 6.1).

3.2 Material. Materials shall be in accordance with the applicable drawings and specifications.

3.3 Parts. The container parts shall comply with all requirements specified on Drawing 8889492 and with all requirements specified in applicable specifications.

3.4 Welding. Welds shall be reasonably smooth and free from craters. They shall exhibit characteristics of fusion, penetration and soundness of weld deposits representative of good welding practice. All welding fluxes, scale, and excessive weld spatter, acids or basic solutions shall be completely removed prior to application of any finish. All welding shall be in accordance with applicable specifications. All welding shall be performed by operators who are currently certified in accordance with MIL-STD-1595.

3.5 Assembly and disassembly. The container shall accept the dispensers or fixtures, without evidence of excessive effort, in assembly or disassembly, or closing and securing the cover when tested as specified in 4.4.4.1.

3.6 Performance characteristics. The container shall comply with all the requirements specified on drawing 8889492, and with all requirements specified in this specification, when loaded with dispensers without evidence of loose parts, or broken or permanently set structual members which render the container unusable. Minor dents or creases in non-structural members, bent rings or eyes, and cracking of the wooden skids shall not be considered objectionable. The dispensers shall be operable after completion of the below listed tests. All tests shall be conducted at a temperature of plus (+) 80 degrees Fahrenheit (^{o}F) plus or minus ($\pm$) 20°F [26.66 Degrees Celsius (^{o}C) $\pm$ 11.11^{o}C].

3.6.1 Fork lifting. The loaded container shall be capable of being lifted by a suitable fork type lift truck without evidence of puncture, and broken or bent frame structure when tested as specified in 4.3.2.6.

3.6.2 Stacking. The loaded container shall be capable of supporting a simulated stacking load equal to five (5) times the weight of a loaded container without evidence of permanent set or breakage in any of its structural members. The test shall be conducted as specified in 4.3.2.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

3.6.3 Hoisting. The loaded container shall be capable of carrying an additional load equal to three(3) times the weight of another loaded container without evidence of permanent set or breakage when suspended by the lift rings provided and as specified in 4.3.2.8.

3.6.4 Pushing. The loaded container shall withstand pushing without damage to skids or structure that would render the container unserviceable when tested as specified in 4.3.2.9.

3.6.5 Edgewise Drop. The loaded container shall withstand edgewise dropping and meet the requirements of 3.6, when tested as specified in 4.3.2.2.

3.6.6 Cornerwise Drop. The loaded container shall withstand cornerwise dropping and meet the requirements of 3.6, when tested as specified in 4.3.2.3.

3.6.7 End impact. The loaded container shall withstand end impacts and meet the requirements of 3.6, when tested as specified in 4.3.2.4.

3.6.8 Roll-Over. The loaded container shall withstand roll-over and meet the requirements of 3.6, when tested as specified in 4.3.2.5.

3.6.9 Vibration. The loaded container, shall withstand vibrations as specified in Table I without evidence of loose parts or fasteners and breakage or cracks in the case structure. The vibration shall be applied in the vertical axis and as specified in 4.3.2.1.

TABLE I

Frequency (Hertz-Hz)	Maximum Acceleration	Test Duration
20 ± 2	1.3 G (.06 Double Amplitude)	30 minutes

3.7 Workmanship. All parts and assemblies shall be fabricated and finished in a thorough workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products, and other foreign matter. The cleaning method used shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agent.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product. At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 Classifications of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3)
b. Quality conformance inspection (see 4.4)

4.3 First article inspection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

4.3.1 Submission. The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.3.2 (See 6.1). The first article sample shall consist of one (1) Shipping & Storage Container, CNU-80/E25. All parts and completed assemblies submitted shall have been produced by the contractor (or furnished by a supplier) using the same production processes, procedures and equipment as will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance. A first article quantity, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.3.2 Inspections to be performed. The container will be subjected by the Government to any or all of the examinations or test specified in 4.4.3 and 4.4.4 of this specification and any or all requirements of the applicable drawings. In addition any or all of the following examinations and tests will be performed.

Sequence	Test
1	Vibration
Optional	Edgewise drop
"	Cornerwise drop
"	End Impact
"	Rollover
"	Fork-lifting
"	Stacking
"	Hoisting
"	Pushing

4.3.2.1 Vibration. The loaded container shall withstand the vibrations specified in Table 1. The container shall be assembled to a suitable fixture with cover closed and latches fastened in a normal manner. Adequate safety precautions shall be observed to preclude endangering personnel and equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

4.3.2.2 Edgewise drop. The container, with load assembled, shall be supported at one end of its base on a sill approximately five (5) inches [12.7 centimeters (CM)] in height and placed at right angles to the skids. The other end of the container shall be raised and allowed to fall freely from an eighteen inch (45.72 CM) height to a concrete or similarly hard surface. This test shall be applied to both ends of the container.

4.3.2.3 Cornerwise drop. The container with load assembled, shall be supported at one corner of its base on a block approximately five (5) inches (12.7 CM) in height and with a block approximately twelve (12) inches (30.48 CM) high placed under the other corner of the same end of the container. The opposite end of the container shall be raised and allowed to fall freely from a eighteen inch (45.72 CM) height, measured from the lower of the two (2) corners, to a concrete or similarly hard surface. This test shall be applied to one corner of each end of the container.

4.3.2.4 End impact. The container with load assembled shall be suspended as a pendulum at the end of four (4) cables, one (1) through each hoisting provision. The container shall be permitted to swing, with a velocity of 10 ± 1.5 feet per second [3.048 ± 0.457 meters/second (M/S)], into a hard, flat, vertical surface. The impact shall be applied to both ends of the container, parallel to the longitudinal axis. Observation shall be made for evidence of external damage. Damage to wooden skids shall be disregarded.

4.3.2.5 Roll over. The loaded container, erect on it's skids on a hard, level floor, shall be tipped slowly sideways until it falls freely by its own weight to the floor. This process shall be repeated for one (1) revolution with falls from side to top, top to opposite side, and from that side to base.

4.3.2.6 Fork lifting. The container shall be lifted clear of another container (or equipment) when stacked lowered to the floor by a fork-lift truck having forks forty (40) inches (1.016M) minimum in length. The truck shall be cleared of the container, reassume lifting position and restack. This procedure shall be followed in lifting once from each side. The container shall be examined for punctures or broken or bent frame structures.

4.3.2.7 Stacking.. The required load shall be placed on top of the container in such a manner as to simulate stacking of five (5) additional loaded containers thereon. The containers shall be examined for permanent set and breakage of structural members.

4.3.2.8 Hoisting. The loaded container shall be lifted free of any support by means of the lifting eyes or rings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

4.3.2.9 Pushing. The loaded container shall be pushed across at least five (5) feet (1.524 M) of rough concrete in a direction parallel to the axis of the container with the ends of fork truck blades in contact with skids, The test shall be repeated in a direction normal to the axis of the container with the ends of fork truck blades in contact with the skids.

4.3.3 Rejection. If any container fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article sample or portion thereof. Until a first article sample is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.4 QUALITY CONFORMANCE INSPECTION

4.4.1 Types of quality conformance inspection required. Quality conformance inspection shall consist of visual examinations and a functional test.

4.4.2 Lot formation. The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required shall be in accordance with MIL-STD-1168.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

4.4.3 Visual examinations. The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.4.2) of the components or assemblies designated in the applicable paragraph headings. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the government. Instead of applying the Acceptable quality Levels (AQLs) designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQLs to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in 4.4.3.1 and be documented as part of the contractor's inspection system Equipment necessary for the performance of the inspections listed shall be in accordance with 4.4.5.

4.4.3.1 Visual examination defects. Shipping and storage container (see Dwg 8889492)

Category	Defect	Method of Inspection	Defect Code
Critical:	None defined		
Major	AQL 0.65 Percent		
101.	T-Bolts missing or damaged	Visual	01001
102.	Metal identification plate missing	Visual	01002
103.	Any component missing or damaged	Visual	01003
104.	Improper weld (See 3.4)	Visual	01004
Minor	AQL 1.50 Percent		
201.	Holes for car seal missing	Visual	01005
202.	Marking misleading or unidentifiable	Visual	01006
203.	Evidence of poor workmanship (see 3.7)	Visual	01007

4.4.4 Functional Test Procedures.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

4.4.4.1 Assembly and Disassembly (See 3.5)

Category	Defect	Method of Inspection	Defect Code
Major			
105.	Excess effort required to assemble the dispensers and/or fixtures, or to reassemble and lock the container.	Functional	02001

a. The T-bolts shall be released and the upper assembly removed, utilizing the handles. The dispensers and/or fixtures, as required by the Contracting Officer, are to be loaded into the container. There shall be no excess effort required to assemble the dispensers and/or fixtures, or to reassemble and lock the container.

b. Inspect each container until one hundred (100) consecutive containers are found acceptable then inspect one (1) container out of every ten (10) containers produced.

c. In the event a container is rejected, it shall be removed from production and, commencing with the last container found acceptable, then inspect each container until one hundred (100) consecutive containers are found acceptable then return to inspecting one (1) of ten (10) containers.

4.4.5 Inspection equipment. Data List (DL) 8889492 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions, in paragraph 6.3.

4.4.5.1 Supply and maintenance. Supply and maintenance of the equipment listed on the DL shall be in accordance with Specification MIL-I-45607.

4.4.5.2 Government use of Contractor's inspection equipment. The contractor shall, when required by the Government, make available all inspection equipment necessary for determining conformance with contract requirements. Operation of the equipment and verification of its accuracy shall be supplied by the contractor, when required, for the performance of examination or test by the Government.

4.4.5.3 Government rights to documentation. Inspection equipment drawings and lists provided and revised in accordance with the requirements of the DL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

receiving inspection, overhaul, shipping, storage identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

5. PACKAGING

5.1 Marking. Marking shall be in accordance with Standard MIL-STD-129.

6. NOTES

6.1 Ordering data. Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

6.2 Inspection code numbers. The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Data Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor (see 6.3.5).

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced Data Lists in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Data lists. Data lists indicate the availability of inspection equipment designs by showing in the "Document Identification Number" column of the list of inspection equipment (AF Form 1659) the Drawing Number of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Document Identification Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

6.3.2 Data list codes. The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the DL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.

USAF - Air Force design, mandatory for use.

6.3.3 Air Force designs. Air Force designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Air Force design is listed for an item of inspection equipment. Air Force designs fall into two basic classifications: Mandatory (designated "USAF") and non-mandatory (indicated by a drawing number). When a data list references mandatory Air Force Designs, the contractor shall comply with, and use these designs accordingly. The contractor may however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (see 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs. Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification DOD-D-1000, Level 3. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

6.3.5 Submission of contractor design. All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the DL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the appropriate engineering agency through the contracting officer.

6.4 Submission of results of contractor-conducted examinations and tests. Unless otherwise specified, the contractor shall forward requested records or examinations or tests to the contracting officer.

Custodian:
Air Force - 99

Preparing Activity:
Air Force - 70

(Project 1325-F072)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR ☐ USER ☐ MANUFACTURER ☐ OTHER *(Specify)*: _____
b. ADDRESS *(Street, City, State, ZIP Code)*	

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:28Z
Check the source to verify that this is the current version before use.