MILITARY SPECIFICATION
MAINTENANCE ACCESSORY KIT, MK-1192( )/ARM
(UNITS OF)

1. SCOPE

1.1 This specification covers one type of maintenance kit which provides accessories for trouble-shooting and bench testing of communication systems. The maintenance kit is designated, Maintenance Accessory Kit, MK-1192( )/ARM. (See 6.1 and 6.3)

2. APPLICABLE DOCUMENTS

2.1 The documents of the issue in effect on date of invitation for bids, or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATION

FEDERAL

PPP-B-585	Box, Wood, Wirebound
PPP-B-601	Box, Wood, Cleated Plywood
PPP-B-621	Box, Wood, Nailed and Lock-corner
PPP-B-636	Box, Fiberboard
PPP-B-640	Boxes, Fiberboard, Corrugated, Triplewall
PPP-C-843	Cellulosic Cushioning Material
PPP-F-320	Fiberboard; Corrugated and Solid, Sheet Stock (Container Grade), and Cut Shapes
PPP-S-760	Strapping, Non-Metallic Paper, Reinforced and Plain, for Sealing and Securing
PPP-T-76	Tape, Pressure-Sensitive Adhesive Paper, (For Carton Sealing)
PPP-T-97	Tape, Pressure-Sensitive Filament Reinforced
QQ-S-781	Strapping, Flat Steel

MILITARY

MIL-P-116	Preservation, Method of Barrier

FSC 6625

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:16Z
Check the source to verify that this is the currentersion before use.

MILITARY (Cont'd)

MIL-P-3938	Pallet, Material Handling Hardwood Stinger Construction, 4 way (partial)
MIL-T-5422	Testing, Environmental, Aircraft Electronic Equipment
MIL-P-15011	Pallet, Material Handling Wood, Post Construction, 4 way entry
MIL-M-13231	Marking of Electronic Items
MIL-F-14072	Finishes for Ground Signal Equipment

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-108	Definitions of and Basic Requirement for Enclosure for Electric and Electronic Equipment
MIL-STD-129	Marking for Shipment and Storage
MIL-STD-147	Palletized Unit Loads; (40 in x 48 in 4 way partial and 4 way pallets)
MIL-STD-252	Wired Equipment, Classification of Visual and Mechanical Defects
MIL-STD-454	Standard General Requirements for Electronic Equipment
MIL-STD-810	Environmental Test Methods

DRAWINGS

ELECTRONIC COMMAND

SM-DL-664532	Maintenance Accessory Kit, MK-1192 ( )/ARM

(Copies of specifications, standards and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies.)

3. REQUIREMENTS

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

3.1 Description. - The Maintenance Kit, MK-1192( )/ARM is a portable Maintenance Kit, contained in a lightweight spray-light transit case. The maintenance kit provides accessories for trouble shooting and fault isolation of Radio Sets, AN/ARC-114( ), AN/ARC-115( ), and AN/ARC-116( ). The kit is a completely passive device that makes connections and affords points for otherwise inaccessible circuits to the radio sets. All power supplied to the maintenance kit is external source. The accessories consist of breakout boxes, extender cards, extender cables, adapters and a termination box. The accessories are not exposed when the case cover is in place.

3.2 Preproduction samples. - The contractor shall furnish three (3) preproduction samples for approval, if required by the invitation for bids and contract. (See 4.3 and 6.2).

3.3 Construction. - The equipment shall be constructed in accordance with the following data lists and drawings thereon.

SM-DL-664532	Maintenance Accessory Kit, MK-1192 ( )/ARM

3.4 Cleaning. -

3.4.1 Parts. - After fabrication, parts shall be cleaned in accordance with good commercial practice, or as specified in an applicable document. Cleaning processes shall have no deleterious effect. Corrosive material shall be removed completely before the parts are mounted on chassis, panels, etc.

3.4.2 Units. - After assembly, units shall be cleaned thoroughly and shall be free from particles of solder, flux, and other material. In addition, when necessary, such cleaning shall also be performed before final assembly of the units.

3.5 Controls. - All movable controls shall operate properly without binding or other undue restriction. Controls shall not be assembled in a misaligned condition.

3.6 Finish, protective. - The equipment shall be given protective finish in accordance with Specification MIL-F-14072 and the equipment drawings. This includes finish of hardware, such as handles, hinges, screws, etc., and necessary touch-up after mounting. The final paint film on Type 1 surfaces shall be semi-gloss, light gray (Film E) conforming to Specification MIL-F-14072. (See 4.4).

3.7 Securing of parts. -

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

3.7.1 General. - Brackets, lugs, inserts, bolts, and other mounting arrangements shall retain items securely when subjected to specified service conditions.

3.7.2 Securing of parts by threaded fasteners. - Nylok or other screws with plastic devices and Loctite or similar sealants shall not be subjected to temperatures in excess of 250°F (as during baking of paint). Loctite or similar sealants shall be applied in accordance with the manufacturer's instructions.

3.8 Marking. -

3.8.1 General. - Marking shall conform to Specification MIL-M-13231. Front panel marking shall be Group I as described in that specification. (See 4.4).

3.8.2 Visibility. - Wherever practicable, parts shall be so mounted that their identification markings will be readily visible with minimum disassembly of the equipment.

3.8.3 Serial numbers. - The following items shall be serial numbered:

Maintenance Accessory kit	MK-1192( )/ARM

3.9 Soldering. -

3.9.1 Solder. - Solder shall conform to the equipment drawings.

3.9.2 Acid or acid salts. - No acid or acid salts shall be used in preparation for or during soldering; however, exception is permitted for preliminary tinning of electrical connections and for tinning or soldering of mechanical joints not used to complete electrical circuits, but in no case shall acid or acid salts be used where they can come in contact with insulation material. Where acid or acid salts are used, as permitted above, they shall be completely neutralized and removed immediately after use.

3.9.3 Process. - There shall be no sharp points or rough surfaces resulting from insufficient heating. The solder shall feather out to a thin edge, indicating proper flowing and wetting actions, and shall not be crystalized, overheated, or underheated. The minimum necessary amount of flux and solder shall be used for electrical connections. Any means employed to remove an unavoidable excess of flux shall not incur the risk of loose particles of flux, brush bristles, or other foreign material remaining in the equipment, flux being spread over a larger area, or damage to the unit. Insulation material that has been subjected to heating during the soldering operation shall be undamaged and parts fastened thereto shall not have become loosened.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

3.10 Wiring and cabling. - Wiring and cabling shall be neat and sturdy.

3.10.1 Cabling. - Insulated wires shall be formed into cables except where operation of the equipment would be adversely affected thereby or where it is physically impracticable as in the case where the resulting cables would be excessively large and would interfere with operation or maintenance.

3.10.2 Slack. - Wires and cables shall be as short as practical except that sufficient slack shall be provided for the following purposes:

a. To prevent undue stress on cable forms, wires, and connections, including connections to resiliently supported parts.

b. To enable parts to be removed and replaced during servicing without disconnecting other parts.

c. To provide for at least two replacements of the part to which the wire or cable is connected, except where unin ulated wires are used.

3.10.3 Protection. - Wires and cables shall be so placed and protected as to avoid contact, under specified service conditions, with rough or irregular surfaces or sharp edges.

3.10.4 Support. - Wire and cable shall be properly supported and secured to prevent undue stress on the conductors and terminals and undue change in position of the wire or cable (i) during and after subjection of the equipment to specified service conditions or (ii) after service or repair of the equipment in a normal manner.

3.10.5 Clearance. - Clearance between solder connections or bare conductors, on terminal boards, relays, or other parts, shall be such that no accidental contact can occur between adjacent connections when subjected to specified service conditions.

3.10.6 Splicing. - Wires in a continuous run between two terminals shall not be spliced during the wiring operation.

3.10.7 Connections. -

3.10.7.1 General. - Before being soldered to terminal lugs or fixed terminals, wires shall be mechanically secured so that the connections are not dependent for strength on solder alone. Where practicable, wires soldered to fixed terminals shall be looped at least one-half turn but not more than three-quarters turn around the terminal before soldering. Bared ends of wire leads to be terminated in solder-type terminal lugs shall be tinned, silver plated, or lead-alloy coated. No varnish, lacquer, inspection paint, or other coating shall be applied to completed electrical connections.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

3.11 Tropicalization of materials. - Materials shall be treated as follows.

3.11.1 Treating materials. - Treating materials containing a mercury bearing fungicide shall not be used. The contractor shall determine that the treating material is compatible with material or surface to be treated. Selection of treating materials shall be such that any increase in flammability of treated material will be held to the practical minimum.

3.11.2 Toxicity. - Treating materials shall cause no skin irritation or other injury to personnel handling the treated material during fabrication, transportation, operation, or maintenance of the equipment, or during use of the finished items when used for the purpose intended.

3.11.3 Flexibility. - Treatment shall not affect the flexibility of treated material, to the extent that the equipment may fail to meet specified requirements when subjected to specified service conditions.

3.11.4 Statement of treatment. - The contractor shall submit for approval, to the Contracting Officer, a statement describing in detail the materials to be treated and the treating materials and processes that he proposes to use. (See 6.2)

3.12 Service Conditions (See 4.8). - The MK-1192( )/ARM shall meet the following service conditions -- where a test is referenced, meeting the test shall be considered as compliance with the requirement.

3.12.1 Temperature (See 4.8.1). -

3.12.1.1 Operating. - Ambient temperature in the range of +100°F to 0°F. Exposure to the high temperature extreme not to exceed 4 hours, and at the low temperature not to exceed 72 hours, at any one time.

3.12.1.2 Non-Operating. - Exposure in the range of +160°F to -65°F; exposure at the high temperature extreme not to exceed 4 hours, and at the low temperature extreme not to exceed 24 hours, at any one time.

3.12.2 Humidity (See 4.8.2). - The equipment shall meet the requirements in accordance with the procedure prescribed in MIL-T-5422 as specified herein.

3.12.3 Altitude (See 4.8.3). -

3.12.3.1 Operating. - Up to 10,000 feet above sea level.

3.12.3.2 Non-Operating. - Up to 50,000 feet above sea level.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

3.12.4 Spray-tight protection (See 4.8.4). - The equipment shall meet the Table I conditions of MIL-STD-108 for "spray-tight" enclosure. There shall be no evidence of moisture inside the equipment.

3.12.5 Fungus (See 4.8.5). - The unit(s) shall show no evidence of viable fungus or corrosion after being subjected to 28 days of fungus test.

3.12.6 Vibration (See 4.8.6). - The equipment shall meet the requirements of Test Method 514-1 and Figure 514-6 (Curve AB) in MIL-STD-810.

3.12.7 Shock (See 4.8.7). - The equipment shall not suffer damage or fail to operate after subjection to the requirements of Table I, as follows:

TABLE I

Paragraph Heading	Paragraph No.	Performance After Test
Shock; bench handling	4.8.7.1	Specified performance (Note A) No physical damage.
Shock; drop	4.8.7.2	Operable. (Note A). Any physical damage shall be minor only.

Note A: The equipment shall meet the requirements listed in 3.13.

3.13 Electrical requirements (See 4.9). -

3.13.1 Adapter, Breakout MX-8497( )/ARM (See 4.9.1). - The continuity of each wire between each terminal and test point shall not exceed 0.5 ohms.

3.13.2 Adapter, Breakout MX-8498( )/ARM (See 4.9.2). - The continuity of each wire between each terminal and test point shall not exceed 0.5 ohms.

3.13.3 Adapter, Breakout MX-8499( )/ARM (See 4.9.3). - The continuity of each wire between each terminal and test point shall not exceed 0.5 ohms.

3.13.4 Cable, CX-12175( )/ARM (See 4.9.4). - The continuity of each wire between each terminal shall not exceed 0.5 ohms.

3.13.5 Cable, CX-12176( )/ARM (See 4.9.5). - The continuity of each wire between each terminal shall not exceed 0.5 ohms.

3.13.6 Cable, CX-12172( )/ARM (See 4.9.6). - The continuity of each wire between each terminal shall not exceed 0.5 ohms.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:16Z
Check the source to verify that this is the current version before use.

3.13.7 Cable, CX-12173( )/ARM (See 4.9.7). - The continuity of each wire between each terminal shall not exceed 0.5 ohms.

3.13.8 Cable, CX-12174( )/ARM (See 4.9.8). - The continuity of each wire between each terminal shall not exceed 0.5 ohms.

3.13.9 Termination box, MX-8500( )/ARM (See 4.9.9). - The continuity and resistance of each conductor between each terminal shall be within limits specified in Table V.

3.13.10 Extender, Module MX-( ) (See 4.9.10). - The continuity of each trace shall be in accordance with SH-D-664551. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.11 Extender, Module MX-( ) (See 4.9.11). - The continuity of each trace shall be in accordance with SH-D-664552. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.12 Extender, Module MX-( ) (See 4.9.12). - The continuity of each trace shall be in accordance with SH-D-664553. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.13 Extender, Module MX-( ) (See 4.9.13). - The continuity of each trace shall be in accordance with SH-D-664554. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.14 Extender, Module MX-( ) (See 4.9.14). - The continuity of each trace shall be in accordance with SH-D-664555. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.15 Extender, Module MX-( ) (See 4.9.15). - The continuity of each trace shall be in accordance with SH-D-664557. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.16 Extender, Module MX-( ) (See 4.9.16). - The continuity of each trace shall be in accordance with SH-D-664558. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.17 Extender, Module MX-( ) (See 4.9.17). - The continuity of each trace shall be in accordance with SH-D-664559. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.18 Extender, Module MX( ) (See 4.9.18). - The continuity of each trace shall be in accordance with SH-D-664560. The resistance between each terminal and test point shall not exceed 0.5 ohms.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

3.13.19 Extender, Module MX-( ) (See 4.9.19). - The continuity of each trace shall be in accordance with SM-D-664561. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.20 Extender, Module MX-( ) (See 4.9.20). - The continuity of each trace shall be in accordance with SM-D-664563. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.21 Extender, Module MX-( ) (See 4.9.21). - The continuity of each trace shall be in accordance with SM-D-664564. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.22 Extender, Module MX-( ) (See 4.9.22). - The continuity of each trace shall be in accordance with SM-D-664565. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.23 Extender, Module MX ( ) (See 4.9.23). - The continuity of each trace shall be in accordance with SM-D-664566. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.24 Extender, Module MX-( ) (See 4.9.24). - The continuity of each trace shall be in accordance with SM-D-664567. The resistance between each terminal and test point shall not exceed 0.5 ohms.

3.13.25 Adapter, Breakout MX-8497( )/ARM (See 4.9.25). - With 500 VDC applied, the insulation requirement shall not be less than 50 megohms.

3.13.26 Adapter, Breakout MX-8498( )/ARM (See 4.9.26). - With 500 VDC applied, the insulation requirement shall not be less than 50 megohms.

3.13.27 Adapter, Breakout MX-8499( )/ARM (See 4.9.27). - With 500 VDC applied, the insulation requirement shall not be less than 50 megohms.

3.13.28 Cable, CX-12175( )/ARM (See 4.9.28). - With 500 VDC applied, the insulation requirement shall not be less than 50 megohms.

3.13.29 Cable, CX-12176( )/ARM (See 4.9.29). - With 500 VDC applied, the insulation requirement shall not be less than 50 megohms.

3.13.30 Cable, CX-12172( )/ARM (See 4.9.30). - With 500 VDC applied, the insulation requirement shall not be less than 50 megohms.

3.13.31 Cable, CX-12173( )/ARM (See 4.9.31). - With 500 VDC applied, the insulation requirement shall not be less than 50 megohms.

3.13.32 Cable, CX-12174( )/ARM (See 4.9.32). - With 500 VDC applied, the insulation requirement shall not be less than 50 megohms.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:16Z
Check the source to verify that this is the current version before use.

3.13.33 Extender, Module MX-( ) (See 4.9.33). - The insulation requirement shall be in accordance with SM-D-664551. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.34 Extender, Module MX-( ) (See 4.9.34). - The insulation requirement shall be in accordance with SM-D-664552. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.35 Extender, Module MX-( ) (See 4.9.35). - The insulation requirement shall be in accordance with SM-D-664553. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.36 Extender, Module MX-( ) (See 4.9.36). - The insulation requirement shall be in accordance with SM-D-664554. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.37 Extender, Module MX-( ) (See 4.9.37). - The insulation requirement shall be in accordance with SM-D 664555. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.38 Extender, Module MX-( ) (See 4.9.38). - The insulation requirement shall be in accordance with SM-D-664557. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.39 Extender, Module MX-( ) (See 4.9.39). - The insulation requirement shall be in accordance with SM-D-664558. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.40 Extender, Module MX-( ) (See 4.9.40). - The insulation requirement shall be in accordance with SM-D-664559. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.41 Extender, Module MX-( ) (See 4.9.41). - The insulation requirement shall be in accordance with SM-D-664560. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.42 Extender, Module MX-( ) (See 4.9.42). - The insulation requirement shall be in accordance with SM-D-664561. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.43 Extender, Module MX-( ) (See 4.9.43). - The insulation requirement shall be in accordance with SM-D-664563. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.44 Extender Module MX-( ) (See 4.9.44). - The insulation requirement shall be in accordance with SM-D-664564. With 500 VDC applied, the resistance shall not be less than 50 megohms.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

3.13.45 Extender, Module MX-( ) (See 4.9.45). - The insulation requirement shall be in accordance with SH-D-664565. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.46 Extender, Module MX-( ) (See 4.9.46). - The insulation requirement shall be in accordance with SH-D-664566. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.13.47 Extender, Module MX-( ) (See 4.9.47). - The insulation requirement shall be in accordance with SH-D-664567. With 500 VDC applied, the resistance shall not be less than 50 megohms.

3.14 Bounce preconditioning (See 4.6). - The equipment shall be capable of meeting the requirements specified herein, without subsequent processing, after subjection to the bounce preconditioning.

3.15 Operational inspection (See 4.12). - The test set shall be capable of meeting the specified test after applicable processes, inspection and test have been completed to determine that each test set on order is operable prior to packaging.

3.16 Interchangeability (See 4.11). - Like units, assemblies, subassemblies, modules and replaceable parts shall conform to requirement 7 of MIL-STD-454 and shall be physically and functionally interchangeable, without modification of such items or of the units.

3.17 Technical literature and spare parts. - Technical literature and running spares and spare parts shall be furnished if specified in the contract. Spare parts shall be identical to corresponding parts in the equipment furnished on the order. (See 6.2)

3.18 Workmanship. - The equipment shall be manufactured and assembled in accordance with the equipment drawings and requirement nine (9) of MIL-STD-454 and the following paragraphs herein:

Cleaning	3.4
Controls	3.5
Securing of parts	3.7
Soldering	3.9
Wiring and Cabling	3.10
Tropicalization of materials	3.11

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commerical laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspection. - Inspection shall be classified as follows:

a. Preproduction inspection (does not include preparation for delivery). (See 4.3)

b. Inspection by subsidiary documents. (See 4.4)

c. Quality conformance inspection.

(1) Quality conformance inspection of equipment before preparation for delivery. (See 4.5)

(2) Quality conformance inspection of preparation for delivery. (See 4.13 and 4.14)

4.3 Preproduction inspection. - This inspection will be performed by the Government unless otherwise specified in the contract. It shall consist of the inspection specified in the subsidiary documents covering the items listed in 4.4, and the inspection specified for Group A, Group B and Group C, (See Tables II and III and IV respectively). The preproduction inspection will normally be performed in this order: (1) altitude, (2) temperature, (3) vibration, (4) humidity, (5) shock, (6) shock-bench-handling and (7) shockdrop. Other preproduction inspection may precede, follow, or be interspersed between the foregoing.

4.4 Inspection covered by subsidiary documents. - The following shall be inspected under the applicable subsidiary documents as part of the inspection of the units before preparation for delivery:

Item	Where Required
Finish	3.6
Marking	3.8

4.5 Quality conformance inspection of equipment before preparation for delivery. - The contractor shall perform the inspection specified in 4.4 and 4.5.1 through 4.5.6. This does not relieve the contractor of his responsibility for performance of any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition, the Government, at its discretion, may perform all or any part of the specified inspection, to verify the contractor's compliance with specified requirements. (See 6.7) Test equipment for Government verification inspection shall be made available by the contractor. Each unit shall be bounce preconditioned after final assembly and shall not be considered as a portion of acceptance inspection. (See 3.14)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

4.5.1 Group A Inspection. - Each unit of each lot of equipment shall be inspected for conformance to all the inspection and test requirements of Table II. Each lot will be subject to verification utilizing the procedures of MIL-STD-105 using the general inspection levels and the AQL's indicated in Table II. Group A inspection shall be performed in any order which is satisfactory to the Government, except that the operational inspection 4.12 shall be last. (See 6.6)

TABLE II - Group A Inspection

Inspection	Reqt Para	Insp Para	AQL Major	AQL Minor
Visual and Mechanical	3.18	4.10		
MK-1192( )/ARM (assembled) w/accessories			1.0%	4.0%
Adapter - breakout boxes			4.0%	6.5%
Cables Assemblies (assembled)			1.0%	4.0%
Extender, Modules MX-( )			1.0%	4.0%
Transit Case (assembled)			4.0%	6.5%
Adapter, UG-Connectors			4.0%	6.5%
Termination box, MX-8500( )/ARM			4.0%	6.5%
Electrical				
Accessories:				
Adapter, Breakout MX-8497( )/ARM	3.13.1	4.9.1	1.0% for the combined group (Extender Modules excluded)	
Adapter, Breakout MX-8498( )/ARM	3.13.2	4.9.2		
Adapter, Breakout MX-8499( )/ARM	3.13.3	4.9.3		
Cable, CX-12175( )/ARM	3.13.4	4.9.4		
Cable, CX-12176( )/ARM	3.13.5	4.9.5		
Cable, CX-12172( )/ARM	3.13.6	4.9.6		
Cable, CX-12173( )/ARM	3.13.7	4.9.7		
Cable, CX-12174( )/ARM	3.13.8	4.9.8		
Termination box, MX-8500( )/ARM	3.13.9	4.9.9		
Extender, Module MX-( )	3.13.10	4.9.10		
Extender, Module MX-( )	3.13.11	4.9.11		
Extender, Module MX-( )	3.13.12	4.9.12		
Extender, Module MX-( )	3.13.13	4.9.13	1.0% for the Extender Modules	
Extender, Module MX-( )	3.13.14	4.9.14		
Extender, Module MX-( )	3.13.15	4.9.15		
Extender, Module MX-( )	3.13.16	4.9.16		
Extender, Module MX-( )	3.13.17	4.9.17		
Extender, Module MX-( )	3.13.18	4.9.18		
Extender, Module MX-( )	3.13.19	4.9.19		
Extender, Module MX-( )	3.13.20	4.9.20		
Extender, Module MX-( )	3.13.21	4.9.21		
Extender, Module MX-( )	3.13.22	4.9.22		
Extender, Module MX-( )	3.13.23	4.9.23		
Extender, Module MX-( )	3.13.24	4.9.24		
Operational Inspection	3.15	4.12	0.1%	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

4.5.2 Group B Inspection. - This inspection, including Sampling, shall conform to Table III and to the small-sample inspection of Standard MIL-STD-105 using the Special Inspection levels. The AQL shall be 6.5 percent defective and the inspection level shall be S-4 for normal, tightened and reduced inspection. Group B Inspection shall normally be performed on inspection lots that have passed Group A inspection and on samples selected from units that have not met Group A inspection.

TABLE III - Group B Inspection

Inspection	Reqt Para	Insp Para	AQL
Electrical Accessories			
Adapter, Breakout MX-8497( )/ARM	3.13.25	4.9.25	6.5% for the
Adapter, Breakout MX-8498( )/ARM	3.13.26	4.9.26	Combined Group
Adapter, Breakout MX-8499( )/ARM	3.13.27	4.9.27	(extender Modules
Cable, CX-12175( )/ARM	3.13.28	4.9.28	excluded)
Cable, CX-12176( )/ARM	3.13.29	4.9.29	
Cable, CX-12172( )/ARM	3.13.30	4.9.30	
Cable, CX-12173( )/ARM	3.13.31	4.9.31	
Cable, CX-12174( )/ARM	3.13.32	4.9.32	
Extender, Module MX-( )	3.13.33	4.9.33	
Extender, Module MX-( )	3.13.34	4.9.34	
Extender, Module MX-( )	3.13.35	4.9.35	
Extender, Module MX-( )	3.13.36	4.9.36	6.5% for Extender
Extender, Module MX-( )	3.13.37	4.9.37	Modules
Extender, Module MX-( )	3.13.38	4.9.38	
Extender, Module MX-( )	3.13.39	4.9.39	
Extender, Module MX-( )	3.13.40	4.9.40	
Extender, Module MX-( )	3.13.41	4.9.41	
Extender, Module MX-( )	3.13.42	4.9.42	
Extender, Module MX-( )	3.13.43	4.9.43	
Extender, Module MX-( )	3.13.44	4.9.44	
Extender, Module MX-( )	3.13.45	4.9.45	
Extender, Module MX-( )	3.13.46	4.9.46	
Extender, Module MX-( )	3.13.47	4.9.47	
Interchangeability	3.16	4.11	6.5%

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

4.5.3 Group C Inspection. - This inspection shall be as listed in Table IV and shall normally be performed on sample units that have been subjected to and met Group A and B inspection. No defects shall be allowed. Sample unit(s) shall be selected in accordance with 4.5.4.

TABLE IV - Group C Inspection

Inspection	Reqt Para	Insp Para
Subgroup I:		
Altitude	3.12.3	4.8.3
Temperature	3.12.1	4.8.1
Vibration	3.12.6	4.8.6
Humidity	3.12.2	4.8.2
Subgroup II:		
Spraytight protection	3.12.4	4.8.4
Shock, bench-handling	3.12.7	4.8.7.1
Shock, Drop	3.12.7	4.8.7.2
Subgroup III:		
Fungus	3.12.5	4.8.5

4.5.4 Sampling for inspection of equipment. - Units selected for each Group C inspection shall be selected without regard to their quality in accordance with the following:

4.5.4.1 Subgroup I. - For this subgroup, two units from the first 10 production units shall be selected for the first Group C inspection. For subsequent Group C inspections, one unit from each successive 25 or fractions thereof shall be selected.

4.5.4.2 Subgroup II. - For this subgroup, two units from the first 10 production units shall be selected for the first Group C inspection. For subsequent Group C inspection, one unit from each successive 50 shall be selected or fraction thereof shall be selected.

4.5.3 Subgroup III. - For this subgroup, only one (1) unit(s) from the first 10 production units shall be selected for the first Group C inspection. For subsequent inspection one (1) unit(s) shall be selected when one half of the units on order have been accepted by the Government's QA Representative.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:16Z
Check the source to verify that this is the current version before use.

4.5.5 Noncompliance. - The contractor shall immediately report in writing each Group C failure occurrence, including details of the failure and characteristics affected. The contractor shall immediately investigate the cause of failure and further report the results of investigation and details of the proposed corrective action on (i) the process and materials, as applicable, and (ii) all units of product which were manufactured under the same conditions and which the Government considers subject to the same failure. Reports shall be forwarded to the responsible technical activity designated in the contract through the Quality Assurance Representative. After corrective action has been taken, additional sample units shall be subjected to Group C inspection (all inspections, or the inspections which the sample failed, at the option of the Government) and Group A and B inspection may be reinstituted; however, final acceptance and shipment will be withheld until the Group C reinspection results have shown that the corrective action was effective. (See 6.4)

4.5.6 Reinspection of conforming Group C sample units. - Unless otherwise specified, sample units which have been subjected to and passed Group C inspection may be delivered on the contract or order, provided all damage is repaired, cleaned of all foreign matter, and the sample units are re-subjected to and pass Group A inspection.

4.6 Bounce preconditioning. - The Maintenance Kit shall be placed in its normal operating position on a L.A.B. ARV-30-200 vibration table or suitable equivalent. The unit shall be secured to the vibration table and subjected to a two (2) minutes vibration. The vibration force shall be approximately 1g at 25 Hz. After bounce preconditioning, the unit shall not be repaired, aligned, cleaned, or otherwise changed prior to subjection to acceptance inspection.

4.7 Standard test conditions. - Unless otherwise specified, all inspection shall be performed at normal room temperature, pressure, and humidity.

4.8 Service conditions. - The service condition tests shall be conducted as specified. When electrical tests are required, the equipment shall meet the requirements of 3.13.1 thru 3.13.47. Upon completion of each service condition test, the equipment shall be subjected to and pass a visual and mechanical inspection. No defects will be allowed.

4.8.1 Temperature (See 3.12.1). -

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:16Z
Check the source to verify that this is the current version before use.

4.8.1.1 Operating. - The equipment shall be subjected to the temperature limits in accordance with Methods 501 and 502 of MIL-STD-810. Tests shall be conducted at ambient before and after the temperature tests, and at extreme temperatures when the temperature limits have been reached. The requirements of 3.12.1.1 shall be met.

4.8.1.2 Non-operating. - The equipment shall be subjected to the temperature limits in accordance with Methods 501 and 502 of MIL-STD-810. Electrical tests shall be conducted at ambient before and after the temperature tests. The requirements of 3.12.1.2 shall be met.

4.8.2 Humidity. - The equipment shall be subjected to and meet the humidity test of Specification MIL-T-5422 with the transit case and the miscellaneous parts section open. Mechanical-Visual inspection and electrical tests shall be performed before and after the humidity test. The requirements of 3.12.2 shall be met.

4.8.3 Altitude. - The equipment shall be subjected to the altitude tests in accordance with Procedure 1, Method 500, of MIL-STD-810. Electrical tests shall be conducted before and after the altitude test at ambient pressure and at 10,000 feet. The requirements of 3.12.3 shall be met.

4.8.4 Spray-tight protection. - The equipment shall have CY-6774( )/ARM in place and be subjected to the tests specified in Table 1 of Specification MIL-STD-108, except the equipment shall be sprayed at normal rainfall, for compliance with paragraph 3.12.4.

4.8.5 Fungus. - The unit(s) shall be subjected to 28 days of the fungus test specified in Procedure 1, Method 508 of MIL-STD-810. For gasket or other non-hermetically sealed equipment, the parts and materials of the chassis shall be sprayed with the spore suspension. The interior of the case shall also be sprayed. The unit(s) shall be subjected to the test in this open condition and as specified for compliance with 3.12.5. The unit(s) shall not be required to operate.

4.8.6 Vibration. - The equipment shall be subjected to the vibration test in accordance with Method 514-1 of MIL-STD-810, except the equipment shall not be operated during vibration. Electrical tests shall be conducted before and after the vibration test. With the equipment mounted in the test fixture on the vibration table, determine resonant modes of the maintenance kit by varying the frequency of applied vibration slowly through the specified range at an amplitude not exceeding that for which the equipment is to be tested. Individual resonance surveys shall be conducted with vibration applied along each of the three orthogonal axes of the equipment. Electrical tests shall be conducted after the completion of the vibration tests. The requirements of 3.12.6 shall be met.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

4.8.7 Shock. -

4.8.7.1 Shock, bench-handling. - The chassis-with-front-panel assembly shall be removed from its transit case, as for servicing, and placed in a suitable position for servicing on a solid, 2-inch fir bench top. The test shall be performed as follows, in a manner simulating shocks liable to occur during servicing:

a. Tilt up the assembly through an angle of 30 degrees, using one edge of the assembly as an axis, and permit the assembly to drop back freely to the horizontal. Repeat, using other practicable edges of the same horizontal face as axes, for a total of four drops.

b. Repeat "a" with the assembly resting on other faces, until it has been dropped for a total of four times on each face on which the assembly might practically be placed during servicing. The requirement of 3.12.7 shall be met.

4.8.7.2 Shock, drop. - The equipment in its transit case shall be subjected to 18 impact shocks of 15g consisting of 3 shocks in opposite directions along each of 3 mutually perpendicular axes, each shock impulse having a time duration of 11 ± 1 milliseconds. Except for abrasion, paint chipping, and small local deformations, no damage shall occur. Upon completion of the test, without adjustment or repair, the equipment shall be tested for compliance with 3.12.7.

4.9 Electrical requirements. -

4.9.1 Adapter, Breakout CX-8497( )/ARM. - Check the continuity of each wire between the applicable terminals and test points to determine compliance with 3.13.1.

4.9.2 Adapter, Breakout CX-8498( )/ARM. - Check the continuity of each wire between the applicable terminals and test points to determine compliance with 3.13.2.

4.9.3 Adapter, Breakout CX-8499( )/ARM. - Check the continuity of each wire between the applicable terminals and test points to determine compliance with 3.13.3.

4.9.4 Cable, CX-12175( )/ARM. - Check the continuity of each wire between the applicable terminals to determine compliance with 3.13.4.

4.9.5 Cable, CX-12176( )/ARM. - Check the continuity of each wire between the applicable terminals to determine compliance with 3.13.5.

4.9.6 Cable, CX-12172( )/ARM. - Check the continuity of each wire between the applicable terminals to determine compliance with 3.13.6.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:16Z
Check the source to verify that this is the current version before use.

4.9.7 Cable, CX-12173( )/ARM. - Check the continuity of each wire between the applicable terminals to determine compliance with 3.13.7.

4.9.8 Cable, CX-12174( )/ARM. - Check the continuity of each wire between the applicable terminals to determine compliance with 3.13.8.

4.9.9 Termination box, MX-8500( )/ARM. - Check the continuity and resistance of each conductor as indicated in Table V to determine compliance with 3.13.9.

4.9.10 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664551 to determine compliance with 3.13.10.

4.9.11 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664552 to determine compliance with 3.13.11.

4.9.12 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664553 to determine compliance with 3.13.12.

4.9.13 Extender Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664554 to determine compliance with 3.13.13.

4.9.14 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664555 to determine compliance with 3.13.14.

4.9.15 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664557 to determine compliance with 3.13.15.

4.9.16 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664558 to determine compliance with 3.13.16.

4.9.17 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664559 to determine compliance with 3.13.17.

4.9.18 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664560 to determine compliance with 3.13.18.

4.9.19 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664561 to determine compliance with 3.13.19.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

4.9.20 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664563 to determine compliance with 3.13.20.

4.9.21 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664564 to determine compliance with 3.13.21.

4.9.22 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664565 to determine compliance with 3.13.22.

4.9.23 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664566 to determine compliance with 3.13.23.

4.9.24 Extender, Module MX-( ). - Check the continuity of each trace between the applicable terminals in accordance with SM-D-664567 to determine compliance with 3.13.24.

4.9.25 Adapter, Breakout MX-8497( )/ARM. - Apply 500 VDC, measure the insulation resistance between each test point in test point field and all other test points on breakout box to determine compliance with 3.13.25.

4.9.26 Adapter, Breakout MX-8498( )/ARM. - Apply 500 VDC, measure the insulation resistance between each test point in test point field and all other test points on breakout box to determine compliance with 3.13.26.

4.9.27 Adapter, Breakout MX-8499( )/ARM. - Apply 500 VDC, measure the insulation resistance between each test point in test point field and all other test points on breakout box to determine compliance with 3.13.27.

4.9.28 Cable, CX-12175( )/ARM. - Apply 500 VDC, measure the insulation resistance between each pin on the connector and all pins on the same connector to determine compliance with 3.13.28.

4.9.29 Cable, CX-12176( )/ARM. - Apply 500 VDC, measure the insulation resistance between each pin on the connector and all pins on the same connector to determine compliance with 3.13.29.

4.9.30 Cable, CX-12172( )/ARM. - Apply 500 VDC, measure the insulation resistance between each pin on the connector and all pins on the same connector to determine compliance with 3.13.30.

4.9.31 Cable, CX-12173( )/ARM. - Apply 500 VDC, measure the insulation resistance between each pin on the connector and all pins on the same connector to determine compliance with 3.13.31.

Source: https://assist.dla.mil -- Downloaded: 202640-26T04:16Z
Check the source to verify that this is the currentversion before use.

4.9.32 Cable, CX-12174( )/ARM. - Apply 500 VDC, measure the insulation resistance between each pin on the connector and all pins on the same connector to determine compliance with 3.13.32.

4.9.33 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664551 to determine compliance with 3.13.33.

4.9.34 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664552 to determine compliance with 3.13.34.

4.9.35 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664553 to determine compliance with 3.13.35.

4.9.36 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664554 to determine compliance with 3.13.36.

4.9.37 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664555 to determine compliance with 3.13.37.

4.9.38 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664557 to determine compliance with 3.13.38.

4.9.39 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664558 to determine compliance with 3.13.39.

4.9.40 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664559 to determine compliance with 3.13.40.

4.9.41 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664560 to determine compliance with 3.13.41.

4.9.42 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664561 to determine compliance with 3.13.42.

4.9.43 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664563 to determine compliance with 3.13.43.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

4.9.44 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664564 to determine compliance with 3.13.44.

4.9.45 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664565 to determine compliance with 3.13.45.

4.9.46 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664566 to determine compliance with 3.13.46.

4.9.47 Extender, Module MX-( ). - Apply 500 VDC, measure the insulation resistance between each test point and adjacent test point in accordance with SM-D-664567 to determine compliance with 3.13.47.

TABLE V - Continuity Resistance

Item	From	To	Limits Ohms (Min)	Limits Ohms (Max)
Termination Box	1	Blk bdg post (MIC)		0.5
MX-8500( )/U	3	Red bdg post (MIC)	5,100-5%	5,100+5%
	1	3	5.1 -5%	5.1 +5%
	2	4	8.2 -5%	8.2 +5%

4.10 Visual and Mechanical inspection. - Prior to and after assembly, the equipment shall be examined for the defects in accordance with MIL-STD-252.

4.11 Interchangeability. - The dimensions listed below shall be gaged or measured to determine compliance with the physical interchangeability requirements of 3.16. When a listed dimension is not within specified or design limits, it shall be considered a major defect.

a. External and internal dimensions of cases, covers, and insertable assemblies when such dimensions affect mating of parts.

b. Dimensions of cavities, of the console and other units, when such dimensions affect insertion of items.

c. Location of hinges and fasteners on separable parts or assemblies which must mate, such as cases, covers and mountings.

d. Location of connectors, locking pins, fasteners, slides and mountings which receive mating parts of plug-in assemblies and major units, and location of the mating parts on the plug-in assembly or major units.

e. Size and form of special threads.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

4.12 Operational inspection test. - The MT-1192( )/ARM shall be inspected and tested for assurance that all accessories are in place and that the test set controls perform their required functions.

4.13 Quality conformance inspection of preparation for delivery. - Preparation for delivery shall be inspected in accordance with Specification MIL-P-116 to determine conformance to the packaging requirements of Section 5.

4.14 Rough handling test (preparation for delivery). - When rough handling test in accordance with Specification MIL-P-116 is required by the contract, the operational inspection test 4.12 shall be conducted to determine freedom from operational malfunction caused by rough handling.

5. Preparation for delivery. -

5.1 Preservation and packaging. - Preservation and packaging shall be A or C as specified. (See 6.2)

5.1.1 Level A. -

5.1.1.1 Cleaning. - Cleaning shall be accomplished in accordance with process C-1 of MIL-P-116.

5.1.1.2 Drying. - Drying shall be accomplished in accordance with the applicable procedures of MIL-P-116.

5.1.1.3 Preservation application. - None required.

5.1.1.4 Unit packaging. - Unit packaging shall be in accordance with the methods prescribed in MIL-P-116 as specified herein.

5.1.1.4.1 Technical literature. - Each technical literature shall be packaged Method IC-1.

5.1.1.4.2 Maintenance Accessory Kit MK-1192( )/ARM. - Units of the Maintenance Accessory Kit MK-1192( )/ARM shall be packaged Method III as follows: Stow the units and the accessories within the carrying case. Fill the voids within the case with cushioning material conforming to PPP-C-843, Type I, Class A, to prevent movement of the units. Close the lid of the carrying case and secure fastenings. Cushion the case on all surfaces with cells or pads or both fabricated of fiberboard conforming to PPP-F-320, Type CF, Class weather-resistant, Variety SW, Grade W5c, designed to protect all projections and to absorb the shock of impact encountered in handling and transit. Place the cushioned case within a close-fitting fiberboard box conforming to PPP-B-636, W5c. Place the technical literature, packaged as specified in 5.1.1.4.1, on top of the cushioned case, directly under the lid of the box. Close the box in accordance with the appendix of the box specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

5.1.2 Level C. - Maintenance Accessory Kit MK-1192( )/ARM shall be preserved and packaged in a manner that will afford adequate protection against physical and environmental damage during shipment, handling and limited intransit storage.

5.2 Packing. - Packing shall be level A, B, or C as specified. Shipping containers for all levels shall be capable of stacking and supporting superimposed loads during shipment and storage without damaging the container(s) or its contents. (See 6.2)

5.2.1 Level A. -

5.2.1.1 Palletized load. - A quantity of MK-1192( )/ARM, packaged as specified in 5.1, shall be placed on a pallet, load type I, conforming to MIL-STD-147. A fiberboard cap shall be employed over the load having two sides extending down the stacked load at least 12 inches to accommodate marking requirements. The cap shall be fabricated of fiberboard conforming to PPP-F-320, Class weather-resistant, W5s or V3c. The load shall be "bonded" to the pallet by strapping.

5.2.1.2 Less than palletized load. - When quantities per destination are less than a pallet load, the item packaged as specified in 5.1, shall be waterproofed, with tape conforming to PPP-T-76, in accordance with the taping requirements of the appendix of the box specification. A quantity of the waterproofed containers shall be placed within a close-fitting box conforming to PPP-B-601, overseas type; PPP-B-621, style 4, class 2; or PPP-B-585, style 2 or 3, class 3. When the gross weight exceeds 200 pounds, or the container length and width is 48 x 24 inches or more and the wieght exceeds 100 pounds, 3 x 4 inch skids, laid flat, shall be applied in accordance with the requirements of the container specification, or if not specified in the specification, in a manner which will adequately support the item and facilitate the use of material handling equipment. Closure and strapping shall be, in accordance with the applicable container specification or appendix thereto except that metal strapping shall conform to QQ-S-781, Type I, Class B.

5.2.2 Level B. -

5.2.2.1 Palletized load. - A quantity of MK-1192( )/ARM, packaged as specified in 5.1, shall be palletized as specified in 5.2.1.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

5.2.2.2 Less than palletized load. - When quantities per destination are less than a pallet load, a quantity of MK-1192( )/ARM, packaged as specified in 5.1, shall be placed within a close-fitting fiberboard box conforming to PPP-B-640, Class 2, Style E, or PPP-B-636, Type CF, Class weather-resistant, Variety DW. The gross weight of boxes conforming to PPP-B-640 shall not exceed 250 pounds. When the gross weight exceeds 200 pounds, or the container length and width is 48 x 24 inches or more and the weight exceeds 100 pounds, containers will be pallet-mounted on pallets conforming to MIL-P-15011 or MIL-P-3938. Closure shall be in accordance with the appendix of the applicable box specification. Reinforcing shall be by nonmetallic strapping or pressure-sensitive filament tape conforming to PPP-S-760, Type II and PPP-T-97, Type IV respectively; selection of the material and application shall be in accordance with the appendix of the applicable box specification.

5.2.3 Level C. -

5.2.3.1 Palletized load. - A quantity of MK-1192( )/ARM, packaged as specified in 5.1, shall be palletized as specified in 5.2.1.1 except that the fiberboard caps shall be Class Domestic.

5.2.3.2 Less than palletized load. - When quantities per destination are less than a pallet load, a quantity of MK-1192( )/ARM, packaged as specified in 5.2.2.2 except that the fiberboard boxes shall conform to PPP-B-640 and PPP-B-636, Class 1 and Class Domestic, respectively, and renforcing shall not be required for boxes conforming to PP-B-636.

5.3 Marking. - In addition to any special marking required by the contract or order, interior packages and exterior containers shall be marked in accordance with requirements of MIL-STD-129.

6. NOTES

6.1 Intended use. - Maintenance Accessory Kit, MK-1192( )/ARM, is used in conjunction with the MK-994( )/AR and standard test equipment. The kit is used as an aid in maintenance; providing accessories for bench-testing Radio Sets AN/ARC-114( ), AN/ARC-115( ) and AN/ARC-116( ) at Direct Support level of maintenance.

6.2 Ordering data. - Procurement documents should specify the following:

a. Title, Number, and date of this Specification and any amendment thereto.

b. Level of preservations, packaging and level of packing required for shipment.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:16Z
Check the source to verify that this is the current version before use.

c. The specific paragraphs of Section 5 which are applicable to the particular procurement.

d. Preproduction inspection. -

(1) Three (3) sample units of each item cited in Section 1 are generally required so that lengthy environmental tests can be completed on one sample unit while complete performance measurements can be made on the second sample unit. (See 3.2).

(2) Preproduction Pack(s) as follows:

(a) Makeup of pack(s)

(b) Number of each kind of pack to be submitted.

(c) Inspection to be performed thereon. (Including rough handling and functional tests).

(d) Marking and shipping of samples

(e) Place of final inspection.

(f) Technical literature required. (See 3.17)

(g) Quantity of tools and running spare parts required.

(h) Submission of the statement of treatment referenced in 3.11 should be as specified in the Solicitation/Contract.

6.3 Nomenclature. - The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example: MK-1192W/ARM. The contractor should apply for nomenclature in accordance with the applicable clause in the contract.

6.4 Group C Inspection. - Approval to ship may be withheld, at the discretion of the Government, pending results of the corrective action specified in the contract.

6.5 Definition of Level B. - Level B packaging requirements detailed herein are designed to furnish protection against corrosion, deterioration, and physical damage during domestic shipments; covered storage for a period of three years or less; and distribution within the continental limits of the United States.

Source: https://assist.dla.mil -- Downloaded: 202610-26T04:16Z
Check the source to verify that this is the current version before use.

6.6 Location of Operational Inspection. - It is desirable that the operational inspection 4.12 be performed at a location that will minimize handling (which might cause damage to the units) after this inspection. It is recommended that the entire lot (including the sample units) be inspected immediately prior to packaging.

6.7 Verification Inspection. - Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive Quality Assurance provisions established in this Specification and the contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product.

Custodian:
Army EL

Preparing Activity
Army EL
Project No. 6625-A478

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE. This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO 12062 WASHINGTON D C
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commanding General
US Army Electronics Command
ATTN: AMSEL-PP-ED
Fort Monmouth NJ 07703

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.

(TO DETACH THIS FOR..., CUT ALONG THIS LINE.)

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2 DOCUMENT TITLE

3a. NAME OF SUBMITTING ORGANIZATION	4 TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR ☐ USER ☐ MANUFACTURER ☐ OTHER *(Specify)* ____
b ADDRESS *(Street, City, State, ZIP Code)*	

5 PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording

c. Reason/Rationale for Recommendation

6 REMARKS

7a NAME OF SUBMITTER *(Last, First, MI)* – Optional	b WORK TELEPHONE NUMBER *(Include Code)* – Optional
c MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8 DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T04:16Z
Check the source to verify that this is the current version before use.