# MILITARY SPECIFICATION

## MINE, DUMMY

This specification is approved for use by all Departments and Agencies of the Department of Defense.

## 1. SCOPE

1.1 This specification covers the Dummy Mine for use in test projectiles.

## 2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

| | | |
|---|---|---|
| MIL-A-48078 | - | Ammunition Standard Quality Assurance Provisions, General Specification For |

STANDARDS

MILITARY

| | | |
|---|---|---|
| MIL-STD-105 | - | Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105) |
| MIL-STD-1169 | - | Packaging, Packing and Marking for Shipment of Inert Ammunition Components |

DRAWINGS

PICATINNY ARSENAL

| | | |
|---|---|---|
| 9298325 | - | Mine, Dummy |

FSC: 1320

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

## 3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and specifications.

3.2 Mine, Dummy.-The dummy mine shall comply with all requirements specified on Drawing (Dwg) 9298325, and with all requirements specified in applicable specifications.

3.3 Workmanship.-All components shall be fabricated in a thorough, workmanlike manner and shall be free of porosity, twist, warpage, heat marks, sinks, checks, cracks, chipped edges, burrs, blisters, scratches, excess flash, and other defects which would affect their serviceability. All components shall be free of dirt, grease and other foreign matter.

3.4 First Article Inspection.-This specification contains technical provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

## 4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection and Standard Quality Assurance Provisions.-Unless otherwise specified herein or in the contract, the provisions of MIL-A-48078 shall apply and are hereby made a part of this detail specification.

4.2 Classification of Inspections.-The following types of inspection shall be conducted on this item:

a. First Article Inspection
b. Quality Conformance Inspection

4.3 First Article Inspection.-

4.3.1 Submission.-The contractor shall submit a first article sample as designated by the Contracting Officer for evaluation in accordance with provisions of 4.3.2. The first article sample shall consist of ten (10) consecutively produced dummy mines from each cavity of each mold. (The total quantity shall be ten times the number of cavities). Twenty five (25) dummy mines shall be submitted if not produced by a molding process.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

4.3.2 Inspections to be Performed.-See MIL-A-48078 and Table 1 herein.

4.3.3 Rejection.-See MIL-A-48078.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

TABLE 1 - FIRST ARTICLE INSPECTION

**CLASSIFICATION OF DEFECTS & TESTS**

MIL-M-48869 (PA)

| PARAGRAPH | TITLE | | SHEET 1 OF 1 | | DRAWING NUMBER |
|---|---|---|---|---|---|
| | Mine, Dummy | | | | NEXT HIGHER ASSEMBLY |
| CATEGORY | EXAMINATION OR TEST | NO. OF SAMPLE UNITS | AQL OR 100% | REQUIREMENT PARAGRAPH | PARAGRAPH REFERENCE /INSPECTION METHOD |
| | Mine, Dummy (Dwg 9298325) Examination for Defects | See Note 1 | -- | 3.2 | 4.4.2.1 |
| | Compressive Force Test | See Note 2 | -- | 3.2 | 4.5.1 |

1. Ten (10) consecutively produced parts from each cavity or twenty-five (25) parts if a molding process is not used.
2. Ten (10) dummy mines from each batch (See 4.4.1.2).

NOTES

SARPA-QA FORM 2567 FEB 74 4810

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

4.4 Quality Conformance Inspection.-

4.4.1 Inspection Lot Formation.-Inspection lots shall comply with the lot formation provisions of MIL-A-48078. In addition, inspection lots of Dummy Mines shall contain molding compound from one manufacturer's batch. (See 4.4.1.1).

4.4.1.1 Molding Compound Batch.-A molding compound batch is herein defined as material from one manufacturer's lot, produced in one continuous unchanged process using raw materials from one homogeneous lot.

4.4.1.2 Dummy Mine Batch.-A batch of dummy mines is herein defined as mines molded and cured in one unchanging process using molding compound from one batch (See 4.4.1.1). The mines in the batch shall consist of material mixed and cured at one time.

If a continuous type process is used, a batch of mines shall consist of that quantity of mines molded and cured within a four (4) hour period or portion thereof using molding compound from one batch.

4.4.2 Examination.-See MIL-A-48078.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

QUALITY CONFORMANCE INSPECTION

# CLASSIFICATION OF DEFECTS & TESTS

MIL-M-48869 (PA)

| PARAGRAPH | TITLE | SHEET 1 OF 1 | DRAWING NUMBER |
|---|---|---|---|
| 4.4.2.1 | Mine, Dummy | | 9298325 |
| | | | NEXT HIGHER ASSEMBLY |

| CATEGORY | EXAMINATION OR TEST | NO. OF SAMPLE UNITS | AQL OR 100% | REQUIREMENT PARAGRAPH | PARAGRAPH REFERENCE /INSPECTION METHOD |
|---|---|---|---|---|---|
| Critical | None defined | | | | |
| Major A | | | | | |
| [illegible] | Weight | | 0.40% | 3.2 | Balance |
| 102 | Height (Distance across parallel faces)* | | 0.40% | 3.2 | Gage |
| 103 | Profile of Side (2 places)* | | 0.40% | 3.2 | Gage |
| 104 | Arc face radius* | | 0.40% | 3.2 | Gage |
| 105 | Compressive Force Test | 5-0-1 Note 2 | | | 4.5.1 |
| Minor | | | | | |
| 201 | Radius of Apex* | | 0.40% | 3.2 | Gage |
| 202 | Color incorrect | | 0.65% | 3.2 | Visual |
| 203 | Cavity identification missing (when applicable)* | | 0.65% | 3.2 | Visual |
| 204 | Evidence of poor workmanship | | 0.65% | 3.3 | Visual |

1. *See paragraph 4.5.2.
2. This sampling plan shall apply to each batch of dummy mines (See 4.4.1.2).

NOTES

SARPA-QA FORM 2567 FEB 74 4810

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

4.4.3 Testing.-Testing is described in the First Article and Quality Conformance Inspection Tables.

4.4.4 Inspection Equipment.-The inspection equipment required to perform the examinations and tests prescribed herein is described in the Paragraph Reference/Inspection Method' column in the tables starting with paragraph 4.4.2.1. The contractor shall submit inspection equipment designs for approval in accordance with the terms of the contract. See MIL-A-48078.

4.5 Test Methods and Procedures

4.5.1 Compressive Force Test.-Each dummy mine to be subjected to this test shall be tested on a suitable testing machine. Care shall be taken to assure that the platens are free of foreign material and that the wedge is axially centered on the lower platen. The dummy mine shall be loaded at a crosshead speed of 0.050 ± .010 inches/minutes. The load shall be applied until the force specified on the applicable drawing is reached. The load shall then be removed and observation made for any indication of cracks or fracture. Dummy Mines which pass this test may be returned to the lot provided they comply with the dimensional and visual characteristics listed in 4.4.2.1.

4.5.2 Dimensional control of molded or plastic parts.-In place of the normal sampling and inspections associated with the Classification of Defects, and after a curing time for the parts has been approved (See Note 1) a sample of three (3) parts (as molded) from each cavity shall be fully inspected dimensionally to qualify a new or reworked cavity for use in production. The molded parts shall carry the individual cavity identification. As a control of each cavity during production, the above quantity of parts from each cavity shall be inspected for at least the defects listed in paragraphs 4.4.2.1 after continuous production of each 5,000 parts or at the end of each week, whichever occurs first. Of the three (3) samples, one (1) sample shall be the last part produced. If any defective parts are found during qualification of the cavity, the cavity producing the defective part will not be used in production. If any defective parts are found when inspection is performed for the control of the cavity, the cavity producing the defective part shall be removed from production. Further, that portion of production since the last control check shall be returned



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

to the contractor for inspection for each separate type of defect according to MIL-STD-105, using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. All cavities removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the Contracting Officer to substantiate the request. Contractor designs of gages and test equipment required to perform the inspections listed herein shall be forwarded to Commander, Picatinny Arsenal, Dover, New Jersey 07801, Attn: SARPA-QA-T- for approval prior to manufacture of equipment. The noted sub-paragraphs identify those items and minimum inspections subject to the requirements of this paragraph.

NOTE 1: In establishing a curing time, dimensionally check ten (10) parts from each cavity at periodic intervals (e.g. every 30, 60 etc mins) until dimensional stability is attained. The curing time will be from the time the part comes out of the mold until dimensional stability is attained. The inspection data used in determining the curing time shall be sent to Picatinny Arsenal, Dover, New Jersey 07801 Attn: SARPA-QA-A-S. If there is a change in material, or in the cycle time, or if a cavity is reworked, or a new cavity is used, a new curing time shall be established and approved.

## 5. PREPARATION FOR DELIVERY

5.1 Packaging and packing (Level C).-The dummy mine shall be packaged and packed in accordance with MIL-STD-1169.

5.2 Marking.-Marking of the cartons shall be in accordance with MIL-STD-1169.

5.3 Shipping.-When components from more than one lot are shipped at one time, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

## 6. NOTES

6.1 Intended Use.-The dummy mine is intended for use in test projectiles.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

6.2 Ordering Data.-See MIL-A-48078.

6.3 Submission of designs for approval.-See MIL-A48078. Submit equipment designs, as required, to Commander, Picatinny Arsenal, ATTN: SARPA-QA-T, Dover, New Jersey 07801.

6.4 Submission of results of contractor-conducted examinations and tests.-Data shall be submitted in accordance with data item DI-R-1721 on the DD Form 1423 for the contract.

Custodian:
Army-PA

Preparing Activity:
Army-PA

Project Number: 1320-A318



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.

# STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

**INSTRUCTIONS:** The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

**DD FORM 1 JAN 72 1426** REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:42Z
Check the source to verify that this is the current version before use.