MILITARY SPECIFICATION

CONTROL BOX, COMPUTER LOGIC UNIT,
TEST SET, C4020 GSM-70: 8623274

This amendment forms a part of Military Specification MIL-C-60656(MU), dated 10 April 1967.

Figure 1: Delete "J1-I-SCOPE" and substitute "J1-i-SCOPE"

Paragraph 4.1: Delete and substitute

"4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements."

Paragraph 4.2: Delete and substitute the following:

"4.2 First Article (Initial Production)Approval.- The requirement for first article approval and the responsibility (Government or contractor) for first article testing shall be as specified in the contract. The sample for first article approval tests shall consist of three (3) control boxes manufactured in the same manner using the same materials, equipment, processes, and procedures as used in regular production. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as used in regular production.

4.2.1 Government Testing.- When the Government is responsible for conducting first article approval tests, the contractor, prior to submitting the sample to the Government, shall inspect the sample to insure that it conforms to all the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials.

4.2.2 Contractor Testing.- When the contractor is responsible for conducting first article approval tests, the sample shall be inspected by the contractor for all the requirements of the contract. The sample and a record of this inspection, including certificates of conformance for materials, shall be submitted to the Government for approval. The Government reserves the right to witness the contractor's inspection."

Paragraph 4.4 Delete first sentence and substitute:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:54Z
Check the source to verify that this is the current version before use.

"Control box units shall be selected at random by a Government representative as control samples from each three (3) months production or portion thereof as follows:

3 units per first 100 produced
5 units per 200
7 units per 300
9 units per 400
10 units per 500
12 units per 700
15 units per 1000
and 2 units for each 100 items produced in excess of 1000."

Table IV, Column A, line 9: Delete "1" and substitute "L".

Paragraph 4.6.2.3, line 2: Delete "J1-I" and substitute "J1-i"

Custodian:

Army - MU

Preparing activity:

Army - MU

Project No. 1220-A095

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:54Z
Check the source to verify that this is the current version before use.