MIL-F-60589B(MU)
AMENDMENT 3
31 July 1972
SUPERSEDING
AMENDMENT 2
24 February 1972

MILITARY SPECIFICATION

FUZE, MT, XM711 ASSEMBLY

This amendment forms a part of Military Specification MIL-F-60589B(MU) dated 5 October 1970.

* Paragraph 3.2.1 Change "0.23 percent" to "0.56 percent".

Paragraph 3.3.3 Delete in its entirety.

Paragraph 4.2.1 Change "450 (Aggregate) subassemblies as delineated in 4.2.3" to "350 (Aggregate) subassemblies as delineated in 4.2.3".

Paragraph 4.2.1.1 line 4 Change "450 subassemblies" to "350 subassemblies".

Paragraph 4.2.3.2 Delete in entirety and substitute:

"4.2.3.2 Twenty-five (25) of each of the three (3) subassemblies shall be tested as in 4.3.3.7.2 (torque)."

Paragraph 4.2.5 under "Test" Delete Forty Foot Drop in its entirety.

Paragraph 4.3.2.22 Add MAJOR characteristic 105.

"105. Perpendicularity of lever wings with Datum A & B Gage"

Paragraph 4.3.2.34 Add:

"g. Laminated Plate #1 and #2 Assembly D10542816
(1) Damaged or bent lever
(Check immediately, prior to assembly of plates)"

Paragraph 4.3.3.7.2 Delete the following:

"No. 1 Gear & Pinion Assembly	C10543220
No. 2 Gear & Pinion Assembly	C10520769
No. 3 Gear & Pinion Assembly	C10543222
No. 4 Gear & Pinion Assembly	C10543221"

Paragraph 4.3.3.11.5 Change "subassembly" to "assembly" and "F10542817" to "D10542813".

Paragraph 4.3.3.16 Under "Test" Delete Forty Foot Drop in its entirety.

Paragraph 4.4.11.5 Change "F10542817" to "D10542813".

FSC 1390

Source: https://assist.dla.mil -- Downloaded: 202640-23T00:46Z
Check the source to verify that this is the currentversion before use.

Paragraph 4.4.16.3 Delete in its entirety.

* Para. 4.4.17.2, add "(see 6.2.5)" at the end of the paragraph.

* Para. 4.4.17.2.1 Delete the following: "Where both chronograph systems fail to provide a value, the value obtained by the velocimeter system shall be used."

* Add new para. 6.2.5 "6.2.5 Hawk - Doppler Velocimeter System.-Where only velocimeter system time measurements are obtained and these values indicate a prior function or outlier which would affect lot disposition, the lot shall be referred to the responsible procuring activity. Hawk - Doppler values will not be used to determine sample average ($\overline{X}$)or standard deviation (S).

Add Paragraphs 6.11, 6.11.1, 6.11.2, 6.11.3, 6.11.4 and 6.11.5

"6.11 Statement of Safety Requirements

6.11.1 Safety Limitations and Precautions Relating to Production Equipment and Facilities:

Assembly of detonators and relay into fuze should be performed under protective hoods with static electricity controls. Protective hood should be used when performing the jolt and transportation vibration test.

6.11.2 Hazards Presented by Materials:

Possible injury (burns or dismemberment) to limbs and body from flash of detonators and relay.

6.11.3 Known Hazards or Hazardous Areas:

All areas in which detonators are used in assembly operations or stored.

6.11.4 Specific Instructions Relative to Manufacture, Handling, Storage and Shipment of Material: The number of persons exposed to explosive operations and the quantities of explosive materials should at all times be the minimum consistent with safety and the efficiency of operation. Signs setting forth personnel and explosive limits also should be posted. Prior to starting operations including any of the hazardous materials or items described herein, a standard operating procedure should be developed and approved by the contractor outlining the specific requirements to safely perform the particular operation. All personnel concerned should be cognizant of SOP contents. Applicable portions of the approved procedure should be conspicuously posted convenient to all stations involved in the operation for guidance of all personnel.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:46Z
Check the source to verify that this is the current version before use.

6.11.5 Explosive Hazard Classification of Materials:

Assembled fuzes - Class 1, Detonators in Storage - Class 7.

* The margins of this amendment are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodian:

Army - MU

Preparing activity

Army - MU(FA)

Project No. 1390-A109

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:46Z
Check the source to verify that this is the current version before use.