MILITARY SPECIFICATION

CARTRIDGES, 40MM, STAR PARACHUTE: XM661 AND XM662

METAL PARTS FOR

1. SCOPE

1.1 This specification covers the metal parts for Cartridges, 40MM, Star Parachute: XM661 and XM662.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons, General Specification for

MIL-C-5541 - Chemical Films and Chemical Film Materials for Aluminum and Aluminum Alloys

MIL-I-45607 - Inspection Equipment, Acquisition, Maintenance and Disposition of

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)

MIL-STD-109 - Quality Assurance Terms and Definitions

MIL-STD-1168 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components

FSC: 1310

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. Army Munitions Command

9274474 - Projectile Assembly Parts Arrangement

PUBLICATIONS
ARMY
ET-9274474 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer).

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and specifications.

3.2 Parts.-The parts shall comply with all requirements specified on Drawing (Dwg.) 9274464, all associated drawings, and with all requirements specified in applicable specifications.

3.3 Workmanship.-All parts and assemblies shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products, and other foreign matter. The cleaning method used shall not be injurious to any parts, nor shall the parts be contaminated by the cleaning agents. All marking and stamping shall be neat and sharply defined.

3.4 Submission of results of contractor-conducted examinations and tests.-The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract. (See 6.4).

3.5 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contractor or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.

b. Drawing and specification number and date, together with identification and date of changes thereto.

c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.

d. Number of items in the lot.

e. Date submitted.

The certificates shall be signed by a responsible agent of the certifying organization. The intitial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection.

4.2.1 Submission.-The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2. (See 6.1) The first article sample shall consist of the following:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

a. Twenty-five (25) parachute assemblies.
b. Twenty-five (25) plug anchors.
c. Twenty-five (25) ogives.
d. Thirty (30) housing delays (5 for salt spray).
e. Fifteen (15) bodies (5 for salt spray).
f. Twenty-five (25) bodies, prior to painting.
g. Twenty-five (25) tube illuminants.

All parts and completed assemblies submitted shall have been produced by the contractor (or furnished by a supplier) using the same production processes, procedures and equipment as will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance. A first article quantity, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process (including heat treatment procedures and equipment), material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspection to be performed.-All parts and assemblies shall be subjected by the Government to any or all the examinations or tests specified in this specification and any or all requirements of the applicable drawings.

4.2.3 Rejection.-If any part or assembly fails to comply with any of the applicable requirements, the first article quantity shall be rejected. The Government reserves the right to terminate its inspection upon any failure of a part or assembly in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity or portion thereof. Until a first article quantity is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions.-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision, and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (See 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall bel00 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Ogive (See Dwg. 9251920)

Categories	Defects	Method of Inspection (See 4.3.3.1)	Code No.
Critical:			
	1. Incorrect ogive	Visual	01001

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

Major	AQL 0.65 Percent		
101.	Large outside diameter	Gage	01002
102.	Concentricity of large outside diameter with third largest outside diameter	Gage	01003
103.	Second largest outside diameter	Gage	01004
104.	Inside diameter	Gage	01005
Minor	AQL 2.50 Percent		
201.	Total length	Gage	01006
202.	Width of slots	Gage	01007
203.	Diameter of groove	Gage	01008
204.	Width of groove	Gage	01009
205.	Evidence of poor workmanship (See 3.3)	Visual	01010

4.3.2.2 Body, prior to painting (See Dwg. 9255778).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 Percent		
101.	Outside diameter	Gage	02001
102.	Smallest inside diameter	Gage	02002
103.	Concentricity of smallest inside diameter with outside diameter	Gage	02003
104.	Perpendicularity of both ends with outside diameter	Gage	02004
105.	Wall thickness at indicated area	Gage	02005
Minor	AQL 2.50 Percent		
201.	Largest inside diameters	Gage	02006
202.	Second largest inside diameter	Gage	02007
203.	Concentricity of largest inside diameter with outside diameter	Gage	02008
204.	Concentricity of second largest inside diameter with outside diameter	Gage	02009
205.	Total length	Gage	02010

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

206.	Distance to groove	Gage	02011
207.	Evidence of poor workmanship (See 3.3)	Visual	02012

4.3.2.3 Body after painting (See Dwg. 9255778).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.40 Percent		
101.	Second largest outside diameter	Gage	03001
Minor	AQL 0.65 Percent		
201.	Incorrect color	Visual	03002

4.3.2.4 Plug, anchor (See Dwg. 9252413).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 1.00 Percent		
101.	Large outside diameter	Gage	04001
102.	Width of bead chain notch	Gage	04002
103.	Depth of bead chain notch	Gage	04003
104.	Diameter of hole	Gage	04004
105.	Thickness of flange	Gage	04005
106.	Concentricity of bead chain notch with large outside diameter	Gage	04006
Minor	AQL 1.50 Percent		
201.	Total length	Gage	04007
202.	Diameter grooved end	Gage	04008
203.	Evidence of poor workmanship (See 3.3.)	Visual	04009

4.3.2.5 Housing, delay (See Dwg. 9252378).-

Categories	Defects	Method of Inspection	Code No.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

Major		AQL 1.00 Percent	
101.	Pitch diameter of thread	Gage	05001
102.	Major diameter of thread	Gage	05002
103.	Small inside diameter	Gage	05003
104.	Large inside diameter	Gage	05004
105.	Concentricity of small inside diameter with large inside diameter	Gage	05005
Minor:		**AQL 1.50 Percent**	
201.	Length to flange	Gage	05006
202.	Concentricity of body diameter with large inside diameter	Gage	05007
203.	Diameter of thread undercut	Gage	05008
204.	Evidence of poor workmanship (See 3.3)	Visual	05009

4.3.2.6 Tube, Illuminant (See Dwg. 9252414).-

Categories	Defects	Method of Inspection (See 4.3.3.1)	Code No.
Critical:	None defined		
Major		AQL 0.65 Percent	
101.	Outside diameter	Gage	06001
102.	Wall thickness	Gage	06002
103.	Perpendicularity, both ends, with outside diameter	Gage	06003
Minor		AQL 1.00 Percent	
201.	Total length	Gage	06004
202.	Evidence of poor workmanship (See 3.3)	Visual	06005

4.3.2.7 Parachute assembly (See Dwg. 9255140).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major		AQL 1.00 Percent	
101.	Tears or holes in parachute	Visual	07001
102.	Shroud lines not secure to parachute	Visual	07002
103.	Shroud lines improperly tied to coupling	Visual	07003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

104.	Coupling not secure to chain	Visual	07004
105.	Shrouds twisted	Visual	07005

Minor — AQL 0.65 Percent

201.	Evidence of poor workmanship (See 3.3)	Visual	07006

4.3.3 Testing.-

4.3.3.1 Dimensional control of plastic parts.-In place of the normal sampling associated with the Classification of Defects, and with the approval of the Contracting Officer, and after a stabilization time for the parts has been approved (See Note 1), a sample of five (5) parts (as molded) from each cavity may be dimensionally inspected to qualify a new or reworked cavity for use in production or as a control of each cavity during production.

The inspection of the parts shall be performed only when the stabilization time for the parts has been reached. The inspection for control of each cavity during production shall be performed on the above quantities from each cavity at the beginning of production and at intervals of 5,000 parts, or at the beginning and end of each shift, providing the number of parts produced during that shift is less than 5,000 parts.

The samples inspected for the beginning of production and the intervals described above shall be the first five (5) parts produced for the former and the last five (5) parts produced for the latter. Parts that fail to comply with dimensional requirements after dimensional stability has been attained shall be classed defective.

If any defective parts are found during qualification of the cavity, the cavity producing the defective part will not be used in production. If any defective parts are found when inspection is performed for control of the cavity, the cavity producing the defective part shall be removed from production. Further, that portion of production since the last control check shall be returned to the contractor for corrective action.

All cavities formerly removed from production because of some fault, may, after reworking, be returned to production providing they pass the qualification test as above. The contractor may request a change of inspection frequency providing he presents objective evidence to substantiate the request to the Contracting Officer.

(NOTE 1) - In establishing a stabilization time, dimensionally check ten (10) parts from each cavity at periodic intervals

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

(e.g. every 30, 60, etc. mins.) until dimensional stability is attained. The stabilization time will be from the time the part comes out of the mold until dimensional stability is attained. The inspection data used in determining the stabilization time shall be sent to Picatinny Arsenal, SMUPA-QA-A-S. If any new change in material, process parameters, a reworked cavity, or new cavity is used, a new stabilization time shall be established and approved.

4.3.3.2 Salt spray of body and housing delay (See Dwgs. 9255778 and 9252378), Major Defect, Code No. 08001.-Sampling and rejection shall be in accordance with MIL-C-5541. The test shall be performed as specified in 4.4.1 using equipment in accordance with 4.3.4.

4.3.4 Inspection equipment.-Equipment Tabulation (ET) number 9274464 and Equipment Lists (EL's) referenced thereon identify the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures.-

4.4.1 Salt spray of body and housing delay.-The parts shall be subjected to the salt spray test using the equipment, method and procedures specified in MIL-C-5541. This test is a destructive test. Parts so tested shall not be returned to any lot.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 Level C.-The metal parts shall be preserved and packaged in accordance with MIL-STD-1169.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

5.2 Packing.

5.2.1 Level C.-The metal parts, preserved and packaged as specified in 5.1.1, shall be packed for shipment in accordance with MIL-STD-1169.

5.3 Marking.-Marking of the carton shall comply with MIL-STD-1169.

5.4 Shipping.-When components from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor (see 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment Lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor desisgn on controlled contractor format and/or commercial equipment.
MU - Army design,-mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed classifications: Mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army Designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (See 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspectior equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information sepcified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category A, Form 3. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.

6.3.5 Submission of contractor design.-All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-QA-A-S. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

6.4 Submission of results of contractor-conducted examinations and tests.-Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-QA-A-S.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1310-A006

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:15Z
Check the source to verify that this is the current version before use.